Responses to Contractor Questions
Addendum #1
AHEC-27901-D – CAVEA Lighting
Date: 11/11/2026

Includes:

1. **Modified Documented Quote with changes to quote due date, public bid opening, and construction schedule**
2. **All questions received and the corresponding answers, including contractor-proposed addendum attachment**
3. **Mandatory pre-quote sign-in sheets**
4. **Six (6) photos of the space**
5. **Two (2) specification sheets for existing downlight type and new downlight type**

1. Test fit clause: *Quote includes field verification and a first-fixture test fit of each type. Fixtures furnished under the design that do not fit existing construction, and existing conditions differing materially from the Drawings, will be reported by RFI before the affected installation proceeds; resulting modifications, substitutions, or re-work are change-order work with equitable price and schedule adjustment. This quote does not include a guarantee that design-furnished fixtures fit existing construction, redesign services, or termination exposure for a timely reported fit failure.*
Will the Owner/Engineer issue the dimensional-verification and tolerance/fit allowance (attached draft) by addendum? If not, will the one-line test-fit clause above be accepted as a quote qualification without rendering the quote non-responsive?
Answer: The proposed addendum will not be issued. MSU Denver directs all bidders to include field verification and a first-fixture test fit of each fixture type in their bid. Any existing conditions identified during field verification that differ materially from the Drawings shall be reported by the Contractor through an RFI before the affected installation proceeds. Any resulting modifications, substitutions, re-work, or requests for adjustment shall be evaluated in accordance with the Contract Documents, including applicable change order provisions. MSU Denver, RMH, and the awarded Contractor will coordinate in good faith to address fixture fit issues identified through the field-verification and test-fit process and determine an appropriate resolution consistent with the Contract Documents.

2. Existing track: confirm manufacturer, series, and circuit/voltage of the installed track, and whether new heads/adapters must be the same manufacturer's system.
Answer: Existing track is not being reused. On sheet E-411, refer to keynote 15 for track and trackhead demolition information. On sheet E-411, refer to keynote 7 for new track and trackhead information, and sheet E-601 Luminaire Schedule.

3. Existing downlight openings: confirm nominal opening diameter and ceiling construction (drywall vs. panel) at the D2 locations, and whether trim-ring/goof-ring remedies are acceptable if a furnished trim under-covers an existing opening.
Answer: The existing downlight and new downlight type D2 product data are attached for reference. Exact ceiling construction is unknown, photos above the ceiling are attached for reference. Trim rings/goof rings are an acceptable remedy.

4. Ring fixtures: confirm the soffit-ring inner diameter and chase depth available for the ring-mounted fixtures that remain, and who furnishes any adapter/mounting hardware.
Answer: The existing downlight and new downlight type D2 product data are attached for reference. Contractor is responsible for any adapter and/or mounting hardware required for a complete installation.

5. Above-ceiling access: confirm access-panel locations and whether additional access panels, if required for the DRd and rack work, are by this Contractor or others.

Answer: There are two (2) existing access panels in the ceiling and two (2) additional access panels, one (1) in each of the storage closets, refer to photos attached. Contractor is responsible for additional access panels, if required.

6. Mock-up: will the Engineer accept the first installed fixture of each type as the fit mock-up, and what is the review turnaround so the Dec 14–Jan 15 window is protected?

Answer: Engineer will accept the first installed lights of each type as the fit mock-up. Engineer will work with Contractor and MSU Denver regarding scheduling to maintain schedule, and requests a minimum of five (5) working-days' notice.

7. Staging: as of the Nov 4 job walk, no staging area has been arranged; it is under discussion. Will the Owner designate a staging/storage area for fixtures and materials during the Dec 14–Jan 15 construction window, where will it be located, and will it be available for the full window including deliveries before Dec 14?

Answer: Staging locations include one or both breakrooms noted below.

