ELEVATE SOLAR CO LLC
13785 W 64th Pl, Arvada, CO 80004 · 303-246-5819 · aureliom@elevatesolarco.com

Proposed Addendum · Dimensional Verification and Tolerance / Fit Allowance

Project: MSU Denver CAVEA Theater Lighting Upgrades · Solicitation 26PR05 (AHEC-27901-D)

Submitted by Elevate Solar Co LLC with its pre-quote questions, November 8, 2026. For adoption by the Owner / Engineer of Record by addendum.

1. Field verification responsibility.

The Contractor shall field-verify existing conditions affecting the Work · ceiling openings and trim condition, track gauge/type and adapter compatibility, soffit-ring inner diameter and chase depth, mounting surfaces, and above-ceiling conditions at the DRd panel and rack · and shall report any discrepancy from the Contract Documents to the Engineer in writing within five (5) business days of Notice to Proceed and before ordering or rough-in. Field verification transfers no design responsibility to the Contractor; the Engineer of Record retains responsibility for the design fitting the existing conditions shown on the Drawings.

2. Dimensional tolerance allowance.

New fixtures, trim, track heads, and adapters furnished under this Section shall fit the existing construction within the fixture and track manufacturers· published tolerances for the existing systems, and within the as-built dimensions of the existing construction, without modification of existing construction. Fixtures falling outside those published tolerances, or existing conditions differing materially from the Drawings, shall be treated under Paragraph 4.

3. Mock-up / first-install acceptance.

The first installed fixture of each type (downlight, wall washer, track head, ring fixture) shall serve as the mock-up for the Engineer·s acceptance of fit, trim seating, and finish match before the balance of that type is installed. Rejection of the mock-up for fit reasons attributable to the furnished fixture or to existing conditions not shown on the Drawings shall be resolved by the Engineer (alternate fixture, detail revision, or directed modification) and is not grounds to direct the remaining installation at the Contractor·s risk.

4. Discrepancy = RFI, answered before proceeding; cost/schedule relief preserved.

Where a furnished fixture does not fit existing construction, or existing construction differs materially from the Drawings, the Contractor shall stop work on the affected fixture type, submit an RFI, and proceed only on the Engineer·s written direction. Directed modification of existing construction, substitution of fixtures, or re-work caused by such discrepancies shall be performed as a change with equitable adjustment to price and schedule; the construction window is extended day-for-day for time lost awaiting direction.

5. Expressly NOT accepted.

(a) No guarantee, express or implied, that owner/engineer-furnished or design-specified fixtures will fit existing construction; (b) no unpaid redesign · the Contractor does not assume the Engineer·s design responsibility or any duty to redesign fixtures, details, or systems at no cost; (c) no termination or default exposure arising from a fit failure reported in accordance with Paragraphs 1 and 4, provided the Contractor stops the affected work and seeks direction as required.

Alternate one-line qualification (if no addendum is issued):

·Quote includes field verification and a first-fixture test fit of each type. Fixtures furnished under the design that do not fit existing construction, and existing conditions differing materially from the Drawings, will be reported by RFI before the affected installation proceeds; resulting modifications, substitutions, or re-work are change-order work with equitable price and schedule adjustment. This quote does not include a guarantee that design-furnished fixtures fit existing construction, redesign services, or termination exposure for a timely reported fit failure.·