Addendum 1

To

RFP B-26-019

Switchgear and Protective Relay Maintenance Services

Questions and Answers

Q1: Regarding Section 6.4, Proposed Team Resources, and Attachment 1, Section 1.5, Contractor Qualifications: Please confirm whether NETA Electrical Testing Technician certification is a mandatory qualification for bidders or whether personnel with equivalent electrical testing experience, training, and industry-recognized qualifications are acceptable. If NETA certification is mandatory, please clarify: The minimum required NETA certification level (Level 2, 3, or 4). Whether the requirement applies to all electrical testing personnel or only the Lead Technician/Field Supervisor. Whether the bidding company must be a NETA Accredited Company or whether qualified non-NETA-accredited companies are eligible to submit proposals. Thank you for your clarification.
A: NETA certification is desired but can be substituted for equivalent certifications, training, or documented experience. Documentation should be provided showing certifications, training, and/or experience.

Q2: Please confirm that all items under VME will be NETA testing and all items under V&M are only getting inspected?
A: Full VME is defined as Visual and Mechanical Inspection and Electrical Tests per applicable NETA MTS-2023 section numbers. V&M is defined as Visual and Mechanical Inspection only per the same NETA MTS-2023 sections.

Q3: Under device type for current transformers and MCOV are we counting these as groups of 3 or 1?
A: Each MCOV listed is a group of three, one per phase.

Q4. Does VME include cleaning, torque verification, or just inspections? Clarify.

A: VME includes ALL applicable Visual and Mechanical Inspections and Electrical Test per the referenced NETA MTS-2023 sections.

Q5: Please confirm the permitted working hours for each scheduled outage, including whether extended shifts, nights, weekends, and/or holidays may be required or permitted to complete the work within the maximum allowable outage durations.

A: Normal outage times will be Monday-Friday from 7AM-3PM, with most scheduled Tuesday-Thursday. Metro staff works 6AM-4PM.

Q6: Please confirm the anticipated number of outage events and mobilizations for each contract year and whether multiple scheduled locations may be performed concurrently or consecutively during a single mobilization.

A: It is anticipated that most low voltage switchgear/transformers and 902-905 substations for a given year (see specification) will be completed concurrently approximately within a one-month window, typically April. The 901 Substation work will likely be completed at a separate time and may involve two non-concurrent outages per year (one for VME and one for VM only).

Q7: For the low-voltage power circuit breakers identified under NETA MTS Section 7.6.1.2, please confirm whether trip-unit verification/testing is to be performed by primary current injection or secondary injection. If requirements vary by breaker type or trip unit, please identify the required test method for each applicable equipment type.

A: Please review NETA MTS 7.6.1.2 (B) 5, 6, 7, 8. They require primary current injection.

Q8: Please confirm the required extent of protective-relay testing, including whether testing requires secondary injection of each enabled protection element, verification of logic/interlocks and outputs, and functional trip testing through the associated circuit breaker.

A: Protective relay testing should be in accordance with NETA specification to include all actively used protective features of the relay. Features not in use do not require testing.

Q9: Will Metro provide the current approved relay setting files and logic/configuration files prior to each scheduled outage?

A: Yes

Q10: Please confirm the required test method for medium-voltage shielded cables identified under NETA MTS Section 7.3.3, including the required test voltage, duration, and acceptance criteria.

A: All tests except 8. Online PD and 9. Offline PD shall be required.

Q11: Please confirm the required electrical and insulating-fluid tests for transformers identified with NETA MTS Sections 7.2.2 and 7.12.3, and identify which transformers require oil sampling/laboratory analysis as part of the base annual lump-sum scope.

A: In accordance with the text of the specification "Transformer oil sampling/testing is included only where specifically identified or authorized." There are not any transformers where sampling/testing is identified as part of this scope.

Q12: Please confirm the outage/isolation responsibilities and coordination interface for the 115-kV equipment associated with the Xcel switchyard, including whether Metro will coordinate all required utility switching and clearances before Contractor testing.

A: Metro will coordinate all switching with all parties.

Q13: Will Metro provide available previous maintenance/test reports, equipment manuals, one-line diagrams, protective-relay settings, breaker trip-unit settings, and historical deficiency records prior to each annual maintenance outage?

A: Yes.

Q14: Please clarify how troubleshooting, corrective repairs, replacement parts, and retesting resulting from failed or abnormal test results will be compensated when such work is authorized during a scheduled outage.

A: Please see 4.6 of the specification. Troubleshooting, corrective repairs, and replacement parts are not part of the scope of this work. In the event such repairs are authorized, a separate authorization and PO will be issued.

Q15: If an approved outage is postponed, interrupted, shortened, or terminated by Metro after Contractor mobilization for reasons outside the Contractor's control, please confirm whether resulting standby labor, additional mobilization, and schedule impacts will be treated as compensable additional work.

A: See Addendum 2

Q16: Given the maximum allowable outage durations, please confirm whether the Contractor's annual lump-sum price should include anticipated overtime necessary to complete scheduled maintenance within the specified outage windows, or whether overtime requires separate written authorization by Metro.

A: The contractor's lump sum price should include all anticipated costs to complete outages within the requested outage windows. Note: Anticipated outage windows are the time the equipment will be out of service, which does not limit prep/clean-up time before and after the outage window.

Q17: Please confirm whether Metro-owned aerial lifting/racking devices, carts, and manufacturer-specific handling equipment will be available for Contractor use, or whether the Contractor shall provide all such equipment.

A: Contractor should provide all necessary equipment required to perform the scope of the work.

Q18: Please confirm that all equipment listed in Appendix B, including equipment identified as “SPARE” or “FUTURE,” is included in the required maintenance/testing scope for the applicable contract year unless otherwise directed by Metro.

A: All equipment listed, including "SPARES" and "FUTURE" equipment, shall be tested.

Q19: Please confirm whether Metro has a required test-report template, naming convention, electronic file structure, or test-data format that the Contractor must use for annual deliverables.

A: Contractor shall use Metro asset naming convention in their reporting. There is no required report template.

Q20: Please confirm whether badge registration is a one-time or daily requirement and identify the anticipated time required for initial registration and daily site-access/check-in procedures.

A: Badge registration is up to a maximum of annual or shorter term, depending on the duration the individual being badged will be on site.

Q21: Please confirm the anticipated month(s) or timeframe for performing the 2027 Annual Maintenance Program and whether all 2027 services are expected to be completed within calendar year 2027. Please also confirm whether contract-year pricing and invoicing are based on the calendar year or Metro's fiscal year.

A: A majority of the work is expected to occur in April of each year, to include 902-905 and the low voltage switchgear and transformers. The 901 VME and VM testing will likely occur at separate times throughout the year.