# Exhibit A, Scope of Work

CPW Native Aquatic Species Facility Heater Replacement, Installation and Electrical Upgrade

## Overview

Contractor shall remove 6 existing heating units and replace them with electrical heating units for the native aquatic species facility, alongside necessary electrical infrastructure upgrades and dedicated circuit breaker installations. Additionally, the contractor shall install a new high-efficiency space heater in the garage facility.

## Tasks

### Heater Replacement (6 units)

- **Decommissioning:** Safely disconnect, isolate, and remove outdated or malfunctioning heater units servicing the native aquatic species conduit system.
- **Equipment Installation:** Supply and install high-efficiency aquatic inline/immersion heaters specifically rated for sensitive aquatic species environments. Replacement units should be at least 35,000 BTU.
- **Conduit & Plumbing Integration:** Inspect, adjust, and seal connections to ensure proper fluid flow, leak containment, and precise temperature regulation across the conduit system.

### Electrical Infrastructure & Panel Upgrades

- **Breaker Installation:** Install appropriate dedicated circuit breakers in the main/sub-panel to handle the increased electrical load of the new heating units and prevent circuit overloading.
- **Conduit & Wiring:** Run code-compliant electrical wiring and protective conduits from the distribution panel to both the aquatic heaters and garage locations.
- **Safety Controls:** Integrate GFCI (Ground Fault Circuit Interrupter) protection and emergency cutoff switches near aquatic areas to strictly comply with environmental and safety codes.

### Garage Heater Installation

- **Unit Mounting:** Securely mount a new space heater (electric unit heater / overhead ceiling-mount heater) in the designated garage workspace.
- **Electrical Connection:** Connect the unit to its newly installed dedicated circuit and configure an accessible thermostat control unit.
- **Testing & Commissioning:** Verify thermostat operation, thermal output, safety clearances, and overall system integration.

## Deliverables

- 6 replaced heating units that are fully operational and provide a temperature-controlled heating system for the aquatic species conduit
- Newly installed, properly sized, and clearly labeled circuit breakers in the main distribution panel.
- A fully functional garage heater with dedicated controls and safety testing completed.
- Complete system testing, electrical inspection compliance, and thorough job-site clean-up.