DENVER
HUMAN SERVICES

QUESTIONS & ANSWERS
BidNet - November 6, 2026

On-Call Security Access Control Services

REQUEST FOR PROPOSALS

RFA NO. FS/CA/FSS_AccessControl_2026

Question 1: Are the 3 requested back up techs expected to also be S2 Certified?
Answer: Yes. As outlined in Section II.D.i.c of the RFP, the contractor must have a minimum of two LenelS2 NetBox-certified technical personnel available to support the City's account. Section II.D.i.c.1 identifies a preference for three additional certified technical personnel on staff to provide backup support. These additional personnel are expected to hold applicable LenelS2 NetBox certifications. The three additional certified technicians are preferred, not a mandatory minimum qualification. However, personnel assigned to perform configuration, programming, installation, troubleshooting, maintenance, or upgrades to the LenelS2 NetBox environment must meet the certification requirements outlined in Section II.D.i.b of the RFP.
Question 2: How many emergency or critical calls did DHS log last year, and how does DHS define a "critical" event?
Answer: A verified historical count of emergency or critical technical service requests for the previous year is not available. For proposal-planning purposes, Section II.B.vi of the RFP identifies an estimated volume of approximately four emergency service requests per quarter across all DHS facilities covered under this solicitation. These figures are estimates and do not represent verified historical service volumes. As outlined in Section II.B.ii.a.1 of the RFP, critical issues may include: • Complete access control system outages. • Failures affecting multiple controlled access points. • Inability to secure a DHS facility or critical area. • Failure of critical panic or duress functionality. • Other conditions designated by DHS as creating an immediate security or operational risk. The classification of a service request will depend on the nature of the issue and its impact on facility security and operational continuity.
Question 3: What version of S2 Netbox is DHS running now, and does DHS have a policy on upgrading to current versions, including approved upgrade windows?
Answer: DHS is currently running LenelS2 NetBox software version 6.0.2.

Sections II.A.iv and II.B.iii of the RFP address system upgrades, compatibility, and future scalability. Software and firmware upgrades will be evaluated based on manufacturer recommendations, system compatibility, cybersecurity requirements, and DHS operational needs.

Upgrades must be coordinated with DHS and Technology Services, as applicable, and receive appropriate authorization before implementation.

For upgrades that may temporarily interrupt access control operations, DHS generally prefers scheduling before or after normal business hours when practicable. Work may also be performed during business hours when DHS determines that adequate physical security coverage and operational safeguards are available.

Specific upgrade windows will be coordinated and approved based on the nature of the work and its anticipated operational impact.

Questions 4: Are the estimated volumes, like the 4 non-critical requests a month and 4 emergency events a quarter, per building or across all 5 sites?

Answer: The estimated service volumes outlined in Section II.B.vi of the RFP apply collectively to all four primary DHS facilities and one satellite office covered under this solicitation, not to each facility individually.

The estimated volume is approximately four non-critical service requests per month and four emergency service requests per quarter across all five sites.

These quantities are provided for informational and proposal-planning purposes. Actual service volumes may vary based on equipment conditions, system performance, and operational needs throughout the contract term.

Question 5: Will the awarded vendor have remote access to the system?

Answer: Yes. Authorized contractor personnel may be provided with remote access to the LenelS2 NetBox environment through a City-approved Virtual Private Network (VPN) to support applicable maintenance, troubleshooting, configuration, and other authorized technical services.

Remote access will be subject to City access authorization procedures, applicable cybersecurity requirements, and coordination with DHS and Technology Services.

Access permissions will be established based on the contractor's authorized responsibilities and operational requirements.

Questions 6: Could you please specify the original equipment manufacturers (OEMs) for the Card Readers, Panic / Duress Devices, Servers and Supporting Infrastructure?

Answer: DHS currently operates LenelS2 NetBox as its primary electronic access control platform. The existing infrastructure includes LenelS2 access control equipment, legacy Interlogix card readers, and DMP alarm infrastructure supporting wireless panic/duress functionality. HID readers have also been identified for lifecycle replacement initiatives.

A complete manufacturer and model inventory for all card readers, panic/duress devices, servers, power supplies, and other supporting infrastructure has not been fully verified for purposes of this solicitation.

Specific equipment manufacturers, models, and configurations will be reviewed as applicable during system assessments and inventory verification.

In accordance with Section II.C of the RFP, the contractor must support existing functional City-owned equipment and ensure that newly installed or replacement equipment remains compatible with the existing environment unless DHS authorizes an alternative.

Question 7: Could you specify the details of the current Hardware and Software of the NetBox?

Answer: DHS currently operates LenelS2 NetBox software version 6.0.2 as its primary electronic access control platform.

The existing environment includes LenelS2 network nodes, access control application blades, card readers, electronic locking hardware, alarm inputs, panic/duress devices, power supplies, servers, software, licensing, and associated infrastructure.

As identified in the RFP, the system supports approximately 207 controlled access points and approximately 40 panic/duress devices across four primary DHS facilities and one satellite office.

Detailed server specifications, hardware model numbers, hardware revisions, firmware versions, and licensing configurations have not been fully verified for purposes of this solicitation. These details will be reviewed as applicable during system assessments and inventory verification.

The solicitation is intended to provide continued support, maintenance, expansion, and lifecycle services for the existing LenelS2 NetBox environment rather than require wholesale replacement of functional City-owned infrastructure.

Questions 8: Could you provide the Warranty details for the existing NetBox installation, as well as the readers and Duress Alarm buttons?

Answer: Warranty information and associated equipment documentation are maintained by DHS's current access control service provider, Stone Security.

Specific warranty terms, expiration dates, and equipment-level coverage for the existing NetBox installation, card readers, and panic/duress devices have not been fully verified for purposes of this solicitation.

Available warranty documentation will be reviewed as applicable to determine coverage for existing equipment and support appropriate maintenance, repair, or replacement activities.

Where a change in service provider occurs, any necessary transfer of warranty information and associated documentation will be coordinated in accordance with Section II.A.i of the RFP.

Question 9: Could you please clarify when proposers must submit the Certificate of Good Standing? Should proposers include it with their proposal or provide it at a later stage?

Answer: The Certificate of Good Standing from CO Secretary of State (SOS) is **not** a required document for the proposal submission and will not impact proposal scores. We recommend submission of this document if you are registered with SOS and can conduct business in the State of Colorado. If you are awarded, any failure to attain good standing with the SOS during the contract development stage may result in nullification of your award.

Question 10: What Video Door Entry system is currently being used onsite?

Answer: DHS does not currently utilize a video door entry system.

DHS operates LenelS2 NetBox as its primary access control platform and Milestone as its separate video management system.

Any future implementation or integration of video door entry technology would be evaluated based on DHS operational requirements, technical compatibility, and appropriate authorization under the applicable provisions of the RFP.

Question 11: Are the duress alarms connected to just the access control system or an intrusion detection system as well? If it is attached to an intrusion system what system is that?

Answer: DHS's existing wireless panic/duress devices operate through the DMP alarm infrastructure and generate corresponding alarm events within LenelS2 NetBox.

DHS utilizes DMP keypads and Virtual Keypad functionality as part of its existing alarm infrastructure. Panic/duress activations are monitored through LenelS2 NetBox by DHS Security Operations Center personnel on a continuous basis.

Section II.A.ii of the RFP includes alarm systems and intrusion detection systems within the maintenance and support scope. The contractor will be expected to support applicable maintenance, troubleshooting, and authorized repairs involving these systems and their existing interfaces.

Wholesale replacement of the existing DMP infrastructure is not required under this solicitation.

Question 12: Does maintaining door hardware include maintaining and servicing ADA operators or just ADA functionality/button?

Answer: The contractor's responsibilities include maintenance and support of electronic locking hardware and access control-related functionality, including applicable ADA activation devices, interfaces, and coordination between the access control system and automatic door operators.

Maintenance and repair of the automatic door operator itself, including its mechanical components, motors, and other operator-specific equipment, are generally coordinated separately through DHS Facilities, General Services, and Safety, as applicable, using the appropriate door service contractor.

The access control contractor will be expected to coordinate with DHS and other applicable service providers when work affects the interface between electronic locking hardware and automatic door operation.

All applicable work must maintain compliance with accessibility, building, fire, and life-safety requirements. Any additional work beyond the existing access control-related scope would require appropriate DHS review and authorization.