DENVER HUMAN SERVICES

QUESTIONS & ANSWERS
Public Information Session - November 3, 2026

On-Call Security Access Control Services

REQUEST FOR PROPOSALS

RFA NO. FS/CA/FSS_AccessControl_2026

*Note: The following questions and answers, received verbally during the in-person session, have been slightly adjusted in order to ensure context and clarity.

Question 1: What are the existing wall insulation, construction, and mounting conditions for access control equipment enclosures?
Answer: Specific wall insulation, construction, and mounting conditions have not been fully verified across all DHS facilities. Generally, DHS expects access control equipment to be securely mounted, properly ventilated, and installed in suitable environmental conditions in accordance with applicable building and fire codes, manufacturer specifications, and safety requirements. For any authorized installation, relocation, or modification, the contractor will be responsible for evaluating applicable site conditions, including mounting surfaces, structural support, ventilation, and equipment operating requirements, in coordination with DHS Facilities as needed.
Question 2: Is existing access control wiring documentation available, or will field verification be required?
Answer: DHS's current access control service provider maintains documentation associated with the existing system, including wiring information. Available documentation will be reviewed and validated as applicable to the services being performed. Field verification may be necessary to confirm existing conditions, address documentation discrepancies, or support authorized maintenance and project work. Where a change in service provider occurs, any necessary documentation handoff and coordination will be conducted in accordance with Section II.A.i of the RFP to ensure continuity of operations.
Question 3a: Is Milestone integration required, and is Milestone certification mandatory?
Answer: DHS currently operates LenelS2 NetBox as its primary access control platform and maintains a separate Milestone video management system. The primary scope of this solicitation is maintenance, support, troubleshooting, lifecycle replacement, and authorized expansion of the existing LenelS2 NetBox environment. Integration with Milestone or other security technologies may be considered for future projects based on DHS operational needs and appropriate authorization.

Milestone certification is not a mandatory minimum qualification. Section II.E of the RFP identifies Milestone Systems partner status and/or Milestone-certified technical personnel as preferred qualifications.

Questions 4: What credential formats and reader technologies are currently used within DHS's access control environment?

Answer: DHS's existing LenelS2 NetBox environment includes 26-bit, 36-bit, and 37-bit Wiegand credential format configurations, with confirmed active use of the 37-bit Wiegand format within the DHS environment. The 36-bit configuration is identified as a legacy format.

Not all configured credential formats are necessarily in active use across DHS facilities. Credential bit length should not be interpreted as an indication of encryption or reader communication security.

Specific reader models and applicable credential requirements will be verified as necessary. In accordance with Section II.C of the RFP, new or replacement equipment must remain compatible with the existing access control infrastructure unless DHS authorizes an alternative.

Question 5: Are all existing access control equipment operational, or are there known deficiencies?

Answer: DHS maintains an operational LenelS2 NetBox access control environment across its facilities. However, portions of the existing infrastructure include aging equipment and components that may require maintenance, repair, troubleshooting, or lifecycle replacement.

The awarded contractor will be expected to assess existing equipment conditions, identify deficiencies, and provide recommendations for corrective actions and future improvements.

DHS intends to continue utilizing functional City-owned equipment. Any proposed replacement must be supported by documented technical justification and approved by DHS in accordance with Section II.C of the RFP.

Questions 6: How many access control readers or controlled access points are currently installed?

Answer: The RFP identifies approximately 207 controlled access points across four primary DHS facilities and one satellite office.

This figure represents controlled access points rather than a verified count of individual physical badge readers. Reader configurations may differ depending on the access point, including locations with multiple readers or other electronically controlled access arrangements.

Actual equipment quantities and configurations will be verified as applicable during system assessments and inventory reviews. The quantities provided are for informational and proposal-planning purposes and may change during the contract term.

Question 7: Does DHS utilize different types of electronic locking hardware, including magnetic locks?

Answer: Yes. DHS utilizes different types of electronic locking hardware, including electromagnetic locks and other electronically controlled locking devices.

Specific hardware configurations vary depending on the access point and its operational requirements. The contractor will be expected to maintain and support applicable existing equipment and identify any necessary repairs or replacements.

All work must comply with applicable City and County of Denver building and fire codes, emergency egress requirements, manufacturer specifications, and relevant life-safety standards.

Questions 8: Are electronic locks and associated door hardware included in the contract scope?

Answer: Yes. Section II.A.ii of the RFP includes card readers, door locks, panic buttons, alarm systems, and intrusion detection systems within the maintenance and support scope. This includes applicable troubleshooting, maintenance, repair, and authorized replacement of electronic locking hardware and associated access control components.

Any non-recurring equipment replacement, installation, or modification must receive appropriate authorization in accordance with Section II.B.viii. Work involving electronic locking or egress hardware must maintain compliance with applicable building, fire, and life-safety requirements.

Question 9: Does DHS currently utilize glass-break detection and panic or duress devices?

Answer: Yes. DHS currently utilizes glass-break detection devices and wireless panic/duress devices as part of its physical security infrastructure. Glass-break alarm events are monitored through LenelS2 NetBox. Wireless panic/duress devices operate through the existing DMP alarm infrastructure and generate corresponding alarm events within NetBox.

The RFP identifies approximately 40 panic/duress devices. Applicable maintenance, troubleshooting, repair, and authorized replacement activities are included within the scope of services.

Question 10: Does the contract include support for the existing DMP alarm system?

Answer: DHS currently utilizes DMP alarm infrastructure, including DMP keypads and Virtual Keypad functionality, in conjunction with portions of its physical security systems.

Section II.A.ii of the RFP includes alarm and intrusion detection systems within the maintenance and support scope. Accordingly, the awarded contractor may be required to provide or coordinate technical support for DMP-related components associated with DHS access control, alarm, and duress functionality.

Any equipment modifications, replacements, or expansions will be evaluated and authorized based on DHS operational requirements. Wholesale replacement of the existing DMP infrastructure is not required under this solicitation.

Question 11: Are panic and duress alarms monitored continuously by DHS security personnel?

Answer: Yes. DHS maintains a Security Operations Center (SOC) staffed 24 hours per day, seven days per week. Wireless panic/duress activations generate corresponding alarm events within LenelS2 NetBox, where SOC personnel monitor activity and coordinate security responses in accordance with established procedures.
The awarded contractor will be responsible for applicable technical maintenance, troubleshooting, and support to help ensure continued system reliability and functionality.

DENVER
HUMAN SERVICES

Question 12: Does DHS have lockdown functionality integrated with flashing lights, audible alerts, or other notification systems?

Answer: DHS currently utilizes lockdown functionality through the LenelS2 NetBox access control software. Lockdown actions are initiated through the software interface rather than a separate dedicated physical lockdown button.

The existing lockdown functionality is not currently integrated with building-wide flashing lights, audible alerts, or other mass-notification equipment. Any future integration or enhancement would be evaluated based on DHS operational needs and would require appropriate technical review and authorization.

Question 13: Is the existing lockdown functionality integrated with a building paging or public-address system?

Answer: No. DHS's existing lockdown functionality operates through the LenelS2 NetBox access control platform and is not currently integrated with a building paging or public-address system.

Future integration with paging, public-address, or other emergency notification technologies may be considered based on operational needs. Such work would require DHS authorization and compliance with applicable contract provisions.

Question 14: Are the existing panic and duress devices wired or wireless?

Answer: DHS's existing panic/duress devices are wireless and operate through the DMP alarm infrastructure, generating corresponding alarm events within LenelS2 NetBox for monitoring and response. The awarded contractor will be expected to support applicable maintenance, troubleshooting, and authorized replacement of these devices and associated components.

Any proposed modifications must maintain compatibility with the existing security infrastructure and receive DHS approval before implementation.

Question 15: What are the required service hours and emergency response expectations?

Answer: Routine maintenance, inspections, and scheduled project activities will be coordinated with DHS based on operational needs and facility schedules.

For work that may temporarily interrupt access control operations, including doors, access control nodes, or other security equipment, DHS generally prefers scheduling before or after normal business hours when practicable to minimize disruptions.

Work may also be performed during business hours when DHS determines that adequate physical security coverage and operational safeguards are available. Scheduling will be coordinated in advance based on the nature and potential impact of the work.

Critical issues may include major access control outages, failures affecting multiple controlled access points, inability to secure a facility or critical area, critical panic/duress failures, or other conditions designated by DHS as presenting an immediate security or operational risk.