PROJECT MANUAL

WESTMINSTER PUBLIC SCHOOLS – 2026 BOND PROJECTS
TENNYSON KNOLLS PREPARATORY SCHOOL RENOVATIONS

Westminster, CO

FINAL
SEPTEMBER 25, 2026

ARCHITECT
DAO Architecture
7230 Meade St
Westminster, CO 80030
720-273-0431
www.daoarch.com

WESTMINSTER PUBLIC SCHOOLS – 2026 Bond Projects
Tennyson Knolls Preparatory School Renovations
Arvada, CO

PROJECT MANUAL

TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

Document 000010 Cover
Document 000110 Table of Contents

CONTRACTING REQUIREMENTS

By Owner

SPECIFICATIONS

DIVISION 01 - GENERAL REQUIREMENTS

Section 011000 General Requirements
Section 012200 Unit Prices
Section 014330 Mock-Ups
Section 016200 Substitution Request Form

DIVISION 02 - EXISTING CONDITIONS

Section 024100 Demolition

DIVISION 03 - CONCRETE

Not Used

DIVISION 04 - MASONRY

Section 040120 Masonry Restoration and Cleaning
Section 042000 Unit Masonry

DIVISION 05 - METALS

Not Used

DIVISION 06 - WOOD, PLASTICS AND COMPOSITES

Section 061000 Rough Carpentry
Section 064020 Interior Architectural Woodwork

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

Section 078410 Penetration Firestopping
Section 078440 Fire-Resistive Joint Systems
Section 079200 Joint Sealants

DIVISION 08 - OPENINGS

Section 083110 Access Doors and Frames

DIVISION 09 - FINISHES

Section 099000 Painting and Coating
Section 099805 Masonry Staining

DIVISIONS 10 - 11

Not Used

DIVISION 12 - FURNISHINGS

Not Used

DIVISION 13 - SPECIAL CONSTRUCTION

Not Used

DIVISION 21 - FIRE SUPPRESSION

Section 210000 Fire Protection

DIVISION 22 - PLUMBING

Section 220000 Plumbing

DIVISION 23 - HEATING VENTILATING AND AIR CONDITIONING

Section 230000 Heating, Ventilating and Air-Conditioning

DIVISION 26 - ELECTRICAL

Section 260000 Electrical

DIVISION 27 - COMMUNICATIONS

Section 270000 Communications

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

Section 280000 Electronic Safety and Security

END OF TABLE OF CONTENTS

SECTION 011000

GENERAL REQUIREMENTS

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS, which are hereby made a part of this Section of the Specifications.

1.2 PROJECT REQUIREMENTS

A. Project Identification: Westminster Public Schools 2026 Bond Projects.

B. Project Requirements for Temporary Utilities and Facilities:

1. Utility Costs: The Contractor shall meter and pay for cost of utility services consumed, including electricity, water, gas and temporary heat.
2. Temporary Offices: A separate field office for the Architect and the Owner's Representative is not required.
3. Toilet Facilities: The Contractor shall provide and maintain temporary toilets outside the building.

C. Permits and Fees: Apply for, obtain, and pay for permits, fees, and utility company backcharges required to perform the work. Submit copies to Architect.

D. Codes: Comply with applicable codes and regulations of authorities having jurisdiction. Submit copies of inspection reports, notices and similar communications to Architect.

E. Dimensions: Verify dimensions indicated on drawings with field dimensions before fabrication or ordering of materials. Do not scale drawings.

F. Existing Conditions: Notify Architect of existing conditions differing from those indicated on the drawings.

G. Contractor’s Conduct on Premises: The Contractor and their employees shall behave in a respectful, courteous and safe manner. Abusive, harassing, and lewd behavior is prohibited. Music playing is prohibited. Alcohol, tobacco, and drug use is prohibited.

1.3 SPECIFICATION INFORMATION

A. These specifications are a specialized form of technical writing edited from master specifications and contain deviations from traditional writing formats. Capitalization, underlining and bold print is only used to assist reader in finding information and no other meaning is implied.

B. Except where specifically indicated otherwise, the subject of all imperative statements is the Contractor.

C. Sections are generally numbered in conformance with Construction Specifications Institute Masterformat System. Numbering sequence is not consecutive. Refer to the Table of Contents for names and numbers of sections included in this Project.

D. Pages are numbered separately for each section. Each section is noted with "End of Section" to indicate the last page of a section.

1.4 DEFINITIONS

A. General: Basic Contract definitions are included in the Conditions of the Contract.

B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.

C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "approved," "required," and "permitted" have the same meaning as "directed."

D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."

E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.

F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.

G. "Install": Operations at Project site including unloading, temporarily storing, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.

H. "Provide": Furnish and install, complete and ready for the intended use.

I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.5 INDUSTRY STANDARDS

A. Referenced standards are part of the Contract Documents and have the same force and effect as if bound with these specifications.

B. Except where specifically indicated otherwise, comply with the current standard in effect as of the date of the Owner/Contractor Agreement. Obtain copies of industry standards directly from publisher.

C. The titles of industry standard organizations are commonly abbreviated; full titles may be found in Encyclopedia of Associations or consult Architect.

1.6 CODES AND REGULATIONS

A. Comply with all applicable codes, ordinances, regulations and requirements of authorities having jurisdiction.

B. Submit copies of all permits, licenses, certifications, inspection reports, releases, notices, judgments, and communications from authorities having jurisdiction to the Architect.

1.7 PROGRESS SCHEDULE

A. Provide comprehensive bar chart schedule showing all major and critical minor portions of the work, sequence of work and duration of each activity. Update and reissue regularly, but not less than monthly.

1.8 SCHEDULE OF VALUES

A. Prepare Schedule of Values to coordinate with application for payment breakdown. Submit at least 10 days before first payment application. Update and reissue regularly, but not less than monthly.

1.9 PAYMENT REQUESTS

A. Provide three copies or digital distribution of each request on completely filled out copies of AIA G702 and continuation sheet G703. Substantiate requests with complete documentation; include change orders to date. Provide partial lien waivers for work in progress and full lien waivers for completed work.

B. As-Constructed Record Drawing Certification: Certify as a part of each application for payment that the project as-constructed record documents are current at the time of application is submitted. The Contractor shall require such drawings to be current as a condition of approving any payment to the trade Contractor and Subcontractor.

C. Before first payment application, provide the following:

1. List of subcontractors, suppliers and fabricators.
2. Schedule of values.
3. Progress schedule.
4. Submittal schedule keyed to project schedule.
5. List of Contractor's key project personnel.
6. Copies of permits and other communications from authorities.
7. Contractor's certificate of insurance.
8. Performance and payment bonds if required.
9. Unit price schedule.

D. Before final payment application, provide and complete the following:

1. Complete closeout requirements.
2. Complete punch list items.
3. Settle all claims.
4. Transmit record documents to Architect. Include statement that Architect's Supplemental Instructions, Change Orders, Construction Change Directives and minor changes in the work have been incorporated in the as-constructed record drawings.
5. Prove that all taxes, fees and similar obligations have been paid.
6. Remove temporary facilities and surplus materials.
7. Change lock cylinders or cores.
8. Clean the work.
9. Submit consent of surety, if any, for final payment.
10. Complete required LEED documentation.

1.10 PROCEDURES AND CONTROLS

A. Project Meetings: Arrange for and attend meetings with the Architect and such other persons as the Architect requests to have present. The Contractor shall be represented by a principal, project manager, general superintendent or other authorized main office representative, as well as by the Contractor's field superintendent. An authorized representative of any subcontractor or sub-subcontractor shall attend such meetings if the representative's presence is requested by the Architect. Such representatives shall be empowered to make binding commitments on all matters to be discussed at such meetings, including costs, payments, change orders, time schedules and manpower. Any notices required under the Contract may be served on such representatives. Written reports of meeting minutes shall be prepared by the Contractor and distributed by the Contractor to attendees, the Architect, and Owner within three business days.

1. Pre-Construction Conference: Attendance by Architect, Contractor, major subcontractors. Agenda shall include: Quality of workmanship, coordination, interpretations, job schedule, submittals, approvals, requisition procedures, testing, protection of construction, indoor air quality, and construction waste management.
2. Exterior Envelope Meeting: Attendance by Architect, Contractor, major subcontractors. Agenda shall include as applicable: Review of exterior wall details, wall construction, sample panel preparation, cleaning, control and expansion joints, cold weather procedures.
3. Roofing/Flashings Meeting: Attendance by Architect, Contractor, roofing subcontractor, and representative of roofing manufacturer. Agenda shall include as applicable: Preparation of roof decks, flashing and blocking details, roofing procedures and inspections, bonds and guarantees, weather conditions during roofing, protection of roof membrane during construction.
4. Interior Finishes Meeting: Attendance by Architect, Contractor, major subcontractors. Agenda shall include as applicable: Quality of workmanship, environmental conditions for

application of finishes, drywall details, millwork details, condition of surfaces to receive finishes, tile work, painting work, samples and test areas and approvals, coordination with mechanical and electrical interfaces and penetrations, indoor air quality.

5. Progress Meetings: Hold regularly before preparation of payment requests and additional meetings as requested by the Architect. Attendance by Architect, Contractor, and others as determined by Contractor. Agenda shall include work in progress and payment requests.
6. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction, as specified. Preinstallation Conferences may be part of Progress Meeting agenda. Attendance by Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow. Agenda shall include a review of progress of other construction activities and preparations for the particular activity under consideration.

B. Emergency Contacts: Furnish the Owner and Architect, in writing, the names and telephone numbers of individuals to be contacted in the event of an out-of-hours emergency at the building site. Post a similar list readily visible from the outside of the field office or a location acceptable to the Architect.

C. Layout: Layout work and be responsible for all lines, elevations, and measurements of the building, grading, utilities and other work executed under the contract. Retain a registered professional engineer or registered land surveyor, acceptable to the Architect, to initially establish exterior lines and required elevations of all buildings and structures to be erected on the site. The registered professional engineer or registered land surveyor shall certify the actual location of the constructed facilities in relation to property lines, building lines, easements, set-backs, and other restrictive boundaries.

D. Field Measurements: Verify measurements at the building prior to ordering materials or commencing work. No extra charge or compensation will be allowed because of differences between actual dimensions and measurements indicated on the Drawings. Differences which may be found shall be submitted to the Architect for decision before proceeding with the work.

E. Field Measurements for Fixed Equipment: Dimensions for fixed equipment to be supplied under this Contract or separate contracts shall be determined by field measurements taken jointly by the Contractor and the equipment supplier involved. A record of the field measurements shall be kept until time of substantial completion of the project, or until the equipment has been fully installed and accepted by the Owner, whichever is later. Responsibility for fixed equipment fabricated accurately to field measurements for proper fit and operation shall be that of the Contractor. Contractor shall pay all costs involved in correcting any misfitting fixed equipment as fabricated.

F. Project Limit Line: The boundaries of the site do not limit the responsibility of the Contractor to perform the work in its entirety. Make utility connections as indicated.

G. Matching: Where matching is indicated, the Architect shall be the sole and final judge of what is an acceptable match. Mockups and sample submissions are required.

H. Observation: Notify the Architect and authorities having jurisdiction at least thirty-six hours in advance of concealing any work.

I. Utilities: Prior to interrupting utilities, services or facilities, notify the utility owner and the Owner and obtain their written approval a minimum 48 hours in advance.

J. Furnishings, Fixtures, and Equipment: Cooperate and permit the Owner to install their furnishings and equipment during the progress of the work. Owner's installation of furnishings or equipment does not signify Owner's acceptance of any portion of the work.

K. Clean-Up: Frequently clean-up all waste, remove from site regularly, and legally dispose of off-site.

L. Installer's Acceptance of Conditions: All installers shall inspect substrates and conditions under which work is to be executed and shall report in writing to the Contractor all conditions detrimental to the proper execution and completion of the work. Do not proceed with work until unsatisfactory conditions are corrected. Beginning work means installer accepts previous work and conditions.

M. Coordination: The Contractor shall be fully responsible for coordinating all trades, coordinating construction sequences and schedules, and coordinating the actual installed location and interface of all work.

1. Prior to beginning mechanical, electrical and fire protection work, the Contractor shall prepare coordination drawings showing the exact alignment, physical location and configuration of the mechanical, electrical and fire protection installations and demonstrating to the Contractor's satisfaction that the installations will clear all obstructions, permit proper clearances for the Work of other trades, and present an orderly appearance where exposed. The Contractor shall be solely liable and responsible for any costs and delays resulting from the Contractor's failure to prepare such coordination drawings or from the negligent preparation of such coordination drawings.
2. Exact locations and groupings of mechanical, electrical and fire protection fixtures, switches, heads and outlets shall be obtained from the Architect before the Work is roughed in. Work installed without such information from the Architect shall be relocated at the Contractor's expense if the Architect so requests.

N. Request For Interpretation (RFIs):

1. Procedure: Immediately on discovery of the need for interpretation of the Contract Documents, and if not possible to request interpretation at Project meeting, prepare and submit an RFI in the form specified.
   a. RFIs shall originate with Contractor. RFIs submitted by entities other than Contractor will be returned with no response.
2. Content of the RFI: Include a detailed, legible description of item needing interpretation.
3. Architect's Action: Architect will review each RFI, determine action required, and return it. Allow three working days for Architect's response for each RFI. RFIs received after 1:00 p.m. will be considered as received the following working day.
4. The following RFIs will be returned without action:
   a. Requests for approval of submittals.
   b. Requests for approval of substitutions.
   c. Requests for coordination information already indicated in the Contract Documents.
   d. Requests for adjustments in the Contract Time or the Contract Sum.
   e. Requests for interpretation of Architect's actions on submittals.
   f. Incomplete RFIs or RFIs with numerous errors.

O. Existing Articles of Unusual Value: If during demolition, excavation, or disposal work articles of unusual value or of historical or archaeological significance are encountered, the ownership of such articles is retained by the Owner, and information regarding their discovery shall be immediately furnished to the Architect. If the nature of the article is such that work cannot proceed without danger of damage, work in the area shall be immediately discontinued until the Architect has determined the proper procedure to be followed. Delays in time thereby shall be a condition for which the time of the Contract may be extended. Costs incurred after discovery in the salvaging of such articles shall be borne by the Owner.

1.11 SUBMITTALS

A. Required Submittals: Submit shop drawings, product data, initial selection samples, verification samples, calculations, coordination drawings, schedules, and all other submittals as specified in individual specification sections.

B. Submittal Schedule: Within 30 days after award of contract and before first application for payment, prepare list of submittals in chronological sequence showing all submittals and proposed date first due at Architect's office and proposed date due to be returned to Contractor. Note relevant specification section number.

C. Contractor's Preparation of Submittals: Modify and customize all submittals to show interface with adjacent work and attachment to building. Identify each submittal with name of project, date, Contractor's name, subcontractor's name, manufacturer's name, submittal name, relevant specification section numbers, and Submittal Schedule reference number. Stamp and sign each submittal to show the Contractor's review and approval of each submittal before delivery to Architect's office; unstamped and unsigned submittals will be returned without action by the Architect. Leave 4" x 6" open space for Architect's "action" stamp.

1. Electronic Submittals: Provide a copy of all submittals in electronic format to the Architect. Architect will return a file of reviewed submittal in electronic format to the Contractor for distribution to subcontractors, suppliers, fabricators, governing authorities and others as necessary for proper performance of the Work. Unless otherwise amenable to the Architect, additional hard copies of submittals will not be reviewed by the Architect (or Consultant) and will not be returned to the Contractor.
2. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
3. Name file with submittal number or other unique identifier, including revision identifier.
4. Provide means for insertion to permanently record Contractor's review and approval markings and action taken by Architect and Construction Manager.
5. Transmittal Form for Electronic Submittals: Use electronic form acceptable to Architect.

D. Product Data: Provide manufacturer's preprinted literature including, without limitation, manufacturer's standard printed description of product, materials and construction, recommendations for application and use, certification of compliance with standards, instructions for installation, and special coordination requirements. Collect data into one submittal for each unit of work or system; mark each copy to show which choices and options are applicable to project.

1. Installer Copy: Verify that the Installer has a current copy of the relevant product data, including installation instructions, before permitting installation to begin.

E. Shop Drawings: Provide accurately prepared, large scale and detailed shop drawings prepared specifically for this project. Show adjacent conditions and related work. Show accurate field dimensions and clearly note field conditions. Identify materials and products in the work shown. Note special coordination required.

1. After Architect's action, follow specified distribution procedure.

F. Samples: Provide units identical with final materials and products to be installed in the work. Where indicated, prepare samples to match Architect's sample. Label each sample with description, source, generic name or manufacturer's name and model number. Architect will review samples for confirmation of visual design intent, color, pattern, texture and type only; Architect will not test samples for compliance with other Contract requirements which shall remain the exclusive responsibility of the Contractor.

1. Initial Selection Samples Submittal Quantities: For initial selection purposes, submit 1 set of samples showing the complete range of colors and finishes available.
2. Verification Samples Submittal Quantities: For verification of an initial selection, submit 3 sets of samples; one set will be returned to Contractor to be maintained at project site for quality control comparisons.

G. Timing of Submittals: Submit submittals in a timely fashion to allow at least 10 business days for each office's review and handling. This means that submittals which have to be reviewed by the Architect and one of their consultants require at least 20 business days for review and handling. Add ten business days for each additional consultant who must review a submission.

H. Architect's Action on Submittals: Architect will review submittals, stamp with "action stamp", mark action, and return to Contractor. Architect will review submittals only for conformance with the design concept of the project. The Contractor is responsible for confirming compliance with other Contract requirements, including without limitation, performance requirements, field dimensions, fabrication methods, means, methods, techniques, sequences and procedures of construction, coordination with other work. The Architect's review and approval of submittals shall be held to the limitations stated in the Owner/Architect Agreement and the Conditions of the Contract. In no case shall approval or acceptance by the Architect be interpreted as a release of Contractor of their responsibilities to fulfill all of the requirements of the Contract Documents.

1. Required Resubmittal: Unless submittal is noted "reviewed" or "reviewed except as noted, resubmission not required," make corrections or changes to original and resubmit to Architect.
2. Distribution: When submittal is noted "reviewed" or "reviewed as noted, resubmittal not required," make prints or copies and distribute to Owner, Subcontractors involved, and to all other parties requiring information from the submittal for performance or coordination of related work.

1.12 WARRANTIES

A. Warranties Required: Refer to individual trade sections for specific product warranty requirements.

B. Procurement: Where a warranty is required, do not purchase or subcontract for materials or work until it has been determined that parties required to countersign warranties are willing to do so.

C. Warranty Forms: Submit written warranty to Owner through Architect for approval prior to execution. Furnish two copies of executed warranty to Owner for their records; furnish two additional conformed copies where required for maintenance manual.

D. Work Covered: Contractor shall remove and replace other work of project which has been damaged as a result of failure of warranteed work or equipment, or which must be removed and replaced to provide access to work under warranty. Unless otherwise specified, warranty shall cover full cost of replacement or repair, and shall not be pro-rated on basis of useful service life.

E. Warranty Extensions: Work repaired or replaced under warranty shall be warranted until the original warranty expiration date or for ninety days whichever is later in time.

F. Warranty Effective Starting Date: Guarantee period for all work, material and equipment shall begin on the date of substantial completion of the Project, not when subcontractor has completed their work nor when equipment is turned on. In addition to the one year guarantees for the entire work covered by these Contract Documents, refer to the various sections of the specifications for extended guarantee or maintenance requirements for various material and equipment.

G. Warranties are Irrevocable: Warranties issued to the Owner are irrevocable.

1. Non-Payment: If warrantor refuses to issue warranty, or attempts to revoke warranty due to lack of payment by any party other than the Owner, the Contractor shall resolve the payment conflict, and cause the warranty to be issued or reinstated.
2. Incomplete or incorrect Installation: If warrantor refuses to issue warranty, or attempts to revoke warranty due to improper installation or other deficiency, the Contractor shall correct the deficiency and cause the warranty to be issued or reinstated.

H. Transferable Warranties: All warranties shall permit Owner to transfer or assign warranties to future owners or other assignors at no additional cost to the Owner for the full warranty period.

1.13 CUTTING AND PATCHING

A. Limitations: Do not cut and patch any work in a manner that would result in a failure of the work to perform as intended, decreased energy performance, increased maintenance, decreased operational life, or decreased safety.

1. Structural Work: Do not cut structural work or bearing walls without written approval from Architect. Where cutting and patching of structural work is necessary and approved by Architect, perform work in a manner which will not diminish structural capacity nor increase deflection of member. Provide temporary shoring and bracing as necessary. Ensure the safety of people and property at all times.

B. Cutting and Patching Materials: Use materials identical to materials to be cut and patched. If identical materials are not available or cannot be used, use materials that match existing materials to the greatest extent possible. Provide finished work that will result in equal to or better than existing performance characteristics.

C. Inspection: Before cutting and patching, examine surfaces and conditions under which work is to be performed and correct unsafe and unsatisfactory conditions prior to proceeding.

D. Protection: Protect adjacent work from damage. Protect the work from adverse conditions.

E. Cutting: Cut work using methods least likely to damage adjoining work. Use tools designed for sawing or grinding, not hammering or chopping. Use saws or drills to ensure neat, accurately formed holes to sizes required with minimum disturbance to adjacent work. Temporarily cover openings; maintain weathertightness and safety.

1. Utilities: Locate utilities before cutting. Provide temporary utilities as needed. Cap, valve, or plug and seal ends of abandoned utilities to prevent entrance of moisture or other foreign matter.

F. Patching: Patch with seams and joints which are durable and not visible. Comply with specified tolerances for similar new work; create true even planes with uniform continuous appearance. Restore finishes of patched areas and, if necessary, extend finish restoration onto adjoining unpatched area to eliminate evidence of patching and refinishing. Repaint entire assemblies, not just patched area. Remove and replace work which has been cut and patched in a visually unsatisfactory manner as determined by the Architect.

G. Qualifications: Retain experienced and specialized firms, original installers if possible, to perform cutting and patching. Workmen shall be skilled in type of cutting and patching required.

1.14 TEMPORARY FACILITIES AND UTILITIES

A. Scope of Temporary Work: This article is not intended to limit the scope of temporary work required under the Contract. Provide all temporary facilities and utilities needed.

B. Permits and Fees: Obtain and pay for all permits, fees and charges related to temporary work.

C. Codes and Authorities Having Jurisdiction for Temporary Facilities and Utilities: Comply with all requirements of authorities having jurisdiction, codes, utility companies, OSHA, and industry standards including, but not limited to the following:

1. NFPA 241, Standard for Safeguarding Construction, Alteration, and Demolition Operations.
2. ANSI-A10 Series, Safety Requirements for Construction and Demolition.
3. NECA National Joint Guideline NJG-6, Temporary Job Utilities and Services.
4. Electrical Service: NEMA, NECA, and UL.

D. Field Offices: Provide Contractor's field offices as needed. Keep current copies of all Contract Documents and project paperwork neatly on file at jobsite. Permit Architect's unrestricted use of Contractor's field office facilities including copiers, telephones, plan tables, and other equipment. Furnish, maintain, and pay for light, power, phone, fax, and other field office services.

E. Shops and Sheds: At Contractor's option, provide shops and sheds for Contractor's use as needed. Locate shops and sheds where acceptable to Owner and authorities having jurisdiction. Prior to completion of construction, temporary storage facilities and surplus stored materials shall be removed from the site.

F. Weather Protection: It is the intent of these Specifications to require that the Contractor shall provide temporary enclosures and heat to permit construction work to be carried on during the

months of November through March. Under no circumstances shall the Contractor suspend any work during the months of November through March because of their reluctance to provide and pay for temporary weather protection. These Specifications are not to be construed as requiring enclosures or heat for operations that are not economically feasible to protect in the judgment of the Architect. Included in the preceding category, without limitation, are such items as site work, excavation, steel erection, erection of certain "exterior" wall panels, roofing, and similar operations.

1. 'Weather Protection' shall mean the temporary protection of that work adversely affected by moisture, wind, and cold, by covering, enclosing and/or heating. This protection shall provide adequate working areas during the months of November through March consistent with the approved construction schedule to permit the continuous progress of all work necessary to maintain an orderly and efficient sequence of construction operations. The Contractor shall furnish and install all "weather protection" material and be responsible for all costs, including heating required to maintain a minimum temperature of 55 degrees F. at the working surface. This provision does not supersede any specific requirements for methods of construction, curing of materials or the applicable general conditions set forth in the Contract with added regard to performance obligations of the Contractor.
2. Within 30 calendar days after his award of contract, the Contractor shall submit in writing to the Architect for approval, his proposed methods for "Weather Protection."
3. Installation of weather protection and heating devices shall comply with all safety regulations including provisions for adequate ventilation and fire protection devices. Heating devices which may cause damage to finish surfaces shall not be used.

G. Heating During Construction: Within 30 calendar days after the commencement of work under this Contract, the Contractor shall submit in writing to the Architect for approval, the Contractor's method and time schedule for heating during construction which shall concur with his general progress schedule.

1. After the building or portion thereof is completely enclosed by either permanent construction or substantial temporary materials having a comparable resistance as the specified permanent construction, The Contractor shall pay and provide heat therein of not less than 55 degrees F., nor more than 75 degrees F., which shall be continuously maintained in the enclosed area to the extent necessary to properly progress and protect the work until the project is accepted.
2. The Contractor shall furnish and install one accurate recording Fahrenheit thermometer at a place acceptable to the Architect, and one additional accurate thermometer for every 2,000 square feet of floor space, located as directed by the Architect in order to determine if the specified temperatures are maintained. The Contractor or his authorized agent shall furnish daily to the Architect a signed statement of temperatures recorded every three hours.
3. The Contractor, with the approval of the Architect, may use the permanent heating system as specified for the project once it has been tested, flushed out and chemically treated, thoroughly cleaned of all construction dust and dirt, and is ready to operate. The Contractor shall pay all energy costs for heating during construction and provide meters if required. The Contractor and the HVAC and/or Electrical subcontractor shall coordinate their work so that the permanent heating system for the building will be available and ready to provide heat as soon as the building is closed in. In case the Contract includes more than one building, the heating shall be provided for each building in accordance with the above provision. The guarantee period for equipment shall not start until the equipment is turned over to the Owner for their use. Do not invalidate existing warranty by any action or failure to act. Clean and change air filters frequently to prevent construction dust and debris from contaminating system.
4. Operating labor shall be provided for continuous direct attendance, for frequent inspection of the system, emergency repairs, and keeping of temperature records. Continuous direct attendance shall mean direct attendance for twenty-four hours each day, seven days per

week, Saturdays, Sundays and holidays included, throughout the progress of the work.

5. It shall be the sole responsibility of the Contractor to arrange for and pay the HVAC and/or Electrical subcontractor to operate and to put in first-class condition all portions of the permanent heating system used for heating during construction.
6. If the system is electric heat, the foregoing requirements shall equally apply to all the comparable components thereof.
7. The installation and operation of heating devices shall comply with all safety regulations including provisions for adequate ventilation and fire protection. Heating devices which may cause damage to finish surfaces shall not be used.

H. Pumping and Drainage: Protect excavations, trenches, buildings and materials from rain water, ground water, backup or leakage of sewers, drains and other piping, and from water of any other origin. Promptly remove any accumulation of water. Provide and operate all pumps, piping and other equipment necessary for pumping, drainage and protection from water.

I. Equipment and Tools: Provide all equipment including, but not limited to, hoists, lifts, scaffolding, machines, tools and the like, as needed for execution of the work. Provide safe access to all parts of the work.

J. Temporary Enclosures: Provide temporary enclosures to maintain proper temperatures and to prevent weather damage. Always maintain legal means of egress.

K. Snow and Ice: Remove all snow and ice which interferes with work or safety.

L. Streets, Walks and Grounds: Maintain public and private roads and walks clear of debris caused by construction operations. Repair all damage caused to streets, drives, curbs, sidewalks, fences, poles and similar items where disturbed or damaged by building construction and leave them in as good condition after completion of the work as before operations started.

M. Protection: Protect nearby property and the public from construction activities. Provide and maintain barricades, warning signs and lights, railings, walkways and similar items. Immediately repair damaged property to its condition before being damaged.

N. Public Services: Provide temporary public services such as, street lighting, night lighting, sidewalks, covered passages, signs, signals and the like, as requested by authorities having jurisdiction.

O. Construction Fencing: Provide construction fencing and barriers as applicable to the project and as required by code to protect personnel, the public, and to control access.

P. Security: Secure site against unauthorized entry at all times. Provide secure, locked temporary enclosures. Protect the work at all times. Provide watchman service, if necessary, to protect the work.

Q. Signs: Erect project identification signs in compliance with details to be provided by Architect. Signs shall be minimum 4' x 8' exterior grade plywood and shall contain the names of the project, Owner, Architect, major Consultants, Contractor, and major financing institution. Except for safety and warning signs, no other signs are permitted. Location as acceptable to the

Architect.

R. Fire Prevention: Take every precaution to prevent fire. Provide and maintain in good operating condition suitable and adequate fire protection equipment and services, and comply with recommendations regarding fire protection made by the representative of the fire insurance company carrying insurance on the Work or by the local fire chief or fire marshal. The area within the site limits shall be kept orderly and clean, and all combustible rubbish shall be promptly removed from the site.

S. Egress: Maintain safe and legal means of egress at all times. At all times, provide at least two separate means of egress.

T. Mold Control and Remediation During Construction: The Contractor shall protect construction materials and building systems from moisture damage and from conditions which promote mold growth during and after construction. The Contractor shall be responsible for mold remediation and replacement of materials which cannot be successfully remediated in accordance with the following requirements:

1. Materials which become wet prior to installation shall be cleaned, treated and dried in accordance with EPA Guidelines.
2. Materials which exhibit mold growth prior to installation shall not be installed and shall be removed from the site.
3. Materials which exhibit mold growth after installation shall be remediated in accordance with EPA Guidelines for Remediating Building Materials with Mold Growth Caused by Clean Water. The Contractor shall engage and pay for a qualified industrial hygienist acceptable to the Owner to determine the cause of the mold growth, and to certify in writing that materials have been successfully remediated. In the event that the industrial hygienist recommends methods of remediation in addition to those in the Guidelines, the Contractor shall also be responsible for the additional remediation. Materials which can not be successfully remediated shall be removed and replaced with new materials at no additional expense to the Owner.
4. Prior to the start of construction, the Contractor shall submit the name of the person in the Contractor's organization responsible for ensuring compliance with these requirements for mold control and remediation.

U. Temporary Partitions: Provide floor-to-ceiling dustproof partitions to limit dust and dirt migration and to separate areas occupied by Owner and tenants from fumes and noise.

1. Construct dustproof partitions with gypsum wallboard, with joints taped on occupied side, and fire-retardant-treated plywood on construction operations side.
2. Construct dustproof partitions with two layers of 6-mil (0.14-mm) polyethylene sheet on each side. Cover floor with two layers of 6-mil (0.14-mm) polyethylene sheet, extending sheets 18 inches (460 mm) up the sidewalls. Overlap and tape full length of joints. Cover floor with fire-retardant-treated plywood.
    a. Construct vestibule and airlock at each entrance through temporary partition with not less than 48 inches (1219 mm) between doors. Maintain water-dampened foot mats in vestibule.
3. Where fire-resistance-rated temporary partitions are indicated or are required by authorities having jurisdiction, construct partitions according to the rated assemblies.
4. Insulate partitions to control noise transmission to occupied areas.
5. Seal joints and perimeter. Equip partitions with gasketed dustproof doors and security locks where openings are required.
6. Protect air-handling equipment.

7. Provide walk-off mats at each entrance through temporary partition.

1.15 PRODUCTS AND SUBSTITUTIONS

A. Specified Products: In all cases in which a manufacturer's name, trade name or other proprietary designation is used in connection with materials or articles to be furnished under this Contract, whether or not the phrase "or equal" is used after such name, the Contractor shall provide the product of the named manufacturers without substitution, unless a written request for a substitution has been submitted by the Contractor and approved in writing by the Architect.

B. Deviations from Detailed Requirements: If the Contractor proposes to use material which, while suitable for the intended use, deviates in any way from the detailed requirements of the Contract Documents, the Contractor shall inform the Architect in writing of the nature of such deviations at the time the materials is submitted for approval, and shall request written approval of the deviation from the requirements of the Contract Documents.

C. Approval of Substitutions: In requesting approval of deviations or substitutions, the Contractor shall provide evidence, including, but not limited to manufacturer's data, leading to a reasonable certainty that the proposed substitution or deviation will provide a quality of result at least equal to that attainable if the detailed requirements of the Contract Documents were strictly followed. If, in the opinion of the Architect, the evidence presented by the Contractor does not provide a sufficient basis for such reasonable certainty, the Architect may reject such substitution or deviation without further investigation.

D. Intent of Contract Documents: The Contract Documents are intended to produce a building of consistent character and quality of design. All components of the building including visible items of mechanical and electrical equipment have been selected to have a coordinated design in relation to the overall appearance of the building. The Architect shall judge the design and appearance of proposed substitutes on the basis of the suitability in relation to the overall design of the Project, as well as for their intrinsic merits. The Architect will not approve as equal to materials specified proposed substitutes which in the Architect's opinion, would be out of character, obtrusive, or otherwise inconsistent with the character or quality of design of the Project. In order to permit coordinated design of color and finishes the Contractor shall furnish the substituted material in any color, finish texture, or pattern which would have been available from the manufacturer originally specified, at no additional cost to the Owner.

E. Additional Costs or Impact: Any additional cost, or any loss or damage arising from the substitution of any material or any method for those originally specified shall be borne by the contractor, notwithstanding approval or acceptance of such substitution by the Owner or the Architect, unless such substitution was made at the written request or direction of the Owner and the Architect. Any decrease in the cost of the substitution shall be returned to the Owner.

F. Manufacturers: To the greatest degree possible, provide primary materials and products from one manufacturer for each type or kind. Provide secondary materials as recommended by manufacturers of primary materials.

G. Substitution Requests: Refer to Section 016200 - SUBSTITUTION REQUEST FORM. Submit 3 copies or digital distribution. Identify product to be replaced by substitute by reference to specification sections and drawing numbers. Provide Contractor's certification and evidence to

prove compliance with Contract Document requirements as acceptable to Architect.

H. Substitution Conditions: Substitution requests will be returned without action unless one of the following conditions is satisfied. The Contractor shall state which of the following conditions applies to the requested substitution:

1. Request is due to an "or equal" clause.
2. Specified material or product cannot be coordinated with other work.
3. Specified material or product is not acceptable to authorities having jurisdiction.
4. Substantial advantage is offered Owner in terms of cost, time, or other valuable consideration.
5. Specified material or product is not available.

I. Invalid Substitutions: Contractor's submittal and Architect's acceptance of shop drawings, samples, product data or other submittal is not a valid request for, nor an approval of a substitution unless the Contractor presents the information when first submitted as a Request for Substitution.

J. Compatibility of Materials Used in the Work:

1. Ensure complete compatibility between materials.
2. Compatibility shall include adhesion, erosion, solubility, differential thermal response, and galvanic action.
3. Provide evidence of compatibility.
4. Provide custom testing where evidence is not available.
5. Where materials are not compatible, provide necessary isolation or transition materials and provide details of same.
6. Correct defects resulting from incompatibility including de-construction and re-construction of assemblies – whether materials are part of a submittal and substitution process or not.
7. Proposed substitutions may be rejected where compatibility information is not provided; or where compatibility is not adequately addressed, according to the Architect’s judgment; or where incompatible materials would negatively impact the project’s success.

1.16 DELIVERY, STORAGE AND HANDLING

A. Manufacturer's Instructions: Strictly comply with manufacturer's instructions and recommendations and prevent damage, deterioration and loss, including theft. Minimize long-term storage at the site. Maintain environmental conditions, temperature, ventilation, and humidity within range permitted by manufacturers of materials and products used.

1.17 OWNER-FURNISHED CONTRACTOR-INSTALLED (OFCI) PRODUCTS

A. Owner will furnish products indicated. The Contractor’s Work includes providing support systems to receive Owner's equipment and making plumbing, mechanical, and electrical connections.

1. Owner will arrange for and deliver Shop Drawings, Product Data, and Samples to Contractor.
2. Owner will arrange and pay for delivery of Owner-furnished items according to Contractor's Construction Schedule.
3. After delivery, Owner will inspect delivered items for damage. Contractor shall be present

for and assist in Owner's inspection.

4. If Owner-furnished items are damaged, defective, or missing, Owner will arrange for replacement.
5. Owner will arrange for manufacturer's field services and for delivery of manufacturer's warranties to Contractor.
6. Owner will furnish Contractor the earliest possible delivery date for Owner-furnished products. Using Owner-furnished earliest possible delivery dates, Contractor shall designate delivery dates of Owner-furnished items in Contractor's Construction Schedule.
7. Contractor shall review Shop Drawings, Product Data, and Samples and return them to Architect noting discrepancies or anticipated problems in use of product.
8. Contractor is responsible for receiving, unloading, and handling Owner-furnished items at Project site.
9. Contractor is responsible for protecting Owner-furnished items from damage during storage and handling, including damage from exposure to the elements.
10. If Owner-furnished items are damaged as a result of Contractor's operations, Contractor shall repair or replace them.
11. Contractor shall install and otherwise incorporate Owner-furnished items into the Work.

B. Owner-Furnished Products: As directed by the Architect.

1.18 LABELS

A. Labels, Trademarks, & Tradenames: Locate required labels on inconspicuous surfaces. Do not provide labels, nameplates, or trademarks which are not required. Provide permanent data plate on each item of equipment stating manufacturer, model, serial number, capacity, ratings and all other essential data.

1.19 RECORD DOCUMENTS

A. Definition of As-Constructed Record Drawings: (commonly called “as-builts”) are the record of the Project as constructed based on information the Contractor provides to the Owner under the contract for construction. Because the As-constructed Record Drawings will be based on the Contractor’s mark-ups, the Architect is not responsible for the accuracy or completeness of the As-constructed Record Drawings.

B. Definition of As-Designed Record Drawings: The record of everything the Architect designed for the Project, and including the original Construction Documents plus all addenda, Architect’s Supplemental Instructions, Change Orders, Construction Change Directives and minor changes in the work.

C. General: Keep as-constructed record documents neatly and accurately. Record information as the work progresses and deliver to Architect at time of final acceptance. Include in record documents all field changes made, all relevant dimensions, and all relevant details of the work. Keep record documents up to date with all Architect’s Supplemental Instructions, Change Orders, Construction Change Directives and minor changes in the work clearly indicated.

D. Drawings: Keep four separate sets of blackline prints at the site, one set each for mechanical, electrical, plumbing, and architectural/structural disciplines. Neatly and accurately note all deviations from the Contract Documents and the exact actual location of the work as installed.

Marked-up and colored prints will be used as a guide to determine the progress of the work installed. Requisitions for payment will not be approved until the record documents are accurate and up-to-date.

1. Work Outside Building: Record data outside of building to an accuracy of plus or minus 1 inch and determine and record the invert elevation of all drain lines.
2. At completion of the work, submit one complete set of marked-up as-built prints for review. After acceptance, these marked-up as-built prints shall be used in the preparation of the as-built drawings.
3. Architect shall furnish Contractor with AutoCAD or BIM Design Intent Model or both files for originals of the Contract Drawings. The Contractor shall make modifications to these files as shown on the marked-up prints. Remove superseded data to show the completed installation.
4. The Contractor shall deliver the completed AutoCAD or BIM Design Intent Model or both as-constructed record drawings, in the same version as Contract Drawings, properly titled and dated to the Architect. Indicate preparer of as-built drawings. These as-built drawings shall become the property of the Owner.

E. Specifications: Maintain one clean copy of complete specifications including addenda, modifications, and bulletins with changes, substitutions, and selected options clearly noted. Circle or otherwise clearly indicate which manufacturer and products are actually used.

F. Operating and Maintenance Manuals: Manuals shall be submitted which contain the following:

1. Description of the system provided.
2. Handling, storage, and installation instructions.
3. Detailed description of the function of each principal component of the systems or equipment.
4. Operating procedures, including prestartup, startup, normal operation, emergency shutdown, normal shutdown and troubleshooting.
5. Maintenance procedures including lubrication requirements, intervals between lubrication, preventative and repair procedures, and complete spare parts list with cross reference to original equipment manufacturer's part numbers.
6. Control and alarm features including schematic of control systems, control loop electric ladder diagrams, controller operating set points, settings for alarms and shutdown systems, pump curves and fan curves.
7. Safety and environmental considerations.

G. Copies of Operating and Maintenance Manuals: Three copies or digital, at Owners' preference, of the manuals shall be provided within sufficient time to allow for training of Owner's personnel. Submit one copy of the manuals to the Architect for review no later than 90 calendar days prior to substantial completion, or building turn over, whichever comes first. Submit the remaining five copies within 15 days after first review set is returned to contractor. Progress payment may be withheld if this requirement is not met.

H. Additional Requirements for Operating and Maintenance Manuals: The requirements for manuals applies to each packaged and field-fabricated operating system. The manuals shall be provided in three-ring side binders with durable plastic covers. The manuals shall contain a detailed table of contents and have tab dividers for major sections and special equipment.

I. Instructions for Owner's Personnel: Prior to final inspection, instruct the Owner's personnel in operation, adjustment and maintenance of products, equipment and systems. Provide instruction at mutually agreed upon times. Video all instruction sessions and deliver videos to

Owner on thumb drive or other suitable media.

1. For equipment that requires seasonal operation provide similar instruction during other seasons.
2. Use operation and maintenance manuals for each piece of equipment or system as the basis of instruction. Review contents in detail to explain all aspects of operation and maintenance.

J. Framed Data: Provide charts and lists of all valves, circuits, switches, controls and equipment. Install on walls under glass at locations directed by Architect.

1.20 PROJECT CLOSE OUT

A. Complete the following prior to Substantial Completion:

1. Provide Contractor's Punch List of incomplete items stating reason for incompletion and value of incompletion.
2. Advise Owner of insurance change over requirements.
3. Submit all warranties, maintenance contracts, final certificates and similar documents.
4. Obtain Certificate of Occupancy and similar releases which permit the Owner's full and unrestricted use of the areas claimed "Substantially Complete".
5. Submit record documents.
6. Deliver maintenance stocks of materials where specified.
7. Make final change over of lock cylinders or cores and advise Owner of change of security responsibility.
8. Complete startup of all systems and instruct Owner's personnel in proper operation and routine maintenance of systems and equipment.
9. Complete clean up and restoration of damaged finishes.
10. Remove all temporary facilities and utilities that are no longer needed.
11. Request Architect's inspection for Substantial Completion.

B. Architect will either issue a Certificate of Substantial Completion or notify Contractor of work which must be performed prior to issue of certificate.

C. Complete the following prior to Final Acceptance and payment:

1. Obtain Certificate of Substantial Completion.
2. Submit final application for payment, showing final accounting of changes in the work.
3. Provide final releases and lien waivers not previously submitted.
4. Submit certified copy of final punch list stating that Contractor has completed or corrected each item.
5. Submit final meter readings, record of stored fuel and similar information.
6. Submit Consent of Surety for final payment.
7. Submit evidence of Contractor's continuing insurance coverage (if required by Contract Documents).

1.21 CLASSROOM CLEANING

A. In addition to requirements for final cleaning specified below, Contractor shall provide complete cleaning of classrooms at the following schools:

1. Fairview.

2. Tennyson.
3. Harris Park.
4. Sherrelwood.

B. Classroom cleaning shall be performed following completion of construction, abatement, moving, packing, and other Work that may generate dust, dirt, debris, or other contaminants within classrooms, and prior to turnover of the classrooms to the Owner.

C. Provide thorough cleaning of classrooms, including, but not limited to, the following:

1. Remove construction dust, dirt, debris, and residue from floors, walls, ceilings, doors, frames, windows, window sills, casework, cabinets, shelving, countertops, ledges, trim, and other exposed surfaces.
2. Clean and vacuum floors, including corners, edges, and areas beneath and behind movable furnishings and equipment where accessible.
3. HEPA vacuum dust and debris from horizontal surfaces, ledges, sills, and other areas where dust may accumulate.
4. Damp wipe cleanable surfaces to remove remaining dust and residue.
5. Clean interior glazing and window frames.
6. Clean doors, door frames, hardware, and other accessible surfaces.
7. Clean fixed casework, shelving, countertops, and similar built-in components.
8. Remove labels, tape, temporary protection, adhesive residue, and other construction-related markings from finished surfaces.
9. Remove all remaining construction materials, packaging, debris, and other items not intended to remain.
10. Clean classrooms sufficiently to provide a clean, dust-free condition suitable for occupancy and use by the Owner.

D. Coordinate classroom cleaning with the Owner's schedule and with completion of abatement, moving, packing, and other Work occurring within the schools.

E. Do not perform classroom cleaning until Work that could re-contaminate or otherwise adversely affect the cleaned spaces has been completed, unless otherwise approved by the Owner.

F. Protect cleaned classrooms from subsequent construction activities, dust, debris, and damage. Re-clean affected areas as necessary at no additional cost to the Owner.

G. Contractor shall coordinate access, sequencing, and cleaning operations with the Owner and shall provide sufficient labor and equipment to complete classroom cleaning within the Project schedule.

H. Classroom cleaning specified herein is in addition to and not in lieu of final cleaning requirements specified elsewhere in the Contract Documents.

1.22 FINAL CLEANING AND REPAIR

A. Clean Up: Immediately prior to the Architect's inspection for Substantial Completion, the Contractor shall completely clean the premises and clean and prepare the completed work in order for it to be used for its intended purpose in accordance with the Contract Documents. Such work shall include, but not be limited to the following:

1. Concrete and ceramic surfaces shall be cleaned and washed.
2. Resilient coverings shall be cleaned, waxed and buffed as applicable.
3. Woodwork shall be dusted and cleaned.
4. Sash, fixtures and equipment shall be thoroughly cleaned.
5. Stains, spots, dust, marks and smears shall be removed from all surfaces.
6. Hardware and metal surfaces shall be cleaned and polished.
7. Glass and plastic surfaces shall be thoroughly cleaned by professional window cleaners.
8. Damaged, broken or scratched glass or plastic shall be replaced by the Contractor at the Contractor's expense.
9. Vacuum carpeted and soft surfaces with high efficiency particulate arrestor (HEPA) vacuum.
10. Use low-emitting, environmentally friendly cleaning agents and procedures. Do not use ammonia-, chlorine bleach-, or solvent-based cleaners, unless authorized in writing by Architect.

B. Repairs: Repair and touch-up all damaged and deteriorated products and surfaces.

PART 2 PRODUCTS [NOT USED]

PART 3 EXECUTION

3.1 INSTALLATION, GENERAL

A. Isolation of Work Areas in Occupied Facilities: Prevent dust, fumes, and odors from entering occupied areas.

1. Prior to commencing work, isolate the HVAC system in area where work is to be performed.
   a. Disconnect supply and return ductwork in work area from HVAC systems servicing occupied areas.
   b. Maintain negative air pressure within work area, using HEPA-equipped air-filtration units, starting with commencement of temporary partition construction, and continuing until removal of temporary partitions is complete.
2. Maintain dust partitions during the Work. Use vacuum collection attachments on dust-producing equipment. Isolate limited work within occupied areas using portable dust-containment devices.
3. Perform daily construction cleanup and final cleanup using approved, HEPA-filter-equipped vacuum equipment.

END OF SECTION

SECTION 012200

UNIT PRICES

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 SUMMARY

A. This Section covers those items for which indefinite quantities can be expected and, therefore, pre-agreed prices per unit of work are established as means to determine adjustments to the Contract Price after actual quantities are determined.

1.3 QUANTITIES AND COST ADJUSTMENTS

A. Refer to individual Specification Sections for methods of measurement and payment for unit prices. As soon as the work involved in each unit cost item has been completed, submit documentation to establish the actual quantities provided. Submit to the Architect for review and issuance of Change Order.

B. Change Order amount for each unit cost item will be based on actual quantities multiplied by the unit price. This unit price includes all costs as described below.

1.4 UNIT PRICES

A. Should certain additional work be required, or should the quantities of certain classes of work be increased or decreased from those required by the Contract Documents, by authorization of the Owner, the below unit prices shall, at the option of the Owner, be the basis of payment to the Contractor or credit to the Owner, for such increase or decrease in the work.

B. The Unit Prices shall represent the exact net amount per unit to be paid the Contractor (in the case of additions or increases) or to be refunded the Owner (in the case of decreases). No additional adjustment will be allowed for materials, installation, substrate preparation, overhead, profit, insurance, general conditions, or other direct or indirect expenses of the Contractor or Subcontractors.

PART 2 - PRODUCTS [Not Used]

PART 3 - EXECUTION

3.1 SCHEDULE OF UNIT PRICES

A. Areas of masonry repointing and/or repair, as indicated on the Drawings. Contractor to provide unit pricing for the quantities indicated.

B. As otherwise defined by the Architect or referenced on the drawings.

END OF SECTION

SECTION 014330

MOCKUPS

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 SUMMARY

A. General: Provide and coordinate mock-up assemblies at Project site for Architect's review and acceptance, in accordance with requirements of the Contract Documents. Refer to individual Specification Sections for mock-up requirements. Generally, without limitation, mock-ups on site include the following:

1. Mock-ups of individual pieces of the work, as specified within individual Specification Section.
2. Field Mock-Up of interior construction. Refer to the Drawings for extent of mock-up.

B. It shall be the responsibility of the Contractor to coordinate the work of the related Specification Sections so that each mock-up meets the specified requirements.

C. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Individual Specification Sections for Submittal Samples.

1.3 DEFINITIONS

A. Freestanding Mock-Ups: Full-size, physical assemblies that are constructed on-site in a protected location.

1. Freestanding mock-ups are not part of the final construction. Freestanding mock-ups will be used to verify selections made under sample submittals, to demonstrate aesthetic effects, qualities of materials and execution, and to review construction, coordination, testing, and operation.
2. Approved freestanding mock-ups establish the standard by which the Work will be judged.
3. Approved freestanding mock-ups remain on site during the balance of construction and are demolished and removed from site at completion of the Work they represent.

B. In-Place Mock-Ups: Full-size, physical assemblies that are constructed in-place and remain part of final construction.

1. In-place mock-ups will be used to verify selections made under sample submittals, to demonstrate aesthetic effects, qualities of materials and execution, and to review construction, coordination, testing, or operation.

2. Approved in-place mock-ups establish the standard by which the Work will be judged.
3. Approved mock-ups remain part of the completed Work.

1.4 SUBMITTALS

A. Schedule: Construction Manager shall submit a schedule of mock-up construction, including dates for mock-up review by the Architect.

1. Mock-up schedule shall be reviewed at each progress meeting, revised and resubmitted as required.
2. Schedule shall allow sufficient time for mock-ups which are not accepted to be reconstructed and reviewed until accepted by the Architect.

B. Shop Drawings of Mock-Ups: Provide large scale shop drawings for fabrication, installation and erection of all parts of each mock-up. Provide plans, elevations, and details of anchorage, connections and accessory items.

C. Photographs of Mock-Ups: Submit photographs of mock-ups after completion of installation and acceptance of each mock-up.

D. Submittal Samples: Refer to individual Specification Sections for submittal requirements of mock-up components and coordinate accordingly.

1.5 QUALITY ASSURANCE

A. Design Modifications: Make design modifications to work only as required to meet performance requirements and to coordinate the work. Indicate proposed design modifications on shop drawings. Maintain original design concept without altering profiles and alignments indicated.

PART 2 - PRODUCTS

2.1 MATERIALS AND PRODUCTS

A. Provide materials, components, and products for mock-ups as specified in individual Specification Sections.

PART 3 - EXECUTION

3.1 GENERAL

A. Refer to PART 3, EXECUTION portions of the various Specification Sections for specific requirements regarding condition of surfaces, erection, and erection tolerances.

3.2 FIELD MOCK-UP OF INTERIOR CONSTRUCTION

A. Provide a field mock-up of the interior construction items at locations and in configuration indicated on Drawings or as otherwise directed. Obtain Architect's acceptance of visual qualities prior to commencing work that individual mock-up is intended to represent. Protect and maintain approved mock-ups throughout the work of the Contract. Locate mock-ups at the Project site as directed by Architect.

1. Refer to Drawings for extent of the field mock-up.
2. Provide modifications to mock-up as required until Architect's approval has been received.

B. Interior Construction Mock-ups: Provide mock-ups of various interior construction as indicated or as specified in the applicable Specification Sections, as directed by the Architect.

3.3 INDIVIDUAL MOCK-UPS

A. Provide individual mock-ups of types and sizes required by individual Specification Sections to evaluate and set the standard of quality for that work. Obtain Architect's acceptance of visual qualities prior to commencing work that individual mock-up is intended to represent. Protect and maintain approved mock-ups throughout the work of the Contract. Locate mock-ups at the Project site as directed by the Architect.

1. Provide as many mock-ups as required until Architect's approval has been received.
2. When indicated in individual Specification Sections, approved mock-ups may be incorporated into the finish work.

3.4 REPAIR AND PROTECTION

A. General: On completion of testing, inspecting, sample taking, and similar services, repair and restore substrates and finishes.

1. Provide materials and comply with installation requirements specified in other Specification Sections. Restore patched areas and extend restoration into adjoining areas with durable seams that are as non-visible as possible.

B. Protect construction exposed by or for quality-control service activities.

3.5 REMOVAL AND DISPOSAL

A. Demolish and remove mock-ups from site at the completion of the Project. Legally dispose of demolished mock-up materials.

END OF SECTION

This page left intentionally blank.

SECTION 016200

SUBSTITUTION REQUEST FORM

No substitutions will be considered without this completed substitution request form and supporting documentation. Substitutions made without completion of this form will be considered defective work as stated in AIA A201.

Date: _____ Number: _____

Re: Request for Substitution

The Contractor proposes the following substitution in accordance with the requirements of the Contract Documents:

Scope of Substitution _____

_____

Specification Reference _____

_____

Drawing Reference _____

_____

Reason for Proposed Substitution _____

_____

Benefit to Owner _____

_____

Impact on Project Cost _____

_____

Impact on Project Schedule _____

_____

Impact on Guarantees and Warranties _____

_____

Coordination and Compatibility Required with Adjacent Materials and System _____

_____

_____

List Deviations From Specified Requirements _____

_____

_____

Building Energy Performance: For substitutions of materials and products used for backstop and de-rated calculations, provide an updated envelope backstop and de-rating calculations based on the product being proposed for substitution and demonstrate the equivalence or difference with the original product[s]. Substitutions which, in the opinion of the architect, modify the energy design, and which are submitted without the required evidence of compliance with the code and the original design will be returned without review and are by definition not permitted.

Attachments: Attach supporting documentation sufficient for Architect to evaluate substitution. Substitution Request Forms submitted without adequate documentation will be returned without review.

Attachments _____

_____

_____

Response Date: List date by which response by Architect is requested to maintain project schedule and allow sufficient time for inclusion of proposed substitution.

Response Date _____

Submitted By _____

Firm and Address _____

_____

Signature below signifies acceptance of responsibility for accuracy and completeness of information included in this Substitution Request Form.

Authorized Signature _____

ARCHITECT'S RESPONSE

Notations listed below shall have same meaning as on Architect's approval stamp. Clarifications to or changes in project schedule or time shall be processed using standard project forms.

Architect's Response

_____ Approved

_____ Approved as Corrected

_____ Revise and Resubmit

_____ Rejected

_____ Returned Without Review

Remarks _____

_____

_____

_____

_____

_____

Date _____

Signed _____

END OF FORM

This page left intentionally blank.

SECTION 024100

DEMOLITION

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS, which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included:

1. Selective Demolition to be coordinated with the phasing of the Work.
2. Demolition and removal of selected portions of buildings and structures and as required for new work. Refer to the Drawings for additional requirements.
3. Salvage of existing items to be reused or turned over to the facility.
4. Removal and legal disposal of demolished materials off site. Except those items specifically designated to be relocated, reused, or turned over to the facility, all existing removed materials, items, trash and debris shall become property of the Contractor and shall be completely removed from the site and legally disposed of at their expense. Salvage value belongs to the Contractor. On-site sale of materials is not permitted.
5. Demolition and removal work shall properly prepare for alteration work and new construction to be provided under the Contract.
6. Scheduling and sequencing operations without interruption to utilities serving occupied areas. If interruption is required, obtain written permission from the utility company and the Owner.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 011000 - GENERAL REQUIREMENTS for temporary facilities and controls, for maintenance of access, for cleaning during construction, and for dust and noise control.
2. Section 017400 - CONSTRUCTION WASTE MANAGEMENT for waste management and recycling.
3. Section 018120 - CONSTRUCTION INDOOR AIR QUALITY (IAQ) MANAGEMENT for indoor air quality control procedures.
4. Division 21 - FIRE PROTECTION:
   a. Disconnecting, capping and otherwise making inactive existing fire protection services in areas where demolition and removal work is required.
   b. Disconnect and reinstallation of fire protection equipment temporarily interrupted during construction.
5. Division 22 - PLUMBING:
   a. Disconnecting, capping and otherwise making inactive existing plumbing services in areas where demolition and removal work is required.
   b. Disconnection and reinstallation of plumbing equipment temporarily interrupted during construction.
6. Division 23 - HEATING, VENTILATING AND AIR CONDITIONING:
   a. Disconnecting, capping and otherwise making inactive existing HVAC services in areas

where demolition and removal work is required.
   b. Disconnect and reinstallation of HVAC equipment temporarily interrupted during construction.
7. Division 26 - ELECTRICAL WORK:
   a. Disconnecting, capping and otherwise making inactive existing electrical services in areas where demolition and removal work is required.
   b. Disconnect and reinstallation of electrical equipment temporarily interrupted during construction.

1.3 DEFINITIONS

A. Remove: Detach items from existing construction and legally dispose of them off-site, unless indicated to be removed and salvaged or removed and reinstalled.

B. Remove and Salvage: Detach items from existing construction and deliver them to the Owner ready for reuse, at a location designated by the Owner. Protect from weather until accepted by Owner.

C. Remove and Reinstall: Detach items from existing construction, prepare them for reuse, and reinstall them where indicated. Protect from weather until reinstallation.

D. Existing to Remain: Existing items of construction that are not to be removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.4 MATERIALS OWNERSHIP

A. Historic items, relics, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques, antiques, and other items of interest or value to Owner that may be encountered during selective demolition remain property of the Owner as applicable. Carefully remove each item or object in a manner to prevent damage and deliver promptly to a location acceptable to the Owner.

1.5 SUBMITTALS

A. Schedule of Selective Demolition Activities: Indicate the following:

1. Detailed sequence of selective demolition and removal work, with early and late starting and finishing dates for each activity. Ensure Owner's on-site operations are uninterrupted if applicable.
2. Interruption of utility services. Indicate how long utility services will be interrupted.
3. Coordination for shutoff, capping, and continuation of utility services.
4. Use of elevator and stairs.
5. Locations of proposed dust- and noise-control temporary partitions and means of egress, including for other occupants affected by selective demolition operations.
6. Coordination of Owner's continuing occupancy of portions of existing building and of Owner’s partial occupancy of completed Work.
7. Means of protection for items to remain and items in path of waste removal from building.

B. Inventory: After selective demolition is complete, submit a list of items that have been removed

and salvaged, and turned over the Owner.

C. Predemolition Video and Pictures: Show existing conditions of adjoining construction and site improvements, including finish surfaces, that might be misconstrued as damage caused by selective demolition operations. Comply with Division 01 requirements. Submit before Work begins.

1.6 QUALITY ASSURANCE

A. Examination of Existing Conditions: The Contractor shall examine the Contract Drawings for demolition and removal requirements and provisions for new work. Verify all existing conditions and dimensions before commencing work. The Contractor shall visit the site and examine the existing conditions as he finds them and shall inform herself/himself of the character, extent and type of demolition and removal work to be performed. Submit any questions regarding the extent and character of the demolition and removal work in the manner and within the time period established for receipt of such questions during the bidding period.

B. Demolition Firm Qualifications: An experienced firm that has specialized in demolition work similar in material and extent to that indicated for this Project.

C. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.

D. Standards: Comply with ANSI A10.6 and NFPA 241.

E. Predemolition Conference: Conduct conference at Project site to comply with requirements in Section 011000 - GENERAL REQUIREMENTS, Project Meetings. Review methods and procedures related to selective demolition including, but not limited to, the following:

1. Inspect and discuss condition of construction to be selectively demolished.
2. Review structural load limitations of existing structure.
3. Review and finalize selective demolition schedule and verify availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays.
4. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.
5. Review areas where existing construction is to remain and requires protection.

1.7 WARRANTY

A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials so as not to void existing warranties.

PART 2 PRODUCTS

2.1 SALVAGING

A. Salvaged for Reinstallation: Materials indicated on the Drawings to be salvaged and reinstalled shall be carefully removed and stored at a location acceptable to the Architect and Owner.

B. Salvaged for Storage: Materials indicated on the Drawings or designated in the field by the Owner to be salvaged and stored shall be carefully removed and delivered to the Owner at locations determined by Owner.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that utilities have been disconnected and capped.

B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.

C. Inventory and record the condition of items to be removed and reinstalled and items to be removed and salvaged.

D. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Architect.

E. Engage a professional engineer registered in the state that the project is located to survey condition of building to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of structure or adjacent structures during selective demolition operations.

F. Survey of Existing Conditions: Record existing conditions by use of preconstruction videotapes.

1. Before selective demolition or removal of existing building elements that will be reproduced or duplicated in final Work, make permanent record of measurements, materials, and construction details required to make exact reproduction.

G. Perform surveys as the Work progresses to detect hazards resulting from selective demolition activities.

3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

A. Service/System Requirements: Locate, identify, disconnect, and seal or cap off indicated utility services and mechanical/electrical systems serving areas to be selectively demolished.

1. Arrange to shut off indicated utilities with utility companies and Owner.

2. If services/systems are required to be removed, relocated, or abandoned, before proceeding with selective demolition provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
3. Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit after bypassing. Where entire wall is to be removed, existing services/systems may be removed with removal of the wall.
4. Prior to commencing cutting work in existing surfaces, take all precautionary measures to assure that mechanical and electrical services to the particular area have been made inactive. Coordinate with Fire Suppression, Plumbing, HVAC, and Electrical subcontractors. Only licensed tradesmen of that particular trade shall disconnect and cap existing mechanical and electrical items that are to be removed, abandoned and/or relocated.
5. If, during the process of cutting work, existing utility lines are encountered which are not indicated on the Drawings, regardless of their condition, immediately report such items to the Architect. Do not proceed with work in such areas until instructions are issued by the Architect. Continue work in other areas.

3.3 PREPARATION

A. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.

1. Comply with requirements for access and protection specified in Section 011000 - GENERAL REQUIREMENTS, Temporary Facilities and Controls.
2. Maintain adequate passage to and from all exits at all times. Before any work is done which significantly alters access or egress patterns, consult with the Architect and obtain approval of code required egress. Under no condition block or interfere with the free flow of people at legally required exits, or in any way alter the required condition of such exits.

B. Temporary Shoring: Provide and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.

1. Strengthen or add new supports when required during progress of selective demolition.
2. Remove temporary shoring, bracing and structural supports when no longer required.
3. Post warning signs and place barricades as applicable during placement and removal of temporary shoring.

C. Conduct demolition operations to prevent injury to people and damage to adjacent buildings and facilities to remain. Ensure safe passage of people around demolition area(s).

1. Erect temporary protection, such as walks, fences, railings, canopies, and covered passageways, where required by authorities having jurisdiction. Provide temporary barricades as required to limit access to demolition areas.
2. Protect existing site improvements, appurtenances, and landscaping to remain.

3.4 SELECTIVE DEMOLITION, GENERAL

A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:

1. Proceed with selective demolition systematically, from higher to lower level. Complete

selective demolition operations above each floor or tier before disturbing supporting members on the next lower level.

2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping, to minimize disturbance of adjacent surfaces. Temporarily cover openings to remain.
3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
4. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain fire watch and portable fire-suppression devices during flame-cutting operations.
5. Maintain adequate ventilation when using cutting torches.
6. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
7. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
8. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
9. Maintain clear unimpeded passage through the work area for safety and emergency egress.
10. Saw cut overruns in concrete and masonry for new door, window and other finish openings is not permitted. Core drill corners and finish square to match required opening.
11. Dispose of demolished items and materials promptly.

B. Removed and Salvaged Items:

1. Clean salvaged items.
2. Pack or crate items after cleaning. Identify contents of containers.
3. Store items in a secure area until delivery to Owner.
4. Transport items to storage area designated by the Owner.
5. Protect items from damage during transport and storage.

C. Removed Items for Reinstallation by the Respective Trade.

1. Clean salvaged items.
2. Pack or crate items after cleaning. Identify contents of containers.
3. Store items in a secure area until delivery to Owner.
4. Transport items to storage area designated by the Owner.
5. Protect items from damage during transport and storage.

D. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and cleaned and reinstalled in their original locations after selective demolition operations are complete.

E. Items for Re-use and Preservation of Existing Surfaces to Remain:

1. The Contractor shall inspect closely each item specifically designated to be relocated, re-used, or turned over to the Owner prior to its removal, and immediately report damages and defects to the Architect and the Owner. The Contractor shall be responsible for any subsequent damage to the same other than latent defects not readily apparent from close inspection, and shall bear responsibility for its repair or same replacement as directed by the Architect, to the satisfaction of the Owner.
2. Unless special surface preparation is specified under other Specification Sections, leave existing surfaces that are to remain in a condition suitable to receive new materials and/or

finishes.

3.5 PROTECTION OF PUBLIC AND PROPERTY

A. Provide all measures required by federal, state and municipal laws, regulations, and ordinances for the protection of surrounding property, the public, workmen, and Owner's employees during all demolition and removal operations. Measures are to be taken, but not limited to installation of sidewalks, sheds, barricades, fences, warning lights and signs, trash chutes and temporary lighting.

B. Protect all walks, roads, streets, curbs, pavements, trees and plantings, on and off premises, and bear all costs for correcting such damage as directed by the Architect, and to the satisfaction of the Owner.

C. Demolition shall be performed in such a manner that will insure the safety of adjacent property. Protect adjacent property from damage and protect persons occupying adjacent property from injuries which might occur from falling debris or other cause and so as not to cause interference with the use of other portions of the building, of adjacent buildings or the free access and safe passage to and from the same.

D. Every precaution shall be taken to protect against movement or settlement of the building, of adjacent buildings, sidewalks, roads, streets, curbs and pavements. Provide and place at the Contractor's own expense, all necessary bracing and shoring in connection with demolition and removal work.

E. Remove portions of structures with care by using tools and methods that will not transfer heavy shocks to existing and adjacent building structures, both internal and external of the particular work area.

F. Provide and maintain in proper condition, suitable fire resistive dust barriers around areas where interior demolition and removal work is in progress. Dust barriers shall prevent the dust migration to adjacent areas. Remove dust barriers upon completion of major demolition and removal in the particular work area.

3.6 DISCOVERY OF HAZARDOUS MATERIALS

A. If hazardous materials, such as chemicals, asbestos-containing materials, or other hazardous materials are discovered during the course of the work, cease work in affected area only and immediately notify the Architect and the Owner of such discovery. Do not proceed with work in such areas until instructions are issued by the Architect. Continue work in other areas.

B. If unmarked containers are discovered during the course of the work, cease work in the affected area only and immediately notify the Architect and the Owner of such discovery. Do not proceed with work in such areas until instructions are issued by the Architect. Take immediate precautions to prohibit endangering the containers integrity. Continue work in other areas.

3.7 CUTTING

A. Perform all cutting of existing surfaces in a manner which will ensure a minimal difference between the cut area and new materials when patched. Use extreme care when cutting existing surfaces containing concealed utility lines which are indicated to remain and bear full responsibility for repairing or replacement of all such utilities that are accidentally damaged.

B. Provide a flush saw cut edge where pavement, curb and concrete removals abut new construction work or existing surfaces to remain undisturbed.

C. All slurry and water shall be contained and managed to avoid damage to existing conditions when using a wet saw or wet core driller.

D. Obtain and pay for a hot work permit and arrange to have on-site a Fire Watch when using a cutting torch or similar item.

3.8 DISPOSAL OF DEMOLISHED MATERIALS

A. General: Comply with the following:

1. Do not allow demolished materials to accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.

B. Burning: Do not burn demolished materials.

3.9 CLEANING

A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Premises shall be left in a clean condition and ready to accept alteration work and new construction.

END OF SECTION

SECTION 040120

MASONRY RESTORATION AND CLEANING

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Repairing clay masonry, including replacing damaged units as indicated on Drawings.
2. Reanchoring veneers.
3. Repointing mortar joints, removing existing mortar and replacing with new color mortar.
4. Removing plant growth (vines).
5. Cleaning exposed clay masonry surfaces, including decorative stonework.
6. Provide for repair or replacement of clay and stone masonry broken or damaged during disassembly and reconstruction. Contractor shall be responsible for damage resulting from work of this Section.
7. Provide shoring and bracing required to maintain stability of masonry during work of this Section. Coordinate with requirements of Section 011000 - GENERAL REQUIREMENTS.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 012200 - UNIT PRICES.
2. Section 024100 - DEMOLITION for demolition, removal and salvage requirements, to the extent not specified in this Section.
3. Section 042000 - UNIT MASONRY for new clay masonry veneer.
4. Section 076200 - SHEET METAL FLASHING AND TRIM for metal flashing installed in or on restored masonry.
5. Section 079200 - JOINT SEALANTS for sealing joints in restored masonry.

1.3 SUBMITTALS

A. Product Data: For each type of product indicated. Include recommendations for application and use. Include test data substantiating that products comply with requirements.

B. Samples for Verification: Before erecting mockup, submit samples of the following:

1. Each type of exposed masonry unit to be used for replacing existing units.

a. For each brick type, provide straps or panels containing at least four bricks.

2. Each type of sand used for pointing mortar.

    a. For blended sands, provide samples of each component and blend.
    b. Identify sources, both supplier and quarry, of each type of sand.

3. Each type of pointing mortar in the form of sample mortar strips, 6 inches long by 1/2 inch wide, set in aluminum or plastic channels.

    a. Include with each sample a list of ingredients with proportions of each. Identify sources, both supplier and quarry, of each type of sand and brand names of cementitious materials and pigments if any.

4. Each type of anchor, insert, dowel, and attachment, full size.
5. Each type of masonry patching compound in the form of briquettes, at least 3 inches long by 1-1/2 inches wide. Document each sample with manufacturer and stock number or other information necessary to order additional material.

C. Restoration Program: For each phase of restoration process, provide detailed description of materials, methods, equipment, and sequence of operations to be used for each phase of restoration work including protection of surrounding materials on building and Project site.

1. Include methods for keeping pointing mortar damp during curing period.
2. If materials and methods other than those indicated are proposed for any phase of restoration work, provide a written description, including evidence of successful use on comparable projects, and a testing program to demonstrate their effectiveness for this Project.

D. Cleaning Program: Describe cleaning process in detail, including materials, methods, and equipment to be used and protection of surrounding materials on building and Project site, and control of runoff during operations.

1. If materials and methods other than those indicated are proposed for cleaning work, provide a written description, including evidence of successful use on comparable projects, and a testing program to demonstrate their effectiveness for this Project.

1.4 QUALITY ASSURANCE

A. Chemical Manufacturer Qualifications: A firm regularly engaged in producing masonry cleaners that have been used for similar applications with successful results, and with factory-trained representatives who are available for consultation and Project-site inspection and assistance at no additional cost.

B. Source Limitations: Obtain each type of material for masonry restoration (face brick, stone, cement, sand, etc.) from one source with resources to provide materials of consistent quality in appearance and physical properties.

C. Preconstruction Testing Service: Owner will engage a qualified independent testing agency to test the following. Provide test specimens and assemblies as indicated.

1. Replacement Brick: For each proposed type of replacement brick, according to sampling and testing methods in ASTM C 67 for compressive strength, 24-hour cold-water absorption, 5-hour boil absorption, saturation coefficient, and initial rate of absorption (suction).

2. Existing Brick: For each type of existing brick indicated for replacement, according to testing methods in ASTM C 67 for compressive strength, 24-hour cold-water absorption, 5-hour boil absorption, saturation coefficient, and initial rate of absorption (suction). Carefully remove existing bricks from locations designated by Architect.

D. Mockups: Prepare mockups of restoration and cleaning as follows to demonstrate aesthetic effects and qualities of materials and execution. Prepare mockups on existing walls under same weather conditions to be expected during remainder of the Work.

1. Repair an area approximately 36 inches high by 48 inches wide for each type of masonry material indicated to be rebuilt or replaced.
2. Patch three small areas at least 1 inch in diameter for each type of masonry material indicated to be patched.
3. Clean an area approximately 25 sq. ft. in area for each type of masonry and surface condition.

    a. Test cleaners and methods on samples of adjacent materials for possible adverse reactions unless cleaners and methods are known to have deleterious effect.
    b. Allow a waiting period of not less than seven days after completion of sample cleaning to permit a study of sample panels for negative reactions.

4. Rake out joints in two separate areas approximately 36 inches high by 72 inches wide for each type of repointing required and repoint one of the two areas.

E. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver masonry units to Project site strapped together in suitable packs or pallets or in heavy-duty cartons.

B. Deliver other materials to Project site in manufacturer's original and unopened containers, labeled with manufacturer's name and type of products.

C. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.

D. Store hydrated lime in manufacturer's original and unopened containers. Discard lime if containers have been damaged or have been opened for more than two days.

E. Store lime putty covered with water in sealed containers.

F. Store sand where grading and other required characteristics can be maintained and contamination avoided.

1.6 PROJECT CONDITIONS

A. Repoint mortar joints and repair masonry only when air temperature is between and 40 and 90 deg F and is predicted to remain so for at least 7 days after completion of work.

B. Cold-Weather Requirements: Comply with the following procedures for masonry repair and mortar-joint pointing:

1. When air temperature is below 40 deg F, heat mortar ingredients, masonry repair materials, and existing masonry walls to produce temperatures between 40 and 120 deg F.
2. When mean daily air temperature is below 40 deg F, provide enclosure and heat to maintain temperatures above 32 deg F within the enclosure for 7 days after repair and pointing.

C. Hot-Weather Requirements: Protect masonry repair and mortar-joint pointing when temperature and humidity conditions produce excessive evaporation of water from mortar and repair materials. Provide artificial shade and wind breaks and use cooled materials as required. Do not apply mortar to substrates with temperatures of 90 deg F and above.

D. Patch masonry only when air and surface temperatures are between and 55 and 100 deg F and are predicted to remain above 55 deg F for at least 7 days after completion of work. On days when air temperature is predicted to go above 90 deg F, schedule patching work to coincide with time that surface being patched will be in shade or during cooler morning hours.

E. Clean masonry surfaces only when air temperature is 40 deg F and above and is predicted to remain so for at least 7 days after completion of cleaning.

1.7 SEQUENCING AND SCHEDULING

A. Order replacement materials at earliest possible date, to avoid delaying completion of the Work.

B. Order sand for repointing mortar immediately after approval of Samples or mockups. Take delivery of and store at Project site a sufficient quantity of sand to complete Project.

C. Perform masonry restoration work in the following sequence:

1. Remove plant growth.
2. Repair existing masonry, including the following:

    a. Replacing existing masonry with new masonry materials.

3. Rake out joints that are to be repointed.
4. Point mortar joints.
5. Inspect for open mortar joints and repair before cleaning to prevent the intrusion of water and other cleaning materials into the wall.
6. Clean masonry surfaces.

D. As scaffolding is removed, patch anchor holes used to attach scaffolding. Patch holes in masonry units to comply with Part 3 "Masonry Unit Patching and Repairs" Article. Patch holes in mortar joints to comply with Part 3 "Repointing Masonry" Article.

PART 2 - PRODUCTS

2.1 MASONRY MATERIALS

A. Face Brick and Accessories: Provide face brick and accessories, including specially molded, ground, cut, or sawed shapes where required to complete masonry restoration work.

1. Provide units with colors, surface texture, size, and shape to match existing brickwork and with physical properties not less than those determined from preconstruction testing of selected existing units.

    a. For replacement brick at existing building provide brick to match existing as approved by Architect.
    b. For existing brickwork that exhibits a range of colors, provide brick that matches that range rather than brick that matches an individual color within that range.

2. Provide units with colors, surface texture, and physical properties to match Architect's sample. Match existing units in size and shape.

    a. For sample that exhibits a range of colors, provide brick that matches that range rather than brick that matches an individual color within that range.

3. Provide specially molded shapes for applications where shapes produced by sawing would result in sawed surfaces being exposed to view.
4. Provide specially ground units, shaped to match patterns, for arches and where indicated.

B. Building Brick: Provide building brick complying with ASTM C 62, of same vertical dimension as face brick, for masonry work concealed from view.

1. Grade SW where in contact with earth.
2. Grade SW, MW, or NW for concealed backup.

2.2 MORTAR MATERIALS

A. Portland Cement: ASTM C 150, Type I or Type II.

1. Provide white cement containing not more than 0.60 percent total alkali when tested according to ASTM C 114.

B. Hydrated Lime: ASTM C 207, Type S.

C. Mortar Sand: ASTM C 144, unless otherwise indicated.

1. Color: Provide natural sand or ground marble, granite, or other sound stone; of color necessary to produce required mortar color.
2. For pointing mortar, provide sand with rounded edges.
3. Match size, texture, and gradation of existing mortar sand as closely as possible. Blend several sands, if necessary, to achieve suitable match.

D. Mortar Pigments: Natural and synthetic iron oxides, compounded for mortar mixes. Use only pigments with a record of satisfactory performance in masonry mortars.

1. Available Products: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. SGS Mortar Colors: Solomon Grind-Chem Services, Inc.
    b. True Tone Mortar Colors: Davis Colors, a Subsidiary of Rockwood Industries, Inc.

E. Water: Potable, clean and free from injurious amount of oil, alkali, organic matter or other deleterious material.

2.3 PAINT REMOVERS

A. Alkaline Paste Paint Remover: Manufacturer's standard alkaline paste formulation for removing paint coatings from masonry.

1. Available Products:

    a. American Building Restoration Products, Inc.; 800 Brush Grade.
    b. Diedrich Technologies Inc.; 606/606X Extra Thick Multi-Layer Paint Remover.
    c. Hydrochemical Techniques, Inc.; Hydroclean Heavy Duty Paint Remover (HT-716).
    d. Price Research, Ltd.; Price Heavy Duty Paint Stripper.
    e. ProSoCo; Sure Klean Heavy-Duty Paint Stripper.

2.4 CLEANING MATERIALS

A. Water: Potable, clean and free from injurious amount of oil, alkali, organic matter or other deleterious material.

B. Hot Water: Heat water to a temperature of 140 to 160 deg F.

C. Job-Mixed Detergent Solution: Solution prepared by mixing 2 cups of trisodium phosphate (TSP), 1/2 cup of laundry detergent, and 20 quarts of hot water for every 5 gal. of solution required.

D. Job-Mixed Mold, Mildew, and Algae Remover: Solution prepared by mixing 2 cups of trisodium phosphate (TSP), 5 quarts of 5 percent sodium hypochlorite (bleach), and 15 quarts of hot water for every 5 gal. of solution required.

E. Nonacidic Liquid Cleaner: Manufacturer's standard mildly alkaline liquid cleaner formulated for removing mold, mildew, and other organic soiling from ordinary building materials, including polished stone, brick, aluminum, plastics, and wood.

1. Available Products:

    a. Dominion Restoration, Inc.; Bio-Cleanse.
    b. Dumond Chemicals, Inc.; Safe n' Easy Architectural Cleaner/Restorer.
    c. Price Research, Ltd.; Price Non-Acid Masonry Cleaner.
    d. ProSoCo; Enviro Klean Restoration Cleaner.

2.5 MISCELLANEOUS MATERIALS

A. Masonry Patching Compound: Factory-mixed cementitious product that is custom manufactured for patching masonry, is vapor- and water permeable, exhibits low shrinkage, and develops high bond strength to all types of masonry.

1. Formulate patching compound used for patching brick in colors and textures to match brick being patched. Provide number of colors needed to enable matching each brick.
2. Available Products:

a. Cathedral Stone Products, Inc.; Jahn Restoration Mortar.
b. Edison Coatings, Inc.; Custom System 45.
c. Bonstone Materials Corp., Stone Repair.

B. Liquid Strippable Masking Agent: Manufacturer's standard liquid, film-forming, strippable masking material for protecting glass, metal, and polished stone surfaces from damaging effects of acidic and alkaline masonry cleaners.

1. Available Products:

a. American Building Restoration Products, Inc.; LM 130 Acid Shield.
b. Diedrich Technologies Inc.; Diedrich Acid Guard.
c. Price Research, Ltd.; Price Mask.
d. ProSoCo; Sure Klean Strippable Masking.

C. Masonry Repair Anchors, Expansion Type: Mechanical fasteners designed for masonry veneer stabilization consisting of 1/4-inch- diameter, Type 316 stainless-steel rod with brass expanding shells at each end and water-shedding washer in the middle. Expanding shells shall be designed to provide positive mechanical anchorage to veneer on one end and backup masonry on the other.

1. Available Products:

a. BLOK-LOK, a Hohmann & Barnard Company; Torq-Lok.
b. Dur-O-Wal, a Hohmann & Barnard Company; Dur-O-Wal Repair Anchor.
c. Hohmann & Barnard, Inc.; #521RA-B Restoration Anchor.

D. Masonry Repair Anchors, Spiral Type: Type 304 stainless-steel spiral rods designed to anchor to backing and veneer. Anchors are flexible in plane of veneer but rigid perpendicular to it.

1. Provide adhesive-installed anchors complete with manufacturer's standard epoxy adhesive and injection tubes, screens, sleeves, or other devices required for installation.
2. Provide driven-in anchors designed to be installed in drilled holes and relying on screw effect rather than adhesive to secure them to backup and veneer.
3. Available Products:

a. Dur-O-Wal, a Hohmann & Barnard Company; Dur-O-Flex.
b. Heckmann Building Products, Inc.; #391 Spiro Remedial Tie.
c. Helifix Ltd.; Helifix HRT60 or Helifix HRT80.
d. Hohmann & Barnard, Inc.; Helix Spiro-Ties.

E. Joint Sealant and Backer Rods: Refer to Section 079200 - JOINT SEALANTS.

2.6 MORTAR MIXES

A. Preparing Lime Putty: Slake quicklime and prepare lime putty according to appendix to ASTM C 5 and manufacturer's written instructions.

B. Measurement and Mixing: Measure cementitious materials and sand in a dry condition by volume or equivalent weight. Do not measure by shovel; use known measure. Mix materials in a clean, mechanical batch mixer.

1. Mixing Pointing Mortar: Thoroughly mix cementitious materials and sand together before adding any water. Then mix again adding only enough water to produce a damp, unworkable mix that will retain its form when pressed into a ball. Maintain mortar in this dampened condition for 15 to 30 minutes. Add remaining water in small portions until mortar reaches desired consistency. Use mortar within one hour of final mixing; do not retemper or use partially hardened material.

C. Colored Mortar: Produce mortar of color required by using selected ingredients. Do not alter specified proportions without Architect's approval.

1. Mortar Pigments: Where mortar pigments are indicated, do not exceed a pigment-to-cement ratio of 1:10 by weight.
2. Color: Match existing, or as otherwise directed by Architect.

D. Do not use admixtures of any kind in mortar, unless otherwise indicated.

E. Mortar Proportions: Mix mortar materials in the following proportions:

1. Pointing Mortar for Brick: 1 part portland cement, 2 parts lime, and 6 parts sand.

a. Add mortar pigments to produce mortar colors required.

2. Rebuilding (Setting) and Pointing Mortar, for Stone: Comply with ASTM C 270, Proportion Specification, Type N, unless otherwise indicated, with cementitious material limited to portland cement and lime.

a. Mix: 1 part portland cement, 2 parts lime, and 6-7 parts sand.
b. Add mortar pigments to produce mortar colors required.

2.7 CHEMICAL CLEANING SOLUTIONS

A. Dilute chemical cleaners with water to produce solutions not exceeding concentration recommended by chemical cleaner manufacturer.

PART 3 - EXECUTION

3.1 PROTECTION

A. Protect persons, motor vehicles, surrounding surfaces of building being restored, building site, plants, and surrounding buildings from harm resulting from masonry restoration work.

1. Erect temporary protective covers over walkways and at points of pedestrian and vehicular entrance and exit that must remain in service during course of restoration and cleaning work.

B. Comply with chemical cleaner manufacturer's written instructions for protecting building and other surfaces against damage from exposure to its products. Prevent chemical cleaning solutions from coming into contact with pedestrians, motor vehicles, landscaping, buildings, and other surfaces that could be harmed by such contact.

1. Cover adjacent surfaces with materials that are proven to resist chemical cleaners used unless chemical cleaners being used will not damage adjacent surfaces. Use materials that contain only waterproof, UV-resistant adhesives. Apply masking agents to comply with manufacturer's written instructions. Do not apply liquid masking agent to painted or porous surfaces. When no longer needed, promptly remove masking to prevent adhesive staining.
2. Keep wall wet below area being cleaned to prevent streaking from runoff.
3. Do not clean masonry during winds of sufficient force to spread cleaning solutions to unprotected surfaces.
4. Neutralize and collect alkaline and acid wastes for disposal off Owner's property.
5. Dispose of runoff from cleaning operations by legal means and in a manner that prevents soil erosion, undermining of paving and foundations, damage to landscaping, and water penetration into building interiors.

C. Prevent mortar from staining face of surrounding masonry and other surfaces.

1. Cover sills, ledges, and projections to protect from mortar droppings.
2. Keep wall area wet below rebuilding and pointing work to discourage mortar from adhering.
3. Immediately remove mortar in contact with exposed masonry and other surfaces.
4. Clean mortar splatters from scaffolding at end of each day.

3.2 UNUSED ANCHOR OR EMBEDDED STEEL REMOVAL

A. Remove embedded masonry anchors, brackets, wood nailers, and other extraneous items no longer in use unless identified as historically significant or indicated to remain.

1. Remove items carefully to avoid spalling or cracking masonry.
2. If item cannot be removed without damaging surrounding masonry, cut off item flush with surface and core drill surrounding masonry and item as close around item as practical.
3. Patch holes where items were removed unless directed to remove and replace units.

3.3 MASONRY REMOVAL AND REPLACEMENT

A. At locations indicated, remove masonry units that are damaged, spalled, or deteriorated. Carefully demolish or remove entire units from joint to joint, without damaging surrounding masonry, in a manner that permits replacement with full-size units.

1. When removing single bricks, remove material from center of brick and work toward outside edges.

B. Support and protect remaining masonry that surrounds removal area. Maintain flashing, reinforcement, lintels, and adjoining construction in an undamaged condition.

C. Notify Architect of unforeseen detrimental conditions including voids, cracks, bulges, and loose masonry units in existing masonry backup, rotted wood, rusted metal, and other deteriorated items.

D. Remove in an undamaged condition as many whole bricks and stones as possible.

1. Remove mortar, loose particles, and soil from brick and stone by cleaning with hand chisels, brushes, and water.
2. Remove sealants by cutting close to brick and stone with utility knife and cleaning with solvents.
3. Store brick for reuse, as indicated.
4. Deliver cleaned brick and stone not required for reuse to Owner, unless otherwise directed.

E. Clean masonry surrounding removal areas by removing mortar, dust, and loose particles in preparation for replacement.

F. Install replacement masonry into bonding and coursing pattern of existing masonry, match existing mortar joints for size. If cutting is required, use a motor-driven saw designed to cut masonry with clean, sharp, unchipped edges.

G. Lay replacement masonry units with completely filled bed, head, and collar joints. Butter ends with sufficient mortar to fill head joints and shove into place. Maintain joint width for replacement units to match existing joints.

1. Bricks: Wet both replacement and surrounding bricks that have ASTM C 67 initial rates of absorption (suction) of more than 30 g/30 sq. in. per min. Use wetting methods that ensure that units are nearly saturated but surface is dry when laid.
2. Tool exposed mortar joints in repaired areas to match joints of surrounding existing masonry work.
3. Rake out mortar used for laying brick and stone before mortar sets and point new mortar joints in repaired area to comply with requirements for repointing existing masonry, and at same time as repointing of surrounding area.

3.4 REANCHORING VENEERS

A. Install masonry repair anchors in horizontal mortar joints and according to manufacturer's written instructions. Install at not more than 16 inches o.c. vertically and 32 inches o.c. horizontally, unless otherwise indicated. Install at locations to avoid penetrating flashing.

B. Recess anchors at least 5/8 inch from surface of mortar joint and fill recess with pointing mortar.

3.5 MASONRY UNIT PATCHING AND REPAIRS

A. Patch the following masonry units:

1. Units indicated to be patched.
2. Units with holes.
3. Units with chipped edges or corners.
4. Units with small areas of deep deterioration.

B. Remove and replace existing patches, unless otherwise indicated or approved by Architect.

C. Patching Bricks:

1. Remove loose material from brick surface. Remove additional material so patch will not have feathered edges and will be at least 1/4 inch thick, but not less than recommended by patching compound manufacturer.
2. Mask or remove surrounding mortar joints if patch will extend to edge of brick.
3. Mix patching compound in individual batches to match each unit being patched. Combine one or more colors of patching compound, as needed, to produce exact match.
4. Rinse surface to be patched and leave damp, but without standing water.
5. Brush-coat surfaces with slurry coat of patching compound according to manufacturer's written instructions.
6. Place patching compound in layers as recommended by patching compound manufacturer, but not less than 1/4 inch or more than 2 inches thick. Roughen surface of each layer to provide a key for next layer.
7. Trowel, scrape, or carve surface of patch to match texture and surface plane of surrounding brick. Shape and finish surface before or after curing, as determined by testing, to best match existing brick.
8. Keep each layer damp for 72 hours or until patching compound has set.

3.6 CLEANING MASONRY, GENERAL

A. Examination: Examine all surfaces scheduled for cleaning, for roughness, contaminants, unsound structural substrates, or other conditions that may impair the application. Notify the Architect in writing of any such conditions; do not continue work until directed by Architect on how to proceed.

1. Monitor weather prior to work to ensure that air temperatures remain between 50°F and 85°F, or as recommended by the manufacturer of chemical compounds and proprietors of cleaning methods.
2. Ensure that building components not to be cleaned, adjacent persons, property, and plant life are protected from all cleaning activities and wind drift. Test adjacent non-masonry materials for reaction with cleaning materials. Mask all windows, ornamental fixtures, hardware, wood doors, or other non-masonry surfaces.

B. Proceed with cleaning in an orderly manner; work from top to bottom of each scaffold width and from one end of each elevation to the other.

C. Use only those cleaning methods indicated for each masonry material and location.

1. Do not use wire brushes or brushes that are not resistant to chemical cleaner being used. Do not use plastic-bristle brushes if natural-fiber brushes will resist chemical cleaner being used.
2. Use spray equipment that provides controlled application at volume and pressure indicated, measured at spray tip. Adjust pressure and volume to ensure that cleaning methods do not damage masonry.

    a. Equip units with pressure gages.
    b. Provide spray applications as follows:
        1) Low-Pressure Spray: 100 to 400 psi; 4 to 6 gpm.
        2) Medium-Pressure Spray: 400 to 800 psi; 4 to 6 gpm.
        3) High-Pressure Spray: 800 to 1200 psi; 4 to 6 gpm.

3. For chemical cleaner spray application, use low-pressure tank or chemical pump suitable for chemical cleaner indicated, equipped with cone-shaped spray tip.

4. For water spray application, use fan-shaped spray tip that disperses water at an angle of 25 to 50 degrees.
5. For high-pressure water spray application, use fan-shaped spray tip that disperses water at an angle of at least 40 degrees.
6. For heated water spray application, use equipment capable of maintaining temperature between 140 and 160 deg F at flow rates indicated.
7. For steam application, use steam generator capable of delivering live steam at nozzle.

D. Perform each cleaning method indicated in a manner that results in uniform coverage of all surfaces, including corners, moldings, and interstices, and that produces an even effect without streaking or damaging masonry surfaces.

E. Removing Plant Growth: Completely remove plant, moss, and shrub growth from masonry surfaces. Carefully remove plants, creepers, and vegetation by cutting at roots and allowing to dry as long as possible before removal. Remove loose soil and debris from open masonry joints to whatever depth they occur.

F. Preliminary Cleaning: Before beginning general cleaning, remove extraneous substances that are resistant to cleaning methods being used. Extraneous substances include paint, calking, asphalt, and tar.

1. Carefully remove heavy accumulations of material from surface of masonry with a sharp chisel. Do not scratch or chip masonry surface.
2. Remove paint and calking with alkaline paint remover.

    a. Comply with requirements for paint removal.
    b. Repeat application up to two times if needed.

3. Remove asphalt and tar with solvent-type paint remover.

    a. Apply only to asphalt and tar by brush without prewetting.
    b. Allow paint remover to remain on surface for 10 to 30 minutes.
    c. Rinse off with water using low-pressure spray.
    d. Repeat application if needed.

G. Water Application Methods:

1. Water Soak Application, for Stone: Soak stone surfaces by applying water continuously and uniformly to limited area for time indicated. Apply water at low pressures and low volumes in multiple fine sprays using perforated hoses or multiple spray nozzles. Erect a protective enclosure constructed of polyethylene sheeting to cover area being sprayed.
2. Spray Applications, for Brick and Stone: Unless otherwise indicated, hold spray nozzle at least 6 inches from surface of stone and apply water in horizontal back and forth sweeping motion, overlapping previous strokes to produce uniform coverage.

H. Steam Wash: Apply steam to masonry surfaces at pressures not exceeding 80 psi. Hold nozzle at least 6 inches from surface of masonry and apply steam in horizontal back and forth sweeping motion, overlapping previous strokes to produce uniform coverage.

I. Chemical Cleaner Application Methods: Apply chemical cleaners to masonry surfaces to comply with chemical cleaner manufacturer's written instructions; use brush or spray application methods, at Contractor's option. Do not spray apply at pressures exceeding 50 psi. Do not allow chemicals to remain on surface for periods longer than those indicated or recommended by manufacturer.

J. Rinse off chemical residue and soil by working upward from bottom to top of each treated area at each stage or scaffold setting. Periodically during each rinse, test pH of rinse water running off of cleaned area to determine that chemical cleaner is completely removed.

1. Apply neutralizing agent and repeat rinse, if necessary, to produce tested pH of between 6.7 and 7.5.

K. After cleaning is complete, remove protection no longer required. Remove tape and adhesive marks.

3.7 PAINT REMOVAL

A. Paint Removal with Alkaline Paste Paint Remover:

1. Apply paint remover to dry, painted masonry with brushes.
2. Allow paint remover to remain on surface for period recommended by manufacturer.
3. Rinse with water applied by low-pressure spray to remove chemicals and paint residue.
4. Repeat process, if necessary, to remove all paint.
5. Apply acidic cleaner to masonry, while surface is still wet, using low-pressure spray equipment or soft-fiber brush. Let cleaner remain on surface for period recommended by chemical cleaner manufacturer.
6. Rinse with cold water applied by low-pressure spray to remove chemicals and soil.

3.8 MASONRY CLEANING

A. Cold-Water Wash: Use cold water applied by low-pressure spray.

B. Cold Water Soak:

1. Apply cold water by intermittent soaking.
2. Use perforated hoses or other means that will apply a fine water mist to entire surface being cleaned.
3. Apply water in cycles with at least 30 minutes between cycles.
4. Continue water application until surface encrustation has softened sufficiently to permit its removal by water wash, as indicated by cleaning tests.
5. Remove soil and softened surface encrustation from masonry with cold water applied by low-pressure spray.

C. Hot-Water Wash: Use hot water applied by low-pressure spray.

D. Steam Cleaning: Apply steam at pressures not exceeding 80 psi.

E. Detergent Cleaning:

1. Wet masonry with water applied by low-pressure spray.
2. Scrub masonry with detergent solution using medium-soft brushes until soil is thoroughly dislodged and can be removed by rinsing. Use small brushes to remove soil from mortar joints and crevices. Dip brush in solution often to ensure that adequate fresh detergent is used and that masonry surface remains wet.
3. Rinse with water applied by low-pressure spray to remove detergent solution and soil.
4. Repeat cleaning procedure above where required to produce cleaning effect established by mockup.

F. Mold, Mildew, and Algae Removal:

1. Wet masonry with water applied by low-pressure spray.
2. Apply mold, mildew, and algae remover by brush or low-pressure spray.
3. Scrub masonry with medium-soft brushes until mold, mildew, and algae are thoroughly dislodged and can be removed by rinsing. Use small brushes for mortar joints and crevices. Dip brush in mold, mildew, and algae remover often to ensure that adequate fresh cleaner is used and that masonry surface remains wet.
4. Rinse with water applied by low-pressure spray to remove mold, mildew, and algae remover and soil.
5. Repeat cleaning procedure above where required to produce cleaning effect established by mockup.

G. Nonacidic Liquid Chemical Cleaning:

1. Wet masonry with water applied by low-pressure spray.
2. Apply cleaner to masonry in two applications by brush. Let cleaner remain on surface for period indicated below:

    a. As recommended by chemical cleaner manufacturer.
    b. As established by mockup.
    c. Two to three minutes.

3. Rinse with water applied by low-pressure spray to remove chemicals and soil.
4. Repeat cleaning procedure above where required to produce cleaning effect established by mockup. Do not repeat more than once. If additional cleaning is required, use steam wash.

3.9 REPOINTING MASONRY

A. Rake out and repoint mortar joints to the following extent:

1. All joints in areas indicated.
2. Joints where mortar is missing or where they contain holes.
3. Cracked joints where cracks can be penetrated at least 1/4 inch by a knife blade 0.027 inch thick.
4. Cracked joints where cracks are 1/8 inch or more in width and of any depth.
5. Joints where they sound hollow when tapped by metal object.
6. Joints where they are worn back 1/4 inch or more from surface.
7. Joints where they are deteriorated to point that mortar can be easily removed by hand.
8. Joints, other than those indicated as sealant-filled joints, where they have been filled with substances other than mortar.

B. Do not rake out and repoint joints where not required.

C. Rake out joints as follows:

1. Remove mortar from joints to depth of 2 times joint width, but not less than 1/2 inch or not less than that required to expose sound, unweathered mortar.
2. Remove mortar from masonry surfaces within raked-out joints to provide reveals with square backs and to expose masonry for contact with pointing mortar. Brush, vacuum, or flush joints to remove dirt and loose debris.

3. Do not spall edges of masonry units or widen joints. Replace or patch damaged masonry units as directed by Architect.

    a. Cut out mortar by hand with chisel and mallet. Do not use power-operated grinders without Architect's written approval based on submission by Contractor of a satisfactory quality-control program and demonstrated ability of operators to use tools without damaging masonry. Quality-control program shall include provisions for supervising performance and preventing damage due to worker fatigue.
    b. Cut out center of mortar bed joints using angle grinders with diamond-impregnated metal blades. Remove remaining mortar by hand with chisel and mallet. Strictly adhere to written quality-control program. Quality-control program shall include provisions for demonstrating ability of operators to use tools without damaging masonry, supervising performance, and preventing damage due to worker fatigue.

D. Notify Architect of unforeseen detrimental conditions including voids in mortar joints, cracks, loose masonry units, rotted wood, rusted metal, and other deteriorated items.

E. Point joints as follows:

1. Rinse masonry-joint surfaces with water to remove dust and mortar particles. Time rinsing application so, at time of pointing, joint surfaces are damp but free of standing water. If rinse water dries, dampen masonry-joint surfaces before pointing.
2. Apply pointing mortar first to areas where existing mortar was removed to depths greater than surrounding areas. Apply in layers not greater than 3/8 inch until a uniform depth is formed. Fully compact each layer thoroughly and allow it to become thumbprint hard before applying next layer.
3. After low areas have been filled to same depth as remaining joints, point all joints by placing mortar in layers not greater than 3/8 inch. Fully compact each layer and allow to become thumbprint hard before applying next layer.

    a. Where existing bricks have worn or rounded edges, slightly recess finished mortar surface below face of masonry to avoid widened joint faces.
    b. Take care not to spread mortar over edges onto exposed masonry surfaces or to featheredge mortar.

4. When mortar is thumbprint hard, tool joints to match original appearance of joints. Remove excess mortar from edge of joint by brushing.

F. Cure mortar by maintaining in thoroughly damp condition for at least 72 hours including weekends and holidays.

1. Acceptable curing methods include covering with wet burlap and plastic sheeting, periodic hand misting, and periodic mist spraying using system of pipes, mist heads, and timers.
2. Adjust curing methods to ensure that pointing mortar is damp throughout its depth without eroding surface mortar.

G. Where repointing work precedes cleaning of existing masonry, allow mortar to harden at least 30 days before beginning cleaning work.

3.10 FINAL CLEANING

A. After mortar has fully hardened, thoroughly clean exposed masonry surfaces of excess mortar and foreign matter; use wood scrapers, stiff-nylon or -fiber brushes, and clean water, spray applied at low pressure.

1. Do not use metal scrapers or brushes.
2. Do not use acidic or alkaline cleaners.

B. Wash adjacent woodwork and other nonmasonry surfaces. Use detergent and soft brushes or cloths.

C. Clean masonry debris from roof; remove debris from gutters and downspouts. Rinse off roof and flush gutters and downspouts.

D. Sweep and rake adjacent pavement and grounds to remove masonry debris. Where necessary, pressure wash surfaces to remove mortar, dust, dirt, and stains.

3.11 FIELD QUALITY CONTROL

A. Inspectors: Owner will engage qualified independent inspectors to perform inspections and prepare test reports. Coordinate with inspectors and provide access. Allow inspectors use of lift devices and scaffolding, as needed, to perform inspections.

END OF SECTION

SECTION 042000

UNIT MASONRY

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Concrete masonry units.
2. Face brick.
3. Embedded flashing.
4. Mortar and grout.
5. Reinforcing steel, masonry joint reinforcement, ties and anchors.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 078440 - FIRE-RESISTIVE JOINT SYSTEMS for fire-resistive joint systems openings in masonry walls and at heads of masonry walls.
2. Section 079200 - JOINT SEALANTS for sealing control and expansion joints in unit masonry.

1.3 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings: For the following:

1. Masonry Units: Show sizes, profiles, coursing, and locations of special shapes.
2. Reinforcing Steel: Detail bending and placement of unit masonry reinforcing bars. Comply with ACI 315, “Details and Detailing of Concrete Reinforcement.”

C. Samples for Verification: For each type and color of the following:

1. Exposed concrete masonry units.
2. Face brick, in the form of straps of five or more bricks.
3. Pigmented mortar. Make Samples using same sand and mortar ingredients to be used on Project. Label Samples to indicate types and amounts of pigments used.
4. Weep holes/vents.
5. Accessories embedded in masonry.

D. Qualification Data: For testing agency.

E. Material Certificates: Include statements of material properties indicating compliance with requirements including compliance with standards and type designations within standards. Provide for each type and size of the following:

1. Masonry units:

a. Include material test reports substantiating compliance with requirements.
b. For bricks, include size-variation data verifying that actual range of sizes falls within specified tolerances.
c. For exposed brick, include material test report for efflorescence according to ASTM C 67.
d. For masonry units used in structural masonry, include data and calculations establishing average net-area compressive strength of units.

2. Cementitious materials. Include brand, type, and name of manufacturer.
3. Mortar mixes. Include description of type and proportions of ingredients.
4. Grout mixes. Include description of type and proportions of ingredients.
5. Reinforcing bars.
6. Joint reinforcement.
7. Anchors, ties, and metal accessories.

F. Mix Designs: For each type of mortar and grout. Include description of type and proportions of ingredients.

1. Include test reports, per ASTM C 780 for mortar mixes required to comply with property specification.
2. Include test reports, per ASTM C 1019 for grout mixes required to comply with compressive strength requirement.

G. Cold-Weather Procedures: Detailed description of methods, materials, and equipment to be used to comply with cold-weather requirements.

1.4 QUALITY ASSURANCE

A. Testing Agency Qualifications: An independent agency qualified according to ASTM C 1093 for testing indicated.

B. Source Limitations for Masonry Units: Obtain exposed masonry units of a uniform texture and color, or a uniform blend within the ranges accepted for these characteristics, through one source from a single manufacturer for each product required.

C. Source Limitations for Mortar Materials: Obtain mortar ingredients of a uniform quality, including color for exposed masonry, from a single manufacturer for each cementitious component and from one source or producer for each aggregate.

D. Preconstruction Testing Service: The Owner will engage a qualified independent testing agency to perform preconstruction testing indicated below. Payment for these services will be made by the Owner. Retesting of materials that fail to meet specified requirements shall be done at Contractor’s expense.

1. Prism Test: For each type of construction required, per ASTM C 1314.

E. Fire-Resistance Ratings: Where indicated, provide materials and construction identical to those of assemblies with fire-resistance ratings determined per ASTM E 119 by a testing and inspecting agency, by equivalent concrete masonry thickness, or by other means, as acceptable to authorities having jurisdiction.

F. Sample Panels: Build sample panels to verify selections made under sample submittals and to demonstrate aesthetic effects. Comply with requirements in Division 01 for mockups.

1. Build sample panels for typical exterior and interior walls in sizes approximately 48 inches long by 48 inches high by full thickness.
2. Where masonry is to match existing, erect panels adjacent and parallel to existing surface.
3. Clean one-half of exposed faces of panels with masonry cleaner indicated.
4. Protect approved sample panels from the elements with weather-resistant membrane.
5. Approval of sample panels is for color, texture, and blending of masonry units; relationship of mortar and sealant colors to masonry unit colors; tooling of joints; aesthetic qualities of workmanship; and other material and construction qualities specifically approved by Architect in writing.

    a. Approval of sample panels does not constitute approval of deviations from the Contract Documents contained in sample panels unless such deviations are specifically approved by Architect in writing.

G. Defective Units: Referenced masonry unit standards may allow a certain percentage of units to exceed tolerances and to contain chips, cracks, or other defects exceeding limits stated in the standard. Do not uses units where such defects, including dimensions that vary from specified dimensions by more than stated tolerances, will be exposed in the completed Work or will impair the quality of completed masonry.

H. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01. Agenda shall include protection of air barrier membrane during construction.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Store masonry units on elevated platforms in a dry location. If units are not stored in an enclosed location, cover tops and sides of stacks with waterproof sheeting, securely tied. If units become wet, do not install until they are dry.

B. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.

C. Store aggregates where grading and other required characteristics can be maintained and contamination avoided.

D. Deliver preblended, dry mortar mix in moisture-resistant containers designed for lifting and emptying into dispensing silo. Store preblended, dry mortar mix in delivery containers on elevated platforms, under cover, and in a dry location or in a metal dispensing silo with weatherproof cover.

E. Store masonry accessories, including metal items, to prevent corrosion and accumulation of dirt and oil.

1.6 PROJECT CONDITIONS

A. Protection of Air Barrier Membrane: During construction, protect air barrier membrane from penetrations which allow air to pass through air barrier assemblies. Engage original installer to repair damage promptly using identical materials and methods of installation, and to the satisfaction of the Architect.

B. Protection of Masonry: During construction, cover tops of walls, projections, and sills with waterproof sheeting at end of each day's work. Cover partially completed masonry when construction is not in progress.

1. Extend cover a minimum of 24 inches down both sides and hold cover securely in place.
2. Where 1 wythe of multiwythe masonry walls is completed in advance of other wythes, secure cover a minimum of 24 inches down face next to unconstructed wythe and hold cover in place.

C. Do not apply uniform floor or roof loads for at least 12 hours and concentrated loads for at least 3 days after building masonry walls or columns.

D. Stain Prevention: Prevent grout, mortar, and soil from staining the face of masonry to be left exposed or painted. Immediately remove grout, mortar, and soil that come in contact with such masonry.

1. Protect base of walls from rain-splashed mud and from mortar splatter by spreading coverings on ground and over wall surface.
2. Protect sills, ledges, and projections from mortar droppings.
3. Protect surfaces of window and door frames, as well as similar products with painted and integral finishes, from mortar droppings.
4. Turn scaffold boards near the wall on edge at the end of each day to prevent rain from splashing mortar and dirt onto completed masonry.

E. Cold-Weather Requirements: Do not use frozen materials or materials mixed or coated with ice or frost. Do not build on frozen substrates. Remove and replace unit masonry damaged by frost or by freezing conditions. Comply with cold-weather construction requirements contained in ACI 530.1/ASCE 6/TMS 602.

1. Cold-Weather Cleaning: Use liquid cleaning methods only when air temperature is 40 deg F and above and will remain so until masonry has dried, but not less than 7 days after completing cleaning.

F. Hot-Weather Requirements: Comply with hot-weather construction requirements contained in ACI 530.1/ASCE 6/TMS 602.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Delegated Design: Design masonry veneer anchors, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

B. Structural Performance: Provide masonry veneer anchors capable of withstanding design loads within limits and under conditions indicated.

1. Design Loads: As indicated on the Structural Drawings, but not less than required by Code.

2.2 CONCRETE MASONRY UNITS (CMUs)

A. Concrete Masonry Units: ASTM C 90, normal weight unless indicated otherwise manufactured to dimensions 3/8 inch less than nominal dimensions.

B. Shapes: Provide standard shapes indicated and as required for building configuration. Provide special shapes for lintels, corners, jambs, sashes, movement joints, headers, bonding, and other special conditions.

2.3 BRICK

A. Face Brick: ASTM C 216, Grade SW, Type FBS.

1. Basis-of-Design: Summit Brick or equal.
2. Color: Painters' grade brick mix similar to existing color. Match texture to existing brick.
3. Size (Actual Dimensions): As selected by Architect.
4. Initial Rate of Absorption: Less than 30 g/30 sq. in. per minute when tested per ASTM C 67.
5. Efflorescence: Provide brick that has been tested according to ASTM C 67 and is rated "not effloresced."
6. Where shown to "match existing," provide face brick matching color range, texture, and size of existing adjacent brickwork.

B. Building (Common) Brick where Concealed: ASTM C 62, Grade SW.

C. General: Provide shapes indicated and as follows:

1. For ends of sills and caps and for similar applications that would otherwise expose unfinished brick surfaces, provide units without cores or frogs and with exposed surfaces finished.
2. Provide special shapes for applications where stretcher units cannot accommodate special conditions, including those at corners, movement joints, bond beams, sashes, and lintels.
3. Provide special shapes for applications requiring brick of size, form, color, and texture on exposed surfaces.
4. Provide special shapes for applications where shapes produced by sawing would result in sawed surfaces being exposed to view.
5. Units which are sawn and less than one-half full size shall not be used.

2.4 MORTAR AND GROUT MATERIALS

A. Regional Materials: Provide aggregate for mortar and grout, cement, and lime that have been extracted, harvested, or recovered, as well as manufactured, within 500 miles of Project site.

B. Portland Cement: ASTM C 150, Type I or II, except Type III may be used for cold-weather construction. Provide natural color or white cement as required to produce mortar color indicated.

C. Hydrated Lime: ASTM C 207, Type S.

D. Mortar Pigments: Natural and synthetic iron oxides and chromium oxides, compounded for use in mortar mixes. Use only pigments with a record of satisfactory performance in masonry mortar.

1. Available Products:

a. LanXess; Bayferrox Iron Oxide Pigments.
b. Davis Colors; True Tone Mortar Colors.
c. Solomon Grind-Chem Services, Inc.; SGS Mortar Colors.

E. Aggregate for Mortar: ASTM C 144. For mortar that is exposed to view, use washed aggregate consisting of natural sand or crushed stone.

F. Aggregate for Grout: ASTM C 404.

G. Water: Potable.

2.5 REINFORCEMENT

A. Uncoated Steel Reinforcing Bars: ASTM A 615/A 615M or ASTM A 996/A 996M, Grade 60.

B. Masonry Joint Reinforcement, General: ASTM A 951.

1. Interior Walls: Mill-galvanized, carbon steel.
2. Exterior Walls: Hot-dip galvanized, carbon steel.
3. Wire Size and Spacing: As required by Code.
4. Provide in lengths of not less than 10 feet, with prefabricated corner and tee units.

C. Masonry Joint Reinforcement for Multiwythe Masonry:

1. Ladder type with 1 side rod at each face shell of hollow masonry units more than 4 inches in width, plus 1 side rod at each wythe of masonry 4 inches or less in width.

2.6 TIES AND ANCHORS

A. Materials: Provide ties and anchors specified in subsequent paragraphs that are made from materials that comply with subparagraphs below, unless otherwise indicated.

1. Mill-Galvanized, Carbon-Steel Wire: ASTM A 82; with ASTM A 641/A 641M, Class 1 coating.
2. Hot-Dip Galvanized, Carbon-Steel Wire: ASTM A 82; with ASTM A 153/A 153M, Class B-2 coating.
3. Stainless-Steel Wire: ASTM A 580/A 580M, Type 316.
4. Galvanized Steel Sheet: ASTM A 653/A 653M, Commercial Steel, G60 zinc coating.
5. Steel Plates, Shapes, and Bars: ASTM A 36/A 36M.
6. Stainless Steel Bars: ASTM A 276 or ASTM A 666, Type 304.

B. Adjustable Anchors for Connecting to Structure: Provide anchors that allow vertical or horizontal adjustment but resist tension and compression forces perpendicular to plane of wall.

1. Anchor Section for Welding to Steel Frame: Crimped 1/4-inch-diameter, hot-dip galvanized steel. Mill-galvanized wire may be used at interior walls, unless otherwise indicated.

C. Partition Top Anchors: 0.097-inch-thick metal plate with 3/8-inch-diameter metal rod 6 inches long welded to plate and with closed-end plastic tube fitted over rod that allows rod to move in and out of tube. Fabricate from steel, hot-dip galvanized after fabrication.

D. Adjustable Masonry-Veneer Anchors – Thermally-Broken:

1. General: Provide thermally-broken anchors that allow vertical adjustment but resist tension and compression forces perpendicular to plane of wall, for attachment over sheathing to wood or metal studs, with structural performance capable of withstanding a 100-lbf load in both tension and compression without deforming or developing play in excess of 0.05 inch.
2. Screw-Attached, Masonry-Veneer Anchors: Units consisting of a wire tie and a metal anchor section.

a. Anchor Section: Stainless steel barrel section, polymer coated screw with hex head with plastic-encapsulated steel wing and corrosion-resistant, self-drilling screw. Wing designed to receive wire tie . Barrel length to suit sheathing thickness, allowing screw to seat directly against framing with flanged head covering hole in sheathing.
b. Wire Ties: Triangular-, rectangular-, or T-shaped wire ties fabricated from 0.188-inch-diameter, hot-dip galvanized steel wire.
c. Basis-of-Design: 2-Seal Thermal Wing Nut Anchor by Hohmann & Barnard or approved equal by Posi-Tie (thermally broken), or equal.

2.7 MISCELLANEOUS ANCHORS

A. Anchor Bolts: L-shaped steel bolts complying with ASTM A 307, Grade A; with ASTM A 563 hex nuts and, where indicated, flat washers; hot-dip galvanized to comply with ASTM A 153/A 153M, Class C; of dimensions indicated.

2.8 EMBEDDED FLASHING MATERIALS

A. Flexible Laminated Stainless Steel Flashing:

1. Available Products:

a. Hohmann & Barnard, Inc.; Mighty-Flash Stainless Steel Fabric Flashing.
b. Illinois Products, Inc.; IPCO Stainless Steel Fabric Flashing.
c. STS Coatings, Inc.; Gorilla Flash Stainless Fabric.
d. TK Products, Inc.; TK TWF.
e. York Manufacturing, Inc.; Multi-Flash SS.

2. Materials:

a. Type: Stainless steel core with polymer fabric laminated to one stainless steel face with non-asphalt adhesive.
b. Stainless steel type: 304, ASTM A666.
c. Fabric: Polymer fabric; laminated back face of stainless steel core.

3. Accessories:

a. Sealant: Provide sealants as recommended by flashing manufacturer.
b. Splice Tape: Provide minimum 4” wide self-adhering strips and as recommended by flashing manufacturer.
c. Termination Bar: Provide stainless steel termination bars with sealant catch lip.
d. Preformed Shapes: Provide Type 304, 0.016 inch (0.40 mm) thick stainless steel preformed end dams, outside and inside corners.

B. Solder and Sealants for Sheet Metal Flashings: As specified in Section 076200 – SHEET METAL FLASHING AND TRIM.

C. Adhesives, Primers, and Seam Tapes for Flashings: Flashing manufacturer’s standard products or products recommended by flashing manufacturer for bonding flashing sheets to each other and to substrates. Verify compatibility between flashing materials and substrates.

D. Transition Strips: Provide long-term compatible 6” wide transition strips to seal embedded flashing terminations to air barrier membrane.

E. Drip Edge: Provide type 316, 0.016 inch (0.40 mm) thick stainless steel drip edge plates with factory applied adhesive strip for all through-wall flashing conditions. Provide preformed outside and inside corner drip plate corners with smooth uninterrupted soldered seams and hemmed drip edges to maintain continuity. Custom sizes will be required see drawings for profiles required.

2.9 MISCELLANEOUS MASONRY ACCESSORIES

A. Compressible Filler: Premolded filler strips complying with ASTM D 1056, Grade 2A1; compressible up to 35 percent; of width and thickness indicated; formulated from neoprene.

B. Preformed Control-Joint Gaskets: Made from styrene-butadiene-rubber compound, complying with ASTM D 2000, Designation M2AA-805 designed to fit standard sash block and to maintain lateral stability in masonry wall; size and configuration as indicated.

C. Bond-Breaker Strips: Asphalt-saturated, organic roofing felt complying with ASTM D 226, Type I (No. 15 asphalt felt).

D. Weep/Vent Products: Free-draining mesh; made from polyethylene strands, full height and width of head joint and depth 1/8 inch less than depth of outer wythe; in color selected from manufacturer’s standard.

E. Cavity Drainage Material: Free-draining mesh, made from polymer strands that will not degrade within the wall cavity. Provide strips, full-depth of cavity and 10 inches wide, with dovetail shaped notches 7 inches deep that prevent mesh from being clogged with mortar droppings or equivalent. Available products:

1. Advanced Building Products Inc.; Mortar Break II.
2. Archovations, Inc.; CavClear Masonry Mat.

3. Hohmann & Barnard; MortarTrap.
4. Mortar Net USA, Ltd.; Mortar Net.

2.10 MASONRY CLEANERS

A. Proprietary Acidic Cleaner: Manufacturer's standard-strength cleaner designed for removing mortar/grout stains, efflorescence, and other new construction stains from new masonry without discoloring or damaging masonry surfaces. Use product expressly approved for intended use by cleaner manufacturer and manufacturer of masonry units being cleaned.

1. Available Manufacturers:

   a. Diedrich Technologies, Inc.
   b. EaCo Chem, Inc.
   c. ProSoCo, Inc.

2.11 MORTAR AND GROUT MIXES

A. General: Do not use admixtures, including pigments, air-entraining agents, accelerators, retarders, water-repellent agents, antifreeze compounds, or other admixtures, unless otherwise indicated.

1. Do not use calcium chloride in mortar or grout.
2. Limit cementitious materials in mortar to portland cement and lime.

B. Mortar for Unit Masonry: Comply with ASTM C 270, Proportion Specification. Provide the following types of mortar for applications stated unless another type is indicated or needed to provide required compressive strength of masonry.

1. For masonry below grade or in contact with earth, use Type M.
2. For reinforced masonry, use Type S.
3. For exterior, above-grade, load-bearing and non-load-bearing walls and parapet walls; for interior load-bearing walls; for interior non-load-bearing partitions; and for other applications where another type is not indicated, use Type N.

C. Pigmented Mortar: Use colored cement product. Pigments shall not exceed 10 percent of portland cement by weight.

D. Grout for Unit Masonry: Comply with ASTM C 476.

1. Use grout of type indicated or, if not otherwise indicated, of type (fine or coarse) that will comply with Table 1.15.1 in ACI 530.1/ASCE 6/TMS 602 for dimensions of grout spaces and pour height.
2. Provide grout with a slump of 8 to 11 inches as measured according to ASTM C 143/C 143M.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of work.

1. For the record, prepare written report, endorsed by Installer, listing conditions detrimental to performance of work.
2. Verify that foundations are within tolerances specified.

B. Before installation, examine rough-in and built-in construction for piping systems to verify actual locations of piping connections.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Thickness: Build cavity and composite walls and other masonry construction to full thickness shown. Build single-wythe walls to actual widths of masonry units, using units of widths indicated.

B. Build chases and recesses to accommodate items specified in this and other Sections.

C. Leave openings for equipment to be installed before completing masonry. After installing equipment, complete masonry to match the construction immediately adjacent to opening.

D. Use full-size units without cutting if possible. If cutting is required to provide a continuous pattern or to fit adjoining construction, cut units with motor-driven saws; provide clean, sharp, unchipped edges. Allow units to dry before laying unless wetting of units is specified. Install cut units with cut surfaces and, where possible, cut edges concealed. Do not use units cut to less than one-half size.

E. Do not install concrete masonry units with more than 5 percent damage to the face. Do not install brick units which will show defects after installation.

F. Select and arrange units for exposed unit masonry to produce a uniform blend of colors and textures. Mix units from several pallets or cubes as they are placed.

G. Matching Existing Masonry: Match coursing, bonding, color, and texture of existing masonry.

H. Comply with construction tolerances in ACI 530.1/ASCE 6/TMS 602 and with the following:

1. For conspicuous vertical lines, such as external corners, door jambs, reveals, and expansion and control joints, do not vary from plumb by more than 1/8 inch in 10 feet, 1/4 inch in 20 feet, or 1/2 inch maximum.
2. For vertical alignment of exposed head joints, do not vary from plumb by more than 1/4 inch in 10 feet, or 1/2 inch maximum.
3. For conspicuous horizontal lines, such as lintels, sills, parapets, and reveals, do not vary from level by more than 1/8 inch in 10 feet, 1/4 inch in 20 feet, or 1/2 inch maximum.

4. For exposed bed joints, do not vary from thickness indicated by more than plus or minus 1/8 inch, with a maximum thickness limited to 1/2 inch. Do not vary from bed-joint thickness of adjacent courses by more than 1/8 inch.
5. For exposed head joints, do not vary from thickness indicated by more than plus or minus 1/8 inch. Do not vary from adjacent bed-joint and head-joint thicknesses by more than 1/8 inch.
6. For faces of adjacent exposed masonry units, do not vary from flush alignment by more than 1/16 inch except due to warpage of masonry units within tolerances specified for warpage of units.

3.3 LAYING MASONRY WALLS

A. Lay out walls in advance for accurate spacing of surface bond patterns with uniform joint thicknesses and for accurate location of openings, movement-type joints, returns, and offsets. Avoid using less-than-half-size units, particularly at corners, jambs, and, where possible, at other locations.

B. Bond Pattern for Exposed Masonry: Unless otherwise indicated, lay exposed masonry in bond pattern indicated on Drawings; do not use units with less than nominal 4-inch horizontal face dimensions at corners or jambs. Prior to installation review bond pattern with Architect.

C. Stopping and Resuming Work: Stop work by racking back units in each course from those in course below; do not tooth. When resuming work, clean masonry surfaces that are to receive mortar, remove loose masonry units and mortar, and wet brick if required before laying fresh masonry.

D. Built-in Work: As construction progresses, build in items specified in this and other Sections. Fill in solidly with masonry around built-in items.

E. Fill space between steel frames and masonry solidly with mortar, unless otherwise indicated.

F. Fill cores in hollow concrete masonry units with grout 24 inches under bearing plates, beams, lintels, posts, and similar items, unless otherwise indicated.

G. Build non-load-bearing interior partitions full height of story to underside of solid floor or roof structure above, unless otherwise indicated.

1. Install compressible filler in joint between top of partition and underside of structure above.
2. Fasten partition top anchors to structure above and build into top of partition. Grout cells of CMUs solidly around plastic tubes of anchors and push tubes down into grout to provide 1/2-inch clearance between end of anchor rod and end of tube. Space anchors 48 inches o.c., unless otherwise indicated.
3. Wedge non-load-bearing partitions against structure above with small pieces of tile, slate, or metal. Fill joint with mortar after dead-load deflection of structure above approaches final position.
4. At fire-rated partitions, treat joint between top of partition and underside of structure above to comply with Section 078440 – FIRE-RESISTIVE JOINT SYSTEMS.

3.4 MORTAR BEDDING AND JOINTING

A. Lay hollow brick and concrete masonry units as follows:

1. With face shells fully bedded in mortar and with head joints of depth equal to bed joints.
2. With webs fully bedded in mortar in all courses of piers, columns, and pilasters.
3. With webs fully bedded in mortar in grouted masonry, including starting course on footings.
4. With entire units, including areas under cells, fully bedded in mortar at starting course on footings where cells are not grouted.

B. Lay solid masonry units with completely filled bed and head joints; butter ends with sufficient mortar to fill head joints and shove into place. Do not deeply furrow bed joints or slush head joints.

C. Tool exposed joints slightly concave when thumbprint hard, using a jointer larger than joint thickness, unless otherwise indicated.

D. Cut joints flush for masonry walls to receive plaster or other direct-applied finishes (other than paint), unless otherwise indicated.

3.5 CAVITY WALLS

A. Bond wythes of cavity walls together using bonding system indicated on Drawings.

B. Keep cavities clean of mortar droppings and other materials during construction. Bevel beds away from cavity, to minimize mortar protrusions into cavity. Do not attempt to trowel or remove mortar fins protruding into cavity.

C. Coordinate and allow access for air and vapor barrier membrane installed in cavity under Section 072700 - AIR BARRIERS.

3.6 MASONRY JOINT REINFORCEMENT

A. General: Install entire length of longitudinal side rods in mortar with a minimum cover of 5/8 inch on exterior side of walls, 1/2 inch elsewhere. Lap reinforcement a minimum of 6 inches. Space reinforcement not more than 16 inches o.c.

B. Interrupt joint reinforcement at control and expansion joints, unless otherwise indicated.

C. Provide continuity at wall intersections by using prefabricated T-shaped units.

D. Provide continuity at corners by using prefabricated L-shaped units.

3.7 ANCHORING MASONRY TO STRUCTURAL MEMBERS

A. Anchor masonry to structural members where masonry abuts or faces structural members to comply with the following:

1. Provide an open space not less than 1 inch in width between masonry and structural member, unless otherwise indicated. Keep open space free of mortar and other rigid materials.
2. Anchor masonry to structural members with anchors embedded in masonry joints and attached to structure.

3. Space anchors as indicated, but not more than 24 inches o.c. vertically and 36 inches o.c. horizontally.

3.8 ANCHORING MASONRY VENEERS

A. Anchor masonry veneers with masonry-veneer anchors to comply with the following requirements:

1. Fasten screw-attached anchors through insulation and sheathing to wall framing and to concrete and masonry backup as applicable with metal fasteners of type indicated.
2. Embed tie sections in masonry joints. Provide air space indicated on the Drawings between back of masonry veneer and face of insulation.
3. Locate anchor sections to allow maximum vertical differential movement of ties up and down.
4. Space anchors as required by Code.

3.9 CONTROL AND EXPANSION JOINTS

A. General: Install control and expansion joint materials in unit masonry as masonry progresses. Do not allow materials to span control and expansion joints without provision to allow for in-plane wall or partition movement.

B. Form control joints in concrete masonry using one of the following methods:

1. Fit bond-breaker strips into hollow contour in ends of concrete masonry units on one side of control joint. Fill resultant core with grout and rake out joints in exposed faces for application of sealant.
2. Install preformed control-joint gaskets designed to fit standard sash block.
3. Install interlocking units designed for control joints. Install bond-breaker strips at joint. Keep head joints free and clear of mortar or rake out joint for application of sealant.
4. Install temporary foam-plastic filler in head joints and remove filler when unit masonry is complete for application of sealant.

C. Form expansion joints in brick made from clay or shale as follows:

1. Build flanges of metal expansion strips into masonry. Lap each joint 4 inches in direction of water flow. Seal joints below grade and at junctures with horizontal expansion joints if any.
2. Build flanges of factory-fabricated, expansion-joint units into masonry.
3. Build in compressible joint fillers where indicated.
4. Form open joint full depth of brick wythe and of width indicated, but not less than 3/8 inch for installation of sealant and backer rod specified in Section 079200 - JOINT SEALANTS.

D. Provide horizontal, pressure-relieving joints by either leaving an air space or inserting a compressible filler of width required for installing sealant and backer rod specified in Section 079200 - JOINT SEALANTS but not less than 3/8 inch.

1. Locate horizontal, pressure-relieving joints beneath shelf angles supporting masonry.

3.10 LINTELS

A. Install steel lintels where indicated.

B. Provide minimum bearing of 8 inches at each jamb, unless otherwise indicated.

3.11 FLASHING, WEEP HOLES, CAVITY DRAINAGE, AND VENTS

A. General: Install embedded flashing and weep holes in masonry at shelf angles, lintels, ledges, other obstructions to downward flow of water in wall, and where indicated.

B. Install flashing as follows, unless otherwise indicated:

1. Prepare masonry surfaces so they are smooth and free from projections that could puncture flashing. Where flashing is within mortar joint, place through-wall flashing on sloping bed of mortar and cover with mortar. Before covering with mortar, seal penetrations in flashing with adhesive, sealant, or tape as recommended by flashing manufacturer.
2. At multiwythe masonry walls, including cavity walls, extend flashing through outer wythe, turned up a minimum of 8 inches, and 1-1/2 inches into the inner wythe. Form 1/4-inch hook in edge of flashing embedded in inner wythe.
3. At masonry-veneer walls, extend flashing through veneer, across air space behind veneer, and up face of sheathing at least 8 inches; with upper edge covered with elastomeric membrane, lapping at least 4 inches.
4. At lintels and shelf angles, extend flashing a minimum of 6 inches into masonry at each end. At heads and sills, extend flashing 6 inches at ends and turn up not less than 2 inches to form end dams.
5. Install air barrier transition strips to seal embedded flashings in masonry to air barrier membrane in accordance with Section 072700 – AIR BARRIERS.

C. Install reglets and nailers for flashing and other related construction where they are shown to be built into masonry.

D. Install metal drip edge plate in accordance with architectural details and manufacturer’s requirements.

E. Install weep holes in head joints in exterior wythes of first course of masonry immediately above embedded flashing and as follows:

1. Use specified weep/vent products to form weep holes.
2. Space weep holes 24 inches o.c., unless otherwise indicated.

F. Place cavity drainage material in cavities to comply with configuration requirements for cavity drainage material in Part 2 “Miscellaneous Masonry Accessories” Article.

G. Install vents in head joints in exterior wythes at spacing indicated.

3.12 REINFORCED UNIT MASONRY INSTALLATION

A. Temporary Formwork and Shores: Construct formwork and shores as needed to support reinforced masonry elements during construction.

1. Construct formwork to provide shape, line, and dimensions of completed masonry as indicated. Make forms sufficiently tight to prevent leakage of mortar and grout. Brace, tie, and support forms to maintain position and shape during construction and curing of reinforced masonry.
2. Do not remove forms and shores until reinforced masonry members have hardened sufficiently to carry their own weight and other temporary loads that may be placed on them during construction.

B. Placing Reinforcement: Comply with requirements in ACI 530.1/ASCE 6/TMS 602.

C. Grouting: Do not place grout until entire height of masonry to be grouted has attained enough strength to resist grout pressure. Comply with requirements in ACI 530.1/ASCE 6/TMS 602 for cleanouts and for grout placement, including minimum grout space and maximum pour height.

3.13 FIELD QUALITY CONTROL

A. Inspectors: Owner will engage qualified independent inspectors to perform inspections and prepare reports. Allow inspectors access to scaffolding and work areas, as needed to perform inspections. Place grout only after inspectors have verified compliance of grout spaces and grades, sizes, and locations of reinforcement.

B. Testing Agency: Engage a qualified independent testing and inspecting agency to perform field tests and inspections indicated below and prepare test reports. Retesting of materials failing to comply with specified requirements shall be done at Contractor’s expense.

C. Testing Frequency: One set of tests for each 5000 sq. ft. of wall area or portion thereof. Test types as determined by the independent testing and inspection agency.

3.14 REPAIRING, POINTING, AND CLEANING

A. Remove and replace masonry units that are loose, chipped, broken, stained, or otherwise damaged or that do not match adjoining units. Install new units to match adjoining units; install in fresh mortar, pointed to eliminate evidence of replacement.

B. Pointing: During the tooling of joints, enlarge voids and holes, except weep holes, and completely fill with mortar. Point up joints, including corners, openings, and adjacent construction, to provide a neat, uniform appearance. Prepare joints for sealant application, around penetrations and where indicated.

C. In-Progress Cleaning: Clean unit masonry as work progresses by dry brushing to remove mortar fins and smears before tooling joints.

D. Final Cleaning: After mortar is thoroughly set and cured, clean exposed masonry as follows:

1. Remove large mortar particles by hand with wooden paddles and nonmetallic scrape hoes or chisels.
2. Test cleaning methods on sample wall panel; leave one-half of panel uncleaned for comparison purposes. Obtain Architect’s approval of sample cleaning before proceeding with cleaning of masonry.
3. Protect adjacent stone and nonmasonry surfaces from contact with cleaner by covering them with liquid strippable masking agent or polyethylene film and waterproof masking tape.

4. Wet wall surfaces with water before applying cleaners; remove cleaners promptly by rinsing surfaces thoroughly with clear water.
5. Clean concrete masonry by cleaning method indicated in NCMA TEK 8-2A applicable to type of stain on exposed surfaces.
6. Clean brick by bucket-and-brush hand-cleaning method described in BIA Technical Notes 20.

3.15 MASONRY WASTE DISPOSAL

A. Salvageable Materials: Unless otherwise indicated, excess masonry materials are Contractor's property. At completion of unit masonry work, remove from Project site.

B. Waste Disposal as Fill Material: Dispose of clean masonry waste, including excess or soil-contaminated sand, waste mortar, and broken masonry units, by crushing and mixing with fill material as fill is placed.

1. Crush masonry waste to less than 4 inches in each dimension.
2. Mix masonry waste with at least two parts of specified fill material for each part of masonry waste. Fill material is specified in Division 31 - EARTHWORK.
3. Do not dispose of masonry waste as fill within 18 inches of finished grade.

C. Excess Masonry Waste: Remove excess clean masonry waste that cannot be used as fill, as described above, and other masonry waste, and legally dispose of off the Site.

END OF SECTION

SECTION 061000

ROUGH CARPENTRY

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Framing with dimension lumber.
2. Framing with engineered wood products.
3. Wood blocking, cants, and nailers.
4. Plywood backing panels.

1.3 DEFINITIONS

A. Exposed Framing: Framing not concealed by other construction.

B. Dimension Lumber: Lumber of 2 inches nominal or greater but less than 5 inches nominal in least dimension.

C. Lumber grading agencies, and the abbreviations used to reference them, include the following:

1. NeLMA: Northeastern Lumber Manufacturers' Association.
2. NLGA: National Lumber Grades Authority.
3. RIS: Redwood Inspection Service.
4. SPIB: The Southern Pine Inspection Bureau.
5. WCLIB: West Coast Lumber Inspection Bureau.
6. WWPA: Western Wood Products Association.

1.4 SUBMITTALS

A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.

1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Indicate type of preservative used, net amount of preservative retained, and chemical treatment manufacturer's written instructions for handling, storing, installing, and finishing treated material.
2. Include data for fire-retardant treatment from chemical treatment manufacturer and

certification by treating plant that treated materials comply with requirements. Include physical properties of treated materials, both before and after exposure to elevated temperatures when tested according to ASTM D 5516 and ASTM D 5664.

3. For products receiving a waterborne treatment, include statement that moisture content of treated materials was reduced to levels specified before shipment to Project site.
4. Include copies of warranties from chemical treatment manufacturers for each type of treatment.

B. Material Certificates: For dimension lumber specified to comply with minimum allowable unit stresses. Indicate species and grade selected for each use and design values approved by the ALSC Board of Review.

1.5 QUALITY ASSURANCE

A. Testing Agency Qualifications: For testing agency providing classification marking for fire-retardant treated material, an inspection agency acceptable to authorities having jurisdiction that periodically performs inspections to verify that the material bearing the classification marking is representative of the material tested.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Stack lumber, plywood, and other panels; place spacers between each bundle to provide air circulation. Provide for air circulation around stacks and under coverings.

PART 2 PRODUCTS

2.1 DECK FRAMING

A. Lumber: DOC PS 20 and applicable rules of lumber grading agencies certified by the American Lumber Standards Committee Board of Review.

1. Factory mark each piece of lumber with grade stamp of grading agency.
2. For exposed lumber indicated to receive a stained or natural finish, mark grade stamp on end or back of each piece or omit grade stamp and provide certificates of grade compliance issued by grading agency.
3. Where nominal sizes are indicated, provide actual sizes required by DOC PS 20 for moisture content specified. Where actual sizes are indicated, they are minimum dressed sizes for dry lumber.
4. Provide dressed lumber, S4S, unless otherwise indicated.

B. Preservative Treatment by Pressure Process: AWPA U1; Use Category UC3b for exterior construction not in contact with the ground, and Use Category UC4a for items in contact with the ground.

1. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium. Do not use inorganic boron (SBX) for sill plates.
2. For exposed items indicated to receive a stained or natural finish, use chemical formulations that do not require incising, contain colorants, bleed through, or otherwise adversely affect finishes.

C. Kiln-dry material after treatment to a maximum moisture content of 19 percent for lumber and 15

percent for plywood. Do not use material that is warped or does not comply with requirements for untreated material.

D. Mark each treated item with the treatment quality mark of an inspection agency approved by the American Lumber Standards Committee Board of Review.

E. Fasteners: Type 304 stainless steel.

1. Where carpentry is exposed to weather, in ground contact, pressure-preservative treated, or in area of high relative humidity, provide fasteners of Type 304 stainless steel.

F. Nails, Wire, Brads, and Staples: FS FF-N-105.

G. Power-Driven Fasteners: CABO NER-272.

H. Wood Screws: ASME B18.6.1.

I. Screws for Fastening to Cold-Formed Metal Framing: ASTM C 954, except with wafer heads and reamer wings, length as recommended by screw manufacturer for material being fastened.

J. Bolts: Steel bolts complying with ASTM A 307, Grade A with ASTM A 563 hex nuts and, where indicated, flat washers.

K. Expansion Anchors: Anchor bolt and sleeve assembly of material indicated below with capability to sustain, without failure, a load equal to 6 times the load imposed when installed in unit masonry assemblies and equal to 4 times the load imposed when installed in concrete as determined by testing per ASTM E 488 conducted by a qualified independent testing and inspecting agency.

1. Material: Carbon-steel components, zinc plated to comply with ASTM B 633, Class Fe/Zn 5; except provide Type 304 stainless steel where in contact with pressure-preservative treated wood.

2.2 METAL FRAMING ANCHORS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Cleveland Steel Specialty Co.
2. KC Metals Products, Inc.
3. Phoenix Metal Products, Inc.
4. Simpson Strong-Tie Co., Inc.
5. USP Structural Connectors.

B. Allowable Design Loads: Provide products with allowable design loads, as published by manufacturer, that meet or exceed those indicated. Manufacturer's published values shall be determined from empirical data or by rational engineering analysis and demonstrated by comprehensive testing performed by a qualified independent testing agency.

C. Galvanized-Steel Sheet: Hot-dip, zinc-coated steel sheet complying with ASTM A 653/A 653M, G60 coating designation.

1. Use for interior locations unless otherwise indicated.

D. Hot-Dip, Heavy-Galvanized Steel Sheet: ASTM A 653/A 653M; structural steel (SS), high-strength low-alloy steel Type A (HSLAS Type A), or high-strength low-alloy steel Type B (HSLAS Type B); G185 coating designation; and not less than 0.036 inch thick.

1. Use for wood-preservative-treated lumber and where indicated.

E. Joist Hangers: U-shaped joist hangers with 2-inch-long seat and 1-1/4-inch-wide nailing flanges at least 85 percent of joist depth.

1. Thickness: 0.062 inch.

F. I-Joist Hangers: U-shaped joist hangers with 2-inch-long seat and 1-1/4-inch-wide nailing flanges full depth of joist. Nailing flanges provide lateral support at joist top chord.

1. Thickness: 0.062 inch.

G. Rafter Tie-Downs: Bent strap tie for fastening rafters or roof trusses to wall studs below, 1-1/2 inches wide by 0.050 inch thick.

H. Floor-to-Floor Ties: Flat straps, with holes for fasteners, for tying upper floor wall studs to band joists and lower floor studs, 1-1/4 inches wide by 0.050 inch thick by 36 inches long.

2.3 MISCELLANEOUS MATERIALS

A. Sill-Sealer Gaskets: Glass-fiber-resilient insulation, fabricated in strip form, for use as a sill sealer; 1-inch nominal thickness, compressible to 1/32 inch; selected from manufacturer's standard widths to suit width of sill members indicated.

B. Adhesive, Including Gluing Furring and Sleepers to Concrete or Masonry: Formulation complying with ASTM D 3498 that is approved for use indicated by adhesive manufacturer.

PART 3 EXECUTION

3.1 INSTALLATION, GENERAL

A. Discard units of material with defects that impair quality of carpentry and that are too small to use with minimum number of joints or optimum joint arrangement.

B. Set carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit carpentry to other construction; scribe and cope as needed for accurate fit. Locate furring, nailers, blocking, grounds, and similar supports to comply with requirements for attaching other construction.

C. Apply field treatment complying with AWPA M4 to cut surfaces of preservative-treated lumber and plywood.

D. Framing Standard: Comply with AF&PA's WCD 1, "Details for Conventional Wood Frame Construction," unless otherwise indicated.

E. Framing with Engineered Wood Products: Install engineered wood products to comply with manufacturer's written instructions.

F. Metal Framing Anchors: Install metal framing anchors to comply with manufacturer's written instructions. Install fasteners through each fastener hole.

G. Install sill sealer gasket to form continuous seal between sill plates and foundation walls.

H. Do not splice structural members between supports unless otherwise indicated.

I. Securely attach carpentry work as indicated and according to applicable codes and recognized standards.

J. Countersink fastener heads on exposed carpentry work and fill holes with wood filler.

K. Use fasteners of appropriate type and length. Predrill members when necessary to avoid splitting wood.

L. Provide fire blocking in furred spaces, stud spaces, and other concealed cavities as indicated and as follows:

1. Fire block furred spaces of walls, at each floor level, at ceiling, and at not more than 96 inches o.c. with solid wood blocking or noncombustible materials accurately fitted to close furred spaces.
2. Fire block concealed spaces of wood-framed walls and partitions at each floor level, at ceiling line of top story, and at not more than 96 inches o.c. Where fire blocking is not inherent in framing system used, provide closely fitted solid wood blocks of same width as framing members and 2-inch nominal-thickness.
3. Fire block concealed spaces between floor sleepers with same material as sleepers to limit concealed spaces to not more than 100 sq. ft. and to solidly fill space below partitions.
4. Fire block concealed spaces behind combustible cornices and exterior trim at not more than 20 feet o.c.

3.2 WOOD BLOCKING, AND NAILER INSTALLATION

A. Install where indicated and where required for attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.

B. Attach items to substrates to support applied loading. Recess bolts and nuts flush with surfaces, unless otherwise indicated.

3.3 WALL AND PARTITION FRAMING INSTALLATION

A. General: Provide single bottom plate and double top plates using members of 2-inch nominal thickness whose widths equal that of studs, except single top plate may be used for non-load-bearing partitions and for load-bearing partitions where framing members bearing on partition are located directly over studs. Fasten plates to supporting construction unless otherwise indicated.

1. For exterior walls, provide 2-by-6-inch nominal-size wood studs spaced 16 inches o.c. unless otherwise indicated.
2. For interior partitions and walls, provide 2-by-6-inch nominal-size wood studs spaced 16 inches o.c. unless otherwise indicated.
3. Provide continuous horizontal blocking at midheight of partitions more than 96 inches high, using members of 2-inch nominal thickness and of same width as wall or partitions.

B. Construct corners and intersections with three or more studs, except that two studs may be used for interior non-load-bearing partitions.

C. Frame openings with multiple studs and headers. Provide nailed header members of thickness equal to width of studs. Support headers on jamb studs.

1. For non-load-bearing partitions, provide double-jamb studs and headers not less than 4-inch nominal depth for openings 48 inches and less in width, 6-inch nominal depth for openings 48 to 72 inches in width, 8-inch nominal depth for openings 72 to 120 inches in width, and not less than 10-inch nominal depth for openings 10 to 12 feet in width.
2. For load-bearing walls, provide double-jamb studs for openings 60 inches and less in width, and triple-jamb studs for wider openings. Provide headers of depth indicated.

D. Provide diagonal bracing in walls, at locations indicated, at 45-degree angle, full-story height unless otherwise indicated. Use 1-by-4-inch nominal-size boards, let-in flush with faces of studs.

3.4 PROTECTION

A. Protect wood that has been treated with inorganic boron (SBX) from weather. If, despite protection, inorganic boron-treated wood becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

B. Protect rough carpentry from weather. If, despite protection, rough carpentry becomes sufficiently wet that moisture content exceeds that specified, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

END OF SECTION

SECTION 064020

INTERIOR ARCHITECTURAL WOODWORK

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Wood cabinets.
2. Solid-surfacing-material countertops.
3. Shop finishing of interior woodwork to receive transparent finish.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 061000 - ROUGH CARPENTRY for wood furring, blocking, shims, and hanging strips required for installing woodwork and concealed within other construction before woodwork installation.

1.3 SUBMITTALS

A. Product Data: For each type of product specified, including cabinet hardware and accessories, and finishing materials and processes.

1. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements.
2. For engineered quartz and natural stone countertops, submit fabricator's letter certifying compliance with OSHA 1926.1153, Respirable Crystalline Silica.
3. For upholstery fabric and padding, documentation indicating that the materials contain no chemical flame retardants..
4. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements.
5. Include submittal of stone sealer manufacturer's recommended methods for application of impregnator and surface protection coatings based on testing of project specific stone countertop materials

B. Shop Drawings: Submit shop drawings showing locations of each item, dimensioned plans and elevations, large-scale details, attachment devices, and other components. Elevations shall be drawn at a scale of not less than 1/2" = 1'-0" (1:25). Details shall be drawn at a scale of not less than 3" = 1'-0" (1:5).

1. Show locations and sizes of furring, blocking, and hanging strips, including concealed blocking and reinforcement specified in other Sections.

a. Provide schedule of blocking required to support the Work of this Section.

2. Show locations and sizes of cutouts and holes for plumbing fixtures, electrical components and other items installed in architectural woodwork.
3. Show veneer leaves with dimensions, grain direction, exposed face, and identification numbers indicating the flitch and sequence within the flitch for each leaf.

C. Hardware Schedule: For each type of hardware used in architectural woodwork. Include keying requirements.

D. Samples for Verification:

1. Lumber with or for transparent finish, not less than 5 inches wide by 12 inches long for each species and cut, finished on 1 side and 1 edge.
2. Veneer leaves representative of and selected from flitches to be used for transparent-finished woodwork.

a. Submit step-type range sample sets of factory finished plywood and factory finished solid wood in size illustrating wood grain and specified finish, including edge banding detail and any veneer or solid edge glue joints.
b. Submit full length diagrams for veneers.
c. Submit pictures of specific wood materials.

3. Lumber and panel products for transparent finish, for each species and cut, finished on one side and one edge. Furnish lumber in 12 inch lengths, furnish panel samples in 12 inch squares.
4. Solid-surfacing materials, 4 inches square, showing edge condition.
5. Decorative Hardware: One of each type, including locks.
6. Metal Trim Shapes: Thee samples of each type and finish, 12 inches long.

E. Qualification Data: For Installer and fabricator.

1.4 QUALITY ASSURANCE

A. Fabricator Qualifications: Shop that employs skilled workers who custom-fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.

B. Installer Qualifications:

1. Fabricator shall comply with OSHA 1926.1153, Respirable Crystalline Silica, and does not dry-cut engineered-quartz and natural stone materials.
2. Fabricator shall be certified for chain of custody by an FSC-accredited certification body.

C. Source Limitations: Engage a qualified woodworking firm to assume undivided responsibility for production of interior architectural woodwork with blueprint-matched wood veneers and components.

D. Quality Standard: Unless otherwise indicated, comply with AWI/AWMAC/WI's "Architectural Woodwork Standards," latest edition, including errata, for grades of interior architectural woodwork indicated for construction, finishes, installation, and other requirements.

E. Fire-Test-Response Characteristics: Where fire-retardant materials or products are indicated, provide materials and products with specified fire-test-response characteristics as determined

by testing identical products per test method indicated by UL, ITS, or another testing and inspecting agency acceptable to authorities having jurisdiction. Identify with appropriate markings of applicable testing and inspecting agency in the form of separable paper label or, where required by authorities having jurisdiction, imprint on surfaces of materials that will be concealed from view after installation.

1. Fire-Test-Response Characteristics of Upholstery Fabric and Padding: Comply with California Technical Bulletin 117-2013 Update, with no chemical flame retardants.

F. Mockups: Build mockups to verify selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Confirm size and type of mock-ups with Architect with sufficient time in schedule for fabrication and modifications if required.
2. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

G. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Protect woodwork during transit, delivery, storage, and handling to prevent damage, soilage, and deterioration. Do not deliver woodwork until painting, wet work, grinding, and similar operations that could damage, soil, or deteriorate woodwork have been completed in installation areas. If woodwork must be stored in other than installation areas, store only in areas whose environmental conditions meet requirements specified in "Field Conditions" Article.

1.6 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install woodwork until building is enclosed, wet work is complete, and HVAC system is operating and maintaining temperature and relative humidity at occupancy levels during the remainder of the construction period.

1. The HVAC systems as specified elsewhere may not provide for humidity controls. The expected ranges of relative humidity are expected to be as high as 55 percent to a low of uncontrolled during the heating system. Comply with AWI Section 2, Care and Storage.

B. Field Measurements: Where woodwork is indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication, and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

1. Locate concealed framing, blocking, and reinforcements that support woodwork by field measurements before being enclosed, and indicate measurements on Shop Drawings.
2. Established Dimensions: Where field measurements cannot be made without delaying the Work, establish dimensions and proceed with fabricating woodwork without field measurements. Provide allowance for trimming at site, and coordinate construction to ensure that actual dimensions correspond to established dimensions.

1.7 COORDINATION

A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of Work specified in other Sections to ensure that interior architectural woodwork can be supported and installed as indicated.

1.8 PREINSTALLATION COORDINATION MEEETING

A. Convene a meeting at the Project site, prior to installation of architectural woodwork, to review the substrate preparation, installation and coordination with other trades, special details and conditions, and other topics related to the architectural woodwork. The preinstallation meeting shall include the Architect, the Contractor, architectural woodworker, and any subcontractors affected by the architectural woodwork installation.

PART 2 - PRODUCTS

2.1 BASIS-OF-DESIGN

A. Basis-of-Design Products: Refer to the Finish Schedule on the Drawings.

2.2 MATERIALS

A. General: Provide materials that comply with requirements of AWI/AWMAC/WI's "Architectural Woodwork Standards" for each type of woodwork and quality grade specified, unless otherwise indicated.

B. Wood Veneers and Lumber: Provide AWI Custom Grade materials and workmanship, unless otherwise indicated. For species not listed in the AWI comply with the following:

1. Provide AWI Lumber Grade 1 and AWI Grade A Veneer, book-matched, minimum 6 inch face veneer width. Kiln dry to 6-8 percent moisture content. Components shall be free of defects and sapwood. Match adjacent pieces for color and grain pattern.
2. Single-Source Requirement for Wood Veneers and Solids: Intent is to provide wood which matches as closely as possible throughout the project. Provide wood veneers and solids from the same distributor, and from the same flitches and solids sources to the greatest extent possible.

C. Wood Species and Cut for Transparent Finish: Plain-sliced white maple with clear finish.

1. Architect’s control samples for transparent finish, veneer grain and figure characteristics are available for review at the office of the Architect.
2. Veneer Matching Requirements:

    a. Matching Between Adjacent Veneer Leaves: Book match and architectural end match.
    b. Matching Within Individual Panel Faces: Balance and Center Match.
    c. Method of Matching Panels: Blueprint-matched panels and components.

D. Composite Wood Products: Comply with the following:

1. Medium-Density Fiberboard (MDF): ANSI A208.2, Grade MD, made with binder containing no added urea formaldehyde.
2. Particleboard: ANSI A208.1, Grade M-2 Exterior Glue.

3. Plywood: Marine grade.
4. Softwood Plywood: DOC PS 1, Medium Density Overlay (MDO).
5. Veneer-Faced Panel Products (Hardwood Plywood): HPVA HP-1.

    a. Resin impregnated paper backs are not permitted. Backs shall be of compatible hardwood species and cut. Contact adhesive is not permitted..
    b. MDO and OSB are not permitted.

E. Solid-Surfacing Material: Homogeneous solid sheets of filled plastic resin complying with ISFA-2.

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Avonite Surfaces; Aristech Surfaces.
    b. E. I. du Pont de Nemours and Company; Corian.
    c. Formica Corporation.
    d. LG Hausys; Hi-Macs.
    e. Nevamar.
    f. Wilsonart LLC.

F. Tempered Float Glass for Cabinet: ASTM C 1048, Kind FT, Condition A, Type I, Class 1 (clear), Quality-Q3, with exposed edges seamed before tempering, 1/4 inch (6 mm) thick, unless otherwise indicated.

2.3 FIRE-RETARDANT-TREATED MATERIALS

A. General: Where fire-retardant-treated materials are indicated, use materials complying with requirements in this Article, that are acceptable to authorities having jurisdiction, and with fire-test-response characteristics specified.

1. Do not use treated materials that do not comply with requirements of referenced woodworking standard or that are warped, discolored, or otherwise defective.
2. Use fire-retardant-treatment formulations that do not bleed through or otherwise adversely affect finishes. Do not use colorants to distinguish treated materials from untreated materials.
3. Identify fire-retardant-treated materials with appropriate classification marking of UL, U.S. Testing, Timber Products Inspection, or another testing and inspecting agency acceptable to authorities having jurisdiction.

B. Fire-Retardant-Treated Lumber and Plywood by Pressure Process: Comply with performance requirements of AWPA C20 (lumber) and AWPA C27 (plywood). Use the following treatment type:

1. Exterior Type: Organic-resin-based formulation thermally set in wood by kiln drying.
2. Mill lumber before treatment and implement special procedures during treatment and drying processes that prevent lumber from warping and developing discolorations from drying sticks or other causes, marring, and other defects affecting appearance of treated woodwork.
3. Kiln-dry materials before and after treatment to levels required for untreated materials.

C. Fire-Retardant Particleboard: Panels complying with the following requirements, made from softwood particles and fire-retardant chemicals mixed together at time of panel manufacture to

achieve flame-spread index of 25 or less and smoke-developed index of 25 or less per ASTM E 84.

1. Basis-of-Design: Arauco NA; Duraflake FR.

D. Fire-Retardant Fiberboard: Medium-density fiberboard panels complying with ANSI A208.2, made from softwood fibers, synthetic resins, and fire-retardant chemicals mixed together at time of panel manufacture to achieve flame-spread index of 25 or less and smoke-developed index of 200 or less per ASTM E 84.

1. Basis-of-Design: Roseburg; Medite FR.

2.4 CABINET HARDWARE AND ACCESSORIES

A. General: Provide cabinet hardware and accessory materials associated with architectural cabinet, except for items specified in Section 087100 - DOOR HARDWARE.

B. Catches: Magnetic, complying with BHMA A156.9, B03141 for single doors and B03161 for double doors.

C. Hardware Standard: Comply with BHMA A156.9 for items indicated by referencing BHMA numbers or items referenced to this standard.

D. Butt Hinges: 2-3/4-inch (70-mm), five-knuckle steel hinges made from 0.095-inch- (2.4-mm-) thick metal, and as follows:

1. Semiconcealed Hinges for Flush Doors: ANSI/BHMA A156.9, B01361.
2. Semiconcealed Hinges for Overlay Doors: ANSI/BHMA A156.9, B01521.

E. Wire Pulls: Back mounted, fabricated from satin finished stainless steel (US32D), complying with BHMA A156.9, B52011, unless otherwise indicated.

F. Drawer Slides: BHMA A156.9, B05091; side mounted and extending under bottom edge of drawer; full-extension type; epoxy-coated-steel with steel ball-bearings; of the following grades:

1. Type: Heavy-Duty (Grade 1HD-100 and Grade 1HD-200).
2. Pencil Drawer Slides: 3/4 extension carburized steel ball bearing, side mounting, 45 lbs. capacity medium duty load rating, cold rolled steel slide members and ball retainers, bright electro zinc plate finish.
3. Drawers less than 4 inches (102 mm) deep: Full extension carburized steel ball bearing, side mounting, 200 lb. capacity heavy duty load rating, cold rolled steel slide members and ball retainers, cushioned in and outstops, detent-in, progressive action, positive stop, bright electro zinc plate finish.
4. Drawers greater than 4 inches (102 mm) but less than 8 inches (203 mm) deep: Full extension carburized steel ball bearing, side mounting, 200 lb. capacity heavy duty load rating, cold rolled steel slide members and ball retainers, cushioned in and outstops, detent-in, progressive action, positive stop, bright electro zinc plate finish.
5. Drawers greater than 8 inches (203 mm) deep: Full extension carburized steel ball bearing, rail mounting, 150 lb. capacity heavy duty load rating, cold rolled steel slide members and ball retainers, cushioned in and outstops, detent-in, progressive action, positive stop, bright electro zinc plate finish.
6. Refuse Cabinets: Full extension carburized steel ball bearing, bottom mounting, 175 lb. capacity heavy duty load rating, cold rolled steel slide members and ball retainers,

cushioned in and outstops, progressive action, positive stop, bright electro zinc plate finish.

G. Aluminum Slides for Sliding Glass Doors: BHMA A156.9, B07063.

H. Silencers: Provide rubber silencers on jamb and/or head and sill strike areas of all cabinet doors and drawers, 2 for paired doors, and 3 for single doors. Silencers shall be approximately 1/4-inch (6.4-mm) diameter, color compatible with adjacent finish.

I. Door and Drawer Locks: Teacher's cabinets shall be furnished with cabinet locks on both doors. Other cabinets shall be furnished with cabinet locks as indicated on the drawings. Finish exposed portions of locks to match cabinet pull finish. Furnish 2 keys with each lock and key all locks inside one room alike and provide masterkey for all locks in Project.

1. Door Locks: BHMA A156.11, E07121.
2. Drawer Locks: BHMA A156.11, E07041.
3. Teacher's cabinets shall have SFIC format compatible locks. Other locks shall be standard cabinet locks.

J. Grommets for Cable Passage through Countertops: Metal grommets and caps with slot for wire passage.

K. Exposed Hardware Finishes: Unless otherwise specified above, or on the Drawings, all exposed portions of the woodwork hardware shall comply with BHMA A156.18 for BHMA finish number indicated.

1. Satin Stainless Steel: BHMA 630.

L. Screws: Select material, type, size, and finish required for each use. Comply with ASME B18.6.1.

M. Nails, Wire, Brads, and Staples: Select material, type, size, and finish required for each use.

1. ASTM F 1667 for driven fasteners such as nails, spikes and staples.
2. ASTM F 547 for nails used with wood and wood based products.

N. Anchors: Select material, type, size, and finish required by each substrate for secure anchorage. Provide toothed steel or lead expansion bolt devices for drilled-in-place anchors.

O. Blind Splines: Specialty devices, as required for tight butt joining, types and size as recommended by woodwork fabricator.

P. Covercaps: Where mortises of fastener heads, or draw downs are exposed (blind holes) in finished work, provide black plastic covercaps.

Q. Dual-Row Shelf Supports:

1. Basis-of-Design: Knape & Vogt; Dual-Row Standards Shelf Supports.
2. Mounting: Recessed into casework.

2.5 MISCELLANEOUS MATERIALS

A. Furring, Blocking, Shims, and Hanging Strips: Fire-retardant-treated softwood lumber, kiln dried to less than 15 percent moisture content.

B. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide nonferrous-metal or hot-dip galvanized anchors and inserts on inside face of exterior walls and elsewhere as required for corrosion resistance. Provide toothed-steel or lead expansion sleeves for drilled-in-place anchors.

C. Installation Adhesives and Wood Glues: Formulations approved for use indicated by adhesive manufacturer.

2.6 FABRICATION, GENERAL

A. Wood Moisture Content: Comply with requirements of referenced quality standard for wood moisture content in relation to ambient relative humidity during fabrication and in installation areas.

B. Sand fire-retardant-treated wood lightly to remove raised grain on exposed surfaces before fabrication.

C. Fabricate woodwork to dimensions, profiles, and details indicated. Ease edges to radius indicated for the following:

1. Corners of Cabinet and Edges of Solid-Wood (Lumber) Members and Rails: 1/16 inch.

D. Complete fabrication, including assembly, finishing, and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.

E. Shop-cut openings to maximum extent possible to receive hardware, appliances, plumbing fixtures, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

1. Seal edges of openings in countertops with a coat of varnish.

F. Install glass to comply with applicable requirements in Section 088000 - GLAZING and in GANA's "Glazing Manual." For glass in wood frames, secure glass with removable stops.

2.7 INTERIOR FRAMES AND JAMBS FOR TRANSPARENT FINISH

A. AWI Grade: Custom.

B. Wood Species and Cut: As specified hereinabove

C. For frames or jambs wider than available lumber, use veneered construction. Do not glue for width.

D. Fire-Rated Interior Frames and Jambs Where Indicated: Products fabricated from fire-retardant particleboard or fire-retardant medium-density fiberboard with veneered, exposed surfaces and listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire ratings indicated, based on testing according to NFPA 252.

1. Fire Rating: 20 minutes.

2.8 INTERIOR FRAMES AND JAMBS FOR OPAQUE FINISH

A. AWI Grade: Custom.

B. Wood Species: Any closed-grain hardwood.

2.9 WOOD CABINET FOR TRANSPARENT FINISH

A. AWI Grade: Custom.

B. AWI Type of Cabinet Construction: Flush overlay.

C. Wood Species and Cut for Exposed Surfaces: As specified hereinabove.

1. Grain Direction: Vertically for drawer fronts, doors, and fixed panels.
2. Matching of Veneer Leaves: Book match.
3. Vertical Matching of Veneer Leaves: End match.
4. Veneer Matching within Panel Face: Running match.
5. Veneer Matching within Room: Provide cabinet veneers in each room or other space from a single flitch with doors, drawer fronts, and other surfaces matched in a sequenced set with continuous match where veneers are interrupted perpendicular to the grain.

D. Semiexposed Surfaces: Provide surface materials indicated below:

1. Surfaces Other Than Drawer Bodies: Compatible species to that indicated for exposed surfaces, stained to match.
2. Drawer Sides and Backs: Solid-hardwood lumber, stained to match species indicated for exposed surfaces.
3. Drawer Bottoms: Hardwood plywood.

2.10 SOLID SURFACING MATERIAL COUNTERTOPS

A. General: Comply with AWI Section 11 and as follows.

B. Solid-Surfacing Material: Homogeneous solid sheets of filled plastic resin complying with ISFA-2.

C. Quality Standard: Unless otherwise indicated, comply with the "Architectural Woodwork Standards" for grades of countertops indicated for construction, finishes, installation, and other requirements.

1. Grade: Custom.
2. Pattern and Veining: Match adjacent pieces as acceptable to the Architect. Replace pieces which are not acceptable at no additional expense to the Owner.

D. Countertops: 1/2-inch- (12.7-mm -) thick, solid surface material with front edge built up with same material.

E. Backsplashes: 1/2-inch- (12.7-mm-) thick, solid surface material.

F. Sealants and Adhesives: As recommended by fabricator based on field conditions.

G. Fabricate tops with shop-applied edges, unless otherwise indicated. Comply with solid surface material manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.

1. Fabricate tops with shop-applied edges of materials and configuration indicated.
2. Fabricate with loose backsplashes for field assembly.
3. Install integral sink bowls in countertops in the shop.

H. Fabricate countertops in sections for joining in field, with joints at locations indicated.

I. Cutouts and Holes:

1. Undercounter Plumbing Fixtures: Make cutouts for fixtures in shop using template or pattern furnished by fixture manufacturer. Form cutouts to smooth, even curves.

   a. Provide vertical edges, slightly eased at juncture of cutout edges with top and bottom surfaces of countertop and projecting 3/16 inch (5 mm) into fixture opening.

2. Counter-Mounted Plumbing Fixtures: Prepare countertops in shop for field cutting openings for counter-mounted fixtures. Mark tops for cutouts and drill holes at corners of cutout locations. Make corner holes of largest radius practical.
3. Fittings: Drill countertops in shop for plumbing fittings, undercounter soap dispensers, and similar items.

J. Wire-Management Grommets: Circular, molded-plastic grommets and matching plastic caps with slot for wire passage.

2.11 SHOP FINISHING

A. General: Comply with AWI/AWMAC/WI's "Architectural Woodwork Standards" for factory finishing.

1. Finish architectural woodwork at fabrication shop as specified in this Section. Defer only final touchup, cleaning, and polishing until after installation.

B. Preparation for Finishing: Comply with referenced quality standard for sanding, filling countersunk fasteners, sealing concealed surfaces, and similar preparations for finishing architectural woodwork, as applicable to each unit of work.

1. Backpriming: Apply one coat of sealer or primer, compatible with finish coats, to concealed surfaces of woodwork. Apply two coats to back of paneling and to end-grain surfaces. Concealed surfaces of plastic-laminate-clad woodwork do not require backpriming when surfaced with plastic laminate, backing paper, or thermoset decorative panels.

C. Transparent Finish: Comply with requirements indicated below for grade, finish system, staining, and sheen with sheen measured on 60-degree gloss meter per ASTM D 523:

1. Grade: Same as item to be finished.
2. AWI Finish System 5: Conversion varnish.
3. Washcoat for Closed-Grain Woods: Apply washcoat sealer to woodwork made from closed-grain wood before staining and finishing
4. Staining: Match approved sample for color.
5. Open Finish for Open-Grain Woods: Do not apply filler to open-grain woods.
6. Sheen: Satin, 30-50 gloss units.
7. Effect: Partially filled pore.

PART 3 - EXECUTION

3.1 PREPARATION

A. Before installation, condition woodwork to average prevailing humidity conditions in installation areas.

B. Before installing architectural woodwork, examine shop-fabricated work for completion and complete work as required, including removal of packing and backpriming.

3.2 INSTALLATION

A. Grade: Install woodwork to comply with requirements for the same grade specified in Part 2 for fabrication of type of woodwork involved.

B. Assemble woodwork and complete fabrication at Project site to comply with requirements for fabrication in Part 2, to extent that it was not completed in the shop.

C. Install woodwork level, plumb, true, and straight. Shim as required with concealed shims. Install level and plumb (including tops) to a tolerance of 1/8 inch in 96 inches.

D. Scribe and cut woodwork to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.

E. Fire-Retardant-Treated Wood: Handle, store, and install fire-retardant-treated wood to comply with chemical treatment manufacturer's written instructions, including those for adhesives used to install woodwork.

F. Anchor woodwork to anchors or blocking built in or directly attached to substrates. Secure with countersunk, concealed fasteners and blind nailing as required for complete installation. Use fine finishing nails or finishing screws for exposed fastening, countersunk and filled flush with woodwork and matching final finish if transparent finish is indicated.

G. Cabinet: Install without distortion so doors and drawers fit openings properly and are accurately aligned. Adjust hardware to center doors and drawers in openings and to provide unencumbered operation. Complete installation of hardware and accessory items as indicated.

1. Install cabinet with no more than 1/8 inch in 96-inch sag, bow, or other variation from a straight line.
2. Maintain veneer sequence matching of cabinet with transparent finish.
3. Attach cabinet to walls with mechanical fasteners. Do not use adhesives, so that cabinet may be removed and salvaged in the future.

H. Countertops: Anchor securely by screwing through corner blocks of base cabinet or other supports into underside of countertop.

1. Align adjacent countertops and form seams to comply with manufacturer's written recommendations using adhesive in color to match countertop. Carefully dress joints smooth, remove surface scratches, and clean entire surface.
2. Install countertops with no more than 1/8 inch in 96-inch sag, bow, or other variation from a straight line.
3. Secure backsplashes to tops with concealed metal brackets at 16 inches and to walls with adhesive.

4. Calk space between backsplash and wall with sealant specified in Section 079200 - JOINT SEALANTS.
5. Do not field cut engineered-quartz and natural stone materials.

I. Touch up finishing work specified in this Section after installation of woodwork. Fill nail holes with matching filler where exposed.

3.3 ADJUSTING AND CLEANING

A. Repair damaged and defective woodwork, where possible, to eliminate functional and visual defects; where not possible to repair, replace woodwork. Adjust joinery for uniform appearance.

B. Clean, lubricate, and adjust hardware.

C. Clean woodwork on exposed and semi-exposed surfaces, using materials and methods recommended by manufacturer. Do not clean with abrasive or acidic cleaners. Touch up shop-applied finishes to restore damaged or soiled areas.

END OF SECTION

SECTION 078410

PENETRATION FIRESTOPPING

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Through-penetration firestopping systems for penetrations through fire-resistance-rated constructions, including both empty openings and openings containing penetrating items.
2. Installation Responsibility: Assign installation of through-penetration firestopping systems and fire-resistive joint systems in Project to a single qualified installer.

B. Related Work: The following items are not included in this Section and will be performed under the designated Sections:

1. Section 078440 - FIRE-RESISTIVE JOINT SYSTEMS for joints in or between fire-resistance-rated construction, at exterior curtain wall/floor intersections, and in smoke barriers.
2. Section 079200 - JOINT SEALANTS for standard joint sealants.

1.3 PERFORMANCE REQUIREMENTS

A. General: For penetrations through fire-resistance-rated constructions, including both empty openings and openings containing penetrating items, provide through-penetration firestopping systems that are produced and installed to resist spread of fire according to requirements indicated, resist passage of smoke and other gases, and maintain original fire-resistance rating of construction penetrated.

B. Penetrations in Fire-Resistance-Rated Walls: Provide penetration firestopping with ratings determined per ASTM E 814 or UL 1479, based on testing at a positive pressure differential of 0.01-inch wg (2.49 Pa).

1. Fire-resistance-rated walls include fire walls, fire-barrier walls, smoke-barrier walls and fire partitions.
2. F-Rating: Not less than the fire-resistance rating of constructions penetrated.

C. Penetrations in Horizontal Assemblies: Provide penetration firestopping with ratings determined per ASTM E 814 or UL 1479, based on testing at a positive pressure differential of 0.01-inch wg (2.49 Pa).

1. Horizontal assemblies include floors, floor/ceiling assemblies and ceiling membranes of

roof/ceiling assemblies.
2. F-Rating: At least 1 hour, but not less than the fire-resistance rating of constructions penetrated.
3. T-Rating: At least 1 hour, but not less than the fire-resistance rating of constructions penetrated except for floor penetrations within the cavity of a wall.

D. Penetrations in Smoke Barriers: Provide penetration firestopping with ratings determined per UL 1479.

1. L-Rating: Not exceeding 5.0 cfm/sq. ft. (0.025 cu. m/s per sq. m) of penetration opening at 0.30-inch wg (74.7 Pa) at both ambient and elevated temperatures.

E. Exposed Penetration Firestopping:

1. Provide products with flame-spread and smoke-developed indexes of less than 25 and 450, respectively, as determined per ASTM E 84.
2. For through-penetration firestopping systems exposed to view, traffic, moisture, and physical damage, provide products that, after curing, do not deteriorate when exposed to these conditions both during and after construction.
   a. For piping penetrations for plumbing and wet-pipe sprinkler systems, provide moisture-resistant through-penetration firestopping systems demonstrating no evidence of water leakage when tested according to UL 1479.
   b. For floor penetrations with annular spaces exceeding 4 inches in width and exposed to possible loading and traffic, provide firestopping systems capable of supporting floor loads involved, either by installing floor plates or by other means.

F. For penetrations involving insulated piping, provide through-penetration firestopping systems not requiring removal of insulation.

1.4 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings: For each through-penetration firestopping system, show each type of construction condition penetrated, relationships to adjoining construction, and type of penetrating item. Include firestop design designation of qualified testing and inspecting agency that evidences compliance with requirements for each condition indicated.

1. Submit documentation, including illustrations, from a qualified testing and inspecting agency that is applicable to each through-penetration firestopping system configuration for construction and penetrating items.

C. Through-Penetration Firestop System Schedule: Indicate locations of each through-penetration firestopping system, along with the following information:

1. Types of penetrating items.
2. Types of constructions penetrated, including fire-resistance ratings and, where applicable, thicknesses of construction penetrated.
3. Through-penetration firestopping systems for each location identified by firestop design designation of qualified testing and inspecting agency.

D. Qualification Data: For Installer.

1.5 QUALITY ASSURANCE

A. Source Limitations: Obtain through-penetration firestopping systems, for each kind of penetration and construction condition indicated, through one source from a single manufacturer.

B. Installer Qualifications: Either a firm that has been approved by FMG according to FM Approval 4991, "Approval Standard for Firestop Contractors" or a firm experienced in installing through-penetration firestopping systems similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction of a minimum of five projects with a record of successful performance.

1. Qualifications include having the necessary experience, staff, and training to install manufacturer's products per specified requirements.

C. Fire-Test-Response Characteristics: Provide through-penetration firestopping systems that comply with the following requirements and those specified in Part 1 "Performance Requirements" Article:

1. Firestopping tests are performed by a qualified testing and inspecting agency. A qualified testing and inspecting agency is UL or another agency performing testing and follow-up inspection services for firestopping systems acceptable to authorities having jurisdiction.
2. Through-penetration firestopping systems are identical to those tested per testing standard referenced in "Part 1 Performance Requirements" Article. Provide rated systems complying with the following requirements:
   a. Through-penetration firestopping system products bear classification marking of qualified testing and inspecting agency.
   b. Through-penetration firestopping systems correspond to those indicated by reference to through-penetration firestopping system designations listed in the UL “Fire Resistance Directory.”

D. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver through-penetration firestopping system products to Project site in original, unopened containers or packages with intact and legible manufacturers' labels identifying product and manufacturer, date of manufacture, lot number, shelf life if applicable, qualified testing and inspecting agency's classification marking applicable to Project, curing time, and mixing instructions for multicomponent materials.

B. Store and handle materials for through-penetration firestopping systems to prevent their deterioration or damage due to moisture, temperature changes, contaminants, or other causes.

1.7 PROJECT CONDITIONS

A. Environmental Limitations: Do not install firestopping systems when ambient or substrate temperatures are outside limits permitted by through-penetration firestopping system manufacturers or when substrates are wet due to rain, frost, condensation, or other causes.

B. Install and cure firestopping materials per manufacturer's written instructions using natural means of ventilation or, where this is inadequate, forced-air circulation.

1.8 COORDINATION

A. Jobsite conditions of each through-penetration firestopping system must meet all details of the UL-Classified System selected. If jobsite conditions do not match any UL-classified systems, contact firestop manufacturer for alternative systems or Engineer Judgment Drawings.

1. Verify that the schedule is current at the time of construction, and that each referenced system is suitable for the intended application.

B. Coordinate work with other trades to assure that penetration-opening sizes are appropriate for penetrant locations.

C. Coordinate construction of openings and penetrating items to ensure that through-penetration firestopping systems are installed according to specified requirements.

D. Coordinate sizing of sleeves, openings, core-drilled holes, and cut openings to accommodate through-penetration firestopping systems.

E. Do not cover up through-penetration firestopping system installations that will become concealed behind other construction until each installation has been examined building inspector, if required by authorities having jurisdiction.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products and firestopping systems that may be incorporated into the Work include, but are not limited to the following:

1. Hilti, Inc.
2. RectorSeal.
3. Specified Technologies, Inc. (STI).
4. Tremco.
5. 3M; Fire Protection Products Division.

2.2 FIRESTOPPING MATERIALS

A. VOC Content: Penetration firestopping sealants and sealant primers shall comply with the following limits for VOC content:

1. Sealant Primers for Nonporous Substrates: 250 g/L.
2. Sealant Primers for Porous Substrates: 775 g/L.
3. Methylene chloride and perchloroethylene may not be intentionally added to sealants.

B. Compatibility: Provide through-penetration firestopping systems that are compatible with one

another; with the substrates forming openings; and with the items, if any, penetrating through-penetration firestopping systems, under conditions of service and application, as demonstrated by through-penetration firestopping system manufacturer based on testing and field experience.

C. Materials: Provide through-penetration firestopping systems containing primary materials and fill materials which are part of the tested assemblies indicated in the approved Through-Penetration Firestop System Schedule submittal. Fill materials are those referred to in directories of referenced testing and inspecting agencies as "fill," "void," or "cavity" materials.

1. Available Products: Subject to compliance with requirements, through-penetration firestopping products that may be incorporated into the Work include, but are not limited to the following:
   a. BioFireshield; RectorSeal Smoke and Acoustic Sealant.
   b. Hilti; CP 606 Flexible Firestop Sealant.
   c. Hilti; CP 653 BA Firestop Speed Sleeve.
   d. Hilti; FS-ONE MAX Intumescent Firestop Sealant.
   e. STI; SpecSeal LCI Intumescent Firestop Sealant.
   f. Tremco; TREMstop Acrylic.

D. Accessories: Provide components for each through-penetration firestopping system that are needed to install fill materials and to comply with Part 1 "Performance Requirements" Article. Use only components specified by through-penetration firestopping system manufacturer and approved by qualified testing and inspecting agency for firestopping systems indicated.

2.3 MIXING

A. For those products requiring mixing before application, comply with through-penetration firestopping system manufacturer's written instructions for accurate proportioning of materials, water (if required), type of mixing equipment, selection of mixer speeds, mixing containers, mixing time, and other items or procedures needed to produce products of uniform quality with optimum performance characteristics for application indicated.

PART 3 EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for opening configurations, penetrating items, substrates, and other conditions affecting performance of work.

1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning: Clean out openings immediately before installing through-penetration firestopping systems to comply with firestopping system manufacturer's written instructions and with the following requirements:

1. Remove from surfaces of opening substrates and from penetrating items foreign materials that could interfere with adhesion of through-penetration firestopping systems.
2. Clean opening substrates and penetrating items to produce clean, sound surfaces capable

of developing optimum bond with through-penetration firestopping systems. Remove loose particles remaining from cleaning operation.
3. Remove laitance and form-release agents from concrete.

B. Priming: Prime substrates where recommended in writing by through-penetration firestopping system manufacturer using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.

C. Taping: Use masking tape to prevent through-penetration firestopping systems from contacting adjoining surfaces that will remain exposed on completion of Work and that would otherwise be permanently stained or damaged by such contact or by cleaning methods used to remove smears from firestopping system materials. Remove tape as soon as possible without disturbing firestopping system's seal with substrates.

3.3 THROUGH-PENETRATION FIRESTOP SYSTEM INSTALLATION

A. General: Install through-penetration firestopping systems to comply with Part 1 "Performance Requirements" Article and with firestopping system manufacturer's written installation instructions and published drawings for products and applications indicated.

B. Install forming/damming/backing materials and other accessories of types required to support fill materials during their application and in the position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.

C. Install fill materials for firestopping systems by proven techniques to produce the following results:

1. Fill voids and cavities formed by openings, forming materials, accessories, and penetrating items as required to achieve fire-resistance ratings indicated.
2. Apply materials so they contact and adhere to substrates formed by openings and penetrating items.
3. For fill materials that will remain exposed after completing Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

3.4 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified independent testing and inspecting agency to perform field tests and inspections indicated below and prepare test reports, as required by 2015 IBC 1705.17 and 1705.17.1.

1. Independent inspecting agency shall comply with ASTM E 2174 requirements including those related to qualifications, conducting inspections, and preparing test reports
2. Cooperate with field quality control personnel. Allow inspectors access to scaffolding and work areas, as needed to perform inspections.

B. Repair or replace work where test results and inspections indicate that it does not comply with specified requirements.

C. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

D. Proceed with enclosing through-penetration firestopping systems with other construction only after inspection reports are issued and firestop installations comply with requirements.

3.5 CLEANING AND PROTECTING

A. Clean excess materials adjacent to openings as Work progresses by methods and with cleaning materials that are approved in writing by through-penetration firestopping system manufacturers and that do not damage materials in which openings occur.

B. Provide final protection and maintain conditions during and after installation that ensure that through-penetration firestopping systems are without damage or deterioration at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated through-penetration firestopping systems immediately and install new materials to produce systems complying with specified requirements.

END OF SECTION

This page left intentionally blank.

SECTION 078440

FIRE-RESISTIVE JOINT SYSTEMS

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the Work of this Section, including but not limited to fire-resistive joint systems for the following:

1. Floor-to-floor joints.
2. Floor-to-wall joints.
3. Head-of-wall joints.
4. Wall-to-wall joints.
5. Perimeter fire-resistive joint systems consisting of floor-to-wall joints between perimeter edge of fire-resistance-rated floor assemblies and exterior curtain walls.

B. Related Work: The following items are not included in this Section and will be performed under the designated Sections:

1. Section 078410 - PENETRATION FIRESTOPPING for firestopping.
2. Division 21 - FIRE SUPPRESSION for fire-protection piping penetrations.
3. Division 22 - PLUMBING for piping penetrations.
4. Division 23 - HEATING, VENTILATING AND AIR CONDITIONING for duct and piping penetrations.
5. Division 26 - ELECTRICAL for cable and conduit penetrations.

1.3 PERFORMANCE REQUIREMENTS

A. General: Provide fire-resistive joint systems that are produced and installed to resist spread of fire according to requirements indicated, resist passage of smoke and other gases, and maintain original fire-resistance rating of assembly in which fire-resistive joint systems are installed.

B. For fire-resistive systems exposed to view, provide products with flame-spread and smoke-developed indexes of less than 25 and 450, respectively, as determined per ASTM E 84.

1.4 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings: For each fire-resistive joint system, show each kind of construction condition in

which joints are installed; also show relationships to adjoining construction. Include fire-resistive joint system design designation of testing and inspecting agency acceptable to authorities having jurisdiction that demonstrates compliance with requirements for each condition indicated.

1. Submit documentation, including illustrations, from a qualified testing and inspecting agency that is applicable to each fire-resistive joint system configuration for construction and penetrating items.

C. Fire-Resistive Joint Systems Schedule: For each fire-resistive joint system. Include location and design designation of qualified testing agency.

1. Where Project conditions require modification to a qualified testing agency's illustration for a particular fire-resistive joint system condition, submit illustration, with modifications marked, approved by fire-resistive joint system manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly.

D. Product Certificates: For each type of fire-resistive joint system, signed by product manufacturer.

E. Qualification Data: For Installer.

F. Field quality-control test reports.

G. Research/Evaluation Reports: For each type of fire-resistive joint system.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: A firm experienced in installing through-penetration fire stop systems similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction of a minimum of five projects with a record of successful performance. Qualifications include having the necessary experience, staff, and training to install manufacturer's products per specified requirements. Evidence of FMG 4991 approval is acceptable for installer qualifications, but not mandatory.

B. Installation Responsibility: Assign installation of through-penetration firestop systems and fire-resistive joint systems in Project to a single qualified installer.

C. Source Limitations: Obtain fire-resistive joint systems, for each kind of joint and construction condition indicated, through one source from a single manufacturer.

D. Fire-Test-Response Characteristics: Provide fire-resistive joint systems that comply with the following requirements and those specified in Part 1 "Performance Requirements" Article:

1. Fire-resistance tests are performed by a qualified testing and inspecting agency. A qualified testing and inspecting agency is UL or another agency performing testing and follow-up inspection services for fire-resistive joint systems acceptable to authorities having jurisdiction.
2. Fire-resistive joint systems are identical to those tested per methods indicated in Part 1 "Performance Requirements" Article and comply with the following:

a. Fire-resistive joint system products bear classification marking of qualified testing and inspecting agency.
b. Fire-resistive joint systems correspond to those indicated by referencing system designations of the qualified testing and inspecting agency.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver fire-resistive joint system products to Project site in original, unopened containers or packages with qualified testing and inspecting agency's classification marking applicable to Project and with intact and legible manufacturers' labels identifying product and manufacturer, date of manufacture, lot number, shelf life, curing time, and mixing instructions for multicomponent materials.

B. Store and handle materials for fire-resistive joint systems to prevent their deterioration or damage due to moisture, temperature changes, contaminants, or other causes.

1.7 PROJECT CONDITIONS

A. Environmental Limitations: Do not install fire-resistive joint systems when ambient or substrate temperatures are outside limits permitted by fire-resistive joint system manufacturers or when substrates are wet due to rain, frost, condensation, or other causes.

B. Ventilate fire-resistive joint systems per manufacturer's written instructions by natural means or, if this is inadequate, forced-air circulation.

1.8 COORDINATION

A. Coordinate construction of joints to ensure that fire-resistive joint systems are installed according to specified requirements.

B. Coordinate sizing of joints to accommodate fire-resistive joint systems.

C. Do not cover up through-penetration firestop system installations that will become concealed behind other construction until each installation has been examined building inspector, if required by authorities having jurisdiction.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Available Products: Subject to compliance with requirements, fire-resistive joint systems that may be incorporated into the Work include, but are not limited to the following:

1. Hilti, Inc.
2. Metacaulk; RectorSeal Corporation.
3. Specified Technologies, Inc. (STI).
4. 3M; Fire Protection Products Division.

2.2 FIRE-RESISTIVE JOINT SYSTEMS

A. Low-Emitting Materials: Fire-resistive joint system sealants shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

B. VOC Content: Provide fire-resistive joint system sealants that comply with the following limits for VOC content:

1. Architectural Sealants: 250 g/L.
2. Sealant Primers for Nonporous Substrates: 250 g/L.
3. Sealant Primers for Porous Substrates: 775 g/L.
4. Methylene chloride and perchloroethylene may not be intentionally added to sealants.

C. General: Where required, provide fire-resistive joint systems that are produced and installed to resist spread of fire according to requirements indicated, resist passage of smoke and other gases, and maintain original fire-resistance rating of assemblies in or between which fire-resistive joint systems are installed. Fire-resistive joint systems shall accommodate building movements without impairing their ability to resist the passage of fire and hot gases.

D. Joints in or between Fire-Resistance-Rated Construction: Provide fire-resistive joint systems with ratings determined per ASTM E 1966 or UL 2079.

E. Joints at Exterior Curtain-Wall/Floor Intersections: Provide fire-resistive joint systems with rating determined by ASTM E 119 based on testing at a positive pressure differential of 0.01-inch wg (2.49 Pa) or ASTM E 2307.

1. Fire-Resistance Rating: Equal to or exceeding the fire-resistance rating of the floor assembly.

F. Joints in Smoke Barriers: Provide fire-resistive joint systems with ratings determined per UL 2079.

1. L-Rating: Not exceeding 5.0 cfm/ft (0.00775 cu. m/s x m) of joint at 0.30 inch wg (74.7 Pa) at both ambient and elevated temperatures.

G. Compatibility: Provide fire-resistive joint systems that are compatible with joint substrates, under conditions of service and application, as demonstrated by fire-resistive joint system manufacturer based on testing and field experience.

H. Accessories: Provide components of fire-resistive joint systems, including primers and forming materials, that are needed to install fill materials and to comply with Part 1 "Performance Requirements" Article. Use only components specified by fire-resistive joint system manufacturer and approved by the qualified testing and inspecting agency for systems indicated.

PART 3 EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for joint configurations, substrates, and other conditions affecting performance of work.

1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning: Clean joints immediately before installing fire-resistive joint systems to comply with fire-resistive joint system manufacturer's written instructions and the following requirements:

1. Remove from surfaces of joint substrates foreign materials that could interfere with adhesion of fill materials.
2. Clean joint substrates to produce clean, sound surfaces capable of developing optimum bond with fill materials. Remove loose particles remaining from cleaning operation.
3. Remove laitance and form-release agents from concrete.

B. Priming: Prime substrates where recommended in writing by fire-resistive joint system manufacturer using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.

C. Masking Tape: Use masking tape to prevent fill materials of fire-resistive joint system from contacting adjoining surfaces that will remain exposed on completion of Work and that would otherwise be permanently stained or damaged by such contact or by cleaning methods used to remove smears from fire-resistive joint system materials. Remove tape as soon as possible without disturbing fire-resistive joint system's seal with substrates or damaging adjoining surfaces.

3.3 INSTALLATION

A. General: Install fire-resistive joint systems to comply with Part 1 "Performance Requirements" Article and fire-resistive joint system manufacturer's written installation instructions for products and applications indicated.

B. Install forming/packing/backing materials and other accessories of types required to support fill materials during their application and in position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.

C. Install fill materials for fire-resistive joint systems by proven techniques to produce the following results:

1. Fill voids and cavities formed by openings and forming/packing/backing materials as required to achieve fire-resistance ratings indicated.
2. Apply fill materials so they contact and adhere to substrates formed by joints.
3. For fill materials that will remain exposed after completing Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

3.4 FIELD QUALITY CONTROL

A. Inspecting Agency: Owner will engage a qualified testing agency to perform tests and inspections and prepare test reports, as required by 2015 IBC 1705.17 and 1705.17.2. Independent inspecting agency shall comply with ASTM E 2393 requirements including those related to qualifications, conducting inspections, and preparing test reports.

B. Testing Services: Inspecting of completed installations of fire-resistive joint systems shall take place in successive stages as installation of fire-resistive joint systems proceeds. Do not proceed with installation of joint systems for the next area until inspecting agency determines completed work shows compliance with requirements.

1. Inspecting agency shall state in each report whether inspected fire-resistive joint systems comply with or deviate from requirements.

C. Remove and replace fire-resistive joint systems where inspections indicate that they do not comply with specified requirements.

D. Additional inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

E. Proceed with enclosing fire-resistive joint systems with other construction only after inspection reports are issued and fire-resistive joint systems comply with requirements.

3.5 CLEANING AND PROTECTING

A. Clean off excess fill materials adjacent to joints as Work progresses by methods and with cleaning materials that are approved in writing by fire-resistive joint system manufacturers and that do not damage materials in which openings occur.

B. Provide final protection and maintain conditions during and after installation that ensure fire-resistive joint systems are without damage or deterioration at time of Substantial Completion. If damage or deterioration occurs despite such protection, cut out and remove damaged or deteriorated fire-resistive joint systems immediately and install new materials to produce fire-resistive joint systems complying with specified requirements.

END OF SECTION

SECTION 079200

JOINT SEALANTS

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Joint sealants and fillers, at exterior and interior.

1.3 PERFORMANCE REQUIREMENTS

A. Provide elastomeric joint sealants that establish and maintain watertight and airtight continuous joint seals without staining or deteriorating joint substrates.

B. Provide joint sealants for interior applications that establish and maintain airtight and water-resistant continuous joint seals without staining or deteriorating joint substrates.

1.4 SUBMITTALS

A. Product Data: For each product indicated.

B. Samples for Verification: For each type and color of joint sealant required, provide Samples with joint sealants in 1/2-inch- wide joints formed between two 6-inch-long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.

C. Joint-Sealant Schedule: Include the following information:

1. Joint-sealant application, joint location, and designation.
2. Joint-sealant manufacturer and product name.
3. Joint-sealant formulation.
4. Joint-sealant color.

D. Qualification Data: For Installer and qualified testing agency.

E. Product Test Reports: Based on comprehensive testing of product formulations performed by a qualified testing agency, indicating that sealants comply with requirements.

F. Preconstruction Field Test Reports: Indicate which sealants and joint preparation methods resulted in optimum adhesion to joint substrates based on preconstruction testing specified in "Quality Assurance" Article.

G. Compatibility and Adhesion Test Reports: From sealant manufacturer, indicating the following:

1. Materials forming joint substrates and joint-sealant backings have been tested for compatibility and adhesion with joint sealants.
2. Interpretation of test results and written recommendations for primers and substrate preparation needed for adhesion.

H. Field Test Report Log: For each elastomeric sealant application.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: Manufacturer's authorized Installer who is approved or licensed for installation of elastomeric sealants required for this Project.

B. Product Testing: Test joint sealants using a qualified testing agency.

1. Testing Agency Qualifications: Qualified according to ASTM C 1021 to conduct the testing indicated.

C. Source Limitations: Obtain each type of joint sealant through one source from a single manufacturer.

D. Preconstruction Compatibility and Adhesion Testing: Submit to joint-sealant manufacturers, for testing indicated below, samples of materials that will contact or affect joint sealants.

1. Use manufacturer's standard test method to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of joint sealants to joint substrates.
   a. Adhesion Testing: Use ASTM C 794 to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of joint sealants to joint substrates.
   b. Compatibility Testing: Use ASTM C 1087 to determine sealant compatibility when in contact with joint sealant backing and glazing and gasket materials.
2. Schedule sufficient time for testing and analyzing results to prevent delaying the Work.
3. For materials failing tests, obtain joint-sealant manufacturer's written instructions for corrective measures including use of specially formulated primers.
4. Testing will not be required if joint-sealant manufacturers submit joint preparation data that are based on previous testing of current sealant products for adhesion to, and compatibility with, joint substrates and other materials matching those submitted.

E. Preconstruction Field-Adhesion Testing: Before installing elastomeric sealants, field test their adhesion to Project joint substrates as follows:

1. Locate test joints where indicated on Project or, if not indicated, as directed by Architect.
2. Conduct field tests for each application indicated below:
   a. Each type of elastomeric sealant and joint substrate indicated.
   b. Each type of nonelastomeric sealant and joint substrate indicated.
3. Notify Architect seven days in advance of dates and times when test joints will be erected.

a. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C 1193.
   1). For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.

4. Report whether sealant in joint connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each type of product and joint substrate. For sealants that fail adhesively, retest until satisfactory adhesion is obtained.
5. Evaluation of Preconstruction Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing, in absence of other indications of noncompliance with requirements, will be considered satisfactory. Do not use sealants that fail to adhere to joint substrates during testing.

F. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01.

1.6 PROJECT CONDITIONS

A. Do not proceed with installation of joint sealants under the following conditions:

1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
2. When joint substrates are wet.
3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

1.7 WARRANTY

A. Special Installer's Warranty: Installer's standard form in which Installer agrees to repair or replace elastomeric joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

B. Special Manufacturer's Warranty: Manufacturer's standard form in which elastomeric sealant manufacturer agrees to furnish elastomeric joint sealants to repair or replace those that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

C. Special warranties specified in this Article exclude deterioration or failure of joint sealants from the following:

1. Movement of the structure caused by stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.
2. Disintegration of joint substrates from natural causes exceeding design specifications.
3. Mechanical damage caused by individuals, tools, or other outside agents.
4. Changes in sealant appearance caused by accumulation of dirt or other atmospheric contaminants.

PART 2 PRODUCTS

2.1 MATERIALS, GENERAL

A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by sealant manufacturer, based on testing and field experience.

B. Colors of Exposed Joint Sealants: Provide colors as selected by the Architect from manufacturer's full range of standard and custom colors; maximum of five colors, three standard colors and two custom colors.

2.2 JOINT SEALANTS

A. Elastomeric Sealants: Comply with ASTM C 920 and other requirements indicated for each liquid-applied chemically curing sealant specified, including those referencing ASTM C 920 classifications for type, grade, class, and uses related to exposure and joint substrates.

B. Stain-Test-Response Characteristics: Elastomeric sealants shall be nonstaining to porous substrates. Provide products that have undergone testing according to ASTM C 1248 and have not stained porous joint substrates indicated for Project.

C. Suitability for Contact with Food: Where elastomeric sealants are indicated for joints that will come in repeated contact with food, provide products that comply with 21 CFR 177.2600 or ANSI/NSF Standard 51.

D. Exterior Silicone Sealant, Single-Component Neutral-Curing Type: ASTM C 920, Type S, Grade NS, Class 50, Use NT, M, G, A.

1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
   a. Dow Corning Corporation; 790.
   b. GE Silicones; SilPruf LM SCS2700.
   c. Pecora Corporation; 864 NST (low modulus type).
   d. Tremco Inc.; Spectrem 1.
2. Extent of Use: Exterior joints in vertical and soffit surfaces.

E. Exterior Urethane Sealant, Multicomponent Pourable (Self-Leveling) Type for Pedestrian Traffic: ASTM C 920, Type M, Grade P, Class 25, Use T, M, & O.

1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
   a. MAPEI Corporation; Mapeflex P2 SL.
   b. Pecora Corporation; Urexpan NR-200.
   c. Sika; Sikaflex-2c SL.
   d. Tremco Inc.; THC-901.
2. Extent of Use: Exterior joints in horizontal surfaces.

F. Interior Sanitary Silicone Sealant, Single-Component Mildew-Resistant, Acid-Curing (Acetoxy) Type: ASTM C 920, Type S, Grade NS, Class 25, Use NT, G, A, and O.

1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
   a. GE Silicones; Sanitary SCS1700.
   b. Pecora; 898 NST.
   c. Tremco; Tremsil 200.
2. Extent of Use: Interior sanitary joints at toilet rooms, kitchens, and other wet areas.

G. Interior Acrylic Latex Sealant: Acrylic latex or siliconized acrylic latex, ASTM C 834, Type OP, Grade NF; water-based (solvent-free) products.

1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
   a. Pecora Corporation; AC-20+ Silicone.
   b. Sherwin-Williams (S-W); Powerhouse 1100A.
   c. Tremco Inc.; Tremflex 834.
2. Extent of Use: Interior non-moving joints.

2.3 JOINT-SEALANT BACKING

A. Sealant Backing Material, General: Nonstaining; compatible with joint substrates, sealants, primers, and other joint fillers; and approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.

B. Cylindrical Sealant Backings: ASTM C 1330, Type B (bicellular material with a surface skin) or other type, as approved in writing by joint-sealant manufacturer for joint application indicated, and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.

1. Basis of Design: Armacell Canada Inc.; ITP Standard Backer Rod.

C. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint where such adhesion would result in sealant failure. Provide self-adhesive tape where applicable.

2.4 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting joint-sealant performance.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
2. Clean porous joint substrate surfaces by brushing, grinding, blast cleaning, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include concrete, masonry, unglazed surfaces of ceramic tile, and exterior insulation and finish systems.
3. Remove laitance and form-release agents from concrete.
4. Clean nonporous surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following metal, glass, porcelain enamel, and glazed surfaces of ceramic tile.

B. Joint Priming: Prime joint substrates, where recommended in writing by joint-sealant manufacturer, based on preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of sealant with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.

B. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.

C. Install sealant backings of type indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.

1. Do not leave gaps between ends of sealant backings.
2. Do not stretch, twist, puncture, or tear sealant backings.
3. Remove absorbent sealant backings that have become wet before sealant application and replace them with dry materials.

D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.

E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:

1. Place sealants so they directly contact and fully wet joint substrates.
2. Completely fill recesses in each joint configuration.
3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.

F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.

1. Remove excess sealant from surfaces adjacent to joints.
2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
3. Provide concave joint configuration per Figure 5A in ASTM C 1193, unless otherwise indicated.

3.4 FIELD QUALITY CONTROL

A. Field-Adhesion Testing: Field test joint-sealant adhesion to joint substrates as follows:

1. Extent of Testing: Test completed and cured sealant joints as follows:
   a. Perform one test for each 1000 feet of joint length thereafter or one test per each floor per elevation.
2. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C1193 or Method A, Tail Procedure, in ASTM C1521.
   a. For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.
3. Inspect tested joints and report on the following:
   a. Whether sealants filled joint cavities and are free of voids.
   b. Whether sealant dimensions and configurations comply with specified requirements.
   c. Whether sealants in joints connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. Compare these results to determine if adhesion complies with sealant manufacturer's field-adhesion hand-pull test criteria.
4. Record test results in a field-adhesion-test log. Include dates when sealants were installed, names of persons who installed sealants, test dates, test locations, whether joints were primed, adhesion results and percent elongations, sealant material, sealant configuration, and sealant dimensions.

5. Repair sealants pulled from test area by applying new sealants following same procedures used originally to seal joints. Ensure that original sealant surfaces are clean and that new sealant contacts original sealant.

B. Evaluation of Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

3.5 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.6 PROTECTION

A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

END OF SECTION

SECTION 083110

ACCESS DOORS AND FRAMES

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Access doors and frames for walls and ceilings.

1.3 SUBMITTALS

A. Product Data: For each type of access door and frame indicated. Include construction details, fire ratings, materials, individual components and profiles, and finishes.

B. Shop Drawings: Show fabrication and installation details of access doors and frames for each type of substrate. Include plans, elevations, sections, details, and attachments to other work.

C. Samples: For each door face material, at least 3 by 5 inches in size, in specified finish.

D. Access Door and Frame Schedule: Provide complete access door and frame schedule, including types, locations, sizes, latching or locking provisions, and other data pertinent to installation.

E. Ceiling Coordination Drawings: Reflected ceiling plans, drawn to scale, on which ceiling-mounted items including access doors and frames, lighting fixtures, diffusers, grilles, speakers, sprinklers, and special trim are shown and coordinated with each other.

1.4 QUALITY ASSURANCE

A. Source Limitations: Obtain each type of access door and frame through one source from a single manufacturer.

B. Fire-Rated Access Doors and Frames: Units complying with NFPA 80 that are identical to access door and frame assemblies tested for fire-test-response characteristics per the following test method and that are listed and labeled by UL or another testing and inspecting agency acceptable to authorities having jurisdiction:

1. NFPA 252 for vertical access doors and frames.
2. ASTM E 119 for horizontal access doors and frames.

C. Size Variations: Obtain Architect's acceptance of manufacturer's standard-size units, which may vary slightly from sizes indicated.

1.5 COORDINATION

A. Verification: Determine specific locations and sizes for access doors needed to gain access to concealed plumbing, mechanical, or other concealed work, and indicate in the schedule specified in "Submittals" Article.

PART 2 PRODUCTS

2.1 STEEL MATERIALS

A. Steel Plates, Shapes, and Bars: ASTM A 36/A 36M.

1. ASTM A 123/A 123M, for galvanizing steel and iron products.
2. ASTM A 153/A 153M, for galvanizing steel and iron hardware.

B. Steel Sheet: Electrolytic zinc-coated, ASTM A 879/A 879M with cold-rolled steel sheet substrate complying with ASTM A 1008/A 1008M, Commercial Steel (CS), exposed.

C. Steel Finishes: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.

1. Surface Preparation for Steel Sheet: Clean surfaces to comply with SSPC-SP 1, "Solvent Cleaning," to remove dirt, oil, grease, or other contaminants that could impair paint bond. Remove mill scale and rust, if present, from uncoated steel, complying with SSPC-SP 5/NACE No. 1, "White Metal Blast Cleaning," or SSPC-SP 8, "Pickling."
   a. Galvanizing Repair Paint: High-zinc-dust-content paint for regalvanizing welds in steel, complying with SSPC-Paint 20.
2. Factory-Primed Finish: Apply shop primer immediately after cleaning and pretreating.

D. Drywall Beads: Edge trim formed from 0.0299-inch zinc-coated steel sheet formed to receive joint compound and in size to suit thickness of gypsum board.

2.2 STAINLESS-STEEL MATERIALS

A. Rolled-Stainless-Steel Floor Plate: ASTM A 793, manufacturer's standard finish.

B. Stainless-Steel Sheet, Strip, Plate, and Flat Bars: ASTM A 666, Type 316. Remove tool and die marks and stretch lines or blend into finish.

1. Finish: Directional Satin Finish, No. 4.

2.3 ACCESS DOORS AND FRAMES FOR WALLS AND CEILINGS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Acudor Products, Inc.
2. Babcock-Davis.
3. Dur-Red Products.
4. JL Industries (a division of Activar Construction Products Group).
5. Karp Associates, Inc.
6. Larsen's Manufacturing Company.
7. Milcor Inc.
8. Nystrom, Inc.

B. Flush Access Doors and Trimless Frames: Fabricated from steel sheet at typical areas and from stainless-steel sheet at toilet and wet areas.

1. Locations: Wall and ceiling surfaces.
2. Door: Minimum 0.060-inch-thick sheet metal, set flush with surrounding finish surfaces.
3. Frame: Minimum 0.060-inch-thick sheet metal with drywall bead flange.
4. Hinges: Continuous piano.
5. Lock: Cylinder.
    a. Lock Preparation: Prepare door panel to accept cylinder specified in Section 087100, DOOR HARDWARE.

C. Recessed Access Doors and Trimless Frames: Fabricated from steel sheet at typical areas and from stainless-steel sheet at toilet and wet areas.

1. Locations: Wall and ceiling surfaces.
2. Door: Minimum 0.060-inch-thick sheet metal in the form of a pan recessed 5/8 inch for gypsum board infill.
3. Frame: Minimum 0.060-inch-thick sheet metal with drywall bead for gypsum board surfaces.
4. Hinges: Concealed pivoting rod hinge.
5. Lock: Cylinder.
    a. Lock Preparation: Prepare door panel to accept cylinder specified in Section 087100, DOOR HARDWARE.

D. Fire Rated, Uninsulated, Flush Access Doors and Frames with Exposed Trim: Fabricated from steel at typical areas and from stainless-steel sheet at toilets and wet areas.

1. Locations: Wall surfaces.
2. Fire-Resistance Rating: Not less than that of adjacent construction.
3. Door: Minimum 0.060-inch-thick sheet metal, flush construction.
4. Frame: Minimum 0.060-inch-thick sheet metal with 1-inch-wide, surface-mounted trim.
5. Hinges: Continuous piano.
6. Automatic Closer: Spring type.
7. Lock: Self-latching device with cylinder lock.
    a. Lock Preparation: Prepare door panel to accept cylinder specified in Section 087100, DOOR HARDWARE

2.4 FABRICATION

A. General: Provide access door and frame assemblies manufactured as integral units ready for installation.

B. Metal Surfaces: For metal surfaces exposed to view in the completed Work, provide materials with smooth, flat surfaces without blemishes. Do not use materials with exposed pitting, seam marks, roller marks, rolled trade names, or roughness.

C. Doors and Frames: Grind exposed welds smooth and flush with adjacent surfaces. Furnish attachment devices and fasteners of type required to secure access panels to types of supports indicated.

1. For trimless frames with drywall bead, provide edge trim for gypsum board and gypsum base securely attached to perimeter of frames.
2. For trimless frames with plaster bead for full-bed plaster applications, provide zinc-coated expanded metal lath and exposed casing bead welded to perimeter of frames.
3. Provide mounting holes in frames for attachment of units to metal or wood framing.
4. Provide mounting holes in frame for attachment of masonry anchors.

D. Recessed Access Doors: Form face of panel to provide recess for application of applied finish. Reinforce panel as required to prevent buckling.

1. For recessed doors with plaster infill, provide self-furring expanded metal lath attached to door panel.

E. Latching Mechanisms: Furnish number required to hold doors in flush, smooth plane when closed.

1. For cylinder lock, furnish two keys per lock and key all locks alike.
2. For recessed panel doors, provide access sleeves for each locking device. Furnish plastic grommets and install in holes cut through finish.

PART 3 EXECUTION

3.1 INSTALLATION

A. Comply with manufacturer's written instructions for installing access doors and frames.

B. Set frames accurately in position and attach securely to supports with plane of face panels aligned with adjacent finish surfaces.

C. Install doors flush with adjacent finish surfaces or recessed to receive finish material.

3.2 ADJUSTING AND CLEANING

A. Adjust doors and hardware after installation for proper operation.

B. Remove and replace doors and frames that are warped, bowed, or otherwise damaged.

END OF SECTION

SECTION 099000

PAINTING AND COATING

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Field painting of exposed interior items and surfaces.
2. Field painting of exposed exterior items and surfaces.
3. Surface preparation for painting.

1.3 DEFINITIONS AND EXTENT

A. General: Standard coating terms defined in ASTM D 16 apply to this Section.

1. Flat refers to a lusterless or matte finish with a gloss range below 15 when measured at an 85-degree meter.
2. Eggshell refers to low-sheen finish with a gloss range between 20 and 35 when measured at a 60-degree meter.
3. Semigloss refers to medium-sheen finish with a gloss range between 35 and 70 when measured at a 60-degree meter.
4. Full gloss refers to high-sheen finish with a gloss range more than 70 when measured at a 60-degree meter.

B. This Section includes surface preparation and field painting of exposed exterior and interior items and surfaces.

1. Surface preparation, priming, and finish coats specified in this Section are in addition to shop priming and surface treatment specified in other Sections.

C. Paint exposed surfaces, except where these Specifications indicate that the surface or material is not to be painted or is to remain natural. If an item or a surface is not specifically mentioned, paint the item or surface the same as similar adjacent materials or surfaces. If a color of finish is not indicated, Architect will select from standard colors and finishes available.

1. Painting includes field painting of exposed bare and covered pipes and ducts (including color coding), hangers, exposed steel and iron supports, and surfaces of mechanical and electrical equipment that do not have a factory-applied final finish.

D. Do NOT paint prefinished items, concealed surfaces, finished metal surfaces, operating parts, and labels.

1. Prefinished items include the following factory-finished components:
   a. Architectural woodwork.
   b. Acoustical wall panels.
   c. Toilet enclosures.
   d. Metal lockers.
   e. Kitchen appliances.
   f. Elevator entrance doors and frames.
   g. Elevator equipment.
   h. Finished mechanical and electrical equipment.
   i. Light fixtures.
2. Concealed surfaces include walls or ceilings in the following generally inaccessible spaces:
   a. Foundation spaces.
   b. Furred areas.
   c. Ceiling plenums.
   d. Utility tunnels.
   e. Pipe spaces.
   f. Duct shafts.
   g. Elevator shafts.
3. Finished metal surfaces include the following:
   a. Anodized aluminum.
   b. Stainless steel.
   c. Chromium plate.
   d. Copper and copper alloys.
   e. Bronze and brass.
4. Operating parts include moving parts of operating equipment and the following:
   a. Valve and damper operators.
   b. Linkages.
   c. Sensing devices.
   d. Motor and fan shafts.
5. Labels: Do not paint over UL, FMG, or other code-required labels or equipment name, identification, performance rating, or nomenclature plates.

1.4 SUBMITTALS

A. Product Data: For each paint system indicated. Include block fillers and primers.

   1. Material List: An inclusive list of required coating materials. Indicate each material and cross-reference specific coating, finish system, and application. Identify each material by manufacturer's catalog number and general classification.
      a. Disclose material ingredients by name and Chemical Abstract Service (CAS) Registry Number.
   2. Manufacturer's Information: Manufacturer's technical information, including label analysis and instructions for handling, storing, and applying each coating material.

B. Samples for Verification: For each color and material to be applied, with texture to simulate actual conditions, on representative Samples of the actual substrate.

   1. Provide stepped Samples, defining each separate coat, including block fillers and primers. Use representative colors when preparing Samples for review. Resubmit until required sheen, color, and texture are achieved.
   2. Provide a list of materials and applications for each coat of each Sample. Label each Sample for location and application.
   3. Submit two 8 inch by 12 inch Samples for each type of finish coating for Architect's review of color and texture only.

C. Qualification Data: For Applicator.

1.5 QUALITY ASSURANCE

A. Applicator Qualifications: A firm or individual experienced in applying paints and coatings similar in material, design, and extent to those indicated for this Project, whose work has resulted in applications with a record of successful in-service performance.

B. Source Limitations: Obtain block fillers and primers for each coating system from the same manufacturer as the finish coats.

C. Mockups: Provide a full-coat benchmark finish sample for each type of coating and substrate required. Comply with procedures specified in PDCA P5. Duplicate finish of approved sample Submittals.

1. Architect will select one room or surface to represent surfaces and conditions for application of each type of coating and substrate.
   a. Wall Surfaces: Provide samples on at least 100 sq. ft.
   b. Small Areas and Items: Architect will designate items or areas required.
2. Apply benchmark samples, according to requirements for the completed Work, after permanent lighting and other environmental services have been activated. Provide required sheen, color, and texture on each surface.
   a. After finishes are accepted, Architect will use the room or surface to evaluate coating systems of a similar nature.
3. Final approval of colors will be from benchmark samples.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials to Project site in manufacturer's original, unopened packages and containers bearing manufacturer's name and label and the following information:

1. Product name or title of material.
2. Product description (generic classification or binder type).
3. Manufacturer's stock number and date of manufacture.
4. Contents by volume, for pigment and vehicle constituents.
5. Thinning instructions.
6. Application instructions.
7. Color name and number.
8. VOC content.

B. Store materials not in use in tightly covered containers in a well-ventilated area at a minimum ambient temperature of 45 deg F. Maintain storage containers in a clean condition, free of foreign materials and residue.

1. Protect from freezing. Keep storage area neat and orderly. Remove oily rags and waste daily.

1.7 PROJECT CONDITIONS

A. Apply waterborne paints only when temperatures of surfaces to be painted and surrounding air are between 50 and 90 deg F.

B. Apply solvent-thinned paints only when temperatures of surfaces to be painted and surrounding air are between 45 and 95 deg F.

C. Do not apply paint in snow, rain, fog, or mist; or when relative humidity exceeds 85 percent; or at temperatures less than 5 deg F above the dew point; or to damp or wet surfaces.

1. Painting may continue during inclement weather if surfaces and areas to be painted are enclosed and heated within temperature limits specified by manufacturer during application and drying periods.

1.8 EXTRA MATERIALS (ATTIC STOCK)

A. Furnish extra materials that match and are from same production runs as products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Paint: Furnish one unopened gallon of each type of paint and coating work, in color and gloss as used for the Project.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work are listed in the Finish Schedule at the end of this Section.

2.2 PAINT MATERIALS, GENERAL

A. Material Compatibility: Provide block fillers, primers, and finish-coat materials that are compatible with one another and with the substrates indicated under conditions of service and application, as demonstrated by manufacturer based on testing and field experience.

B. Material Quality: Provide manufacturer's best-quality paint material of the various coating types specified that are factory formulated and recommended by manufacturer for application indicated. Paint-material containers not displaying manufacturer's product identification will not be acceptable.

1. Proprietary Names: Use of manufacturer's proprietary product names to designate colors or materials is not intended to imply that products named are required to be used to the exclusion of equivalent products of other manufacturers. Furnish manufacturer's material data and certificates of performance for proposed substitutions.

C. Paint Colors (PT-#): Refer to Finish Schedule.

PART 3 EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Applicator present, for compliance with requirements for paint application.

1. Proceed with paint application only after unsatisfactory conditions have been corrected and surfaces receiving paint are thoroughly dry.
2. Start of painting will be construed as Applicator's acceptance of surfaces and conditions within a particular area.

B. Coordination of Work: Review other Sections in which primers are provided to ensure compatibility of the total system for various substrates. On request, furnish information on characteristics of finish materials to ensure use of compatible primers.

1. Notify Architect about anticipated problems when using the materials specified over substrates primed by others.

3.2 PREPARATION

A. General: Remove hardware and hardware accessories, plates, machined surfaces, lighting fixtures, and similar items already installed that are not to be painted. If removal is impractical or impossible because of size or weight of the item, provide surface-applied protection before surface preparation and painting.

1. After completing painting operations in each space or area, reinstall items removed using workers skilled in the trades involved.

B. Cleaning: Before applying paint or other surface treatments, clean substrates of substances that could impair bond of the various coatings. Remove oil and grease before cleaning.

1. Schedule cleaning and painting so dust and other contaminants from the cleaning process will not fall on wet, newly painted surfaces.

C. Surface Preparation: Clean and prepare surfaces to be painted according to manufacturer's written instructions and technical bulletins for each particular substrate condition and as specified.

1. Provide barrier coats over incompatible primers or remove and reprime.
2. Cementitious Materials: Prepare concrete, concrete unit masonry, cement plaster, and mineral-fiber-reinforced cement panel surfaces to be painted. Remove efflorescence, chalk, dust, dirt, grease, oils, and release agents. Roughen as required to remove glaze. If hardeners or sealers have been used to improve curing, use mechanical methods of surface preparation.
   a. Use abrasive blast-cleaning methods if recommended by paint manufacturer.
   b. Determine alkalinity and moisture content of surfaces by performing appropriate tests. If surfaces are sufficiently alkaline to cause the finish paint to blister and burn, correct this condition before application. Do not paint surfaces if moisture content exceeds that permitted in manufacturer's written instructions.
   c. Clean concrete floors to be painted with a 5 percent solution of muriatic acid or other etching cleaner. Flush the floor with clean water to remove acid, neutralize with ammonia, rinse, allow to dry, and vacuum before painting.
3. Wood: Clean surfaces of dirt, oil, and other foreign substances with scrapers, mineral spirits, and sandpaper, as required. Sand surfaces exposed to view smooth and dust off.
   a. Scrape and clean small, dry, seasoned knots, and apply a thin coat of recommended knot sealer before applying primer. After priming, fill holes and imperfections in finish surfaces with putty or plastic wood filler. Sand smooth when dried.
   b. Prime, stain, or seal wood to be painted immediately on delivery. Prime edges, ends, faces, undersides, and back sides of wood, including cabinets, counters, cases, and paneling.
   c. If transparent finish is required, backprime with clear sealer.

d. Backprime paneling on interior partitions where masonry, plaster, or other wet wall construction occurs on back side.
e. Seal tops, bottoms, and cutouts of unprimed wood doors with a heavy coat of varnish or sealer immediately on delivery.

4. Ferrous Metals: Clean ungalvanized ferrous-metal surfaces that have not been shop coated; remove oil, grease, dirt, loose mill scale, and other foreign substances. Use solvent or mechanical cleaning methods that comply with SSPC's recommendations.
   a. Exterior Exposed Steel: Clean steel surfaces in accordance with SSPC-SP 6/NACE No. 3 Commercial Blast Cleaning. Abrasive blast cleaned surfaces shall exhibit a uniform, angular profile of 1.5-3.0 mils. Prime cleaned surfaces within 8 hours and prior to surface rusting.
   b. Interior Exposed Steel, in Humid Environments: Clean steel surfaces in accordance with SSPC-SP 6/NACE No. 3 Commercial Blast Cleaning. Abrasive blast cleaned surfaces shall exhibit a uniform, angular profile of 1.5-3.0 mils. Prime cleaned surfaces within 8 hours and prior to surface rusting.
   c. Interior Exposed Steel, in Dry Environments: Clean steel surfaces in accordance with SSPC-SP2 or SP3 Hand or Power Tool Cleaning.
5. Galvanized Surfaces: Clean galvanized surfaces in accordance with SSPC-SP16 Brush off Blast Cleaning of Galvanized Steel and NonFerrous Metals, to achieve a minimum 1 mil anchor profile.

D. Material Preparation: Mix and prepare paint materials according to manufacturer's written instructions.

1. Maintain containers used in mixing and applying paint in a clean condition, free of foreign materials and residue.
2. Stir material before application to produce a mixture of uniform density. Stir as required during application. Do not stir surface film into material. If necessary, remove surface film and strain material before using.
3. Use only thinners approved by paint manufacturer and only within recommended limits.

E. Tinting: Tint each undercoat a lighter shade to simplify identification of each coat when multiple coats of same material are applied. Tint undercoats to match the color of the finish coat, but provide sufficient differences in shade of undercoats to distinguish each separate coat.

3.3 APPLICATION

A. General: Apply paint according to manufacturer's written instructions. Use applicators and techniques best suited for substrate and type of material being applied.

1. Paint colors, surface treatments, and finishes are indicated in the paint schedules.
2. Do not paint over dirt, rust, scale, grease, moisture, scuffed surfaces, or conditions detrimental to formation of a durable paint film.
3. Provide finish coats that are compatible with primers used.
4. The term "exposed surfaces" includes areas visible when permanent or built-in fixtures, grilles, convector covers, covers for finned-tube radiation, and similar components are in place. Extend coatings in these areas, as required, to maintain system integrity and provide desired protection.
5. Paint surfaces behind movable equipment and furniture the same as similar exposed surfaces. Before final installation of equipment, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
6. Paint interior surfaces of ducts with a flat, nonspecular black paint where visible through registers or grilles.
7. Paint backsides of access panels and removable or hinged covers to match exposed

surfaces.
8. Finish exterior doors and doors in wet areas on tops, bottoms, and side edges the same as exterior faces.
9. Sand lightly between each succeeding enamel or varnish coat.

B. Scheduling Painting: Apply first coat to surfaces that have been cleaned, pretreated, or otherwise prepared for painting as soon as practicable after preparation and before subsequent surface deterioration.

1. The number of coats and film thickness required are the same regardless of application method. Do not apply succeeding coats until previous coat has cured as recommended by manufacturer. If sanding is required to produce a smooth, even surface according to manufacturer's written instructions, sand between applications.
2. Omit primer over metal surfaces that have been shop primed and touchup painted.
3. If undercoats, stains, or other conditions show through final coat of paint, apply additional coats until paint film is of uniform finish, color, and appearance. Give special attention to ensure that edges, corners, crevices, welds, and exposed fasteners receive a dry film thickness equivalent to that of flat surfaces.
4. Allow sufficient time between successive coats to permit proper drying. Do not recoat surfaces until paint has dried to where it feels firm, and does not deform or feel sticky under moderate thumb pressure, and until application of another coat of paint does not cause undercoat to lift or lose adhesion.

C. Application Procedures: Apply paints and coatings by brush, roller, spray, or other applicators according to manufacturer's written instructions.

1. Brushes: Use brushes best suited for type of material applied. Use brush of appropriate size for surface or item being painted.
2. Rollers: Use rollers of carpet, velvet-back, or high-pile sheep's wool as recommended by manufacturer for material and texture required.
3. Spray Equipment: Use airless spray equipment with orifice size as recommended by manufacturer for material and texture required.

D. Minimum Coating Thickness: Apply paint materials no thinner than manufacturer's recommended spreading rate to achieve dry film thickness indicated. Provide total dry film thickness of the entire system as recommended by manufacturer.

E. Mechanical and Electrical Work: Painting of mechanical and electrical work is limited to items exposed in equipment rooms and occupied spaces.

F. Mechanical items to be painted include, but are not limited to, the following:

1. Uninsulated metal piping.
2. Uninsulated plastic piping.
3. Pipe hangers and supports.
4. Tanks that do not have factory-applied final finishes.
5. Visible portions of internal surfaces of metal ducts, without liner, behind air inlets and outlets.
6. Duct, equipment, and pipe insulation having "all-service jacket" or other paintable jacket material.
7. Mechanical equipment that is indicated to have a factory-primed finish for field painting.

G. Electrical items to be painted include, but are not limited to, the following:

1. Switchgear.

2. Panelboards.
3. Electrical equipment that is indicated to have a factory-primed finish for field painting.

H. Block Fillers: Apply block fillers to concrete masonry block at a rate to ensure complete coverage with pores filled.

I. Prime Coats: Before applying finish coats, apply a prime coat, as recommended by manufacturer, to material that is required to be painted or finished and that has not been prime coated by others. Recoat primed and sealed surfaces where evidence of suction spots or unsealed areas in first coat appears, to ensure a finish coat with no burn-through or other defects due to insufficient sealing.

J. Pigmented (Opaque) Finishes: Completely cover surfaces as necessary to provide a smooth, opaque surface of uniform finish, color, appearance, and coverage. Cloudiness, spotting, holidays, laps, brush marks, runs, sags, ropiness, or other surface imperfections will not be acceptable.

K. Transparent (Clear) Finishes: Use multiple coats to produce a glass-smooth surface film of even luster. Provide a finish free of laps, runs, cloudiness, color irregularity, brush marks, orange peel, nail holes, or other surface imperfections.

1. Provide satin finish for final coats.

L. Completed Work: Match approved samples for color, texture, and coverage. Remove, refinish, or repaint work not complying with requirements.

3.4 FIELD QUALITY CONTROL

A. The Owner reserves the right to invoke the following test procedure at any time and as often as the Owner deems necessary during the period when paint is being applied:

1. The Owner will engage a qualified independent testing agency to sample paint material being used. Samples of material delivered to Project will be taken, identified, sealed, and certified in the presence of Contractor.
2. Testing agency will perform appropriate tests for the following characteristics as required by the Architect.
3. The Architect may direct Contractor to stop painting if test results show material being used does not comply with specified requirements. Contractor shall remove noncomplying paint from Project site, pay for testing, and repaint surfaces previously coated with the noncomplying paint. If necessary, Contractor may be required to remove noncomplying paint from previously painted surfaces if, on repainting with specified paint, the two coatings are incompatible.

3.5 CLEANING

A. Cleanup: At the end of each workday, remove empty cans, rags, rubbish, and other discarded paint materials from Project site.

1. After completing painting, clean glass and paint-spattered surfaces. Remove spattered paint by washing and scraping without scratching or damaging adjacent finished surfaces.

3.6 PROTECTION

A. Protect work of other trades, whether being painted or not, against damage from painting. Correct damage by cleaning, repairing or replacing, and repainting, as approved by Architect.

B. Provide "Wet Paint" signs to protect newly painted finishes. After completing painting operations, remove temporary protective wrappings provided by others to protect their work.

1. After work of other trades is complete, touch up and restore damaged or defaced painted surfaces. Comply with procedures specified in PDCA P1.

3.7 PAINT SCHEDULE

A. Schedule: Provide products and number of coats specified. Use of manufacturer's proprietary product names to designate colors, materials, generic class, standard of quality and performance criteria and is not intended to imply that products named are required to be used to the exclusion of equivalent performing products of other manufacturers.

B. Interior Paint Schedule, Typical:

1. Interior Gypsum Wallboard (GWB), Latex Paint Finish:
   a. One Coat, Primer: MPI 50 X-Green and 149 X-Green.
      1). Moore; Ultra Spec 500 Interior Latex Primer N534.
      2). PPG; Pure Performance Interior Latex Primer 9-900.
      3). PPG; Speedhide Zero VOC Interior Primer 6-4900XI series.
      4). PPG; Speedhide Pro EV Zero VOC Interior Primer 12-900XI series.
      5). S-W; ProMar 200 HP Zero VOC Interior Primer.
   b. And Two Coats, Flat Finish: At ceilings and elsewhere as indicated. MPI 53 X-Green.
      1). Moore; Ultra Spec 500 Interior Latex Flat T535.
      2). PPG; Speedhide Zero VOC Interior Latex Flat 6-4110XI series.
      3). PPG; Speedhide Pro EV Zero VOC Interior Latex Flat 12-110XI series.
      4). S-W; ProMar 400 HP Zero VOC Interior Flat.
   c. or
   d. And Two Coats, Eggshell Finish: At walls and elsewhere as indicated. MPI 144 X-Green.
      1). Moore; Ultra Spec 500 Interior Latex Eggshell T538.
      2). PPG; Speedhide Zero VOC Interior Latex Eggshell 6-4310XI series.
      3). PPG; Speedhide Pro EV Zero VOC Interior Latex Eggshell 12-110XI series.
      4). S-W; ProMar 200 HP Zero VOC Interior Eg-Shel.
   e. or
   f. And Two Coats, Semi-Gloss Finish: At toilet rooms, other wet areas, and elsewhere as indicated. MPI 54 X-Green.
      1). Moore; Ultra Spec 500 Interior Latex Semi-Gloss T546.
      2). PPG; Speedhide Zero VOC Interior Latex Semi-Gloss 6-4510XI series.
      3). PPG; Speedhide Pro EV Zero VOC Interior Latex Semi-Gloss 12-110XI series.
      4). S-W; ProMar 200 HP Zero VOC Interior Semi-Gloss.
2. Interior Architectural Woodwork, Finish Carpentry, and Wood Doors (softwoods, paint grade hardwoods, MDF, MDO, and hardwood veneers), Latex Paint Finish:
   a. One Coat, Primer:
      1) Moore; Ultra Spec 500 Interior Latex Primer 534.
      2) Pittsburgh Paints; Seal Grip Interior/Exterior Acrylic Universal Primer/Sealer 17-921XI series.
      3) S-W; ProMar 200 HP Zero VOC Interior Primer.

b. And Two Coats, Semi-Gloss:
1) Moore; Ultra Spec 500 Interior Latex Satin Pearl 545.
2) Pittsburgh Paints; Speedhide Max Zero VOC Interior Latex Lo-Lustre 6-9610 Series.
3) S-W; ProMar 200 HP Zero VOC Interior Semi-Gloss.

3. Interior Concrete Masonry Unit (CMU), Latex Paint Finish:
a. One Coat, Block Filler:
1). Moore; Ultra Spec Hi-Build Masonry Block Filler 571.
2). PPG; Perma-Crete 4-603. Less than 100 g/L.
3). PPG; Speedhide Interior Masonry Hi Fill Latex Block Filler 6-15XI.
4). S-W; PrepRite Block Filler B25W25.
b. And Two Coats, Eggshell Finish: At walls and elsewhere as indicated.
1). Moore; Ultra Spec 500 Interior Latex Eggshell T538.
2). PPG; Speedhide Zero VOC Interior Latex Eggshell 6-4310XI series.
3). S-W; ProMar 200 HP Zero VOC Interior Eg-Shel.
4. Interior Exposed Steel, Joists, Ductwork, Conduit and Similar Items (where indicated), Waterborne Dry-Fall or Dry-Fog Painted System:
a. One Coat:
1). Moore; Latex Dry Fall Flat 395 at 2.5 to 3.0 mils DFT.
2). PPG; Speedhide Super Tech WB Interior Dry-Fog Latex 6-725XI Flat at 2.0 to 2.5 mils DFT.
3). S-W; WB Pro Industrial Waterborne Acrylic Dryfall Flat B42 series at 2.5 to 3.0 mils DFT.
4). Tnemec 115 WB Unibond DF at 2.5 to 3.0 mils DFT.
5. Interior Concrete Floor, Clear Exposed Sealer (Silicate type):
a. One Coat:
1). Curecrete Chemical; Ashford Formula.
2). Tnemec (Chem Probe); Series 629 CT Densifyer.
3). WR Meadows; Liqui-Hard.
4). Laticrete; L&M Seal Hard.
5). Prosoco; Consolideck LS.

C. Interior Paint Schedule, High Performance and Specialty Systems:

1. Interior Gypsum Wallboard and Plaster at Laboratories, Toilet Rooms, and Other Wet Areas, Urethane Coating:
a. Surface Preparation: Cured, clean and dry, free of surface contaminants.
b. One Coat:
1). Tnemec 201 Epoxoprime at 3.0- 4.0 mils DFT.
2). PPG PMC Amerlock Sealer at 3.0 to 4.5 mils DFT.
3). Dupont Hi-Solids Colar primer at 3.0 to 4.0 mils DFT.
4). International Interseal 670 HS at 3.0 to 4.0 mils DFT.
c. And One Coat:
1). Tnemec 280 Tneme-glaze at 6.0 to 8.0 mils DFT.
2). PPG PMC Amercoat 351 Epoxy at 6.0 to 8.0 mils DFT.
3). Dupont 100 % Solids Epoxy at 8.0-10.0 mils.
4). International Interseal 670 HS at 3.0 to 4.0 mils DFT.
d. And One Coat:
1). Tnemec 1080 or 1081 Endurashield WB at 3.0 to 3.5 mils DFT.
2). PPG PMC AmerShield VOC at 2.0 to 3.0 mils DFT.
3). Dupont WB Urethane at 3.5 to 4.0 mils DFT.
4). International Water Borne Urethane at 3.0 to 4.0 mils DFT.
2. Interior Gypsum Wallboard, Epoxy/Acrylic Coating:
a. Surface Preparation: Cured, clean and dry, free of surface contaminants.
b. Two Coats: Tnemec 27WB at 8-10 mils DFT.

c. And One Coat: Tnemec 1028 at 2-3 mils DFT.

3. Interior Concrete Ceiling Surfaces in Dry Areas, Acrylic Paint Finish:
   a. One Coat:
      1). Tnemec 151 Elasto-Grip at 2.0 mils DFT.
      2). PPG PMC Amerlock Sealer at 1.0 mils DFT.
      3). Dupont High Solids Acrylic Primer at 2.0 mils DFT.
      4). International Intercryl 520 at 3.0 mils DFT.
   b. And Two Coats, Semi-Gloss Finish:
      1). Tnemec 1028/1029 Enduratone at 2.0 –3.0 mils DFT per coat min.
      2). PPG PMC Amercoat 220 at 3.0 mils DFT.
      3). Dupont High Solids Acrylic at 3.0 mils DFT.
      4). International Intercryl 530 at 3.0 mils DFT.
4. Interior Concrete Masonry Units, Epoxy/Acrylic Coating:
   a. Surface Preparation: Cured, clean and dry, free of surface contaminants.
   b. One Coat: Tnemec 130 Envirofil at 100 sqft/gal.
   c. And One Coat: Tnemec 27WB at 8-10 mils DFT.
   d. And One Coat: Tnemec 1028 at 2-3 mils DFT.
5. Interior Concrete Masonry Units, Epoxy/Urethane Coating:
   a. Surface Preparation: Cured, clean and dry, free of surface contaminants.
   b. One Coat:
      1). Tnemec 130 Envirofil at 100 sqft/gal.
      2). PPG PMC Nu-Klad 965 at 100 sqft/gal.
      3). Dupont 25P at 100 sq/ft/gal.
      4). International Acrylic Cementitious Block Filler at 80 sqft/gal.
   c. And One Coat:
      1). Tnemec 280 Tneme-Glaze at 6.0 8.0 mils DFT.
      2). PPG PMC Amercoat 351 6.0 to 8.0 mils DFT.
      3). Dupont 100% Solids Epoxy at 7.0 to 9.0 mils DFT.
      4). International Interseal 670 HS at 8.0 to 10.0 mils DFT.
   d. And One Coat:
      1). Tnemec 1080 or 1081 EnduraShield at 3.0 to 4.0 mils DFT.
      2). PPG PMC AmerShield VOC at 3.0 to 4.0 mils DFT.
      3). Dupont Imron WB Urethane at 3.0 to 4.0 mils DFT.
      4). International Water Borne Urethane at 3.0 to 4.0 mils DFT.
6. Interior Concrete Walls Exposed to View, Urethane Coating:
   a. Surface Preparation: Cured, clean and dry, free of surface contaminants.
   b. And One Coat:
      1). Tnemec 201 Epoxoprime at 3.0- 4.0 mils DFT.
      2). PPG PMC Amerlock Sealer at 3.0 to 4.5 mils DFT.
      3). Dupont Hi-Solids Colar primer at 3.0 to 4.0 mils DFT.
      4). International Interseal 670 HS at 3.0 to 4.0 mils DFT.
   c. And One Coat:
      1). Tnemec 280 Tneme-glaze at 6.0 to 8.0 mils DFT.
      2). PPG PMC Amercoat 351 Epoxy at 6.0 to 8.0 mils DFT.
      3). Dupont 100 % Solids Epoxy at 8.0-10.0 mils.
      4). International Interseal 670 HS at 3.0 to 4.0 mils DFT.
   d. And One Coat:
      1). Tnemec 1080 or 1081 EnduraShield at 3.0 to 3.5 mils DFT.
      2). PPG PMC AmerShield VOC at 2.0 to 3.0 mils DFT.
      3). Dupont WB Urethane at 3.5 to 4.0 mils DFT.
      4). International Water Borne Urethane at 3.0 to 4.0 mils DFT.
7. Interior Concrete Walls Exposed to View (Non-Immersion Service), Epoxy Coating:
   a. Surface Preparation: Cured, clean and dry, free of surface contaminants.
   b. One Coat:

1). Tnemec 201 Epoxoprime at 2.0 to 3.0 mils DFT.
2). PPG PMC Amerlock Sealer at 1.0 to 1.5 mils DFT.
3). Dupont 25P Epoxy at 6.0 to 8.0 mils DFT.
4). International Interseal 670 HS at 3.0 to 4.0 mils DFT.

c. And One Coat:
1). Tnemec 280 Tneme-Glaze at 6.0 to 8.0 mils DFT.
2). PPG PMC Amercoat 133 at 6.0 to8.0 mils DFT.
3). Dupont 100% Solids Epoxy at 8.0 to 10.mils DFT.
4). International Interseal 670 HS at 3.0 to 4.0 mils DFT.

d. And One Coat:
1). Tnemec 1080 or 1081 Endura-Shield 2.0 to 3 mils DFT.
2). PPG PMC AmerShield VOC at 2.0 to 3.0 mils DFT.
3). Dupont WB Urethane at 3.0 to 4.0 mils DFT.
4). International Water Borne Urethane at 3.0 to 4.0 mils DFT.

8. Interior Concrete Ceiling (both new and previously painted), Painted Finish:
a. Surface Preparation: Cured clean and dry.
b. One Coat:
1). Tnemec 151 Elasto-grip at 2.0 mils DFT.
2). RD Coatings Multiprim at 1.0-2.0 mils DFT.
c. And Two Coats:
1). Tnemec 158 Biolastic at 8.0 mils DFT.
2). RD Coatings ElastoFlex at 6.0 to 8.0 mils DFT.

9. Interior Exposed Steel, Joists, Ductwork, Conduit and Similar Items (where indicated), Dry-Fall or Dry-Fog Painted System:
a. One Coat:
1). Tnemec 115 WB Unibond at 2.5 to 3.0 mils DFT.
2). International Intercryl 530 at 2.5 to 3.0 mils DFT.
3). PPG PMC Amercoat 220 Acrylic at 3.0 mils DFT.
4). RD Coatings Muracryl at 2.0 to 3.0 mils DFT.

10. Mechanical Room Concrete Floor System, Waterborne Urethane, dry film thickness 28 mils: Surface preparation: Grind concrete; shot-blast not required.
a. Primer: RD Unifix at 1.0-1.5 mils DFT.
b. Second Coat: RD Elastodeck Slurry with broadcast aggregate, 25 mils DFT.
c. Third Coat: RD Monograph pigmented topcoat, 2-3 mils DFT.

11. Heavy Duty Mechanical Room Concrete Floor, Epoxy Coating System:
a. One Coat:
1). Tnemec 201 Epoxoprime at 4.0 to 6.0 mils DFT.
2). Dex-O-Tex C Bond Coat at 6.0-7.0 mils DFT.
3). RD Coatings Unifix at 2.0 mils DFT.
b. And One Coat:
1). Tnemec 206 Flexible Epoxy Underlayment at 60 mils DFT.
2). Dex-O-Tex Cheminert SC Membrane at 70-80 mils DFT.
3). RD Coatings Elasto Deck at 50-80 mils DFT.
c. And Two Coats:
1). Tnemec 297 at 3.0 mils DFT.
2). Dex-O-Tex Quik-Glaze at 7.0-8.0 mils DFT.
3). RD Coatings Muracryl at 3.0 mils DFT.

D. Mechanical and Electrical Work: Paint all exposed items throughout the project except factory finished items with factory-applied baked enamel finishes which occur in mechanical rooms or areas, and excepting chrome or nickel plating, stainless steel, and aluminum other than mill finished. Paint all exposed ductwork and inner portion of all ductwork. Same as specified for other interior metals, hereinabove.

END OF SECTION

SECTION 099805

MASONRY STAINING

PART 1 - GENERAL

1.1 SECTION INCLUDES

A. This Section includes brush-applied proven masonry stain applied to porous exterior surfaces including the following:
   1. Clay masonry units.

1.2 RELATED SECTIONS

A. Section 042000 – Unit Masonry.

B. Section 040120 – Masonry Restoration and Cleaning.

1.3 SUBMITTALS

A. Product Data: For each type of stain indicated.
   1. Manufacturer's Information: Manufacturer's technical information, and if needed, instructions for handling and storing exterior masonry stain.

B. Qualification Data: For Applicator.

C. Benchmark Samples (mockups): Provide up to five (5) color enhanced loose units that represent the over-all color range to determine closest approved sample matching to existing masonry. A field sample can be created on a 10 sq. ft. area to be determined by the Owner and the Architect on the actual surface of the building to be stained.

D. Project List: Submit a list of 10 successful projects over the last 15 years:
   1. The date on which the work was completed.
   2. The precise location of the job including description of the structure or portion of the structure stained, street address, city, state and zip code.
   3. Name of product used.
   4. Before and after pictures.

1.4 QUALITY ASSURANCE

A. Manufacturer Qualifications: Minimum 20 years experience and successful in-service performance in applying a ceramic based proven masonry stain.

B. Applicator Qualifications: A firm experienced in applying a ceramic based proven masonry stain, design and extent to those indicated for this project. Whose company has resulted in applications with a record of successful in-service performance that exceeds 20 years.

1.5 PROJECT CONDITIONS

A. Temperature Limitations: Apply stains only when temperatures of surfaces to be stained and the surrounding air are between 45 degrees F (7 degrees C) and 100 degrees F (32 degrees C).

B. Weather Limitations: Do not apply stain in snow, rain, dense fog or mist; when the relative humidity exceeds 95%, also do not apply to damp or wet surfaces.
   1. Allow wet surfaces to dry thoroughly and attain temperature and conditions specified before starting or continuing with application.

PART 2 - PRODUCTS

2.1 MANUFACTURER

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
   1. BrickImaging.
   2. Dyebrick.
   3. Masonry Cosmetics Inc.

B. Basis-of-Design: BrickImaging; Stayntech.

2.2 UNIT MASONRY STAIN MATERIALS, GENERAL

A. Materials: Exterior water-based polymer blend that dries to a durable flat finish.

B. Materials once applied should not leave a visible gloss, sheen or film on masonry units.

C. VOC Content is to be very low and shall have a maximum value of 0.01 g/g.

PART 3 - EXECUTION

3.1 PREPARATION

A. General: Remove hardware, machined surfaces, lighting fixtures and similar items already installed that are not being stained. If removal is impractical or not possible because of size and weight of the item, provide surface- applied protection before surface preparation and staining.
   1. After completing staining operations, reinstall items removed using workers skilled in trades involved.

B. Surface Preparation: Clean and prepare surfaces to be stained according to manufacturer's written instructions for each particular substrate condition and as specified.
   1. Remove surface dirt, oil or grease by washing with a detergent solution recommended by masonry manufacturer; rinse thoroughly with clean water and allow to dry.
   2. Walls will need to be free of any acid or cleaning solution residue prior to any staining. Keep the PH level on the wall as close to neutral as possible.
   3. Ensure structurally sound surfaces that are dry, clean and free of the following: dirt, moisture, loose particles, oil, grease, asphalt, tar, paint, wax, rust, waterproofing, curing and parting compounds and other foreign matter.

3.2 APPLICATION

A. Mixing: Mix and prepare stains according to the manufacturer's written instructions. Stir stain thoroughly before applying and frequently during application to maintain color consistency.
   1. Maintain containers used in mixing and application in a clean condition, free of foreign materials and residue.
   2. Stir material before application to ensure all materials stay suspended. Stir as required during application.

B. Minimum Application Rate: Apply stain to manufacturer's recommended required rate, measured by bricks stained per brush, to ensure proper penetration..
   1. Do not apply stain on surfaces that are not sufficiently dry. If succeeding application is needed, ensure that the surface is dry before re-applying.
   2. Apply stain with brush by hand to provide a uniform blending of color to the masonry

wall.

3.3 FIELD QUALITY CONTROL

A. Architect or Owner shall review and approve “artistic” application of stain by Contractor in a test area, mock-up panel or loose samples, and as accepted for approved benchmark samples.

3.4 CLEANING

A. Cleanup: At the end of each work day, remove empty cans, rags, rubbish and other discarded materials from the project site.
   1. After completing staining, clean window glass and other surfaces. Remove splattered stain by proper methods without scratching or damaging adjacent finished surfaces.
   2. Dispose of excess materials according to state, federal and local governmental regulations.

3.5 PROTECTION

A. Protect work of other trades as necessary, whether being stained or not, against damage from staining. Correct damage by cleaning, repairing and re-staining as approved by Architect.

END OF SECTION