PROJECT MANUAL

WESTMINSTER PUBLIC SCHOOLS – 2026 BOND PROJECTS
FAIRVIEW PK-8 RENOVATIONS

Westminster, CO

FINAL
SEPTEMBER 25, 2026

ARCHITECT
DAO Architecture
7230 Meade St
Westminster, CO 80030
720-273-0431
www.daoarch.com

PROJECT MANUAL

TABLE OF CONTENTS

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

Document 000010 Cover
Document 000110 Table of Contents

CONTRACTING REQUIREMENTS

By Owner

SPECIFICATIONS

DIVISION 01 - GENERAL REQUIREMENTS

Section 011000 General Requirements
Section 012200 Unit Prices
Section 014330 Mock-Ups
Section 016200 Substitution Request Form

DIVISION 02 - EXISTING CONDITIONS

Section 024100 Demolition

DIVISION 03 - CONCRETE

Not Used

DIVISION 04 - MASONRY

Section 040120 Masonry Restoration and Cleaning
Section 042000 Unit Masonry

DIVISION 05 - METALS

Not Used

DIVISION 06 - WOOD, PLASTICS AND COMPOSITES

Section 061000 Rough Carpentry
Section 064020 Interior Architectural Woodwork

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

Section 078410 Penetration Firestopping
Section 078440 Fire-Resistive Joint Systems
Section 079200 Joint Sealants

DIVISION 08 - OPENINGS

Section 081110 Hollow Metal Doors and Frames
Section 083110 Access Doors and Frames
Section 084110 Aluminum-Framed Storefronts
Section 085110 Aluminum Windows

Section 087100 Door Hardware
Section 088000 Glazing

DIVISION 09 - FINISHES

Section 096800 Carpeting
Section 099000 Painting and Coating
Section 099805 Masonry Staining

DIVISION 10 - SPECIALTIES

Section 101100 Visual Display Surfaces

DIVISION 11 - EQUIPMENT
Not Used

DIVISION 12 - FURNISHINGS

Section 122400 Shades

DIVISIONS 13 - 20
Not Used

DIVISION 21 - FIRE SUPPRESSION
Not Used

DIVISION 22 - PLUMBING
Not Used

DIVISION 23 - HEATING VENTILATING AND AIR CONDITIONING
Not Used

DIVISION 26 - ELECTRICAL

Section 260500 Common Work Results for Electrical
Section 260519 Low Voltage Electrical Power Conductors and Cables
Section 260526 Grounding and Bonding for Electrical Systems
Section 260529 Hangers and Supports for Electrical Systems
Section 260533 Raceway and Wireway for Electrical Systems
Section 260534 Cabinets, Boxes and Fittings
Section 260553 Identification for Electrical Systems
Section 260583 Wiring Connections
Section 262726 Wiring Devices
Section 262800 Low Voltage Circuit Protective Devices

DIVISION 27 - COMMUNICATIONS
Not Used

DIVISION 28 - ELECTRONIC SAFETY AND SECURITY
Not Used

END OF TABLE OF CONTENTS

SECTION 011000

GENERAL REQUIREMENTS

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS, which are hereby made a part of this Section of the Specifications.

1.2 PROJECT REQUIREMENTS

A. Project Identification: Westminster Public Schools 2026 Bond Projects.

B. Project Requirements for Temporary Utilities and Facilities:

1. Utility Costs: The Contractor shall meter and pay for cost of utility services consumed, including electricity, water, gas and temporary heat.
2. Temporary Offices: A separate field office for the Architect and the Owner's Representative is not required.
3. Toilet Facilities: The Contractor shall provide and maintain temporary toilets outside the building.

C. Permits and Fees: Apply for, obtain, and pay for permits, fees, and utility company backcharges required to perform the work. Submit copies to Architect.

D. Codes: Comply with applicable codes and regulations of authorities having jurisdiction. Submit copies of inspection reports, notices and similar communications to Architect.

E. Dimensions: Verify dimensions indicated on drawings with field dimensions before fabrication or ordering of materials. Do not scale drawings.

F. Existing Conditions: Notify Architect of existing conditions differing from those indicated on the drawings.

G. Contractor’s Conduct on Premises: The Contractor and their employees shall behave in a respectful, courteous and safe manner. Abusive, harassing, and lewd behavior is prohibited. Music playing is prohibited. Alcohol, tobacco, and drug use is prohibited.

1.3 SPECIFICATION INFORMATION

A. These specifications are a specialized form of technical writing edited from master specifications and contain deviations from traditional writing formats. Capitalization, underlining and bold print is only used to assist reader in finding information and no other meaning is implied.

B. Except where specifically indicated otherwise, the subject of all imperative statements is the Contractor.

C. Sections are generally numbered in conformance with Construction Specifications Institute Masterformat System. Numbering sequence is not consecutive. Refer to the Table of Contents for names and numbers of sections included in this Project.

D. Pages are numbered separately for each section. Each section is noted with "End of Section" to indicate the last page of a section.

1.4 DEFINITIONS

A. General: Basic Contract definitions are included in the Conditions of the Contract.

B. "Approved": When used to convey Architect's action on Contractor's submittals, applications, and requests, "approved" is limited to Architect's duties and responsibilities as stated in the Conditions of the Contract.

C. "Directed": A command or instruction by Architect. Other terms including "requested," "authorized," "selected," "approved," "required," and "permitted" have the same meaning as "directed."

D. "Indicated": Requirements expressed by graphic representations or in written form on Drawings, in Specifications, and in other Contract Documents. Other terms including "shown," "noted," "scheduled," and "specified" have the same meaning as "indicated."

E. "Regulations": Laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, and rules, conventions, and agreements within the construction industry that control performance of the Work.

F. "Furnish": Supply and deliver to Project site, ready for unloading, unpacking, assembly, installation, and similar operations.

G. "Install": Operations at Project site including unloading, temporarily storing, unpacking, assembling, erecting, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.

H. "Provide": Furnish and install, complete and ready for the intended use.

I. "Project Site": Space available for performing construction activities. The extent of Project site is shown on Drawings and may or may not be identical with the description of the land on which Project is to be built.

1.5 INDUSTRY STANDARDS

A. Referenced standards are part of the Contract Documents and have the same force and effect as if bound with these specifications.

B. Except where specifically indicated otherwise, comply with the current standard in effect as of the date of the Owner/Contractor Agreement. Obtain copies of industry standards directly from publisher.

C. The titles of industry standard organizations are commonly abbreviated; full titles may be found in Encyclopedia of Associations or consult Architect.

1.6 CODES AND REGULATIONS

A. Comply with all applicable codes, ordinances, regulations and requirements of authorities having jurisdiction.

B. Submit copies of all permits, licenses, certifications, inspection reports, releases, notices, judgments, and communications from authorities having jurisdiction to the Architect.

1.7 PROGRESS SCHEDULE

A. Provide comprehensive bar chart schedule showing all major and critical minor portions of the work, sequence of work and duration of each activity. Update and reissue regularly, but not less than monthly.

1.8 SCHEDULE OF VALUES

A. Prepare Schedule of Values to coordinate with application for payment breakdown. Submit at least 10 days before first payment application. Update and reissue regularly, but not less than monthly.

1.9 PAYMENT REQUESTS

A. Provide three copies or digital distribution of each request on completely filled out copies of AIA G702 and continuation sheet G703. Substantiate requests with complete documentation; include change orders to date. Provide partial lien waivers for work in progress and full lien waivers for completed work.

B. As-Constructed Record Drawing Certification: Certify as a part of each application for payment that the project as-constructed record documents are current at the time of application is submitted. The Contractor shall require such drawings to be current as a condition of approving any payment to the trade Contractor and Subcontractor.

C. Before first payment application, provide the following:

1. List of subcontractors, suppliers and fabricators.
2. Schedule of values.
3. Progress schedule.
4. Submittal schedule keyed to project schedule.
5. List of Contractor's key project personnel.
6. Copies of permits and other communications from authorities.
7. Contractor's certificate of insurance.
8. Performance and payment bonds if required.
9. Unit price schedule.

D. Before final payment application, provide and complete the following:

1. Complete closeout requirements.
2. Complete punch list items.
3. Settle all claims.
4. Transmit record documents to Architect. Include statement that Architect's Supplemental Instructions, Change Orders, Construction Change Directives and minor changes in the work have been incorporated in the as-constructed record drawings.
5. Prove that all taxes, fees and similar obligations have been paid.
6. Remove temporary facilities and surplus materials.
7. Change lock cylinders or cores.
8. Clean the work.
9. Submit consent of surety, if any, for final payment.
10. Complete required LEED documentation.

1.10 PROCEDURES AND CONTROLS

A. Project Meetings: Arrange for and attend meetings with the Architect and such other persons as the Architect requests to have present. The Contractor shall be represented by a principal, project manager, general superintendent or other authorized main office representative, as well as by the Contractor's field superintendent. An authorized representative of any subcontractor or sub-subcontractor shall attend such meetings if the representative's presence is requested by the Architect. Such representatives shall be empowered to make binding commitments on all matters to be discussed at such meetings, including costs, payments, change orders, time schedules and manpower. Any notices required under the Contract may be served on such representatives. Written reports of meeting minutes shall be prepared by the Contractor and distributed by the Contractor to attendees, the Architect, and Owner within three business days.

1. Pre-Construction Conference: Attendance by Architect, Contractor, major subcontractors. Agenda shall include: Quality of workmanship, coordination, interpretations, job schedule, submittals, approvals, requisition procedures, testing, protection of construction, indoor air quality, and construction waste management.
2. Exterior Envelope Meeting: Attendance by Architect, Contractor, major subcontractors. Agenda shall include as applicable: Review of exterior wall details, wall construction, sample panel preparation, cleaning, control and expansion joints, cold weather procedures.
3. Roofing/Flashings Meeting: Attendance by Architect, Contractor, roofing subcontractor, and representative of roofing manufacturer. Agenda shall include as applicable: Preparation of roof decks, flashing and blocking details, roofing procedures and inspections, bonds and guarantees, weather conditions during roofing, protection of roof membrane during construction.
4. Interior Finishes Meeting: Attendance by Architect, Contractor, major subcontractors. Agenda shall include as applicable: Quality of workmanship, environmental conditions for

application of finishes, drywall details, millwork details, condition of surfaces to receive finishes, tile work, painting work, samples and test areas and approvals, coordination with mechanical and electrical interfaces and penetrations, indoor air quality.

5. Progress Meetings: Hold regularly before preparation of payment requests and additional meetings as requested by the Architect. Attendance by Architect, Contractor, and others as determined by Contractor. Agenda shall include work in progress and payment requests.
6. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction, as specified. Preinstallation Conferences may be part of Progress Meeting agenda. Attendance by Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow. Agenda shall include a review of progress of other construction activities and preparations for the particular activity under consideration.

B. Emergency Contacts: Furnish the Owner and Architect, in writing, the names and telephone numbers of individuals to be contacted in the event of an out-of-hours emergency at the building site. Post a similar list readily visible from the outside of the field office or a location acceptable to the Architect.

C. Layout: Layout work and be responsible for all lines, elevations, and measurements of the building, grading, utilities and other work executed under the contract. Retain a registered professional engineer or registered land surveyor, acceptable to the Architect, to initially establish exterior lines and required elevations of all buildings and structures to be erected on the site. The registered professional engineer or registered land surveyor shall certify the actual location of the constructed facilities in relation to property lines, building lines, easements, set-backs, and other restrictive boundaries.

D. Field Measurements: Verify measurements at the building prior to ordering materials or commencing work. No extra charge or compensation will be allowed because of differences between actual dimensions and measurements indicated on the Drawings. Differences which may be found shall be submitted to the Architect for decision before proceeding with the work.

E. Field Measurements for Fixed Equipment: Dimensions for fixed equipment to be supplied under this Contract or separate contracts shall be determined by field measurements taken jointly by the Contractor and the equipment supplier involved. A record of the field measurements shall be kept until time of substantial completion of the project, or until the equipment has been fully installed and accepted by the Owner, whichever is later. Responsibility for fixed equipment fabricated accurately to field measurements for proper fit and operation shall be that of the Contractor. Contractor shall pay all costs involved in correcting any misfitting fixed equipment as fabricated.

F. Project Limit Line: The boundaries of the site do not limit the responsibility of the Contractor to perform the work in its entirety. Make utility connections as indicated.

G. Matching: Where matching is indicated, the Architect shall be the sole and final judge of what is an acceptable match. Mockups and sample submissions are required.

H. Observation: Notify the Architect and authorities having jurisdiction at least thirty-six hours in advance of concealing any work.

I. Utilities: Prior to interrupting utilities, services or facilities, notify the utility owner and the Owner and obtain their written approval a minimum 48 hours in advance.

J. Furnishings, Fixtures, and Equipment: Cooperate and permit the Owner to install their furnishings and equipment during the progress of the work. Owner's installation of furnishings or equipment does not signify Owner's acceptance of any portion of the work.

K. Clean-Up: Frequently clean-up all waste, remove from site regularly, and legally dispose of off-site.

L. Installer's Acceptance of Conditions: All installers shall inspect substrates and conditions under which work is to be executed and shall report in writing to the Contractor all conditions detrimental to the proper execution and completion of the work. Do not proceed with work until unsatisfactory conditions are corrected. Beginning work means installer accepts previous work and conditions.

M. Coordination: The Contractor shall be fully responsible for coordinating all trades, coordinating construction sequences and schedules, and coordinating the actual installed location and interface of all work.

1. Prior to beginning mechanical, electrical and fire protection work, the Contractor shall prepare coordination drawings showing the exact alignment, physical location and configuration of the mechanical, electrical and fire protection installations and demonstrating to the Contractor's satisfaction that the installations will clear all obstructions, permit proper clearances for the Work of other trades, and present an orderly appearance where exposed. The Contractor shall be solely liable and responsible for any costs and delays resulting from the Contractor's failure to prepare such coordination drawings or from the negligent preparation of such coordination drawings.
2. Exact locations and groupings of mechanical, electrical and fire protection fixtures, switches, heads and outlets shall be obtained from the Architect before the Work is roughed in. Work installed without such information from the Architect shall be relocated at the Contractor's expense if the Architect so requests.

N. Request For Interpretation (RFIs):

1. Procedure: Immediately on discovery of the need for interpretation of the Contract Documents, and if not possible to request interpretation at Project meeting, prepare and submit an RFI in the form specified.
   a. RFIs shall originate with Contractor. RFIs submitted by entities other than Contractor will be returned with no response.
2. Content of the RFI: Include a detailed, legible description of item needing interpretation.
3. Architect's Action: Architect will review each RFI, determine action required, and return it. Allow three working days for Architect's response for each RFI. RFIs received after 1:00 p.m. will be considered as received the following working day.
4. The following RFIs will be returned without action:
   a. Requests for approval of submittals.
   b. Requests for approval of substitutions.
   c. Requests for coordination information already indicated in the Contract Documents.
   d. Requests for adjustments in the Contract Time or the Contract Sum.
   e. Requests for interpretation of Architect's actions on submittals.
   f. Incomplete RFIs or RFIs with numerous errors.

O. Existing Articles of Unusual Value: If during demolition, excavation, or disposal work articles of unusual value or of historical or archaeological significance are encountered, the ownership of such articles is retained by the Owner, and information regarding their discovery shall be immediately furnished to the Architect. If the nature of the article is such that work cannot proceed without danger of damage, work in the area shall be immediately discontinued until the Architect has determined the proper procedure to be followed. Delays in time thereby shall be a condition for which the time of the Contract may be extended. Costs incurred after discovery in the salvaging of such articles shall be borne by the Owner.

1.11 SUBMITTALS

A. Required Submittals: Submit shop drawings, product data, initial selection samples, verification samples, calculations, coordination drawings, schedules, and all other submittals as specified in individual specification sections.

B. Submittal Schedule: Within 30 days after award of contract and before first application for payment, prepare list of submittals in chronological sequence showing all submittals and proposed date first due at Architect's office and proposed date due to be returned to Contractor. Note relevant specification section number.

C. Contractor's Preparation of Submittals: Modify and customize all submittals to show interface with adjacent work and attachment to building. Identify each submittal with name of project, date, Contractor's name, subcontractor's name, manufacturer's name, submittal name, relevant specification section numbers, and Submittal Schedule reference number. Stamp and sign each submittal to show the Contractor's review and approval of each submittal before delivery to Architect's office; unstamped and unsigned submittals will be returned without action by the Architect. Leave 4" x 6" open space for Architect's "action" stamp.

1. Electronic Submittals: Provide a copy of all submittals in electronic format to the Architect. Architect will return a file of reviewed submittal in electronic format to the Contractor for distribution to subcontractors, suppliers, fabricators, governing authorities and others as necessary for proper performance of the Work. Unless otherwise amenable to the Architect, additional hard copies of submittals will not be reviewed by the Architect (or Consultant) and will not be returned to the Contractor.
2. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
3. Name file with submittal number or other unique identifier, including revision identifier.
4. Provide means for insertion to permanently record Contractor's review and approval markings and action taken by Architect and Construction Manager.
5. Transmittal Form for Electronic Submittals: Use electronic form acceptable to Architect.

D. Product Data: Provide manufacturer's preprinted literature including, without limitation, manufacturer's standard printed description of product, materials and construction, recommendations for application and use, certification of compliance with standards, instructions for installation, and special coordination requirements. Collect data into one submittal for each unit of work or system; mark each copy to show which choices and options are applicable to project.

1. Installer Copy: Verify that the Installer has a current copy of the relevant product data, including installation instructions, before permitting installation to begin.

E. Shop Drawings: Provide accurately prepared, large scale and detailed shop drawings prepared specifically for this project. Show adjacent conditions and related work. Show accurate field dimensions and clearly note field conditions. Identify materials and products in the work shown. Note special coordination required.

1. After Architect's action, follow specified distribution procedure.

F. Samples: Provide units identical with final materials and products to be installed in the work. Where indicated, prepare samples to match Architect's sample. Label each sample with description, source, generic name or manufacturer's name and model number. Architect will review samples for confirmation of visual design intent, color, pattern, texture and type only; Architect will not test samples for compliance with other Contract requirements which shall remain the exclusive responsibility of the Contractor.

1. Initial Selection Samples Submittal Quantities: For initial selection purposes, submit 1 set of samples showing the complete range of colors and finishes available.
2. Verification Samples Submittal Quantities: For verification of an initial selection, submit 3 sets of samples; one set will be returned to Contractor to be maintained at project site for quality control comparisons.

G. Timing of Submittals: Submit submittals in a timely fashion to allow at least 10 business days for each office's review and handling. This means that submittals which have to be reviewed by the Architect and one of their consultants require at least 20 business days for review and handling. Add ten business days for each additional consultant who must review a submission.

H. Architect's Action on Submittals: Architect will review submittals, stamp with "action stamp", mark action, and return to Contractor. Architect will review submittals only for conformance with the design concept of the project. The Contractor is responsible for confirming compliance with other Contract requirements, including without limitation, performance requirements, field dimensions, fabrication methods, means, methods, techniques, sequences and procedures of construction, coordination with other work. The Architect's review and approval of submittals shall be held to the limitations stated in the Owner/Architect Agreement and the Conditions of the Contract. In no case shall approval or acceptance by the Architect be interpreted as a release of Contractor of their responsibilities to fulfill all of the requirements of the Contract Documents.

1. Required Resubmittal: Unless submittal is noted "reviewed" or "reviewed except as noted, resubmission not required," make corrections or changes to original and resubmit to Architect.
2. Distribution: When submittal is noted "reviewed" or "reviewed as noted, resubmittal not required," make prints or copies and distribute to Owner, Subcontractors involved, and to all other parties requiring information from the submittal for performance or coordination of related work.

1.12 WARRANTIES

A. Warranties Required: Refer to individual trade sections for specific product warranty requirements.

B. Procurement: Where a warranty is required, do not purchase or subcontract for materials or work until it has been determined that parties required to countersign warranties are willing to do so.

C. Warranty Forms: Submit written warranty to Owner through Architect for approval prior to execution. Furnish two copies of executed warranty to Owner for their records; furnish two additional conformed copies where required for maintenance manual.

D. Work Covered: Contractor shall remove and replace other work of project which has been damaged as a result of failure of warranteed work or equipment, or which must be removed and replaced to provide access to work under warranty. Unless otherwise specified, warranty shall cover full cost of replacement or repair, and shall not be pro-rated on basis of useful service life.

E. Warranty Extensions: Work repaired or replaced under warranty shall be warranted until the original warranty expiration date or for ninety days whichever is later in time.

F. Warranty Effective Starting Date: Guarantee period for all work, material and equipment shall begin on the date of substantial completion of the Project, not when subcontractor has completed their work nor when equipment is turned on. In addition to the one year guarantees for the entire work covered by these Contract Documents, refer to the various sections of the specifications for extended guarantee or maintenance requirements for various material and equipment.

G. Warranties are Irrevocable: Warranties issued to the Owner are irrevocable.

1. Non-Payment: If warrantor refuses to issue warranty, or attempts to revoke warranty due to lack of payment by any party other than the Owner, the Contractor shall resolve the payment conflict, and cause the warranty to be issued or reinstated.
2. Incomplete or incorrect Installation: If warrantor refuses to issue warranty, or attempts to revoke warranty due to improper installation or other deficiency, the Contractor shall correct the deficiency and cause the warranty to be issued or reinstated.

H. Transferable Warranties: All warranties shall permit Owner to transfer or assign warranties to future owners or other assignors at no additional cost to the Owner for the full warranty period.

1.13 CUTTING AND PATCHING

A. Limitations: Do not cut and patch any work in a manner that would result in a failure of the work to perform as intended, decreased energy performance, increased maintenance, decreased operational life, or decreased safety.

1. Structural Work: Do not cut structural work or bearing walls without written approval from Architect. Where cutting and patching of structural work is necessary and approved by Architect, perform work in a manner which will not diminish structural capacity nor increase deflection of member. Provide temporary shoring and bracing as necessary. Ensure the safety of people and property at all times.

B. Cutting and Patching Materials: Use materials identical to materials to be cut and patched. If identical materials are not available or cannot be used, use materials that match existing materials to the greatest extent possible. Provide finished work that will result in equal to or better than existing performance characteristics.

C. Inspection: Before cutting and patching, examine surfaces and conditions under which work is to be performed and correct unsafe and unsatisfactory conditions prior to proceeding.

D. Protection: Protect adjacent work from damage. Protect the work from adverse conditions.

E. Cutting: Cut work using methods least likely to damage adjoining work. Use tools designed for sawing or grinding, not hammering or chopping. Use saws or drills to ensure neat, accurately formed holes to sizes required with minimum disturbance to adjacent work. Temporarily cover openings; maintain weathertightness and safety.

1. Utilities: Locate utilities before cutting. Provide temporary utilities as needed. Cap, valve, or plug and seal ends of abandoned utilities to prevent entrance of moisture or other foreign matter.

F. Patching: Patch with seams and joints which are durable and not visible. Comply with specified tolerances for similar new work; create true even planes with uniform continuous appearance. Restore finishes of patched areas and, if necessary, extend finish restoration onto adjoining unpatched area to eliminate evidence of patching and refinishing. Repaint entire assemblies, not just patched area. Remove and replace work which has been cut and patched in a visually unsatisfactory manner as determined by the Architect.

G. Qualifications: Retain experienced and specialized firms, original installers if possible, to perform cutting and patching. Workmen shall be skilled in type of cutting and patching required.

1.14 TEMPORARY FACILITIES AND UTILITIES

A. Scope of Temporary Work: This article is not intended to limit the scope of temporary work required under the Contract. Provide all temporary facilities and utilities needed.

B. Permits and Fees: Obtain and pay for all permits, fees and charges related to temporary work.

C. Codes and Authorities Having Jurisdiction for Temporary Facilities and Utilities: Comply with all requirements of authorities having jurisdiction, codes, utility companies, OSHA, and industry standards including, but not limited to the following:

1. NFPA 241, Standard for Safeguarding Construction, Alteration, and Demolition Operations.
2. ANSI-A10 Series, Safety Requirements for Construction and Demolition.
3. NECA National Joint Guideline NJG-6, Temporary Job Utilities and Services.
4. Electrical Service: NEMA, NECA, and UL.

D. Field Offices: Provide Contractor's field offices as needed. Keep current copies of all Contract Documents and project paperwork neatly on file at jobsite. Permit Architect's unrestricted use of Contractor's field office facilities including copiers, telephones, plan tables, and other equipment. Furnish, maintain, and pay for light, power, phone, fax, and other field office services.

E. Shops and Sheds: At Contractor's option, provide shops and sheds for Contractor's use as needed. Locate shops and sheds where acceptable to Owner and authorities having jurisdiction. Prior to completion of construction, temporary storage facilities and surplus stored materials shall be removed from the site.

F. Weather Protection: It is the intent of these Specifications to require that the Contractor shall provide temporary enclosures and heat to permit construction work to be carried on during the

months of November through March. Under no circumstances shall the Contractor suspend any work during the months of November through March because of their reluctance to provide and pay for temporary weather protection. These Specifications are not to be construed as requiring enclosures or heat for operations that are not economically feasible to protect in the judgment of the Architect. Included in the preceding category, without limitation, are such items as site work, excavation, steel erection, erection of certain "exterior" wall panels, roofing, and similar operations.

1. 'Weather Protection' shall mean the temporary protection of that work adversely affected by moisture, wind, and cold, by covering, enclosing and/or heating. This protection shall provide adequate working areas during the months of November through March consistent with the approved construction schedule to permit the continuous progress of all work necessary to maintain an orderly and efficient sequence of construction operations. The Contractor shall furnish and install all "weather protection" material and be responsible for all costs, including heating required to maintain a minimum temperature of 55 degrees F. at the working surface. This provision does not supersede any specific requirements for methods of construction, curing of materials or the applicable general conditions set forth in the Contract with added regard to performance obligations of the Contractor.
2. Within 30 calendar days after his award of contract, the Contractor shall submit in writing to the Architect for approval, his proposed methods for "Weather Protection."
3. Installation of weather protection and heating devices shall comply with all safety regulations including provisions for adequate ventilation and fire protection devices. Heating devices which may cause damage to finish surfaces shall not be used.

G. Heating During Construction: Within 30 calendar days after the commencement of work under this Contract, the Contractor shall submit in writing to the Architect for approval, the Contractor's method and time schedule for heating during construction which shall concur with his general progress schedule.

1. After the building or portion thereof is completely enclosed by either permanent construction or substantial temporary materials having a comparable resistance as the specified permanent construction, The Contractor shall pay and provide heat therein of not less than 55 degrees F., nor more than 75 degrees F., which shall be continuously maintained in the enclosed area to the extent necessary to properly progress and protect the work until the project is accepted.
2. The Contractor shall furnish and install one accurate recording Fahrenheit thermometer at a place acceptable to the Architect, and one additional accurate thermometer for every 2,000 square feet of floor space, located as directed by the Architect in order to determine if the specified temperatures are maintained. The Contractor or his authorized agent shall furnish daily to the Architect a signed statement of temperatures recorded every three hours.
3. The Contractor, with the approval of the Architect, may use the permanent heating system as specified for the project once it has been tested, flushed out and chemically treated, thoroughly cleaned of all construction dust and dirt, and is ready to operate. The Contractor shall pay all energy costs for heating during construction and provide meters if required. The Contractor and the HVAC and/or Electrical subcontractor shall coordinate their work so that the permanent heating system for the building will be available and ready to provide heat as soon as the building is closed in. In case the Contract includes more than one building, the heating shall be provided for each building in accordance with the above provision. The guarantee period for equipment shall not start until the equipment is turned over to the Owner for their use. Do not invalidate existing warranty by any action or failure to act. Clean and change air filters frequently to prevent construction dust and debris from contaminating system.
4. Operating labor shall be provided for continuous direct attendance, for frequent inspection of the system, emergency repairs, and keeping of temperature records. Continuous direct attendance shall mean direct attendance for twenty-four hours each day, seven days per

week, Saturdays, Sundays and holidays included, throughout the progress of the work.

5. It shall be the sole responsibility of the Contractor to arrange for and pay the HVAC and/or Electrical subcontractor to operate and to put in first-class condition all portions of the permanent heating system used for heating during construction.
6. If the system is electric heat, the foregoing requirements shall equally apply to all the comparable components thereof.
7. The installation and operation of heating devices shall comply with all safety regulations including provisions for adequate ventilation and fire protection. Heating devices which may cause damage to finish surfaces shall not be used.

H. Pumping and Drainage: Protect excavations, trenches, buildings and materials from rain water, ground water, backup or leakage of sewers, drains and other piping, and from water of any other origin. Promptly remove any accumulation of water. Provide and operate all pumps, piping and other equipment necessary for pumping, drainage and protection from water.

I. Equipment and Tools: Provide all equipment including, but not limited to, hoists, lifts, scaffolding, machines, tools and the like, as needed for execution of the work. Provide safe access to all parts of the work.

J. Temporary Enclosures: Provide temporary enclosures to maintain proper temperatures and to prevent weather damage. Always maintain legal means of egress.

K. Snow and Ice: Remove all snow and ice which interferes with work or safety.

L. Streets, Walks and Grounds: Maintain public and private roads and walks clear of debris caused by construction operations. Repair all damage caused to streets, drives, curbs, sidewalks, fences, poles and similar items where disturbed or damaged by building construction and leave them in as good condition after completion of the work as before operations started.

M. Protection: Protect nearby property and the public from construction activities. Provide and maintain barricades, warning signs and lights, railings, walkways and similar items. Immediately repair damaged property to its condition before being damaged.

N. Public Services: Provide temporary public services such as, street lighting, night lighting, sidewalks, covered passages, signs, signals and the like, as requested by authorities having jurisdiction.

O. Construction Fencing: Provide construction fencing and barriers as applicable to the project and as required by code to protect personnel, the public, and to control access.

P. Security: Secure site against unauthorized entry at all times. Provide secure, locked temporary enclosures. Protect the work at all times. Provide watchman service, if necessary, to protect the work.

Q. Signs: Erect project identification signs in compliance with details to be provided by Architect. Signs shall be minimum 4' x 8' exterior grade plywood and shall contain the names of the project, Owner, Architect, major Consultants, Contractor, and major financing institution. Except for safety and warning signs, no other signs are permitted. Location as acceptable to the

Architect.

R. Fire Prevention: Take every precaution to prevent fire. Provide and maintain in good operating condition suitable and adequate fire protection equipment and services, and comply with recommendations regarding fire protection made by the representative of the fire insurance company carrying insurance on the Work or by the local fire chief or fire marshal. The area within the site limits shall be kept orderly and clean, and all combustible rubbish shall be promptly removed from the site.

S. Egress: Maintain safe and legal means of egress at all times. At all times, provide at least two separate means of egress.

T. Mold Control and Remediation During Construction: The Contractor shall protect construction materials and building systems from moisture damage and from conditions which promote mold growth during and after construction. The Contractor shall be responsible for mold remediation and replacement of materials which cannot be successfully remediated in accordance with the following requirements:

1. Materials which become wet prior to installation shall be cleaned, treated and dried in accordance with EPA Guidelines.
2. Materials which exhibit mold growth prior to installation shall not be installed and shall be removed from the site.
3. Materials which exhibit mold growth after installation shall be remediated in accordance with EPA Guidelines for Remediating Building Materials with Mold Growth Caused by Clean Water. The Contractor shall engage and pay for a qualified industrial hygienist acceptable to the Owner to determine the cause of the mold growth, and to certify in writing that materials have been successfully remediated. In the event that the industrial hygienist recommends methods of remediation in addition to those in the Guidelines, the Contractor shall also be responsible for the additional remediation. Materials which can not be successfully remediated shall be removed and replaced with new materials at no additional expense to the Owner.
4. Prior to the start of construction, the Contractor shall submit the name of the person in the Contractor's organization responsible for ensuring compliance with these requirements for mold control and remediation.

U. Temporary Partitions: Provide floor-to-ceiling dustproof partitions to limit dust and dirt migration and to separate areas occupied by Owner and tenants from fumes and noise.

1. Construct dustproof partitions with gypsum wallboard, with joints taped on occupied side, and fire-retardant-treated plywood on construction operations side.
2. Construct dustproof partitions with two layers of 6-mil (0.14-mm) polyethylene sheet on each side. Cover floor with two layers of 6-mil (0.14-mm) polyethylene sheet, extending sheets 18 inches (460 mm) up the sidewalls. Overlap and tape full length of joints. Cover floor with fire-retardant-treated plywood.
    a. Construct vestibule and airlock at each entrance through temporary partition with not less than 48 inches (1219 mm) between doors. Maintain water-dampened foot mats in vestibule.
3. Where fire-resistance-rated temporary partitions are indicated or are required by authorities having jurisdiction, construct partitions according to the rated assemblies.
4. Insulate partitions to control noise transmission to occupied areas.
5. Seal joints and perimeter. Equip partitions with gasketed dustproof doors and security locks where openings are required.
6. Protect air-handling equipment.

7. Provide walk-off mats at each entrance through temporary partition.

1.15 PRODUCTS AND SUBSTITUTIONS

A. Specified Products: In all cases in which a manufacturer's name, trade name or other proprietary designation is used in connection with materials or articles to be furnished under this Contract, whether or not the phrase "or equal" is used after such name, the Contractor shall provide the product of the named manufacturers without substitution, unless a written request for a substitution has been submitted by the Contractor and approved in writing by the Architect.

B. Deviations from Detailed Requirements: If the Contractor proposes to use material which, while suitable for the intended use, deviates in any way from the detailed requirements of the Contract Documents, the Contractor shall inform the Architect in writing of the nature of such deviations at the time the materials is submitted for approval, and shall request written approval of the deviation from the requirements of the Contract Documents.

C. Approval of Substitutions: In requesting approval of deviations or substitutions, the Contractor shall provide evidence, including, but not limited to manufacturer's data, leading to a reasonable certainty that the proposed substitution or deviation will provide a quality of result at least equal to that attainable if the detailed requirements of the Contract Documents were strictly followed. If, in the opinion of the Architect, the evidence presented by the Contractor does not provide a sufficient basis for such reasonable certainty, the Architect may reject such substitution or deviation without further investigation.

D. Intent of Contract Documents: The Contract Documents are intended to produce a building of consistent character and quality of design. All components of the building including visible items of mechanical and electrical equipment have been selected to have a coordinated design in relation to the overall appearance of the building. The Architect shall judge the design and appearance of proposed substitutes on the basis of the suitability in relation to the overall design of the Project, as well as for their intrinsic merits. The Architect will not approve as equal to materials specified proposed substitutes which in the Architect's opinion, would be out of character, obtrusive, or otherwise inconsistent with the character or quality of design of the Project. In order to permit coordinated design of color and finishes the Contractor shall furnish the substituted material in any color, finish texture, or pattern which would have been available from the manufacturer originally specified, at no additional cost to the Owner.

E. Additional Costs or Impact: Any additional cost, or any loss or damage arising from the substitution of any material or any method for those originally specified shall be borne by the contractor, notwithstanding approval or acceptance of such substitution by the Owner or the Architect, unless such substitution was made at the written request or direction of the Owner and the Architect. Any decrease in the cost of the substitution shall be returned to the Owner.

F. Manufacturers: To the greatest degree possible, provide primary materials and products from one manufacturer for each type or kind. Provide secondary materials as recommended by manufacturers of primary materials.

G. Substitution Requests: Refer to Section 016200 - SUBSTITUTION REQUEST FORM. Submit 3 copies or digital distribution. Identify product to be replaced by substitute by reference to specification sections and drawing numbers. Provide Contractor's certification and evidence to

prove compliance with Contract Document requirements as acceptable to Architect.

H. Substitution Conditions: Substitution requests will be returned without action unless one of the following conditions is satisfied. The Contractor shall state which of the following conditions applies to the requested substitution:

1. Request is due to an "or equal" clause.
2. Specified material or product cannot be coordinated with other work.
3. Specified material or product is not acceptable to authorities having jurisdiction.
4. Substantial advantage is offered Owner in terms of cost, time, or other valuable consideration.
5. Specified material or product is not available.

I. Invalid Substitutions: Contractor's submittal and Architect's acceptance of shop drawings, samples, product data or other submittal is not a valid request for, nor an approval of a substitution unless the Contractor presents the information when first submitted as a Request for Substitution.

J. Compatibility of Materials Used in the Work:

1. Ensure complete compatibility between materials.
2. Compatibility shall include adhesion, erosion, solubility, differential thermal response, and galvanic action.
3. Provide evidence of compatibility.
4. Provide custom testing where evidence is not available.
5. Where materials are not compatible, provide necessary isolation or transition materials and provide details of same.
6. Correct defects resulting from incompatibility including de-construction and re-construction of assemblies – whether materials are part of a submittal and substitution process or not.
7. Proposed substitutions may be rejected where compatibility information is not provided; or where compatibility is not adequately addressed, according to the Architect’s judgment; or where incompatible materials would negatively impact the project’s success.

1.16 DELIVERY, STORAGE AND HANDLING

A. Manufacturer's Instructions: Strictly comply with manufacturer's instructions and recommendations and prevent damage, deterioration and loss, including theft. Minimize long-term storage at the site. Maintain environmental conditions, temperature, ventilation, and humidity within range permitted by manufacturers of materials and products used.

1.17 OWNER-FURNISHED CONTRACTOR-INSTALLED (OFCI) PRODUCTS

A. Owner will furnish products indicated. The Contractor’s Work includes providing support systems to receive Owner's equipment and making plumbing, mechanical, and electrical connections.

1. Owner will arrange for and deliver Shop Drawings, Product Data, and Samples to Contractor.
2. Owner will arrange and pay for delivery of Owner-furnished items according to Contractor's Construction Schedule.
3. After delivery, Owner will inspect delivered items for damage. Contractor shall be present

for and assist in Owner's inspection.

4. If Owner-furnished items are damaged, defective, or missing, Owner will arrange for replacement.
5. Owner will arrange for manufacturer's field services and for delivery of manufacturer's warranties to Contractor.
6. Owner will furnish Contractor the earliest possible delivery date for Owner-furnished products. Using Owner-furnished earliest possible delivery dates, Contractor shall designate delivery dates of Owner-furnished items in Contractor's Construction Schedule.
7. Contractor shall review Shop Drawings, Product Data, and Samples and return them to Architect noting discrepancies or anticipated problems in use of product.
8. Contractor is responsible for receiving, unloading, and handling Owner-furnished items at Project site.
9. Contractor is responsible for protecting Owner-furnished items from damage during storage and handling, including damage from exposure to the elements.
10. If Owner-furnished items are damaged as a result of Contractor's operations, Contractor shall repair or replace them.
11. Contractor shall install and otherwise incorporate Owner-furnished items into the Work.

B. Owner-Furnished Products: As directed by the Architect.

1.18 LABELS

A. Labels, Trademarks, & Tradenames: Locate required labels on inconspicuous surfaces. Do not provide labels, nameplates, or trademarks which are not required. Provide permanent data plate on each item of equipment stating manufacturer, model, serial number, capacity, ratings and all other essential data.

1.19 RECORD DOCUMENTS

A. Definition of As-Constructed Record Drawings: (commonly called “as-builts”) are the record of the Project as constructed based on information the Contractor provides to the Owner under the contract for construction. Because the As-constructed Record Drawings will be based on the Contractor’s mark-ups, the Architect is not responsible for the accuracy or completeness of the As-constructed Record Drawings.

B. Definition of As-Designed Record Drawings: The record of everything the Architect designed for the Project, and including the original Construction Documents plus all addenda, Architect’s Supplemental Instructions, Change Orders, Construction Change Directives and minor changes in the work.

C. General: Keep as-constructed record documents neatly and accurately. Record information as the work progresses and deliver to Architect at time of final acceptance. Include in record documents all field changes made, all relevant dimensions, and all relevant details of the work. Keep record documents up to date with all Architect’s Supplemental Instructions, Change Orders, Construction Change Directives and minor changes in the work clearly indicated.

D. Drawings: Keep four separate sets of blackline prints at the site, one set each for mechanical, electrical, plumbing, and architectural/structural disciplines. Neatly and accurately note all deviations from the Contract Documents and the exact actual location of the work as installed.

Marked-up and colored prints will be used as a guide to determine the progress of the work installed. Requisitions for payment will not be approved until the record documents are accurate and up-to-date.

1. Work Outside Building: Record data outside of building to an accuracy of plus or minus 1 inch and determine and record the invert elevation of all drain lines.
2. At completion of the work, submit one complete set of marked-up as-built prints for review. After acceptance, these marked-up as-built prints shall be used in the preparation of the as-built drawings.
3. Architect shall furnish Contractor with AutoCAD or BIM Design Intent Model or both files for originals of the Contract Drawings. The Contractor shall make modifications to these files as shown on the marked-up prints. Remove superseded data to show the completed installation.
4. The Contractor shall deliver the completed AutoCAD or BIM Design Intent Model or both as-constructed record drawings, in the same version as Contract Drawings, properly titled and dated to the Architect. Indicate preparer of as-built drawings. These as-built drawings shall become the property of the Owner.

E. Specifications: Maintain one clean copy of complete specifications including addenda, modifications, and bulletins with changes, substitutions, and selected options clearly noted. Circle or otherwise clearly indicate which manufacturer and products are actually used.

F. Operating and Maintenance Manuals: Manuals shall be submitted which contain the following:

1. Description of the system provided.
2. Handling, storage, and installation instructions.
3. Detailed description of the function of each principal component of the systems or equipment.
4. Operating procedures, including prestartup, startup, normal operation, emergency shutdown, normal shutdown and troubleshooting.
5. Maintenance procedures including lubrication requirements, intervals between lubrication, preventative and repair procedures, and complete spare parts list with cross reference to original equipment manufacturer's part numbers.
6. Control and alarm features including schematic of control systems, control loop electric ladder diagrams, controller operating set points, settings for alarms and shutdown systems, pump curves and fan curves.
7. Safety and environmental considerations.

G. Copies of Operating and Maintenance Manuals: Three copies or digital, at Owners' preference, of the manuals shall be provided within sufficient time to allow for training of Owner's personnel. Submit one copy of the manuals to the Architect for review no later than 90 calendar days prior to substantial completion, or building turn over, whichever comes first. Submit the remaining five copies within 15 days after first review set is returned to contractor. Progress payment may be withheld if this requirement is not met.

H. Additional Requirements for Operating and Maintenance Manuals: The requirements for manuals applies to each packaged and field-fabricated operating system. The manuals shall be provided in three-ring side binders with durable plastic covers. The manuals shall contain a detailed table of contents and have tab dividers for major sections and special equipment.

I. Instructions for Owner's Personnel: Prior to final inspection, instruct the Owner's personnel in operation, adjustment and maintenance of products, equipment and systems. Provide instruction at mutually agreed upon times. Video all instruction sessions and deliver videos to

Owner on thumb drive or other suitable media.

1. For equipment that requires seasonal operation provide similar instruction during other seasons.
2. Use operation and maintenance manuals for each piece of equipment or system as the basis of instruction. Review contents in detail to explain all aspects of operation and maintenance.

J. Framed Data: Provide charts and lists of all valves, circuits, switches, controls and equipment. Install on walls under glass at locations directed by Architect.

1.20 PROJECT CLOSE OUT

A. Complete the following prior to Substantial Completion:

1. Provide Contractor's Punch List of incomplete items stating reason for incompletion and value of incompletion.
2. Advise Owner of insurance change over requirements.
3. Submit all warranties, maintenance contracts, final certificates and similar documents.
4. Obtain Certificate of Occupancy and similar releases which permit the Owner's full and unrestricted use of the areas claimed "Substantially Complete".
5. Submit record documents.
6. Deliver maintenance stocks of materials where specified.
7. Make final change over of lock cylinders or cores and advise Owner of change of security responsibility.
8. Complete startup of all systems and instruct Owner's personnel in proper operation and routine maintenance of systems and equipment.
9. Complete clean up and restoration of damaged finishes.
10. Remove all temporary facilities and utilities that are no longer needed.
11. Request Architect's inspection for Substantial Completion.

B. Architect will either issue a Certificate of Substantial Completion or notify Contractor of work which must be performed prior to issue of certificate.

C. Complete the following prior to Final Acceptance and payment:

1. Obtain Certificate of Substantial Completion.
2. Submit final application for payment, showing final accounting of changes in the work.
3. Provide final releases and lien waivers not previously submitted.
4. Submit certified copy of final punch list stating that Contractor has completed or corrected each item.
5. Submit final meter readings, record of stored fuel and similar information.
6. Submit Consent of Surety for final payment.
7. Submit evidence of Contractor's continuing insurance coverage (if required by Contract Documents).

1.21 CLASSROOM CLEANING

A. In addition to requirements for final cleaning specified below, Contractor shall provide complete cleaning of classrooms at the following schools:

1. Fairview.

2. Tennyson.
3. Harris Park.
4. Sherrelwood.

B. Classroom cleaning shall be performed following completion of construction, abatement, moving, packing, and other Work that may generate dust, dirt, debris, or other contaminants within classrooms, and prior to turnover of the classrooms to the Owner.

C. Provide thorough cleaning of classrooms, including, but not limited to, the following:

1. Remove construction dust, dirt, debris, and residue from floors, walls, ceilings, doors, frames, windows, window sills, casework, cabinets, shelving, countertops, ledges, trim, and other exposed surfaces.
2. Clean and vacuum floors, including corners, edges, and areas beneath and behind movable furnishings and equipment where accessible.
3. HEPA vacuum dust and debris from horizontal surfaces, ledges, sills, and other areas where dust may accumulate.
4. Damp wipe cleanable surfaces to remove remaining dust and residue.
5. Clean interior glazing and window frames.
6. Clean doors, door frames, hardware, and other accessible surfaces.
7. Clean fixed casework, shelving, countertops, and similar built-in components.
8. Remove labels, tape, temporary protection, adhesive residue, and other construction-related markings from finished surfaces.
9. Remove all remaining construction materials, packaging, debris, and other items not intended to remain.
10. Clean classrooms sufficiently to provide a clean, dust-free condition suitable for occupancy and use by the Owner.

D. Coordinate classroom cleaning with the Owner's schedule and with completion of abatement, moving, packing, and other Work occurring within the schools.

E. Do not perform classroom cleaning until Work that could re-contaminate or otherwise adversely affect the cleaned spaces has been completed, unless otherwise approved by the Owner.

F. Protect cleaned classrooms from subsequent construction activities, dust, debris, and damage. Re-clean affected areas as necessary at no additional cost to the Owner.

G. Contractor shall coordinate access, sequencing, and cleaning operations with the Owner and shall provide sufficient labor and equipment to complete classroom cleaning within the Project schedule.

H. Classroom cleaning specified herein is in addition to and not in lieu of final cleaning requirements specified elsewhere in the Contract Documents.

1.22 FINAL CLEANING AND REPAIR

A. Clean Up: Immediately prior to the Architect's inspection for Substantial Completion, the Contractor shall completely clean the premises and clean and prepare the completed work in order for it to be used for its intended purpose in accordance with the Contract Documents. Such work shall include, but not be limited to the following:

1. Concrete and ceramic surfaces shall be cleaned and washed.
2. Resilient coverings shall be cleaned, waxed and buffed as applicable.
3. Woodwork shall be dusted and cleaned.
4. Sash, fixtures and equipment shall be thoroughly cleaned.
5. Stains, spots, dust, marks and smears shall be removed from all surfaces.
6. Hardware and metal surfaces shall be cleaned and polished.
7. Glass and plastic surfaces shall be thoroughly cleaned by professional window cleaners.
8. Damaged, broken or scratched glass or plastic shall be replaced by the Contractor at the Contractor's expense.
9. Vacuum carpeted and soft surfaces with high efficiency particulate arrestor (HEPA) vacuum.
10. Use low-emitting, environmentally friendly cleaning agents and procedures. Do not use ammonia-, chlorine bleach-, or solvent-based cleaners, unless authorized in writing by Architect.

B. Repairs: Repair and touch-up all damaged and deteriorated products and surfaces.

PART 2 PRODUCTS [NOT USED]

PART 3 EXECUTION

3.1 INSTALLATION, GENERAL

A. Isolation of Work Areas in Occupied Facilities: Prevent dust, fumes, and odors from entering occupied areas.

1. Prior to commencing work, isolate the HVAC system in area where work is to be performed.
   a. Disconnect supply and return ductwork in work area from HVAC systems servicing occupied areas.
   b. Maintain negative air pressure within work area, using HEPA-equipped air-filtration units, starting with commencement of temporary partition construction, and continuing until removal of temporary partitions is complete.
2. Maintain dust partitions during the Work. Use vacuum collection attachments on dust-producing equipment. Isolate limited work within occupied areas using portable dust-containment devices.
3. Perform daily construction cleanup and final cleanup using approved, HEPA-filter-equipped vacuum equipment.

END OF SECTION

SECTION 012200

UNIT PRICES

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 SUMMARY

A. This Section covers those items for which indefinite quantities can be expected and, therefore, pre-agreed prices per unit of work are established as means to determine adjustments to the Contract Price after actual quantities are determined.

1.3 QUANTITIES AND COST ADJUSTMENTS

A. Refer to individual Specification Sections for methods of measurement and payment for unit prices. As soon as the work involved in each unit cost item has been completed, submit documentation to establish the actual quantities provided. Submit to the Architect for review and issuance of Change Order.

B. Change Order amount for each unit cost item will be based on actual quantities multiplied by the unit price. This unit price includes all costs as described below.

1.4 UNIT PRICES

A. Should certain additional work be required, or should the quantities of certain classes of work be increased or decreased from those required by the Contract Documents, by authorization of the Owner, the below unit prices shall, at the option of the Owner, be the basis of payment to the Contractor or credit to the Owner, for such increase or decrease in the work.

B. The Unit Prices shall represent the exact net amount per unit to be paid the Contractor (in the case of additions or increases) or to be refunded the Owner (in the case of decreases). No additional adjustment will be allowed for materials, installation, substrate preparation, overhead, profit, insurance, general conditions, or other direct or indirect expenses of the Contractor or Subcontractors.

PART 2 - PRODUCTS [Not Used]

PART 3 - EXECUTION

3.1 SCHEDULE OF UNIT PRICES

A. Areas of masonry repointing and/or repair, as indicated on the Drawings. Contractor to provide unit pricing for the quantities indicated.

B. As otherwise defined by the Architect or referenced on the drawings.

END OF SECTION

SECTION 014330

MOCKUPS

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 SUMMARY

A. General: Provide and coordinate mock-up assemblies at Project site for Architect's review and acceptance, in accordance with requirements of the Contract Documents. Refer to individual Specification Sections for mock-up requirements. Generally, without limitation, mock-ups on site include the following:

1. Mock-ups of individual pieces of the work, as specified within individual Specification Section.
2. Field Mock-Up of interior construction. Refer to the Drawings for extent of mock-up.

B. It shall be the responsibility of the Contractor to coordinate the work of the related Specification Sections so that each mock-up meets the specified requirements.

C. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Individual Specification Sections for Submittal Samples.

1.3 DEFINITIONS

A. Freestanding Mock-Ups: Full-size, physical assemblies that are constructed on-site in a protected location.

1. Freestanding mock-ups are not part of the final construction. Freestanding mock-ups will be used to verify selections made under sample submittals, to demonstrate aesthetic effects, qualities of materials and execution, and to review construction, coordination, testing, and operation.
2. Approved freestanding mock-ups establish the standard by which the Work will be judged.
3. Approved freestanding mock-ups remain on site during the balance of construction and are demolished and removed from site at completion of the Work they represent.

B. In-Place Mock-Ups: Full-size, physical assemblies that are constructed in-place and remain part of final construction.

1. In-place mock-ups will be used to verify selections made under sample submittals, to demonstrate aesthetic effects, qualities of materials and execution, and to review construction, coordination, testing, or operation.

2. Approved in-place mock-ups establish the standard by which the Work will be judged.
3. Approved mock-ups remain part of the completed Work.

1.4 SUBMITTALS

A. Schedule: Construction Manager shall submit a schedule of mock-up construction, including dates for mock-up review by the Architect.

1. Mock-up schedule shall be reviewed at each progress meeting, revised and resubmitted as required.
2. Schedule shall allow sufficient time for mock-ups which are not accepted to be reconstructed and reviewed until accepted by the Architect.

B. Shop Drawings of Mock-Ups: Provide large scale shop drawings for fabrication, installation and erection of all parts of each mock-up. Provide plans, elevations, and details of anchorage, connections and accessory items.

C. Photographs of Mock-Ups: Submit photographs of mock-ups after completion of installation and acceptance of each mock-up.

D. Submittal Samples: Refer to individual Specification Sections for submittal requirements of mock-up components and coordinate accordingly.

1.5 QUALITY ASSURANCE

A. Design Modifications: Make design modifications to work only as required to meet performance requirements and to coordinate the work. Indicate proposed design modifications on shop drawings. Maintain original design concept without altering profiles and alignments indicated.

PART 2 - PRODUCTS

2.1 MATERIALS AND PRODUCTS

A. Provide materials, components, and products for mock-ups as specified in individual Specification Sections.

PART 3 - EXECUTION

3.1 GENERAL

A. Refer to PART 3, EXECUTION portions of the various Specification Sections for specific requirements regarding condition of surfaces, erection, and erection tolerances.

3.2 FIELD MOCK-UP OF INTERIOR CONSTRUCTION

A. Provide a field mock-up of the interior construction items at locations and in configuration indicated on Drawings or as otherwise directed. Obtain Architect's acceptance of visual qualities prior to commencing work that individual mock-up is intended to represent. Protect and maintain approved mock-ups throughout the work of the Contract. Locate mock-ups at the Project site as directed by Architect.

1. Refer to Drawings for extent of the field mock-up.
2. Provide modifications to mock-up as required until Architect's approval has been received.

B. Interior Construction Mock-ups: Provide mock-ups of various interior construction as indicated or as specified in the applicable Specification Sections, as directed by the Architect.

3.3 INDIVIDUAL MOCK-UPS

A. Provide individual mock-ups of types and sizes required by individual Specification Sections to evaluate and set the standard of quality for that work. Obtain Architect's acceptance of visual qualities prior to commencing work that individual mock-up is intended to represent. Protect and maintain approved mock-ups throughout the work of the Contract. Locate mock-ups at the Project site as directed by the Architect.

1. Provide as many mock-ups as required until Architect's approval has been received.
2. When indicated in individual Specification Sections, approved mock-ups may be incorporated into the finish work.

3.4 REPAIR AND PROTECTION

A. General: On completion of testing, inspecting, sample taking, and similar services, repair and restore substrates and finishes.

1. Provide materials and comply with installation requirements specified in other Specification Sections. Restore patched areas and extend restoration into adjoining areas with durable seams that are as non-visible as possible.

B. Protect construction exposed by or for quality-control service activities.

3.5 REMOVAL AND DISPOSAL

A. Demolish and remove mock-ups from site at the completion of the Project. Legally dispose of demolished mock-up materials.

END OF SECTION

This page left intentionally blank.

SECTION 016200

SUBSTITUTION REQUEST FORM

No substitutions will be considered without this completed substitution request form and supporting documentation. Substitutions made without completion of this form will be considered defective work as stated in AIA A201.

Date: _____ Number: _____

Re: Request for Substitution

The Contractor proposes the following substitution in accordance with the requirements of the Contract Documents:

Scope of Substitution _____

_____

Specification Reference _____

_____

Drawing Reference _____

_____

Reason for Proposed Substitution _____

_____

Benefit to Owner _____

_____

Impact on Project Cost _____

_____

Impact on Project Schedule _____

_____

Impact on Guarantees and Warranties _____

_____

Coordination and Compatibility Required with Adjacent Materials and System _____

_____

_____

List Deviations From Specified Requirements _____

_____

_____

Building Energy Performance: For substitutions of materials and products used for backstop and de-rated calculations, provide an updated envelope backstop and de-rating calculations based on the product being proposed for substitution and demonstrate the equivalence or difference with the original product[s]. Substitutions which, in the opinion of the architect, modify the energy design, and which are submitted without the required evidence of compliance with the code and the original design will be returned without review and are by definition not permitted.

Attachments: Attach supporting documentation sufficient for Architect to evaluate substitution. Substitution Request Forms submitted without adequate documentation will be returned without review.

Attachments _____

_____

_____

Response Date: List date by which response by Architect is requested to maintain project schedule and allow sufficient time for inclusion of proposed substitution.

Response Date _____

Submitted By _____

Firm and Address _____

_____

Signature below signifies acceptance of responsibility for accuracy and completeness of information included in this Substitution Request Form.

Authorized Signature _____

ARCHITECT'S RESPONSE

Notations listed below shall have same meaning as on Architect's approval stamp. Clarifications to or changes in project schedule or time shall be processed using standard project forms.

Architect's Response

_____ Approved

_____ Approved as Corrected

_____ Revise and Resubmit

_____ Rejected

_____ Returned Without Review

Remarks _____

_____

_____

_____

_____

_____

Date _____

Signed _____

END OF FORM

This page left intentionally blank.

SECTION 024100

DEMOLITION

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS, which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included:

1. Selective Demolition to be coordinated with the phasing of the Work.
2. Demolition and removal of selected portions of buildings and structures and as required for new work. Refer to the Drawings for additional requirements.
3. Salvage of existing items to be reused or turned over to the facility.
4. Removal and legal disposal of demolished materials off site. Except those items specifically designated to be relocated, reused, or turned over to the facility, all existing removed materials, items, trash and debris shall become property of the Contractor and shall be completely removed from the site and legally disposed of at their expense. Salvage value belongs to the Contractor. On-site sale of materials is not permitted.
5. Demolition and removal work shall properly prepare for alteration work and new construction to be provided under the Contract.
6. Scheduling and sequencing operations without interruption to utilities serving occupied areas. If interruption is required, obtain written permission from the utility company and the Owner.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 011000 - GENERAL REQUIREMENTS for temporary facilities and controls, for maintenance of access, for cleaning during construction, and for dust and noise control.
2. Section 017400 - CONSTRUCTION WASTE MANAGEMENT for waste management and recycling.
3. Section 018120 - CONSTRUCTION INDOOR AIR QUALITY (IAQ) MANAGEMENT for indoor air quality control procedures.
4. Division 21 - FIRE PROTECTION:
   a. Disconnecting, capping and otherwise making inactive existing fire protection services in areas where demolition and removal work is required.
   b. Disconnect and reinstallation of fire protection equipment temporarily interrupted during construction.
5. Division 22 - PLUMBING:
   a. Disconnecting, capping and otherwise making inactive existing plumbing services in areas where demolition and removal work is required.
   b. Disconnection and reinstallation of plumbing equipment temporarily interrupted during construction.
6. Division 23 - HEATING, VENTILATING AND AIR CONDITIONING:
   a. Disconnecting, capping and otherwise making inactive existing HVAC services in areas

where demolition and removal work is required.

b. Disconnect and reinstallation of HVAC equipment temporarily interrupted during construction.

7. Division 26 - ELECTRICAL WORK:
   a. Disconnecting, capping and otherwise making inactive existing electrical services in areas where demolition and removal work is required.
   b. Disconnect and reinstallation of electrical equipment temporarily interrupted during construction.

1.3 DEFINITIONS

A. Remove: Detach items from existing construction and legally dispose of them off-site, unless indicated to be removed and salvaged or removed and reinstalled.

B. Remove and Salvage: Detach items from existing construction and deliver them to the Owner ready for reuse, at a location designated by the Owner. Protect from weather until accepted by Owner.

C. Remove and Reinstall: Detach items from existing construction, prepare them for reuse, and reinstall them where indicated. Protect from weather until reinstallation.

D. Existing to Remain: Existing items of construction that are not to be removed and that are not otherwise indicated to be removed, removed and salvaged, or removed and reinstalled.

1.4 MATERIALS OWNERSHIP

A. Historic items, relics, and similar objects including, but not limited to, cornerstones and their contents, commemorative plaques, antiques, and other items of interest or value to Owner that may be encountered during selective demolition remain property of the Owner as applicable. Carefully remove each item or object in a manner to prevent damage and deliver promptly to a location acceptable to the Owner.

1.5 SUBMITTALS

A. Schedule of Selective Demolition Activities: Indicate the following:

1. Detailed sequence of selective demolition and removal work, with early and late starting and finishing dates for each activity. Ensure Owner's on-site operations are uninterrupted if applicable.
2. Interruption of utility services. Indicate how long utility services will be interrupted.
3. Coordination for shutoff, capping, and continuation of utility services.
4. Use of elevator and stairs.
5. Locations of proposed dust- and noise-control temporary partitions and means of egress, including for other occupants affected by selective demolition operations.
6. Coordination of Owner's continuing occupancy of portions of existing building and of Owner’s partial occupancy of completed Work.
7. Means of protection for items to remain and items in path of waste removal from building.

B. Inventory: After selective demolition is complete, submit a list of items that have been removed

and salvaged, and turned over the Owner.

C. Predemolition Video and Pictures: Show existing conditions of adjoining construction and site improvements, including finish surfaces, that might be misconstrued as damage caused by selective demolition operations. Comply with Division 01 requirements. Submit before Work begins.

1.6 QUALITY ASSURANCE

A. Examination of Existing Conditions: The Contractor shall examine the Contract Drawings for demolition and removal requirements and provisions for new work. Verify all existing conditions and dimensions before commencing work. The Contractor shall visit the site and examine the existing conditions as he finds them and shall inform herself/himself of the character, extent and type of demolition and removal work to be performed. Submit any questions regarding the extent and character of the demolition and removal work in the manner and within the time period established for receipt of such questions during the bidding period.

B. Demolition Firm Qualifications: An experienced firm that has specialized in demolition work similar in material and extent to that indicated for this Project.

C. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.

D. Standards: Comply with ANSI A10.6 and NFPA 241.

E. Predemolition Conference: Conduct conference at Project site to comply with requirements in Section 011000 - GENERAL REQUIREMENTS, Project Meetings. Review methods and procedures related to selective demolition including, but not limited to, the following:

1. Inspect and discuss condition of construction to be selectively demolished.
2. Review structural load limitations of existing structure.
3. Review and finalize selective demolition schedule and verify availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays.
4. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.
5. Review areas where existing construction is to remain and requires protection.

1.7 WARRANTY

A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during selective demolition, by methods and with materials so as not to void existing warranties.

PART 2 PRODUCTS

2.1 SALVAGING

A. Salvaged for Reinstallation: Materials indicated on the Drawings to be salvaged and reinstalled shall be carefully removed and stored at a location acceptable to the Architect and Owner.

B. Salvaged for Storage: Materials indicated on the Drawings or designated in the field by the Owner to be salvaged and stored shall be carefully removed and delivered to the Owner at locations determined by Owner.

PART 3 EXECUTION

3.1 EXAMINATION

A. Verify that utilities have been disconnected and capped.

B. Survey existing conditions and correlate with requirements indicated to determine extent of selective demolition required.

C. Inventory and record the condition of items to be removed and reinstalled and items to be removed and salvaged.

D. When unanticipated mechanical, electrical, or structural elements that conflict with intended function or design are encountered, investigate and measure the nature and extent of conflict. Promptly submit a written report to Architect.

E. Engage a professional engineer registered in the state that the project is located to survey condition of building to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of structure or adjacent structures during selective demolition operations.

F. Survey of Existing Conditions: Record existing conditions by use of preconstruction videotapes.

1. Before selective demolition or removal of existing building elements that will be reproduced or duplicated in final Work, make permanent record of measurements, materials, and construction details required to make exact reproduction.

G. Perform surveys as the Work progresses to detect hazards resulting from selective demolition activities.

3.2 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

A. Service/System Requirements: Locate, identify, disconnect, and seal or cap off indicated utility services and mechanical/electrical systems serving areas to be selectively demolished.

1. Arrange to shut off indicated utilities with utility companies and Owner.

2. If services/systems are required to be removed, relocated, or abandoned, before proceeding with selective demolition provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
3. Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit after bypassing. Where entire wall is to be removed, existing services/systems may be removed with removal of the wall.
4. Prior to commencing cutting work in existing surfaces, take all precautionary measures to assure that mechanical and electrical services to the particular area have been made inactive. Coordinate with Fire Suppression, Plumbing, HVAC, and Electrical subcontractors. Only licensed tradesmen of that particular trade shall disconnect and cap existing mechanical and electrical items that are to be removed, abandoned and/or relocated.
5. If, during the process of cutting work, existing utility lines are encountered which are not indicated on the Drawings, regardless of their condition, immediately report such items to the Architect. Do not proceed with work in such areas until instructions are issued by the Architect. Continue work in other areas.

3.3 PREPARATION

A. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.

1. Comply with requirements for access and protection specified in Section 011000 - GENERAL REQUIREMENTS, Temporary Facilities and Controls.
2. Maintain adequate passage to and from all exits at all times. Before any work is done which significantly alters access or egress patterns, consult with the Architect and obtain approval of code required egress. Under no condition block or interfere with the free flow of people at legally required exits, or in any way alter the required condition of such exits.

B. Temporary Shoring: Provide and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.

1. Strengthen or add new supports when required during progress of selective demolition.
2. Remove temporary shoring, bracing and structural supports when no longer required.
3. Post warning signs and place barricades as applicable during placement and removal of temporary shoring.

C. Conduct demolition operations to prevent injury to people and damage to adjacent buildings and facilities to remain. Ensure safe passage of people around demolition area(s).

1. Erect temporary protection, such as walks, fences, railings, canopies, and covered passageways, where required by authorities having jurisdiction. Provide temporary barricades as required to limit access to demolition areas.
2. Protect existing site improvements, appurtenances, and landscaping to remain.

3.4 SELECTIVE DEMOLITION, GENERAL

A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:

1. Proceed with selective demolition systematically, from higher to lower level. Complete

selective demolition operations above each floor or tier before disturbing supporting members on the next lower level.

2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping, to minimize disturbance of adjacent surfaces. Temporarily cover openings to remain.
3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
4. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain fire watch and portable fire-suppression devices during flame-cutting operations.
5. Maintain adequate ventilation when using cutting torches.
6. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
7. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
8. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
9. Maintain clear unimpeded passage through the work area for safety and emergency egress.
10. Saw cut overruns in concrete and masonry for new door, window and other finish openings is not permitted. Core drill corners and finish square to match required opening.
11. Dispose of demolished items and materials promptly.

B. Removed and Salvaged Items:

1. Clean salvaged items.
2. Pack or crate items after cleaning. Identify contents of containers.
3. Store items in a secure area until delivery to Owner.
4. Transport items to storage area designated by the Owner.
5. Protect items from damage during transport and storage.

C. Removed Items for Reinstallation by the Respective Trade.

1. Clean salvaged items.
2. Pack or crate items after cleaning. Identify contents of containers.
3. Store items in a secure area until delivery to Owner.
4. Transport items to storage area designated by the Owner.
5. Protect items from damage during transport and storage.

D. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and cleaned and reinstalled in their original locations after selective demolition operations are complete.

E. Items for Re-use and Preservation of Existing Surfaces to Remain:

1. The Contractor shall inspect closely each item specifically designated to be relocated, re-used, or turned over to the Owner prior to its removal, and immediately report damages and defects to the Architect and the Owner. The Contractor shall be responsible for any subsequent damage to the same other than latent defects not readily apparent from close inspection, and shall bear responsibility for its repair or same replacement as directed by the Architect, to the satisfaction of the Owner.
2. Unless special surface preparation is specified under other Specification Sections, leave existing surfaces that are to remain in a condition suitable to receive new materials and/or

finishes.

3.5 PROTECTION OF PUBLIC AND PROPERTY

A. Provide all measures required by federal, state and municipal laws, regulations, and ordinances for the protection of surrounding property, the public, workmen, and Owner's employees during all demolition and removal operations. Measures are to be taken, but not limited to installation of sidewalks, sheds, barricades, fences, warning lights and signs, trash chutes and temporary lighting.

B. Protect all walks, roads, streets, curbs, pavements, trees and plantings, on and off premises, and bear all costs for correcting such damage as directed by the Architect, and to the satisfaction of the Owner.

C. Demolition shall be performed in such a manner that will insure the safety of adjacent property. Protect adjacent property from damage and protect persons occupying adjacent property from injuries which might occur from falling debris or other cause and so as not to cause interference with the use of other portions of the building, of adjacent buildings or the free access and safe passage to and from the same.

D. Every precaution shall be taken to protect against movement or settlement of the building, of adjacent buildings, sidewalks, roads, streets, curbs and pavements. Provide and place at the Contractor's own expense, all necessary bracing and shoring in connection with demolition and removal work.

E. Remove portions of structures with care by using tools and methods that will not transfer heavy shocks to existing and adjacent building structures, both internal and external of the particular work area.

F. Provide and maintain in proper condition, suitable fire resistive dust barriers around areas where interior demolition and removal work is in progress. Dust barriers shall prevent the dust migration to adjacent areas. Remove dust barriers upon completion of major demolition and removal in the particular work area.

3.6 DISCOVERY OF HAZARDOUS MATERIALS

A. If hazardous materials, such as chemicals, asbestos-containing materials, or other hazardous materials are discovered during the course of the work, cease work in affected area only and immediately notify the Architect and the Owner of such discovery. Do not proceed with work in such areas until instructions are issued by the Architect. Continue work in other areas.

B. If unmarked containers are discovered during the course of the work, cease work in the affected area only and immediately notify the Architect and the Owner of such discovery. Do not proceed with work in such areas until instructions are issued by the Architect. Take immediate precautions to prohibit endangering the containers integrity. Continue work in other areas.

3.7 CUTTING

A. Perform all cutting of existing surfaces in a manner which will ensure a minimal difference between the cut area and new materials when patched. Use extreme care when cutting existing surfaces containing concealed utility lines which are indicated to remain and bear full responsibility for repairing or replacement of all such utilities that are accidentally damaged.

B. Provide a flush saw cut edge where pavement, curb and concrete removals abut new construction work or existing surfaces to remain undisturbed.

C. All slurry and water shall be contained and managed to avoid damage to existing conditions when using a wet saw or wet core driller.

D. Obtain and pay for a hot work permit and arrange to have on-site a Fire Watch when using a cutting torch or similar item.

3.8 DISPOSAL OF DEMOLISHED MATERIALS

A. General: Comply with the following:

1. Do not allow demolished materials to accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.

B. Burning: Do not burn demolished materials.

3.9 CLEANING

A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Premises shall be left in a clean condition and ready to accept alteration work and new construction.

END OF SECTION

SECTION 040120

MASONRY RESTORATION AND CLEANING

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Repairing clay masonry, including replacing damaged units as indicated on Drawings.
2. Reanchoring veneers.
3. Repointing mortar joints, removing existing mortar and replacing with new color mortar.
4. Removing plant growth (vines).
5. Cleaning exposed clay masonry surfaces, including decorative stonework.
6. Provide for repair or replacement of clay and stone masonry broken or damaged during disassembly and reconstruction. Contractor shall be responsible for damage resulting from work of this Section.
7. Provide shoring and bracing required to maintain stability of masonry during work of this Section. Coordinate with requirements of Section 011000 - GENERAL REQUIREMENTS.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 012200 - UNIT PRICES.
2. Section 024100 - DEMOLITION for demolition, removal and salvage requirements, to the extent not specified in this Section.
3. Section 042000 - UNIT MASONRY for new clay masonry veneer.
4. Section 076200 - SHEET METAL FLASHING AND TRIM for metal flashing installed in or on restored masonry.
5. Section 079200 - JOINT SEALANTS for sealing joints in restored masonry.

1.3 SUBMITTALS

A. Product Data: For each type of product indicated. Include recommendations for application and use. Include test data substantiating that products comply with requirements.

B. Samples for Verification: Before erecting mockup, submit samples of the following:

1. Each type of exposed masonry unit to be used for replacing existing units.

a. For each brick type, provide straps or panels containing at least four bricks.

2. Each type of sand used for pointing mortar.

    a. For blended sands, provide samples of each component and blend.
    b. Identify sources, both supplier and quarry, of each type of sand.

3. Each type of pointing mortar in the form of sample mortar strips, 6 inches long by 1/2 inch wide, set in aluminum or plastic channels.

    a. Include with each sample a list of ingredients with proportions of each. Identify sources, both supplier and quarry, of each type of sand and brand names of cementitious materials and pigments if any.

4. Each type of anchor, insert, dowel, and attachment, full size.
5. Each type of masonry patching compound in the form of briquettes, at least 3 inches long by 1-1/2 inches wide. Document each sample with manufacturer and stock number or other information necessary to order additional material.

C. Restoration Program: For each phase of restoration process, provide detailed description of materials, methods, equipment, and sequence of operations to be used for each phase of restoration work including protection of surrounding materials on building and Project site.

1. Include methods for keeping pointing mortar damp during curing period.
2. If materials and methods other than those indicated are proposed for any phase of restoration work, provide a written description, including evidence of successful use on comparable projects, and a testing program to demonstrate their effectiveness for this Project.

D. Cleaning Program: Describe cleaning process in detail, including materials, methods, and equipment to be used and protection of surrounding materials on building and Project site, and control of runoff during operations.

1. If materials and methods other than those indicated are proposed for cleaning work, provide a written description, including evidence of successful use on comparable projects, and a testing program to demonstrate their effectiveness for this Project.

1.4 QUALITY ASSURANCE

A. Chemical Manufacturer Qualifications: A firm regularly engaged in producing masonry cleaners that have been used for similar applications with successful results, and with factory-trained representatives who are available for consultation and Project-site inspection and assistance at no additional cost.

B. Source Limitations: Obtain each type of material for masonry restoration (face brick, stone, cement, sand, etc.) from one source with resources to provide materials of consistent quality in appearance and physical properties.

C. Preconstruction Testing Service: Owner will engage a qualified independent testing agency to test the following. Provide test specimens and assemblies as indicated.

1. Replacement Brick: For each proposed type of replacement brick, according to sampling and testing methods in ASTM C 67 for compressive strength, 24-hour cold-water absorption, 5-hour boil absorption, saturation coefficient, and initial rate of absorption (suction).

2. Existing Brick: For each type of existing brick indicated for replacement, according to testing methods in ASTM C 67 for compressive strength, 24-hour cold-water absorption, 5-hour boil absorption, saturation coefficient, and initial rate of absorption (suction). Carefully remove existing bricks from locations designated by Architect.

D. Mockups: Prepare mockups of restoration and cleaning as follows to demonstrate aesthetic effects and qualities of materials and execution. Prepare mockups on existing walls under same weather conditions to be expected during remainder of the Work.

1. Repair an area approximately 36 inches high by 48 inches wide for each type of masonry material indicated to be rebuilt or replaced.
2. Patch three small areas at least 1 inch in diameter for each type of masonry material indicated to be patched.
3. Clean an area approximately 25 sq. ft. in area for each type of masonry and surface condition.

    a. Test cleaners and methods on samples of adjacent materials for possible adverse reactions unless cleaners and methods are known to have deleterious effect.
    b. Allow a waiting period of not less than seven days after completion of sample cleaning to permit a study of sample panels for negative reactions.

4. Rake out joints in two separate areas approximately 36 inches high by 72 inches wide for each type of repointing required and repoint one of the two areas.

E. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver masonry units to Project site strapped together in suitable packs or pallets or in heavy-duty cartons.

B. Deliver other materials to Project site in manufacturer's original and unopened containers, labeled with manufacturer's name and type of products.

C. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.

D. Store hydrated lime in manufacturer's original and unopened containers. Discard lime if containers have been damaged or have been opened for more than two days.

E. Store lime putty covered with water in sealed containers.

F. Store sand where grading and other required characteristics can be maintained and contamination avoided.

1.6 PROJECT CONDITIONS

A. Repoint mortar joints and repair masonry only when air temperature is between and 40 and 90 deg F and is predicted to remain so for at least 7 days after completion of work.

B. Cold-Weather Requirements: Comply with the following procedures for masonry repair and mortar-joint pointing:

1. When air temperature is below 40 deg F, heat mortar ingredients, masonry repair materials, and existing masonry walls to produce temperatures between 40 and 120 deg F.
2. When mean daily air temperature is below 40 deg F, provide enclosure and heat to maintain temperatures above 32 deg F within the enclosure for 7 days after repair and pointing.

C. Hot-Weather Requirements: Protect masonry repair and mortar-joint pointing when temperature and humidity conditions produce excessive evaporation of water from mortar and repair materials. Provide artificial shade and wind breaks and use cooled materials as required. Do not apply mortar to substrates with temperatures of 90 deg F and above.

D. Patch masonry only when air and surface temperatures are between and 55 and 100 deg F and are predicted to remain above 55 deg F for at least 7 days after completion of work. On days when air temperature is predicted to go above 90 deg F, schedule patching work to coincide with time that surface being patched will be in shade or during cooler morning hours.

E. Clean masonry surfaces only when air temperature is 40 deg F and above and is predicted to remain so for at least 7 days after completion of cleaning.

1.7 SEQUENCING AND SCHEDULING

A. Order replacement materials at earliest possible date, to avoid delaying completion of the Work.

B. Order sand for repointing mortar immediately after approval of Samples or mockups. Take delivery of and store at Project site a sufficient quantity of sand to complete Project.

C. Perform masonry restoration work in the following sequence:

1. Remove plant growth.
2. Repair existing masonry, including the following:

    a. Replacing existing masonry with new masonry materials.

3. Rake out joints that are to be repointed.
4. Point mortar joints.
5. Inspect for open mortar joints and repair before cleaning to prevent the intrusion of water and other cleaning materials into the wall.
6. Clean masonry surfaces.

D. As scaffolding is removed, patch anchor holes used to attach scaffolding. Patch holes in masonry units to comply with Part 3 "Masonry Unit Patching and Repairs" Article. Patch holes in mortar joints to comply with Part 3 "Repointing Masonry" Article.

PART 2 - PRODUCTS

2.1 MASONRY MATERIALS

A. Face Brick and Accessories: Provide face brick and accessories, including specially molded, ground, cut, or sawed shapes where required to complete masonry restoration work.

1. Provide units with colors, surface texture, size, and shape to match existing brickwork and with physical properties not less than those determined from preconstruction testing of selected existing units.

    a. For replacement brick at existing building provide brick to match existing as approved by Architect.
    b. For existing brickwork that exhibits a range of colors, provide brick that matches that range rather than brick that matches an individual color within that range.

2. Provide units with colors, surface texture, and physical properties to match Architect's sample. Match existing units in size and shape.

    a. For sample that exhibits a range of colors, provide brick that matches that range rather than brick that matches an individual color within that range.

3. Provide specially molded shapes for applications where shapes produced by sawing would result in sawed surfaces being exposed to view.
4. Provide specially ground units, shaped to match patterns, for arches and where indicated.

B. Building Brick: Provide building brick complying with ASTM C 62, of same vertical dimension as face brick, for masonry work concealed from view.

1. Grade SW where in contact with earth.
2. Grade SW, MW, or NW for concealed backup.

2.2 MORTAR MATERIALS

A. Portland Cement: ASTM C 150, Type I or Type II.

1. Provide white cement containing not more than 0.60 percent total alkali when tested according to ASTM C 114.

B. Hydrated Lime: ASTM C 207, Type S.

C. Mortar Sand: ASTM C 144, unless otherwise indicated.

1. Color: Provide natural sand or ground marble, granite, or other sound stone; of color necessary to produce required mortar color.
2. For pointing mortar, provide sand with rounded edges.
3. Match size, texture, and gradation of existing mortar sand as closely as possible. Blend several sands, if necessary, to achieve suitable match.

D. Mortar Pigments: Natural and synthetic iron oxides, compounded for mortar mixes. Use only pigments with a record of satisfactory performance in masonry mortars.

1. Available Products: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. SGS Mortar Colors: Solomon Grind-Chem Services, Inc.
    b. True Tone Mortar Colors: Davis Colors, a Subsidiary of Rockwood Industries, Inc.

E. Water: Potable, clean and free from injurious amount of oil, alkali, organic matter or other deleterious material.

2.3 PAINT REMOVERS

A. Alkaline Paste Paint Remover: Manufacturer's standard alkaline paste formulation for removing paint coatings from masonry.

1. Available Products:

    a. American Building Restoration Products, Inc.; 800 Brush Grade.
    b. Diedrich Technologies Inc.; 606/606X Extra Thick Multi-Layer Paint Remover.
    c. Hydrochemical Techniques, Inc.; Hydroclean Heavy Duty Paint Remover (HT-716).
    d. Price Research, Ltd.; Price Heavy Duty Paint Stripper.
    e. ProSoCo; Sure Klean Heavy-Duty Paint Stripper.

2.4 CLEANING MATERIALS

A. Water: Potable, clean and free from injurious amount of oil, alkali, organic matter or other deleterious material.

B. Hot Water: Heat water to a temperature of 140 to 160 deg F.

C. Job-Mixed Detergent Solution: Solution prepared by mixing 2 cups of trisodium phosphate (TSP), 1/2 cup of laundry detergent, and 20 quarts of hot water for every 5 gal. of solution required.

D. Job-Mixed Mold, Mildew, and Algae Remover: Solution prepared by mixing 2 cups of trisodium phosphate (TSP), 5 quarts of 5 percent sodium hypochlorite (bleach), and 15 quarts of hot water for every 5 gal. of solution required.

E. Nonacidic Liquid Cleaner: Manufacturer's standard mildly alkaline liquid cleaner formulated for removing mold, mildew, and other organic soiling from ordinary building materials, including polished stone, brick, aluminum, plastics, and wood.

1. Available Products:

    a. Dominion Restoration, Inc.; Bio-Cleanse.
    b. Dumond Chemicals, Inc.; Safe n' Easy Architectural Cleaner/Restorer.
    c. Price Research, Ltd.; Price Non-Acid Masonry Cleaner.
    d. ProSoCo; Enviro Klean Restoration Cleaner.

2.5 MISCELLANEOUS MATERIALS

A. Masonry Patching Compound: Factory-mixed cementitious product that is custom manufactured for patching masonry, is vapor- and water permeable, exhibits low shrinkage, and develops high bond strength to all types of masonry.

1. Formulate patching compound used for patching brick in colors and textures to match brick being patched. Provide number of colors needed to enable matching each brick.
2. Available Products:

a. Cathedral Stone Products, Inc.; Jahn Restoration Mortar.
b. Edison Coatings, Inc.; Custom System 45.
c. Bonstone Materials Corp., Stone Repair.

B. Liquid Strippable Masking Agent: Manufacturer's standard liquid, film-forming, strippable masking material for protecting glass, metal, and polished stone surfaces from damaging effects of acidic and alkaline masonry cleaners.

1. Available Products:

a. American Building Restoration Products, Inc.; LM 130 Acid Shield.
b. Diedrich Technologies Inc.; Diedrich Acid Guard.
c. Price Research, Ltd.; Price Mask.
d. ProSoCo; Sure Klean Strippable Masking.

C. Masonry Repair Anchors, Expansion Type: Mechanical fasteners designed for masonry veneer stabilization consisting of 1/4-inch- diameter, Type 316 stainless-steel rod with brass expanding shells at each end and water-shedding washer in the middle. Expanding shells shall be designed to provide positive mechanical anchorage to veneer on one end and backup masonry on the other.

1. Available Products:

a. BLOK-LOK, a Hohmann & Barnard Company; Torq-Lok.
b. Dur-O-Wal, a Hohmann & Barnard Company; Dur-O-Wal Repair Anchor.
c. Hohmann & Barnard, Inc.; #521RA-B Restoration Anchor.

D. Masonry Repair Anchors, Spiral Type: Type 304 stainless-steel spiral rods designed to anchor to backing and veneer. Anchors are flexible in plane of veneer but rigid perpendicular to it.

1. Provide adhesive-installed anchors complete with manufacturer's standard epoxy adhesive and injection tubes, screens, sleeves, or other devices required for installation.
2. Provide driven-in anchors designed to be installed in drilled holes and relying on screw effect rather than adhesive to secure them to backup and veneer.
3. Available Products:

a. Dur-O-Wal, a Hohmann & Barnard Company; Dur-O-Flex.
b. Heckmann Building Products, Inc.; #391 Spiro Remedial Tie.
c. Helifix Ltd.; Helifix HRT60 or Helifix HRT80.
d. Hohmann & Barnard, Inc.; Helix Spiro-Ties.

E. Joint Sealant and Backer Rods: Refer to Section 079200 - JOINT SEALANTS.

2.6 MORTAR MIXES

A. Preparing Lime Putty: Slake quicklime and prepare lime putty according to appendix to ASTM C 5 and manufacturer's written instructions.

B. Measurement and Mixing: Measure cementitious materials and sand in a dry condition by volume or equivalent weight. Do not measure by shovel; use known measure. Mix materials in a clean, mechanical batch mixer.

1. Mixing Pointing Mortar: Thoroughly mix cementitious materials and sand together before adding any water. Then mix again adding only enough water to produce a damp, unworkable mix that will retain its form when pressed into a ball. Maintain mortar in this dampened condition for 15 to 30 minutes. Add remaining water in small portions until mortar reaches desired consistency. Use mortar within one hour of final mixing; do not retemper or use partially hardened material.

C. Colored Mortar: Produce mortar of color required by using selected ingredients. Do not alter specified proportions without Architect's approval.

1. Mortar Pigments: Where mortar pigments are indicated, do not exceed a pigment-to-cement ratio of 1:10 by weight.
2. Color: Match existing, or as otherwise directed by Architect.

D. Do not use admixtures of any kind in mortar, unless otherwise indicated.

E. Mortar Proportions: Mix mortar materials in the following proportions:

1. Pointing Mortar for Brick: 1 part portland cement, 2 parts lime, and 6 parts sand.

a. Add mortar pigments to produce mortar colors required.

2. Rebuilding (Setting) and Pointing Mortar, for Stone: Comply with ASTM C 270, Proportion Specification, Type N, unless otherwise indicated, with cementitious material limited to portland cement and lime.

a. Mix: 1 part portland cement, 2 parts lime, and 6-7 parts sand.
b. Add mortar pigments to produce mortar colors required.

2.7 CHEMICAL CLEANING SOLUTIONS

A. Dilute chemical cleaners with water to produce solutions not exceeding concentration recommended by chemical cleaner manufacturer.

PART 3 - EXECUTION

3.1 PROTECTION

A. Protect persons, motor vehicles, surrounding surfaces of building being restored, building site, plants, and surrounding buildings from harm resulting from masonry restoration work.

1. Erect temporary protective covers over walkways and at points of pedestrian and vehicular entrance and exit that must remain in service during course of restoration and cleaning work.

B. Comply with chemical cleaner manufacturer's written instructions for protecting building and other surfaces against damage from exposure to its products. Prevent chemical cleaning solutions from coming into contact with pedestrians, motor vehicles, landscaping, buildings, and other surfaces that could be harmed by such contact.

1. Cover adjacent surfaces with materials that are proven to resist chemical cleaners used unless chemical cleaners being used will not damage adjacent surfaces. Use materials that contain only waterproof, UV-resistant adhesives. Apply masking agents to comply with manufacturer's written instructions. Do not apply liquid masking agent to painted or porous surfaces. When no longer needed, promptly remove masking to prevent adhesive staining.
2. Keep wall wet below area being cleaned to prevent streaking from runoff.
3. Do not clean masonry during winds of sufficient force to spread cleaning solutions to unprotected surfaces.
4. Neutralize and collect alkaline and acid wastes for disposal off Owner's property.
5. Dispose of runoff from cleaning operations by legal means and in a manner that prevents soil erosion, undermining of paving and foundations, damage to landscaping, and water penetration into building interiors.

C. Prevent mortar from staining face of surrounding masonry and other surfaces.

1. Cover sills, ledges, and projections to protect from mortar droppings.
2. Keep wall area wet below rebuilding and pointing work to discourage mortar from adhering.
3. Immediately remove mortar in contact with exposed masonry and other surfaces.
4. Clean mortar splatters from scaffolding at end of each day.

3.2 UNUSED ANCHOR OR EMBEDDED STEEL REMOVAL

A. Remove embedded masonry anchors, brackets, wood nailers, and other extraneous items no longer in use unless identified as historically significant or indicated to remain.

1. Remove items carefully to avoid spalling or cracking masonry.
2. If item cannot be removed without damaging surrounding masonry, cut off item flush with surface and core drill surrounding masonry and item as close around item as practical.
3. Patch holes where items were removed unless directed to remove and replace units.

3.3 MASONRY REMOVAL AND REPLACEMENT

A. At locations indicated, remove masonry units that are damaged, spalled, or deteriorated. Carefully demolish or remove entire units from joint to joint, without damaging surrounding masonry, in a manner that permits replacement with full-size units.

1. When removing single bricks, remove material from center of brick and work toward outside edges.

B. Support and protect remaining masonry that surrounds removal area. Maintain flashing, reinforcement, lintels, and adjoining construction in an undamaged condition.

C. Notify Architect of unforeseen detrimental conditions including voids, cracks, bulges, and loose masonry units in existing masonry backup, rotted wood, rusted metal, and other deteriorated items.

D. Remove in an undamaged condition as many whole bricks and stones as possible.

1. Remove mortar, loose particles, and soil from brick and stone by cleaning with hand chisels, brushes, and water.
2. Remove sealants by cutting close to brick and stone with utility knife and cleaning with solvents.
3. Store brick for reuse, as indicated.
4. Deliver cleaned brick and stone not required for reuse to Owner, unless otherwise directed.

E. Clean masonry surrounding removal areas by removing mortar, dust, and loose particles in preparation for replacement.

F. Install replacement masonry into bonding and coursing pattern of existing masonry, match existing mortar joints for size. If cutting is required, use a motor-driven saw designed to cut masonry with clean, sharp, unchipped edges.

G. Lay replacement masonry units with completely filled bed, head, and collar joints. Butter ends with sufficient mortar to fill head joints and shove into place. Maintain joint width for replacement units to match existing joints.

1. Bricks: Wet both replacement and surrounding bricks that have ASTM C 67 initial rates of absorption (suction) of more than 30 g/30 sq. in. per min. Use wetting methods that ensure that units are nearly saturated but surface is dry when laid.
2. Tool exposed mortar joints in repaired areas to match joints of surrounding existing masonry work.
3. Rake out mortar used for laying brick and stone before mortar sets and point new mortar joints in repaired area to comply with requirements for repointing existing masonry, and at same time as repointing of surrounding area.

3.4 REANCHORING VENEERS

A. Install masonry repair anchors in horizontal mortar joints and according to manufacturer's written instructions. Install at not more than 16 inches o.c. vertically and 32 inches o.c. horizontally, unless otherwise indicated. Install at locations to avoid penetrating flashing.

B. Recess anchors at least 5/8 inch from surface of mortar joint and fill recess with pointing mortar.

3.5 MASONRY UNIT PATCHING AND REPAIRS

A. Patch the following masonry units:

1. Units indicated to be patched.
2. Units with holes.
3. Units with chipped edges or corners.
4. Units with small areas of deep deterioration.

B. Remove and replace existing patches, unless otherwise indicated or approved by Architect.

C. Patching Bricks:

1. Remove loose material from brick surface. Remove additional material so patch will not have feathered edges and will be at least 1/4 inch thick, but not less than recommended by patching compound manufacturer.
2. Mask or remove surrounding mortar joints if patch will extend to edge of brick.
3. Mix patching compound in individual batches to match each unit being patched. Combine one or more colors of patching compound, as needed, to produce exact match.
4. Rinse surface to be patched and leave damp, but without standing water.
5. Brush-coat surfaces with slurry coat of patching compound according to manufacturer's written instructions.
6. Place patching compound in layers as recommended by patching compound manufacturer, but not less than 1/4 inch or more than 2 inches thick. Roughen surface of each layer to provide a key for next layer.
7. Trowel, scrape, or carve surface of patch to match texture and surface plane of surrounding brick. Shape and finish surface before or after curing, as determined by testing, to best match existing brick.
8. Keep each layer damp for 72 hours or until patching compound has set.

3.6 CLEANING MASONRY, GENERAL

A. Examination: Examine all surfaces scheduled for cleaning, for roughness, contaminants, unsound structural substrates, or other conditions that may impair the application. Notify the Architect in writing of any such conditions; do not continue work until directed by Architect on how to proceed.

1. Monitor weather prior to work to ensure that air temperatures remain between 50°F and 85°F, or as recommended by the manufacturer of chemical compounds and proprietors of cleaning methods.
2. Ensure that building components not to be cleaned, adjacent persons, property, and plant life are protected from all cleaning activities and wind drift. Test adjacent non-masonry materials for reaction with cleaning materials. Mask all windows, ornamental fixtures, hardware, wood doors, or other non-masonry surfaces.

B. Proceed with cleaning in an orderly manner; work from top to bottom of each scaffold width and from one end of each elevation to the other.

C. Use only those cleaning methods indicated for each masonry material and location.

1. Do not use wire brushes or brushes that are not resistant to chemical cleaner being used. Do not use plastic-bristle brushes if natural-fiber brushes will resist chemical cleaner being used.
2. Use spray equipment that provides controlled application at volume and pressure indicated, measured at spray tip. Adjust pressure and volume to ensure that cleaning methods do not damage masonry.

    a. Equip units with pressure gages.
    b. Provide spray applications as follows:
        1) Low-Pressure Spray: 100 to 400 psi; 4 to 6 gpm.
        2) Medium-Pressure Spray: 400 to 800 psi; 4 to 6 gpm.
        3) High-Pressure Spray: 800 to 1200 psi; 4 to 6 gpm.

3. For chemical cleaner spray application, use low-pressure tank or chemical pump suitable for chemical cleaner indicated, equipped with cone-shaped spray tip.

4. For water spray application, use fan-shaped spray tip that disperses water at an angle of 25 to 50 degrees.
5. For high-pressure water spray application, use fan-shaped spray tip that disperses water at an angle of at least 40 degrees.
6. For heated water spray application, use equipment capable of maintaining temperature between 140 and 160 deg F at flow rates indicated.
7. For steam application, use steam generator capable of delivering live steam at nozzle.

D. Perform each cleaning method indicated in a manner that results in uniform coverage of all surfaces, including corners, moldings, and interstices, and that produces an even effect without streaking or damaging masonry surfaces.

E. Removing Plant Growth: Completely remove plant, moss, and shrub growth from masonry surfaces. Carefully remove plants, creepers, and vegetation by cutting at roots and allowing to dry as long as possible before removal. Remove loose soil and debris from open masonry joints to whatever depth they occur.

F. Preliminary Cleaning: Before beginning general cleaning, remove extraneous substances that are resistant to cleaning methods being used. Extraneous substances include paint, calking, asphalt, and tar.

1. Carefully remove heavy accumulations of material from surface of masonry with a sharp chisel. Do not scratch or chip masonry surface.
2. Remove paint and calking with alkaline paint remover.

    a. Comply with requirements for paint removal.
    b. Repeat application up to two times if needed.

3. Remove asphalt and tar with solvent-type paint remover.

    a. Apply only to asphalt and tar by brush without prewetting.
    b. Allow paint remover to remain on surface for 10 to 30 minutes.
    c. Rinse off with water using low-pressure spray.
    d. Repeat application if needed.

G. Water Application Methods:

1. Water Soak Application, for Stone: Soak stone surfaces by applying water continuously and uniformly to limited area for time indicated. Apply water at low pressures and low volumes in multiple fine sprays using perforated hoses or multiple spray nozzles. Erect a protective enclosure constructed of polyethylene sheeting to cover area being sprayed.
2. Spray Applications, for Brick and Stone: Unless otherwise indicated, hold spray nozzle at least 6 inches from surface of stone and apply water in horizontal back and forth sweeping motion, overlapping previous strokes to produce uniform coverage.

H. Steam Wash: Apply steam to masonry surfaces at pressures not exceeding 80 psi. Hold nozzle at least 6 inches from surface of masonry and apply steam in horizontal back and forth sweeping motion, overlapping previous strokes to produce uniform coverage.

I. Chemical Cleaner Application Methods: Apply chemical cleaners to masonry surfaces to comply with chemical cleaner manufacturer's written instructions; use brush or spray application methods, at Contractor's option. Do not spray apply at pressures exceeding 50 psi. Do not allow chemicals to remain on surface for periods longer than those indicated or recommended by manufacturer.

J. Rinse off chemical residue and soil by working upward from bottom to top of each treated area at each stage or scaffold setting. Periodically during each rinse, test pH of rinse water running off of cleaned area to determine that chemical cleaner is completely removed.

1. Apply neutralizing agent and repeat rinse, if necessary, to produce tested pH of between 6.7 and 7.5.

K. After cleaning is complete, remove protection no longer required. Remove tape and adhesive marks.

3.7 PAINT REMOVAL

A. Paint Removal with Alkaline Paste Paint Remover:

1. Apply paint remover to dry, painted masonry with brushes.
2. Allow paint remover to remain on surface for period recommended by manufacturer.
3. Rinse with water applied by low-pressure spray to remove chemicals and paint residue.
4. Repeat process, if necessary, to remove all paint.
5. Apply acidic cleaner to masonry, while surface is still wet, using low-pressure spray equipment or soft-fiber brush. Let cleaner remain on surface for period recommended by chemical cleaner manufacturer.
6. Rinse with cold water applied by low-pressure spray to remove chemicals and soil.

3.8 MASONRY CLEANING

A. Cold-Water Wash: Use cold water applied by low-pressure spray.

B. Cold Water Soak:

1. Apply cold water by intermittent soaking.
2. Use perforated hoses or other means that will apply a fine water mist to entire surface being cleaned.
3. Apply water in cycles with at least 30 minutes between cycles.
4. Continue water application until surface encrustation has softened sufficiently to permit its removal by water wash, as indicated by cleaning tests.
5. Remove soil and softened surface encrustation from masonry with cold water applied by low-pressure spray.

C. Hot-Water Wash: Use hot water applied by low-pressure spray.

D. Steam Cleaning: Apply steam at pressures not exceeding 80 psi.

E. Detergent Cleaning:

1. Wet masonry with water applied by low-pressure spray.
2. Scrub masonry with detergent solution using medium-soft brushes until soil is thoroughly dislodged and can be removed by rinsing. Use small brushes to remove soil from mortar joints and crevices. Dip brush in solution often to ensure that adequate fresh detergent is used and that masonry surface remains wet.
3. Rinse with water applied by low-pressure spray to remove detergent solution and soil.
4. Repeat cleaning procedure above where required to produce cleaning effect established by mockup.

F. Mold, Mildew, and Algae Removal:

1. Wet masonry with water applied by low-pressure spray.
2. Apply mold, mildew, and algae remover by brush or low-pressure spray.
3. Scrub masonry with medium-soft brushes until mold, mildew, and algae are thoroughly dislodged and can be removed by rinsing. Use small brushes for mortar joints and crevices. Dip brush in mold, mildew, and algae remover often to ensure that adequate fresh cleaner is used and that masonry surface remains wet.
4. Rinse with water applied by low-pressure spray to remove mold, mildew, and algae remover and soil.
5. Repeat cleaning procedure above where required to produce cleaning effect established by mockup.

G. Nonacidic Liquid Chemical Cleaning:

1. Wet masonry with water applied by low-pressure spray.
2. Apply cleaner to masonry in two applications by brush. Let cleaner remain on surface for period indicated below:

    a. As recommended by chemical cleaner manufacturer.
    b. As established by mockup.
    c. Two to three minutes.

3. Rinse with water applied by low-pressure spray to remove chemicals and soil.
4. Repeat cleaning procedure above where required to produce cleaning effect established by mockup. Do not repeat more than once. If additional cleaning is required, use steam wash.

3.9 REPOINTING MASONRY

A. Rake out and repoint mortar joints to the following extent:

1. All joints in areas indicated.
2. Joints where mortar is missing or where they contain holes.
3. Cracked joints where cracks can be penetrated at least 1/4 inch by a knife blade 0.027 inch thick.
4. Cracked joints where cracks are 1/8 inch or more in width and of any depth.
5. Joints where they sound hollow when tapped by metal object.
6. Joints where they are worn back 1/4 inch or more from surface.
7. Joints where they are deteriorated to point that mortar can be easily removed by hand.
8. Joints, other than those indicated as sealant-filled joints, where they have been filled with substances other than mortar.

B. Do not rake out and repoint joints where not required.

C. Rake out joints as follows:

1. Remove mortar from joints to depth of 2 times joint width, but not less than 1/2 inch or not less than that required to expose sound, unweathered mortar.
2. Remove mortar from masonry surfaces within raked-out joints to provide reveals with square backs and to expose masonry for contact with pointing mortar. Brush, vacuum, or flush joints to remove dirt and loose debris.

3. Do not spall edges of masonry units or widen joints. Replace or patch damaged masonry units as directed by Architect.

    a. Cut out mortar by hand with chisel and mallet. Do not use power-operated grinders without Architect's written approval based on submission by Contractor of a satisfactory quality-control program and demonstrated ability of operators to use tools without damaging masonry. Quality-control program shall include provisions for supervising performance and preventing damage due to worker fatigue.
    b. Cut out center of mortar bed joints using angle grinders with diamond-impregnated metal blades. Remove remaining mortar by hand with chisel and mallet. Strictly adhere to written quality-control program. Quality-control program shall include provisions for demonstrating ability of operators to use tools without damaging masonry, supervising performance, and preventing damage due to worker fatigue.

D. Notify Architect of unforeseen detrimental conditions including voids in mortar joints, cracks, loose masonry units, rotted wood, rusted metal, and other deteriorated items.

E. Point joints as follows:

1. Rinse masonry-joint surfaces with water to remove dust and mortar particles. Time rinsing application so, at time of pointing, joint surfaces are damp but free of standing water. If rinse water dries, dampen masonry-joint surfaces before pointing.
2. Apply pointing mortar first to areas where existing mortar was removed to depths greater than surrounding areas. Apply in layers not greater than 3/8 inch until a uniform depth is formed. Fully compact each layer thoroughly and allow it to become thumbprint hard before applying next layer.
3. After low areas have been filled to same depth as remaining joints, point all joints by placing mortar in layers not greater than 3/8 inch. Fully compact each layer and allow to become thumbprint hard before applying next layer.

    a. Where existing bricks have worn or rounded edges, slightly recess finished mortar surface below face of masonry to avoid widened joint faces.
    b. Take care not to spread mortar over edges onto exposed masonry surfaces or to featheredge mortar.

4. When mortar is thumbprint hard, tool joints to match original appearance of joints. Remove excess mortar from edge of joint by brushing.

F. Cure mortar by maintaining in thoroughly damp condition for at least 72 hours including weekends and holidays.

1. Acceptable curing methods include covering with wet burlap and plastic sheeting, periodic hand misting, and periodic mist spraying using system of pipes, mist heads, and timers.
2. Adjust curing methods to ensure that pointing mortar is damp throughout its depth without eroding surface mortar.

G. Where repointing work precedes cleaning of existing masonry, allow mortar to harden at least 30 days before beginning cleaning work.

3.10 FINAL CLEANING

A. After mortar has fully hardened, thoroughly clean exposed masonry surfaces of excess mortar and foreign matter; use wood scrapers, stiff-nylon or -fiber brushes, and clean water, spray applied at low pressure.

1. Do not use metal scrapers or brushes.
2. Do not use acidic or alkaline cleaners.

B. Wash adjacent woodwork and other nonmasonry surfaces. Use detergent and soft brushes or cloths.

C. Clean masonry debris from roof; remove debris from gutters and downspouts. Rinse off roof and flush gutters and downspouts.

D. Sweep and rake adjacent pavement and grounds to remove masonry debris. Where necessary, pressure wash surfaces to remove mortar, dust, dirt, and stains.

3.11 FIELD QUALITY CONTROL

A. Inspectors: Owner will engage qualified independent inspectors to perform inspections and prepare test reports. Coordinate with inspectors and provide access. Allow inspectors use of lift devices and scaffolding, as needed, to perform inspections.

END OF SECTION

SECTION 042000

UNIT MASONRY

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Concrete masonry units.
2. Face brick.
3. Embedded flashing.
4. Mortar and grout.
5. Reinforcing steel, masonry joint reinforcement, ties and anchors.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 078440 - FIRE-RESISTIVE JOINT SYSTEMS for fire-resistive joint systems openings in masonry walls and at heads of masonry walls.
2. Section 079200 - JOINT SEALANTS for sealing control and expansion joints in unit masonry.

1.3 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings: For the following:

1. Masonry Units: Show sizes, profiles, coursing, and locations of special shapes.
2. Reinforcing Steel: Detail bending and placement of unit masonry reinforcing bars. Comply with ACI 315, “Details and Detailing of Concrete Reinforcement.”

C. Samples for Verification: For each type and color of the following:

1. Exposed concrete masonry units.
2. Face brick, in the form of straps of five or more bricks.
3. Pigmented mortar. Make Samples using same sand and mortar ingredients to be used on Project. Label Samples to indicate types and amounts of pigments used.
4. Weep holes/vents.
5. Accessories embedded in masonry.

D. Qualification Data: For testing agency.

E. Material Certificates: Include statements of material properties indicating compliance with requirements including compliance with standards and type designations within standards. Provide for each type and size of the following:

1. Masonry units:

a. Include material test reports substantiating compliance with requirements.
b. For bricks, include size-variation data verifying that actual range of sizes falls within specified tolerances.
c. For exposed brick, include material test report for efflorescence according to ASTM C 67.
d. For masonry units used in structural masonry, include data and calculations establishing average net-area compressive strength of units.

2. Cementitious materials. Include brand, type, and name of manufacturer.
3. Mortar mixes. Include description of type and proportions of ingredients.
4. Grout mixes. Include description of type and proportions of ingredients.
5. Reinforcing bars.
6. Joint reinforcement.
7. Anchors, ties, and metal accessories.

F. Mix Designs: For each type of mortar and grout. Include description of type and proportions of ingredients.

1. Include test reports, per ASTM C 780 for mortar mixes required to comply with property specification.
2. Include test reports, per ASTM C 1019 for grout mixes required to comply with compressive strength requirement.

G. Cold-Weather Procedures: Detailed description of methods, materials, and equipment to be used to comply with cold-weather requirements.

1.4 QUALITY ASSURANCE

A. Testing Agency Qualifications: An independent agency qualified according to ASTM C 1093 for testing indicated.

B. Source Limitations for Masonry Units: Obtain exposed masonry units of a uniform texture and color, or a uniform blend within the ranges accepted for these characteristics, through one source from a single manufacturer for each product required.

C. Source Limitations for Mortar Materials: Obtain mortar ingredients of a uniform quality, including color for exposed masonry, from a single manufacturer for each cementitious component and from one source or producer for each aggregate.

D. Preconstruction Testing Service: The Owner will engage a qualified independent testing agency to perform preconstruction testing indicated below. Payment for these services will be made by the Owner. Retesting of materials that fail to meet specified requirements shall be done at Contractor’s expense.

1. Prism Test: For each type of construction required, per ASTM C 1314.

E. Fire-Resistance Ratings: Where indicated, provide materials and construction identical to those of assemblies with fire-resistance ratings determined per ASTM E 119 by a testing and inspecting agency, by equivalent concrete masonry thickness, or by other means, as acceptable to authorities having jurisdiction.

F. Sample Panels: Build sample panels to verify selections made under sample submittals and to demonstrate aesthetic effects. Comply with requirements in Division 01 for mockups.

1. Build sample panels for typical exterior and interior walls in sizes approximately 48 inches long by 48 inches high by full thickness.
2. Where masonry is to match existing, erect panels adjacent and parallel to existing surface.
3. Clean one-half of exposed faces of panels with masonry cleaner indicated.
4. Protect approved sample panels from the elements with weather-resistant membrane.
5. Approval of sample panels is for color, texture, and blending of masonry units; relationship of mortar and sealant colors to masonry unit colors; tooling of joints; aesthetic qualities of workmanship; and other material and construction qualities specifically approved by Architect in writing.

    a. Approval of sample panels does not constitute approval of deviations from the Contract Documents contained in sample panels unless such deviations are specifically approved by Architect in writing.

G. Defective Units: Referenced masonry unit standards may allow a certain percentage of units to exceed tolerances and to contain chips, cracks, or other defects exceeding limits stated in the standard. Do not uses units where such defects, including dimensions that vary from specified dimensions by more than stated tolerances, will be exposed in the completed Work or will impair the quality of completed masonry.

H. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01. Agenda shall include protection of air barrier membrane during construction.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Store masonry units on elevated platforms in a dry location. If units are not stored in an enclosed location, cover tops and sides of stacks with waterproof sheeting, securely tied. If units become wet, do not install until they are dry.

B. Store cementitious materials on elevated platforms, under cover, and in a dry location. Do not use cementitious materials that have become damp.

C. Store aggregates where grading and other required characteristics can be maintained and contamination avoided.

D. Deliver preblended, dry mortar mix in moisture-resistant containers designed for lifting and emptying into dispensing silo. Store preblended, dry mortar mix in delivery containers on elevated platforms, under cover, and in a dry location or in a metal dispensing silo with weatherproof cover.

E. Store masonry accessories, including metal items, to prevent corrosion and accumulation of dirt and oil.

1.6 PROJECT CONDITIONS

A. Protection of Air Barrier Membrane: During construction, protect air barrier membrane from penetrations which allow air to pass through air barrier assemblies. Engage original installer to repair damage promptly using identical materials and methods of installation, and to the satisfaction of the Architect.

B. Protection of Masonry: During construction, cover tops of walls, projections, and sills with waterproof sheeting at end of each day's work. Cover partially completed masonry when construction is not in progress.

1. Extend cover a minimum of 24 inches down both sides and hold cover securely in place.
2. Where 1 wythe of multiwythe masonry walls is completed in advance of other wythes, secure cover a minimum of 24 inches down face next to unconstructed wythe and hold cover in place.

C. Do not apply uniform floor or roof loads for at least 12 hours and concentrated loads for at least 3 days after building masonry walls or columns.

D. Stain Prevention: Prevent grout, mortar, and soil from staining the face of masonry to be left exposed or painted. Immediately remove grout, mortar, and soil that come in contact with such masonry.

1. Protect base of walls from rain-splashed mud and from mortar splatter by spreading coverings on ground and over wall surface.
2. Protect sills, ledges, and projections from mortar droppings.
3. Protect surfaces of window and door frames, as well as similar products with painted and integral finishes, from mortar droppings.
4. Turn scaffold boards near the wall on edge at the end of each day to prevent rain from splashing mortar and dirt onto completed masonry.

E. Cold-Weather Requirements: Do not use frozen materials or materials mixed or coated with ice or frost. Do not build on frozen substrates. Remove and replace unit masonry damaged by frost or by freezing conditions. Comply with cold-weather construction requirements contained in ACI 530.1/ASCE 6/TMS 602.

1. Cold-Weather Cleaning: Use liquid cleaning methods only when air temperature is 40 deg F and above and will remain so until masonry has dried, but not less than 7 days after completing cleaning.

F. Hot-Weather Requirements: Comply with hot-weather construction requirements contained in ACI 530.1/ASCE 6/TMS 602.

PART 2 - PRODUCTS

2.1 PERFORMANCE REQUIREMENTS

A. Delegated Design: Design masonry veneer anchors, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

B. Structural Performance: Provide masonry veneer anchors capable of withstanding design loads within limits and under conditions indicated.

1. Design Loads: As indicated on the Structural Drawings, but not less than required by Code.

2.2 CONCRETE MASONRY UNITS (CMUs)

A. Concrete Masonry Units: ASTM C 90, normal weight unless indicated otherwise manufactured to dimensions 3/8 inch less than nominal dimensions.

B. Shapes: Provide standard shapes indicated and as required for building configuration. Provide special shapes for lintels, corners, jambs, sashes, movement joints, headers, bonding, and other special conditions.

2.3 BRICK

A. Face Brick: ASTM C 216, Grade SW, Type FBS.

1. Basis-of-Design: Summit Brick or equal.
2. Color: Painters' grade brick mix similar to existing color. Match texture to existing brick.
3. Size (Actual Dimensions): As selected by Architect.
4. Initial Rate of Absorption: Less than 30 g/30 sq. in. per minute when tested per ASTM C 67.
5. Efflorescence: Provide brick that has been tested according to ASTM C 67 and is rated "not effloresced."
6. Where shown to "match existing," provide face brick matching color range, texture, and size of existing adjacent brickwork.

B. Building (Common) Brick where Concealed: ASTM C 62, Grade SW.

C. General: Provide shapes indicated and as follows:

1. For ends of sills and caps and for similar applications that would otherwise expose unfinished brick surfaces, provide units without cores or frogs and with exposed surfaces finished.
2. Provide special shapes for applications where stretcher units cannot accommodate special conditions, including those at corners, movement joints, bond beams, sashes, and lintels.
3. Provide special shapes for applications requiring brick of size, form, color, and texture on exposed surfaces.
4. Provide special shapes for applications where shapes produced by sawing would result in sawed surfaces being exposed to view.
5. Units which are sawn and less than one-half full size shall not be used.

2.4 MORTAR AND GROUT MATERIALS

A. Regional Materials: Provide aggregate for mortar and grout, cement, and lime that have been extracted, harvested, or recovered, as well as manufactured, within 500 miles of Project site.

B. Portland Cement: ASTM C 150, Type I or II, except Type III may be used for cold-weather construction. Provide natural color or white cement as required to produce mortar color indicated.

C. Hydrated Lime: ASTM C 207, Type S.

D. Mortar Pigments: Natural and synthetic iron oxides and chromium oxides, compounded for use in mortar mixes. Use only pigments with a record of satisfactory performance in masonry mortar.

1. Available Products:

a. LanXess; Bayferrox Iron Oxide Pigments.
b. Davis Colors; True Tone Mortar Colors.
c. Solomon Grind-Chem Services, Inc.; SGS Mortar Colors.

E. Aggregate for Mortar: ASTM C 144. For mortar that is exposed to view, use washed aggregate consisting of natural sand or crushed stone.

F. Aggregate for Grout: ASTM C 404.

G. Water: Potable.

2.5 REINFORCEMENT

A. Uncoated Steel Reinforcing Bars: ASTM A 615/A 615M or ASTM A 996/A 996M, Grade 60.

B. Masonry Joint Reinforcement, General: ASTM A 951.

1. Interior Walls: Mill-galvanized, carbon steel.
2. Exterior Walls: Hot-dip galvanized, carbon steel.
3. Wire Size and Spacing: As required by Code.
4. Provide in lengths of not less than 10 feet, with prefabricated corner and tee units.

C. Masonry Joint Reinforcement for Multiwythe Masonry:

1. Ladder type with 1 side rod at each face shell of hollow masonry units more than 4 inches in width, plus 1 side rod at each wythe of masonry 4 inches or less in width.

2.6 TIES AND ANCHORS

A. Materials: Provide ties and anchors specified in subsequent paragraphs that are made from materials that comply with subparagraphs below, unless otherwise indicated.

1. Mill-Galvanized, Carbon-Steel Wire: ASTM A 82; with ASTM A 641/A 641M, Class 1 coating.
2. Hot-Dip Galvanized, Carbon-Steel Wire: ASTM A 82; with ASTM A 153/A 153M, Class B-2 coating.
3. Stainless-Steel Wire: ASTM A 580/A 580M, Type 316.
4. Galvanized Steel Sheet: ASTM A 653/A 653M, Commercial Steel, G60 zinc coating.
5. Steel Plates, Shapes, and Bars: ASTM A 36/A 36M.
6. Stainless Steel Bars: ASTM A 276 or ASTM A 666, Type 304.

B. Adjustable Anchors for Connecting to Structure: Provide anchors that allow vertical or horizontal adjustment but resist tension and compression forces perpendicular to plane of wall.

1. Anchor Section for Welding to Steel Frame: Crimped 1/4-inch-diameter, hot-dip galvanized steel. Mill-galvanized wire may be used at interior walls, unless otherwise indicated.

C. Partition Top Anchors: 0.097-inch-thick metal plate with 3/8-inch-diameter metal rod 6 inches long welded to plate and with closed-end plastic tube fitted over rod that allows rod to move in and out of tube. Fabricate from steel, hot-dip galvanized after fabrication.

D. Adjustable Masonry-Veneer Anchors – Thermally-Broken:

1. General: Provide thermally-broken anchors that allow vertical adjustment but resist tension and compression forces perpendicular to plane of wall, for attachment over sheathing to wood or metal studs, with structural performance capable of withstanding a 100-lbf load in both tension and compression without deforming or developing play in excess of 0.05 inch.
2. Screw-Attached, Masonry-Veneer Anchors: Units consisting of a wire tie and a metal anchor section.

a. Anchor Section: Stainless steel barrel section, polymer coated screw with hex head with plastic-encapsulated steel wing and corrosion-resistant, self-drilling screw. Wing designed to receive wire tie . Barrel length to suit sheathing thickness, allowing screw to seat directly against framing with flanged head covering hole in sheathing.
b. Wire Ties: Triangular-, rectangular-, or T-shaped wire ties fabricated from 0.188-inch-diameter, hot-dip galvanized steel wire.
c. Basis-of-Design: 2-Seal Thermal Wing Nut Anchor by Hohmann & Barnard or approved equal by Posi-Tie (thermally broken), or equal.

2.7 MISCELLANEOUS ANCHORS

A. Anchor Bolts: L-shaped steel bolts complying with ASTM A 307, Grade A; with ASTM A 563 hex nuts and, where indicated, flat washers; hot-dip galvanized to comply with ASTM A 153/A 153M, Class C; of dimensions indicated.

2.8 EMBEDDED FLASHING MATERIALS

A. Flexible Laminated Stainless Steel Flashing:

1. Available Products:

a. Hohmann & Barnard, Inc.; Mighty-Flash Stainless Steel Fabric Flashing.
b. Illinois Products, Inc.; IPCO Stainless Steel Fabric Flashing.
c. STS Coatings, Inc.; Gorilla Flash Stainless Fabric.
d. TK Products, Inc.; TK TWF.
e. York Manufacturing, Inc.; Multi-Flash SS.

2. Materials:

a. Type: Stainless steel core with polymer fabric laminated to one stainless steel face with non-asphalt adhesive.
b. Stainless steel type: 304, ASTM A666.
c. Fabric: Polymer fabric; laminated back face of stainless steel core.

3. Accessories:

a. Sealant: Provide sealants as recommended by flashing manufacturer.
b. Splice Tape: Provide minimum 4” wide self-adhering strips and as recommended by flashing manufacturer.
c. Termination Bar: Provide stainless steel termination bars with sealant catch lip.
d. Preformed Shapes: Provide Type 304, 0.016 inch (0.40 mm) thick stainless steel preformed end dams, outside and inside corners.

B. Solder and Sealants for Sheet Metal Flashings: As specified in Section 076200 – SHEET METAL FLASHING AND TRIM.

C. Adhesives, Primers, and Seam Tapes for Flashings: Flashing manufacturer’s standard products or products recommended by flashing manufacturer for bonding flashing sheets to each other and to substrates. Verify compatibility between flashing materials and substrates.

D. Transition Strips: Provide long-term compatible 6” wide transition strips to seal embedded flashing terminations to air barrier membrane.

E. Drip Edge: Provide type 316, 0.016 inch (0.40 mm) thick stainless steel drip edge plates with factory applied adhesive strip for all through-wall flashing conditions. Provide preformed outside and inside corner drip plate corners with smooth uninterrupted soldered seams and hemmed drip edges to maintain continuity. Custom sizes will be required see drawings for profiles required.

2.9 MISCELLANEOUS MASONRY ACCESSORIES

A. Compressible Filler: Premolded filler strips complying with ASTM D 1056, Grade 2A1; compressible up to 35 percent; of width and thickness indicated; formulated from neoprene.

B. Preformed Control-Joint Gaskets: Made from styrene-butadiene-rubber compound, complying with ASTM D 2000, Designation M2AA-805 designed to fit standard sash block and to maintain lateral stability in masonry wall; size and configuration as indicated.

C. Bond-Breaker Strips: Asphalt-saturated, organic roofing felt complying with ASTM D 226, Type I (No. 15 asphalt felt).

D. Weep/Vent Products: Free-draining mesh; made from polyethylene strands, full height and width of head joint and depth 1/8 inch less than depth of outer wythe; in color selected from manufacturer’s standard.

E. Cavity Drainage Material: Free-draining mesh, made from polymer strands that will not degrade within the wall cavity. Provide strips, full-depth of cavity and 10 inches wide, with dovetail shaped notches 7 inches deep that prevent mesh from being clogged with mortar droppings or equivalent. Available products:

1. Advanced Building Products Inc.; Mortar Break II.
2. Archovations, Inc.; CavClear Masonry Mat.

3. Hohmann & Barnard; MortarTrap.
4. Mortar Net USA, Ltd.; Mortar Net.

2.10 MASONRY CLEANERS

A. Proprietary Acidic Cleaner: Manufacturer's standard-strength cleaner designed for removing mortar/grout stains, efflorescence, and other new construction stains from new masonry without discoloring or damaging masonry surfaces. Use product expressly approved for intended use by cleaner manufacturer and manufacturer of masonry units being cleaned.

1. Available Manufacturers:

   a. Diedrich Technologies, Inc.
   b. EaCo Chem, Inc.
   c. ProSoCo, Inc.

2.11 MORTAR AND GROUT MIXES

A. General: Do not use admixtures, including pigments, air-entraining agents, accelerators, retarders, water-repellent agents, antifreeze compounds, or other admixtures, unless otherwise indicated.

1. Do not use calcium chloride in mortar or grout.
2. Limit cementitious materials in mortar to portland cement and lime.

B. Mortar for Unit Masonry: Comply with ASTM C 270, Proportion Specification. Provide the following types of mortar for applications stated unless another type is indicated or needed to provide required compressive strength of masonry.

1. For masonry below grade or in contact with earth, use Type M.
2. For reinforced masonry, use Type S.
3. For exterior, above-grade, load-bearing and non-load-bearing walls and parapet walls; for interior load-bearing walls; for interior non-load-bearing partitions; and for other applications where another type is not indicated, use Type N.

C. Pigmented Mortar: Use colored cement product. Pigments shall not exceed 10 percent of portland cement by weight.

D. Grout for Unit Masonry: Comply with ASTM C 476.

1. Use grout of type indicated or, if not otherwise indicated, of type (fine or coarse) that will comply with Table 1.15.1 in ACI 530.1/ASCE 6/TMS 602 for dimensions of grout spaces and pour height.
2. Provide grout with a slump of 8 to 11 inches as measured according to ASTM C 143/C 143M.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of work.

1. For the record, prepare written report, endorsed by Installer, listing conditions detrimental to performance of work.
2. Verify that foundations are within tolerances specified.

B. Before installation, examine rough-in and built-in construction for piping systems to verify actual locations of piping connections.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION, GENERAL

A. Thickness: Build cavity and composite walls and other masonry construction to full thickness shown. Build single-wythe walls to actual widths of masonry units, using units of widths indicated.

B. Build chases and recesses to accommodate items specified in this and other Sections.

C. Leave openings for equipment to be installed before completing masonry. After installing equipment, complete masonry to match the construction immediately adjacent to opening.

D. Use full-size units without cutting if possible. If cutting is required to provide a continuous pattern or to fit adjoining construction, cut units with motor-driven saws; provide clean, sharp, unchipped edges. Allow units to dry before laying unless wetting of units is specified. Install cut units with cut surfaces and, where possible, cut edges concealed. Do not use units cut to less than one-half size.

E. Do not install concrete masonry units with more than 5 percent damage to the face. Do not install brick units which will show defects after installation.

F. Select and arrange units for exposed unit masonry to produce a uniform blend of colors and textures. Mix units from several pallets or cubes as they are placed.

G. Matching Existing Masonry: Match coursing, bonding, color, and texture of existing masonry.

H. Comply with construction tolerances in ACI 530.1/ASCE 6/TMS 602 and with the following:

1. For conspicuous vertical lines, such as external corners, door jambs, reveals, and expansion and control joints, do not vary from plumb by more than 1/8 inch in 10 feet, 1/4 inch in 20 feet, or 1/2 inch maximum.
2. For vertical alignment of exposed head joints, do not vary from plumb by more than 1/4 inch in 10 feet, or 1/2 inch maximum.
3. For conspicuous horizontal lines, such as lintels, sills, parapets, and reveals, do not vary from level by more than 1/8 inch in 10 feet, 1/4 inch in 20 feet, or 1/2 inch maximum.

4. For exposed bed joints, do not vary from thickness indicated by more than plus or minus 1/8 inch, with a maximum thickness limited to 1/2 inch. Do not vary from bed-joint thickness of adjacent courses by more than 1/8 inch.
5. For exposed head joints, do not vary from thickness indicated by more than plus or minus 1/8 inch. Do not vary from adjacent bed-joint and head-joint thicknesses by more than 1/8 inch.
6. For faces of adjacent exposed masonry units, do not vary from flush alignment by more than 1/16 inch except due to warpage of masonry units within tolerances specified for warpage of units.

3.3 LAYING MASONRY WALLS

A. Lay out walls in advance for accurate spacing of surface bond patterns with uniform joint thicknesses and for accurate location of openings, movement-type joints, returns, and offsets. Avoid using less-than-half-size units, particularly at corners, jambs, and, where possible, at other locations.

B. Bond Pattern for Exposed Masonry: Unless otherwise indicated, lay exposed masonry in bond pattern indicated on Drawings; do not use units with less than nominal 4-inch horizontal face dimensions at corners or jambs. Prior to installation review bond pattern with Architect.

C. Stopping and Resuming Work: Stop work by racking back units in each course from those in course below; do not tooth. When resuming work, clean masonry surfaces that are to receive mortar, remove loose masonry units and mortar, and wet brick if required before laying fresh masonry.

D. Built-in Work: As construction progresses, build in items specified in this and other Sections. Fill in solidly with masonry around built-in items.

E. Fill space between steel frames and masonry solidly with mortar, unless otherwise indicated.

F. Fill cores in hollow concrete masonry units with grout 24 inches under bearing plates, beams, lintels, posts, and similar items, unless otherwise indicated.

G. Build non-load-bearing interior partitions full height of story to underside of solid floor or roof structure above, unless otherwise indicated.

1. Install compressible filler in joint between top of partition and underside of structure above.
2. Fasten partition top anchors to structure above and build into top of partition. Grout cells of CMUs solidly around plastic tubes of anchors and push tubes down into grout to provide 1/2-inch clearance between end of anchor rod and end of tube. Space anchors 48 inches o.c., unless otherwise indicated.
3. Wedge non-load-bearing partitions against structure above with small pieces of tile, slate, or metal. Fill joint with mortar after dead-load deflection of structure above approaches final position.
4. At fire-rated partitions, treat joint between top of partition and underside of structure above to comply with Section 078440 – FIRE-RESISTIVE JOINT SYSTEMS.

3.4 MORTAR BEDDING AND JOINTING

A. Lay hollow brick and concrete masonry units as follows:

1. With face shells fully bedded in mortar and with head joints of depth equal to bed joints.
2. With webs fully bedded in mortar in all courses of piers, columns, and pilasters.
3. With webs fully bedded in mortar in grouted masonry, including starting course on footings.
4. With entire units, including areas under cells, fully bedded in mortar at starting course on footings where cells are not grouted.

B. Lay solid masonry units with completely filled bed and head joints; butter ends with sufficient mortar to fill head joints and shove into place. Do not deeply furrow bed joints or slush head joints.

C. Tool exposed joints slightly concave when thumbprint hard, using a jointer larger than joint thickness, unless otherwise indicated.

D. Cut joints flush for masonry walls to receive plaster or other direct-applied finishes (other than paint), unless otherwise indicated.

3.5 CAVITY WALLS

A. Bond wythes of cavity walls together using bonding system indicated on Drawings.

B. Keep cavities clean of mortar droppings and other materials during construction. Bevel beds away from cavity, to minimize mortar protrusions into cavity. Do not attempt to trowel or remove mortar fins protruding into cavity.

C. Coordinate and allow access for air and vapor barrier membrane installed in cavity under Section 072700 - AIR BARRIERS.

3.6 MASONRY JOINT REINFORCEMENT

A. General: Install entire length of longitudinal side rods in mortar with a minimum cover of 5/8 inch on exterior side of walls, 1/2 inch elsewhere. Lap reinforcement a minimum of 6 inches. Space reinforcement not more than 16 inches o.c.

B. Interrupt joint reinforcement at control and expansion joints, unless otherwise indicated.

C. Provide continuity at wall intersections by using prefabricated T-shaped units.

D. Provide continuity at corners by using prefabricated L-shaped units.

3.7 ANCHORING MASONRY TO STRUCTURAL MEMBERS

A. Anchor masonry to structural members where masonry abuts or faces structural members to comply with the following:

1. Provide an open space not less than 1 inch in width between masonry and structural member, unless otherwise indicated. Keep open space free of mortar and other rigid materials.
2. Anchor masonry to structural members with anchors embedded in masonry joints and attached to structure.

3. Space anchors as indicated, but not more than 24 inches o.c. vertically and 36 inches o.c. horizontally.

3.8 ANCHORING MASONRY VENEERS

A. Anchor masonry veneers with masonry-veneer anchors to comply with the following requirements:

1. Fasten screw-attached anchors through insulation and sheathing to wall framing and to concrete and masonry backup as applicable with metal fasteners of type indicated.
2. Embed tie sections in masonry joints. Provide air space indicated on the Drawings between back of masonry veneer and face of insulation.
3. Locate anchor sections to allow maximum vertical differential movement of ties up and down.
4. Space anchors as required by Code.

3.9 CONTROL AND EXPANSION JOINTS

A. General: Install control and expansion joint materials in unit masonry as masonry progresses. Do not allow materials to span control and expansion joints without provision to allow for in-plane wall or partition movement.

B. Form control joints in concrete masonry using one of the following methods:

1. Fit bond-breaker strips into hollow contour in ends of concrete masonry units on one side of control joint. Fill resultant core with grout and rake out joints in exposed faces for application of sealant.
2. Install preformed control-joint gaskets designed to fit standard sash block.
3. Install interlocking units designed for control joints. Install bond-breaker strips at joint. Keep head joints free and clear of mortar or rake out joint for application of sealant.
4. Install temporary foam-plastic filler in head joints and remove filler when unit masonry is complete for application of sealant.

C. Form expansion joints in brick made from clay or shale as follows:

1. Build flanges of metal expansion strips into masonry. Lap each joint 4 inches in direction of water flow. Seal joints below grade and at junctures with horizontal expansion joints if any.
2. Build flanges of factory-fabricated, expansion-joint units into masonry.
3. Build in compressible joint fillers where indicated.
4. Form open joint full depth of brick wythe and of width indicated, but not less than 3/8 inch for installation of sealant and backer rod specified in Section 079200 - JOINT SEALANTS.

D. Provide horizontal, pressure-relieving joints by either leaving an air space or inserting a compressible filler of width required for installing sealant and backer rod specified in Section 079200 - JOINT SEALANTS but not less than 3/8 inch.

1. Locate horizontal, pressure-relieving joints beneath shelf angles supporting masonry.

3.10 LINTELS

A. Install steel lintels where indicated.

B. Provide minimum bearing of 8 inches at each jamb, unless otherwise indicated.

3.11 FLASHING, WEEP HOLES, CAVITY DRAINAGE, AND VENTS

A. General: Install embedded flashing and weep holes in masonry at shelf angles, lintels, ledges, other obstructions to downward flow of water in wall, and where indicated.

B. Install flashing as follows, unless otherwise indicated:

1. Prepare masonry surfaces so they are smooth and free from projections that could puncture flashing. Where flashing is within mortar joint, place through-wall flashing on sloping bed of mortar and cover with mortar. Before covering with mortar, seal penetrations in flashing with adhesive, sealant, or tape as recommended by flashing manufacturer.
2. At multiwythe masonry walls, including cavity walls, extend flashing through outer wythe, turned up a minimum of 8 inches, and 1-1/2 inches into the inner wythe. Form 1/4-inch hook in edge of flashing embedded in inner wythe.
3. At masonry-veneer walls, extend flashing through veneer, across air space behind veneer, and up face of sheathing at least 8 inches; with upper edge covered with elastomeric membrane, lapping at least 4 inches.
4. At lintels and shelf angles, extend flashing a minimum of 6 inches into masonry at each end. At heads and sills, extend flashing 6 inches at ends and turn up not less than 2 inches to form end dams.
5. Install air barrier transition strips to seal embedded flashings in masonry to air barrier membrane in accordance with Section 072700 – AIR BARRIERS.

C. Install reglets and nailers for flashing and other related construction where they are shown to be built into masonry.

D. Install metal drip edge plate in accordance with architectural details and manufacturer’s requirements.

E. Install weep holes in head joints in exterior wythes of first course of masonry immediately above embedded flashing and as follows:

1. Use specified weep/vent products to form weep holes.
2. Space weep holes 24 inches o.c., unless otherwise indicated.

F. Place cavity drainage material in cavities to comply with configuration requirements for cavity drainage material in Part 2 “Miscellaneous Masonry Accessories” Article.

G. Install vents in head joints in exterior wythes at spacing indicated.

3.12 REINFORCED UNIT MASONRY INSTALLATION

A. Temporary Formwork and Shores: Construct formwork and shores as needed to support reinforced masonry elements during construction.

1. Construct formwork to provide shape, line, and dimensions of completed masonry as indicated. Make forms sufficiently tight to prevent leakage of mortar and grout. Brace, tie, and support forms to maintain position and shape during construction and curing of reinforced masonry.
2. Do not remove forms and shores until reinforced masonry members have hardened sufficiently to carry their own weight and other temporary loads that may be placed on them during construction.

B. Placing Reinforcement: Comply with requirements in ACI 530.1/ASCE 6/TMS 602.

C. Grouting: Do not place grout until entire height of masonry to be grouted has attained enough strength to resist grout pressure. Comply with requirements in ACI 530.1/ASCE 6/TMS 602 for cleanouts and for grout placement, including minimum grout space and maximum pour height.

3.13 FIELD QUALITY CONTROL

A. Inspectors: Owner will engage qualified independent inspectors to perform inspections and prepare reports. Allow inspectors access to scaffolding and work areas, as needed to perform inspections. Place grout only after inspectors have verified compliance of grout spaces and grades, sizes, and locations of reinforcement.

B. Testing Agency: Engage a qualified independent testing and inspecting agency to perform field tests and inspections indicated below and prepare test reports. Retesting of materials failing to comply with specified requirements shall be done at Contractor’s expense.

C. Testing Frequency: One set of tests for each 5000 sq. ft. of wall area or portion thereof. Test types as determined by the independent testing and inspection agency.

3.14 REPAIRING, POINTING, AND CLEANING

A. Remove and replace masonry units that are loose, chipped, broken, stained, or otherwise damaged or that do not match adjoining units. Install new units to match adjoining units; install in fresh mortar, pointed to eliminate evidence of replacement.

B. Pointing: During the tooling of joints, enlarge voids and holes, except weep holes, and completely fill with mortar. Point up joints, including corners, openings, and adjacent construction, to provide a neat, uniform appearance. Prepare joints for sealant application, around penetrations and where indicated.

C. In-Progress Cleaning: Clean unit masonry as work progresses by dry brushing to remove mortar fins and smears before tooling joints.

D. Final Cleaning: After mortar is thoroughly set and cured, clean exposed masonry as follows:

1. Remove large mortar particles by hand with wooden paddles and nonmetallic scrape hoes or chisels.
2. Test cleaning methods on sample wall panel; leave one-half of panel uncleaned for comparison purposes. Obtain Architect’s approval of sample cleaning before proceeding with cleaning of masonry.
3. Protect adjacent stone and nonmasonry surfaces from contact with cleaner by covering them with liquid strippable masking agent or polyethylene film and waterproof masking tape.

4. Wet wall surfaces with water before applying cleaners; remove cleaners promptly by rinsing surfaces thoroughly with clear water.
5. Clean concrete masonry by cleaning method indicated in NCMA TEK 8-2A applicable to type of stain on exposed surfaces.
6. Clean brick by bucket-and-brush hand-cleaning method described in BIA Technical Notes 20.

3.15 MASONRY WASTE DISPOSAL

A. Salvageable Materials: Unless otherwise indicated, excess masonry materials are Contractor's property. At completion of unit masonry work, remove from Project site.

B. Waste Disposal as Fill Material: Dispose of clean masonry waste, including excess or soil-contaminated sand, waste mortar, and broken masonry units, by crushing and mixing with fill material as fill is placed.

1. Crush masonry waste to less than 4 inches in each dimension.
2. Mix masonry waste with at least two parts of specified fill material for each part of masonry waste. Fill material is specified in Division 31 - EARTHWORK.
3. Do not dispose of masonry waste as fill within 18 inches of finished grade.

C. Excess Masonry Waste: Remove excess clean masonry waste that cannot be used as fill, as described above, and other masonry waste, and legally dispose of off the Site.

END OF SECTION

SECTION 061000

ROUGH CARPENTRY

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Framing with dimension lumber.
2. Framing with engineered wood products.
3. Wood blocking, cants, and nailers.
4. Plywood backing panels.

1.3 DEFINITIONS

A. Exposed Framing: Framing not concealed by other construction.

B. Dimension Lumber: Lumber of 2 inches nominal or greater but less than 5 inches nominal in least dimension.

C. Lumber grading agencies, and the abbreviations used to reference them, include the following:

1. NeLMA: Northeastern Lumber Manufacturers' Association.
2. NLGA: National Lumber Grades Authority.
3. RIS: Redwood Inspection Service.
4. SPIB: The Southern Pine Inspection Bureau.
5. WCLIB: West Coast Lumber Inspection Bureau.
6. WWPA: Western Wood Products Association.

1.4 SUBMITTALS

A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.

1. Include data for wood-preservative treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Indicate type of preservative used, net amount of preservative retained, and chemical treatment manufacturer's written instructions for handling, storing, installing, and finishing treated material.
2. Include data for fire-retardant treatment from chemical treatment manufacturer and

certification by treating plant that treated materials comply with requirements. Include physical properties of treated materials, both before and after exposure to elevated temperatures when tested according to ASTM D 5516 and ASTM D 5664.

3. For products receiving a waterborne treatment, include statement that moisture content of treated materials was reduced to levels specified before shipment to Project site.
4. Include copies of warranties from chemical treatment manufacturers for each type of treatment.

B. Material Certificates: For dimension lumber specified to comply with minimum allowable unit stresses. Indicate species and grade selected for each use and design values approved by the ALSC Board of Review.

1.5 QUALITY ASSURANCE

A. Testing Agency Qualifications: For testing agency providing classification marking for fire-retardant treated material, an inspection agency acceptable to authorities having jurisdiction that periodically performs inspections to verify that the material bearing the classification marking is representative of the material tested.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Stack lumber, plywood, and other panels; place spacers between each bundle to provide air circulation. Provide for air circulation around stacks and under coverings.

PART 2 PRODUCTS

2.1 DECK FRAMING

A. Lumber: DOC PS 20 and applicable rules of lumber grading agencies certified by the American Lumber Standards Committee Board of Review.

1. Factory mark each piece of lumber with grade stamp of grading agency.
2. For exposed lumber indicated to receive a stained or natural finish, mark grade stamp on end or back of each piece or omit grade stamp and provide certificates of grade compliance issued by grading agency.
3. Where nominal sizes are indicated, provide actual sizes required by DOC PS 20 for moisture content specified. Where actual sizes are indicated, they are minimum dressed sizes for dry lumber.
4. Provide dressed lumber, S4S, unless otherwise indicated.

B. Preservative Treatment by Pressure Process: AWPA U1; Use Category UC3b for exterior construction not in contact with the ground, and Use Category UC4a for items in contact with the ground.

1. Preservative Chemicals: Acceptable to authorities having jurisdiction and containing no arsenic or chromium. Do not use inorganic boron (SBX) for sill plates.
2. For exposed items indicated to receive a stained or natural finish, use chemical formulations that do not require incising, contain colorants, bleed through, or otherwise adversely affect finishes.

C. Kiln-dry material after treatment to a maximum moisture content of 19 percent for lumber and 15

percent for plywood. Do not use material that is warped or does not comply with requirements for untreated material.

D. Mark each treated item with the treatment quality mark of an inspection agency approved by the American Lumber Standards Committee Board of Review.

E. Fasteners: Type 304 stainless steel.

1. Where carpentry is exposed to weather, in ground contact, pressure-preservative treated, or in area of high relative humidity, provide fasteners of Type 304 stainless steel.

F. Nails, Wire, Brads, and Staples: FS FF-N-105.

G. Power-Driven Fasteners: CABO NER-272.

H. Wood Screws: ASME B18.6.1.

I. Screws for Fastening to Cold-Formed Metal Framing: ASTM C 954, except with wafer heads and reamer wings, length as recommended by screw manufacturer for material being fastened.

J. Bolts: Steel bolts complying with ASTM A 307, Grade A with ASTM A 563 hex nuts and, where indicated, flat washers.

K. Expansion Anchors: Anchor bolt and sleeve assembly of material indicated below with capability to sustain, without failure, a load equal to 6 times the load imposed when installed in unit masonry assemblies and equal to 4 times the load imposed when installed in concrete as determined by testing per ASTM E 488 conducted by a qualified independent testing and inspecting agency.

1. Material: Carbon-steel components, zinc plated to comply with ASTM B 633, Class Fe/Zn 5; except provide Type 304 stainless steel where in contact with pressure-preservative treated wood.

2.2 METAL FRAMING ANCHORS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Cleveland Steel Specialty Co.
2. KC Metals Products, Inc.
3. Phoenix Metal Products, Inc.
4. Simpson Strong-Tie Co., Inc.
5. USP Structural Connectors.

B. Allowable Design Loads: Provide products with allowable design loads, as published by manufacturer, that meet or exceed those indicated. Manufacturer's published values shall be determined from empirical data or by rational engineering analysis and demonstrated by comprehensive testing performed by a qualified independent testing agency.

C. Galvanized-Steel Sheet: Hot-dip, zinc-coated steel sheet complying with ASTM A 653/A 653M, G60 coating designation.

1. Use for interior locations unless otherwise indicated.

D. Hot-Dip, Heavy-Galvanized Steel Sheet: ASTM A 653/A 653M; structural steel (SS), high-strength low-alloy steel Type A (HSLAS Type A), or high-strength low-alloy steel Type B (HSLAS Type B); G185 coating designation; and not less than 0.036 inch thick.

1. Use for wood-preservative-treated lumber and where indicated.

E. Joist Hangers: U-shaped joist hangers with 2-inch-long seat and 1-1/4-inch-wide nailing flanges at least 85 percent of joist depth.

1. Thickness: 0.062 inch.

F. I-Joist Hangers: U-shaped joist hangers with 2-inch-long seat and 1-1/4-inch-wide nailing flanges full depth of joist. Nailing flanges provide lateral support at joist top chord.

1. Thickness: 0.062 inch.

G. Rafter Tie-Downs: Bent strap tie for fastening rafters or roof trusses to wall studs below, 1-1/2 inches wide by 0.050 inch thick.

H. Floor-to-Floor Ties: Flat straps, with holes for fasteners, for tying upper floor wall studs to band joists and lower floor studs, 1-1/4 inches wide by 0.050 inch thick by 36 inches long.

2.3 MISCELLANEOUS MATERIALS

A. Sill-Sealer Gaskets: Glass-fiber-resilient insulation, fabricated in strip form, for use as a sill sealer; 1-inch nominal thickness, compressible to 1/32 inch; selected from manufacturer's standard widths to suit width of sill members indicated.

B. Adhesive, Including Gluing Furring and Sleepers to Concrete or Masonry: Formulation complying with ASTM D 3498 that is approved for use indicated by adhesive manufacturer.

PART 3 EXECUTION

3.1 INSTALLATION, GENERAL

A. Discard units of material with defects that impair quality of carpentry and that are too small to use with minimum number of joints or optimum joint arrangement.

B. Set carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit carpentry to other construction; scribe and cope as needed for accurate fit. Locate furring, nailers, blocking, grounds, and similar supports to comply with requirements for attaching other construction.

C. Apply field treatment complying with AWPA M4 to cut surfaces of preservative-treated lumber and plywood.

D. Framing Standard: Comply with AF&PA's WCD 1, "Details for Conventional Wood Frame Construction," unless otherwise indicated.

E. Framing with Engineered Wood Products: Install engineered wood products to comply with manufacturer's written instructions.

F. Metal Framing Anchors: Install metal framing anchors to comply with manufacturer's written instructions. Install fasteners through each fastener hole.

G. Install sill sealer gasket to form continuous seal between sill plates and foundation walls.

H. Do not splice structural members between supports unless otherwise indicated.

I. Securely attach carpentry work as indicated and according to applicable codes and recognized standards.

J. Countersink fastener heads on exposed carpentry work and fill holes with wood filler.

K. Use fasteners of appropriate type and length. Predrill members when necessary to avoid splitting wood.

L. Provide fire blocking in furred spaces, stud spaces, and other concealed cavities as indicated and as follows:

1. Fire block furred spaces of walls, at each floor level, at ceiling, and at not more than 96 inches o.c. with solid wood blocking or noncombustible materials accurately fitted to close furred spaces.
2. Fire block concealed spaces of wood-framed walls and partitions at each floor level, at ceiling line of top story, and at not more than 96 inches o.c. Where fire blocking is not inherent in framing system used, provide closely fitted solid wood blocks of same width as framing members and 2-inch nominal-thickness.
3. Fire block concealed spaces between floor sleepers with same material as sleepers to limit concealed spaces to not more than 100 sq. ft. and to solidly fill space below partitions.
4. Fire block concealed spaces behind combustible cornices and exterior trim at not more than 20 feet o.c.

3.2 WOOD BLOCKING, AND NAILER INSTALLATION

A. Install where indicated and where required for attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.

B. Attach items to substrates to support applied loading. Recess bolts and nuts flush with surfaces, unless otherwise indicated.

3.3 WALL AND PARTITION FRAMING INSTALLATION

A. General: Provide single bottom plate and double top plates using members of 2-inch nominal thickness whose widths equal that of studs, except single top plate may be used for non-load-bearing partitions and for load-bearing partitions where framing members bearing on partition are located directly over studs. Fasten plates to supporting construction unless otherwise indicated.

1. For exterior walls, provide 2-by-6-inch nominal-size wood studs spaced 16 inches o.c. unless otherwise indicated.
2. For interior partitions and walls, provide 2-by-6-inch nominal-size wood studs spaced 16 inches o.c. unless otherwise indicated.
3. Provide continuous horizontal blocking at midheight of partitions more than 96 inches high, using members of 2-inch nominal thickness and of same width as wall or partitions.

B. Construct corners and intersections with three or more studs, except that two studs may be used for interior non-load-bearing partitions.

C. Frame openings with multiple studs and headers. Provide nailed header members of thickness equal to width of studs. Support headers on jamb studs.

1. For non-load-bearing partitions, provide double-jamb studs and headers not less than 4-inch nominal depth for openings 48 inches and less in width, 6-inch nominal depth for openings 48 to 72 inches in width, 8-inch nominal depth for openings 72 to 120 inches in width, and not less than 10-inch nominal depth for openings 10 to 12 feet in width.
2. For load-bearing walls, provide double-jamb studs for openings 60 inches and less in width, and triple-jamb studs for wider openings. Provide headers of depth indicated.

D. Provide diagonal bracing in walls, at locations indicated, at 45-degree angle, full-story height unless otherwise indicated. Use 1-by-4-inch nominal-size boards, let-in flush with faces of studs.

3.4 PROTECTION

A. Protect wood that has been treated with inorganic boron (SBX) from weather. If, despite protection, inorganic boron-treated wood becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

B. Protect rough carpentry from weather. If, despite protection, rough carpentry becomes sufficiently wet that moisture content exceeds that specified, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

END OF SECTION

SECTION 064020

INTERIOR ARCHITECTURAL WOODWORK

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Wood cabinets.
2. Solid-surfacing-material countertops.
3. Shop finishing of interior woodwork to receive transparent finish.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 061000 - ROUGH CARPENTRY for wood furring, blocking, shims, and hanging strips required for installing woodwork and concealed within other construction before woodwork installation.

1.3 SUBMITTALS

A. Product Data: For each type of product specified, including cabinet hardware and accessories, and finishing materials and processes.

1. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements.
2. For engineered quartz and natural stone countertops, submit fabricator's letter certifying compliance with OSHA 1926.1153, Respirable Crystalline Silica.
3. For upholstery fabric and padding, documentation indicating that the materials contain no chemical flame retardants..
4. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements.
5. Include submittal of stone sealer manufacturer's recommended methods for application of impregnator and surface protection coatings based on testing of project specific stone countertop materials

B. Shop Drawings: Submit shop drawings showing locations of each item, dimensioned plans and elevations, large-scale details, attachment devices, and other components. Elevations shall be drawn at a scale of not less than 1/2" = 1'-0" (1:25). Details shall be drawn at a scale of not less than 3" = 1'-0" (1:5).

1. Show locations and sizes of furring, blocking, and hanging strips, including concealed blocking and reinforcement specified in other Sections.

a. Provide schedule of blocking required to support the Work of this Section.

2. Show locations and sizes of cutouts and holes for plumbing fixtures, electrical components and other items installed in architectural woodwork.
3. Show veneer leaves with dimensions, grain direction, exposed face, and identification numbers indicating the flitch and sequence within the flitch for each leaf.

C. Hardware Schedule: For each type of hardware used in architectural woodwork. Include keying requirements.

D. Samples for Verification:

1. Lumber with or for transparent finish, not less than 5 inches wide by 12 inches long for each species and cut, finished on 1 side and 1 edge.
2. Veneer leaves representative of and selected from flitches to be used for transparent-finished woodwork.

a. Submit step-type range sample sets of factory finished plywood and factory finished solid wood in size illustrating wood grain and specified finish, including edge banding detail and any veneer or solid edge glue joints.
b. Submit full length diagrams for veneers.
c. Submit pictures of specific wood materials.

3. Lumber and panel products for transparent finish, for each species and cut, finished on one side and one edge. Furnish lumber in 12 inch lengths, furnish panel samples in 12 inch squares.
4. Solid-surfacing materials, 4 inches square, showing edge condition.
5. Decorative Hardware: One of each type, including locks.
6. Metal Trim Shapes: Thee samples of each type and finish, 12 inches long.

E. Qualification Data: For Installer and fabricator.

1.4 QUALITY ASSURANCE

A. Fabricator Qualifications: Shop that employs skilled workers who custom-fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.

B. Installer Qualifications:

1. Fabricator shall comply with OSHA 1926.1153, Respirable Crystalline Silica, and does not dry-cut engineered-quartz and natural stone materials.
2. Fabricator shall be certified for chain of custody by an FSC-accredited certification body.

C. Source Limitations: Engage a qualified woodworking firm to assume undivided responsibility for production of interior architectural woodwork with blueprint-matched wood veneers and components.

D. Quality Standard: Unless otherwise indicated, comply with AWI/AWMAC/WI's "Architectural Woodwork Standards," latest edition, including errata, for grades of interior architectural woodwork indicated for construction, finishes, installation, and other requirements.

E. Fire-Test-Response Characteristics: Where fire-retardant materials or products are indicated, provide materials and products with specified fire-test-response characteristics as determined

by testing identical products per test method indicated by UL, ITS, or another testing and inspecting agency acceptable to authorities having jurisdiction. Identify with appropriate markings of applicable testing and inspecting agency in the form of separable paper label or, where required by authorities having jurisdiction, imprint on surfaces of materials that will be concealed from view after installation.

1. Fire-Test-Response Characteristics of Upholstery Fabric and Padding: Comply with California Technical Bulletin 117-2013 Update, with no chemical flame retardants.

F. Mockups: Build mockups to verify selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Confirm size and type of mock-ups with Architect with sufficient time in schedule for fabrication and modifications if required.
2. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

G. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Protect woodwork during transit, delivery, storage, and handling to prevent damage, soilage, and deterioration. Do not deliver woodwork until painting, wet work, grinding, and similar operations that could damage, soil, or deteriorate woodwork have been completed in installation areas. If woodwork must be stored in other than installation areas, store only in areas whose environmental conditions meet requirements specified in "Field Conditions" Article.

1.6 FIELD CONDITIONS

A. Environmental Limitations: Do not deliver or install woodwork until building is enclosed, wet work is complete, and HVAC system is operating and maintaining temperature and relative humidity at occupancy levels during the remainder of the construction period.

1. The HVAC systems as specified elsewhere may not provide for humidity controls. The expected ranges of relative humidity are expected to be as high as 55 percent to a low of uncontrolled during the heating system. Comply with AWI Section 2, Care and Storage.

B. Field Measurements: Where woodwork is indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication, and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

1. Locate concealed framing, blocking, and reinforcements that support woodwork by field measurements before being enclosed, and indicate measurements on Shop Drawings.
2. Established Dimensions: Where field measurements cannot be made without delaying the Work, establish dimensions and proceed with fabricating woodwork without field measurements. Provide allowance for trimming at site, and coordinate construction to ensure that actual dimensions correspond to established dimensions.

1.7 COORDINATION

A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of Work specified in other Sections to ensure that interior architectural woodwork can be supported and installed as indicated.

1.8 PREINSTALLATION COORDINATION MEEETING

A. Convene a meeting at the Project site, prior to installation of architectural woodwork, to review the substrate preparation, installation and coordination with other trades, special details and conditions, and other topics related to the architectural woodwork. The preinstallation meeting shall include the Architect, the Contractor, architectural woodworker, and any subcontractors affected by the architectural woodwork installation.

PART 2 - PRODUCTS

2.1 BASIS-OF-DESIGN

A. Basis-of-Design Products: Refer to the Finish Schedule on the Drawings.

2.2 MATERIALS

A. General: Provide materials that comply with requirements of AWI/AWMAC/WI's "Architectural Woodwork Standards" for each type of woodwork and quality grade specified, unless otherwise indicated.

B. Wood Veneers and Lumber: Provide AWI Custom Grade materials and workmanship, unless otherwise indicated. For species not listed in the AWI comply with the following:

1. Provide AWI Lumber Grade 1 and AWI Grade A Veneer, book-matched, minimum 6 inch face veneer width. Kiln dry to 6-8 percent moisture content. Components shall be free of defects and sapwood. Match adjacent pieces for color and grain pattern.
2. Single-Source Requirement for Wood Veneers and Solids: Intent is to provide wood which matches as closely as possible throughout the project. Provide wood veneers and solids from the same distributor, and from the same flitches and solids sources to the greatest extent possible.

C. Wood Species and Cut for Transparent Finish: Plain-sliced white maple with clear finish.

1. Architect’s control samples for transparent finish, veneer grain and figure characteristics are available for review at the office of the Architect.
2. Veneer Matching Requirements:

a. Matching Between Adjacent Veneer Leaves: Book match and architectural end match.
b. Matching Within Individual Panel Faces: Balance and Center Match.
c. Method of Matching Panels: Blueprint-matched panels and components.

D. Composite Wood Products: Comply with the following:

1. Medium-Density Fiberboard (MDF): ANSI A208.2, Grade MD, made with binder containing no added urea formaldehyde.
2. Particleboard: ANSI A208.1, Grade M-2 Exterior Glue.

3. Plywood: Marine grade.
4. Softwood Plywood: DOC PS 1, Medium Density Overlay (MDO).
5. Veneer-Faced Panel Products (Hardwood Plywood): HPVA HP-1.

    a. Resin impregnated paper backs are not permitted. Backs shall be of compatible hardwood species and cut. Contact adhesive is not permitted..
    b. MDO and OSB are not permitted.

E. Solid-Surfacing Material: Homogeneous solid sheets of filled plastic resin complying with ISFA-2.

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

    a. Avonite Surfaces; Aristech Surfaces.
    b. E. I. du Pont de Nemours and Company; Corian.
    c. Formica Corporation.
    d. LG Hausys; Hi-Macs.
    e. Nevamar.
    f. Wilsonart LLC.

F. Tempered Float Glass for Cabinet: ASTM C 1048, Kind FT, Condition A, Type I, Class 1 (clear), Quality-Q3, with exposed edges seamed before tempering, 1/4 inch (6 mm) thick, unless otherwise indicated.

2.3 FIRE-RETARDANT-TREATED MATERIALS

A. General: Where fire-retardant-treated materials are indicated, use materials complying with requirements in this Article, that are acceptable to authorities having jurisdiction, and with fire-test-response characteristics specified.

1. Do not use treated materials that do not comply with requirements of referenced woodworking standard or that are warped, discolored, or otherwise defective.
2. Use fire-retardant-treatment formulations that do not bleed through or otherwise adversely affect finishes. Do not use colorants to distinguish treated materials from untreated materials.
3. Identify fire-retardant-treated materials with appropriate classification marking of UL, U.S. Testing, Timber Products Inspection, or another testing and inspecting agency acceptable to authorities having jurisdiction.

B. Fire-Retardant-Treated Lumber and Plywood by Pressure Process: Comply with performance requirements of AWPA C20 (lumber) and AWPA C27 (plywood). Use the following treatment type:

1. Exterior Type: Organic-resin-based formulation thermally set in wood by kiln drying.
2. Mill lumber before treatment and implement special procedures during treatment and drying processes that prevent lumber from warping and developing discolorations from drying sticks or other causes, marring, and other defects affecting appearance of treated woodwork.
3. Kiln-dry materials before and after treatment to levels required for untreated materials.

C. Fire-Retardant Particleboard: Panels complying with the following requirements, made from softwood particles and fire-retardant chemicals mixed together at time of panel manufacture to

achieve flame-spread index of 25 or less and smoke-developed index of 25 or less per ASTM E 84.

1. Basis-of-Design: Arauco NA; Duraflake FR.

D. Fire-Retardant Fiberboard: Medium-density fiberboard panels complying with ANSI A208.2, made from softwood fibers, synthetic resins, and fire-retardant chemicals mixed together at time of panel manufacture to achieve flame-spread index of 25 or less and smoke-developed index of 200 or less per ASTM E 84.

1. Basis-of-Design: Roseburg; Medite FR.

2.4 CABINET HARDWARE AND ACCESSORIES

A. General: Provide cabinet hardware and accessory materials associated with architectural cabinet, except for items specified in Section 087100 - DOOR HARDWARE.

B. Catches: Magnetic, complying with BHMA A156.9, B03141 for single doors and B03161 for double doors.

C. Hardware Standard: Comply with BHMA A156.9 for items indicated by referencing BHMA numbers or items referenced to this standard.

D. Butt Hinges: 2-3/4-inch (70-mm), five-knuckle steel hinges made from 0.095-inch- (2.4-mm-) thick metal, and as follows:

1. Semiconcealed Hinges for Flush Doors: ANSI/BHMA A156.9, B01361.
2. Semiconcealed Hinges for Overlay Doors: ANSI/BHMA A156.9, B01521.

E. Wire Pulls: Back mounted, fabricated from satin finished stainless steel (US32D), complying with BHMA A156.9, B52011, unless otherwise indicated.

F. Drawer Slides: BHMA A156.9, B05091; side mounted and extending under bottom edge of drawer; full-extension type; epoxy-coated-steel with steel ball-bearings; of the following grades:

1. Type: Heavy-Duty (Grade 1HD-100 and Grade 1HD-200).
2. Pencil Drawer Slides: 3/4 extension carburized steel ball bearing, side mounting, 45 lbs. capacity medium duty load rating, cold rolled steel slide members and ball retainers, bright electro zinc plate finish.
3. Drawers less than 4 inches (102 mm) deep: Full extension carburized steel ball bearing, side mounting, 200 lb. capacity heavy duty load rating, cold rolled steel slide members and ball retainers, cushioned in and outstops, detent-in, progressive action, positive stop, bright electro zinc plate finish.
4. Drawers greater than 4 inches (102 mm) but less than 8 inches (203 mm) deep: Full extension carburized steel ball bearing, side mounting, 200 lb. capacity heavy duty load rating, cold rolled steel slide members and ball retainers, cushioned in and outstops, detent-in, progressive action, positive stop, bright electro zinc plate finish.
5. Drawers greater than 8 inches (203 mm) deep: Full extension carburized steel ball bearing, rail mounting, 150 lb. capacity heavy duty load rating, cold rolled steel slide members and ball retainers, cushioned in and outstops, detent-in, progressive action, positive stop, bright electro zinc plate finish.
6. Refuse Cabinets: Full extension carburized steel ball bearing, bottom mounting, 175 lb. capacity heavy duty load rating, cold rolled steel slide members and ball retainers,

cushioned in and outstops, progressive action, positive stop, bright electro zinc plate finish.

G. Aluminum Slides for Sliding Glass Doors: BHMA A156.9, B07063.

H. Silencers: Provide rubber silencers on jamb and/or head and sill strike areas of all cabinet doors and drawers, 2 for paired doors, and 3 for single doors. Silencers shall be approximately 1/4-inch (6.4-mm) diameter, color compatible with adjacent finish.

I. Door and Drawer Locks: Teacher's cabinets shall be furnished with cabinet locks on both doors. Other cabinets shall be furnished with cabinet locks as indicated on the drawings. Finish exposed portions of locks to match cabinet pull finish. Furnish 2 keys with each lock and key all locks inside one room alike and provide masterkey for all locks in Project.

1. Door Locks: BHMA A156.11, E07121.
2. Drawer Locks: BHMA A156.11, E07041.
3. Teacher's cabinets shall have SFIC format compatible locks. Other locks shall be standard cabinet locks.

J. Grommets for Cable Passage through Countertops: Metal grommets and caps with slot for wire passage.

K. Exposed Hardware Finishes: Unless otherwise specified above, or on the Drawings, all exposed portions of the woodwork hardware shall comply with BHMA A156.18 for BHMA finish number indicated.

1. Satin Stainless Steel: BHMA 630.

L. Screws: Select material, type, size, and finish required for each use. Comply with ASME B18.6.1.

M. Nails, Wire, Brads, and Staples: Select material, type, size, and finish required for each use.

1. ASTM F 1667 for driven fasteners such as nails, spikes and staples.
2. ASTM F 547 for nails used with wood and wood based products.

N. Anchors: Select material, type, size, and finish required by each substrate for secure anchorage. Provide toothed steel or lead expansion bolt devices for drilled-in-place anchors.

O. Blind Splines: Specialty devices, as required for tight butt joining, types and size as recommended by woodwork fabricator.

P. Covercaps: Where mortises of fastener heads, or draw downs are exposed (blind holes) in finished work, provide black plastic covercaps.

Q. Dual-Row Shelf Supports:

1. Basis-of-Design: Knape & Vogt; Dual-Row Standards Shelf Supports.
2. Mounting: Recessed into casework.

2.5 MISCELLANEOUS MATERIALS

A. Furring, Blocking, Shims, and Hanging Strips: Fire-retardant-treated softwood lumber, kiln dried to less than 15 percent moisture content.

B. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide nonferrous-metal or hot-dip galvanized anchors and inserts on inside face of exterior walls and elsewhere as required for corrosion resistance. Provide toothed-steel or lead expansion sleeves for drilled-in-place anchors.

C. Installation Adhesives and Wood Glues: Formulations approved for use indicated by adhesive manufacturer.

2.6 FABRICATION, GENERAL

A. Wood Moisture Content: Comply with requirements of referenced quality standard for wood moisture content in relation to ambient relative humidity during fabrication and in installation areas.

B. Sand fire-retardant-treated wood lightly to remove raised grain on exposed surfaces before fabrication.

C. Fabricate woodwork to dimensions, profiles, and details indicated. Ease edges to radius indicated for the following:

1. Corners of Cabinet and Edges of Solid-Wood (Lumber) Members and Rails: 1/16 inch.

D. Complete fabrication, including assembly, finishing, and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.

E. Shop-cut openings to maximum extent possible to receive hardware, appliances, plumbing fixtures, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

1. Seal edges of openings in countertops with a coat of varnish.

F. Install glass to comply with applicable requirements in Section 088000 - GLAZING and in GANA's "Glazing Manual." For glass in wood frames, secure glass with removable stops.

2.7 INTERIOR FRAMES AND JAMBS FOR TRANSPARENT FINISH

A. AWI Grade: Custom.

B. Wood Species and Cut: As specified hereinabove

C. For frames or jambs wider than available lumber, use veneered construction. Do not glue for width.

D. Fire-Rated Interior Frames and Jambs Where Indicated: Products fabricated from fire-retardant particleboard or fire-retardant medium-density fiberboard with veneered, exposed surfaces and listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire ratings indicated, based on testing according to NFPA 252.

1. Fire Rating: 20 minutes.

2.8 INTERIOR FRAMES AND JAMBS FOR OPAQUE FINISH

A. AWI Grade: Custom.

B. Wood Species: Any closed-grain hardwood.

2.9 WOOD CABINET FOR TRANSPARENT FINISH

A. AWI Grade: Custom.

B. AWI Type of Cabinet Construction: Flush overlay.

C. Wood Species and Cut for Exposed Surfaces: As specified hereinabove.

1. Grain Direction: Vertically for drawer fronts, doors, and fixed panels.
2. Matching of Veneer Leaves: Book match.
3. Vertical Matching of Veneer Leaves: End match.
4. Veneer Matching within Panel Face: Running match.
5. Veneer Matching within Room: Provide cabinet veneers in each room or other space from a single flitch with doors, drawer fronts, and other surfaces matched in a sequenced set with continuous match where veneers are interrupted perpendicular to the grain.

D. Semiexposed Surfaces: Provide surface materials indicated below:

1. Surfaces Other Than Drawer Bodies: Compatible species to that indicated for exposed surfaces, stained to match.
2. Drawer Sides and Backs: Solid-hardwood lumber, stained to match species indicated for exposed surfaces.
3. Drawer Bottoms: Hardwood plywood.

2.10 SOLID SURFACING MATERIAL COUNTERTOPS

A. General: Comply with AWI Section 11 and as follows.

B. Solid-Surfacing Material: Homogeneous solid sheets of filled plastic resin complying with ISFA-2.

C. Quality Standard: Unless otherwise indicated, comply with the "Architectural Woodwork Standards" for grades of countertops indicated for construction, finishes, installation, and other requirements.

1. Grade: Custom.
2. Pattern and Veining: Match adjacent pieces as acceptable to the Architect. Replace pieces which are not acceptable at no additional expense to the Owner.

D. Countertops: 1/2-inch- (12.7-mm -) thick, solid surface material with front edge built up with same material.

E. Backsplashes: 1/2-inch- (12.7-mm-) thick, solid surface material.

F. Sealants and Adhesives: As recommended by fabricator based on field conditions.

G. Fabricate tops with shop-applied edges, unless otherwise indicated. Comply with solid surface material manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.

1. Fabricate tops with shop-applied edges of materials and configuration indicated.
2. Fabricate with loose backsplashes for field assembly.
3. Install integral sink bowls in countertops in the shop.

H. Fabricate countertops in sections for joining in field, with joints at locations indicated.

I. Cutouts and Holes:

1. Undercounter Plumbing Fixtures: Make cutouts for fixtures in shop using template or pattern furnished by fixture manufacturer. Form cutouts to smooth, even curves.

   a. Provide vertical edges, slightly eased at juncture of cutout edges with top and bottom surfaces of countertop and projecting 3/16 inch (5 mm) into fixture opening.

2. Counter-Mounted Plumbing Fixtures: Prepare countertops in shop for field cutting openings for counter-mounted fixtures. Mark tops for cutouts and drill holes at corners of cutout locations. Make corner holes of largest radius practical.
3. Fittings: Drill countertops in shop for plumbing fittings, undercounter soap dispensers, and similar items.

J. Wire-Management Grommets: Circular, molded-plastic grommets and matching plastic caps with slot for wire passage.

2.11 SHOP FINISHING

A. General: Comply with AWI/AWMAC/WI's "Architectural Woodwork Standards" for factory finishing.

1. Finish architectural woodwork at fabrication shop as specified in this Section. Defer only final touchup, cleaning, and polishing until after installation.

B. Preparation for Finishing: Comply with referenced quality standard for sanding, filling countersunk fasteners, sealing concealed surfaces, and similar preparations for finishing architectural woodwork, as applicable to each unit of work.

1. Backpriming: Apply one coat of sealer or primer, compatible with finish coats, to concealed surfaces of woodwork. Apply two coats to back of paneling and to end-grain surfaces. Concealed surfaces of plastic-laminate-clad woodwork do not require backpriming when surfaced with plastic laminate, backing paper, or thermoset decorative panels.

C. Transparent Finish: Comply with requirements indicated below for grade, finish system, staining, and sheen with sheen measured on 60-degree gloss meter per ASTM D 523:

1. Grade: Same as item to be finished.
2. AWI Finish System 5: Conversion varnish.
3. Washcoat for Closed-Grain Woods: Apply washcoat sealer to woodwork made from closed-grain wood before staining and finishing
4. Staining: Match approved sample for color.
5. Open Finish for Open-Grain Woods: Do not apply filler to open-grain woods.
6. Sheen: Satin, 30-50 gloss units.
7. Effect: Partially filled pore.

PART 3 - EXECUTION

3.1 PREPARATION

A. Before installation, condition woodwork to average prevailing humidity conditions in installation areas.

B. Before installing architectural woodwork, examine shop-fabricated work for completion and complete work as required, including removal of packing and backpriming.

3.2 INSTALLATION

A. Grade: Install woodwork to comply with requirements for the same grade specified in Part 2 for fabrication of type of woodwork involved.

B. Assemble woodwork and complete fabrication at Project site to comply with requirements for fabrication in Part 2, to extent that it was not completed in the shop.

C. Install woodwork level, plumb, true, and straight. Shim as required with concealed shims. Install level and plumb (including tops) to a tolerance of 1/8 inch in 96 inches.

D. Scribe and cut woodwork to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.

E. Fire-Retardant-Treated Wood: Handle, store, and install fire-retardant-treated wood to comply with chemical treatment manufacturer's written instructions, including those for adhesives used to install woodwork.

F. Anchor woodwork to anchors or blocking built in or directly attached to substrates. Secure with countersunk, concealed fasteners and blind nailing as required for complete installation. Use fine finishing nails or finishing screws for exposed fastening, countersunk and filled flush with woodwork and matching final finish if transparent finish is indicated.

G. Cabinet: Install without distortion so doors and drawers fit openings properly and are accurately aligned. Adjust hardware to center doors and drawers in openings and to provide unencumbered operation. Complete installation of hardware and accessory items as indicated.

1. Install cabinet with no more than 1/8 inch in 96-inch sag, bow, or other variation from a straight line.
2. Maintain veneer sequence matching of cabinet with transparent finish.
3. Attach cabinet to walls with mechanical fasteners. Do not use adhesives, so that cabinet may be removed and salvaged in the future.

H. Countertops: Anchor securely by screwing through corner blocks of base cabinet or other supports into underside of countertop.

1. Align adjacent countertops and form seams to comply with manufacturer's written recommendations using adhesive in color to match countertop. Carefully dress joints smooth, remove surface scratches, and clean entire surface.
2. Install countertops with no more than 1/8 inch in 96-inch sag, bow, or other variation from a straight line.
3. Secure backsplashes to tops with concealed metal brackets at 16 inches and to walls with adhesive.

4. Calk space between backsplash and wall with sealant specified in Section 079200 - JOINT SEALANTS.
5. Do not field cut engineered-quartz and natural stone materials.

I. Touch up finishing work specified in this Section after installation of woodwork. Fill nail holes with matching filler where exposed.

3.3 ADJUSTING AND CLEANING

A. Repair damaged and defective woodwork, where possible, to eliminate functional and visual defects; where not possible to repair, replace woodwork. Adjust joinery for uniform appearance.

B. Clean, lubricate, and adjust hardware.

C. Clean woodwork on exposed and semi-exposed surfaces, using materials and methods recommended by manufacturer. Do not clean with abrasive or acidic cleaners. Touch up shop-applied finishes to restore damaged or soiled areas.

END OF SECTION

SECTION 078410

PENETRATION FIRESTOPPING

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Through-penetration firestopping systems for penetrations through fire-resistance-rated constructions, including both empty openings and openings containing penetrating items.
2. Installation Responsibility: Assign installation of through-penetration firestopping systems and fire-resistive joint systems in Project to a single qualified installer.

B. Related Work: The following items are not included in this Section and will be performed under the designated Sections:

1. Section 078440 - FIRE-RESISTIVE JOINT SYSTEMS for joints in or between fire-resistance-rated construction, at exterior curtain wall/floor intersections, and in smoke barriers.
2. Section 079200 - JOINT SEALANTS for standard joint sealants.

1.3 PERFORMANCE REQUIREMENTS

A. General: For penetrations through fire-resistance-rated constructions, including both empty openings and openings containing penetrating items, provide through-penetration firestopping systems that are produced and installed to resist spread of fire according to requirements indicated, resist passage of smoke and other gases, and maintain original fire-resistance rating of construction penetrated.

B. Penetrations in Fire-Resistance-Rated Walls: Provide penetration firestopping with ratings determined per ASTM E 814 or UL 1479, based on testing at a positive pressure differential of 0.01-inch wg (2.49 Pa).

1. Fire-resistance-rated walls include fire walls, fire-barrier walls, smoke-barrier walls and fire partitions.
2. F-Rating: Not less than the fire-resistance rating of constructions penetrated.

C. Penetrations in Horizontal Assemblies: Provide penetration firestopping with ratings determined per ASTM E 814 or UL 1479, based on testing at a positive pressure differential of 0.01-inch wg (2.49 Pa).

1. Horizontal assemblies include floors, floor/ceiling assemblies and ceiling membranes of

roof/ceiling assemblies.
2. F-Rating: At least 1 hour, but not less than the fire-resistance rating of constructions penetrated.
3. T-Rating: At least 1 hour, but not less than the fire-resistance rating of constructions penetrated except for floor penetrations within the cavity of a wall.

D. Penetrations in Smoke Barriers: Provide penetration firestopping with ratings determined per UL 1479.

1. L-Rating: Not exceeding 5.0 cfm/sq. ft. (0.025 cu. m/s per sq. m) of penetration opening at 0.30-inch wg (74.7 Pa) at both ambient and elevated temperatures.

E. Exposed Penetration Firestopping:

1. Provide products with flame-spread and smoke-developed indexes of less than 25 and 450, respectively, as determined per ASTM E 84.
2. For through-penetration firestopping systems exposed to view, traffic, moisture, and physical damage, provide products that, after curing, do not deteriorate when exposed to these conditions both during and after construction.
   a. For piping penetrations for plumbing and wet-pipe sprinkler systems, provide moisture-resistant through-penetration firestopping systems demonstrating no evidence of water leakage when tested according to UL 1479.
   b. For floor penetrations with annular spaces exceeding 4 inches in width and exposed to possible loading and traffic, provide firestopping systems capable of supporting floor loads involved, either by installing floor plates or by other means.

F. For penetrations involving insulated piping, provide through-penetration firestopping systems not requiring removal of insulation.

1.4 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings: For each through-penetration firestopping system, show each type of construction condition penetrated, relationships to adjoining construction, and type of penetrating item. Include firestop design designation of qualified testing and inspecting agency that evidences compliance with requirements for each condition indicated.

1. Submit documentation, including illustrations, from a qualified testing and inspecting agency that is applicable to each through-penetration firestopping system configuration for construction and penetrating items.

C. Through-Penetration Firestop System Schedule: Indicate locations of each through-penetration firestopping system, along with the following information:

1. Types of penetrating items.
2. Types of constructions penetrated, including fire-resistance ratings and, where applicable, thicknesses of construction penetrated.
3. Through-penetration firestopping systems for each location identified by firestop design designation of qualified testing and inspecting agency.

D. Qualification Data: For Installer.

1.5 QUALITY ASSURANCE

A. Source Limitations: Obtain through-penetration firestopping systems, for each kind of penetration and construction condition indicated, through one source from a single manufacturer.

B. Installer Qualifications: Either a firm that has been approved by FMG according to FM Approval 4991, "Approval Standard for Firestop Contractors" or a firm experienced in installing through-penetration firestopping systems similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction of a minimum of five projects with a record of successful performance.

1. Qualifications include having the necessary experience, staff, and training to install manufacturer's products per specified requirements.

C. Fire-Test-Response Characteristics: Provide through-penetration firestopping systems that comply with the following requirements and those specified in Part 1 "Performance Requirements" Article:

1. Firestopping tests are performed by a qualified testing and inspecting agency. A qualified testing and inspecting agency is UL or another agency performing testing and follow-up inspection services for firestopping systems acceptable to authorities having jurisdiction.
2. Through-penetration firestopping systems are identical to those tested per testing standard referenced in "Part 1 Performance Requirements" Article. Provide rated systems complying with the following requirements:
   a. Through-penetration firestopping system products bear classification marking of qualified testing and inspecting agency.
   b. Through-penetration firestopping systems correspond to those indicated by reference to through-penetration firestopping system designations listed in the UL “Fire Resistance Directory.”

D. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver through-penetration firestopping system products to Project site in original, unopened containers or packages with intact and legible manufacturers' labels identifying product and manufacturer, date of manufacture, lot number, shelf life if applicable, qualified testing and inspecting agency's classification marking applicable to Project, curing time, and mixing instructions for multicomponent materials.

B. Store and handle materials for through-penetration firestopping systems to prevent their deterioration or damage due to moisture, temperature changes, contaminants, or other causes.

1.7 PROJECT CONDITIONS

A. Environmental Limitations: Do not install firestopping systems when ambient or substrate temperatures are outside limits permitted by through-penetration firestopping system manufacturers or when substrates are wet due to rain, frost, condensation, or other causes.

B. Install and cure firestopping materials per manufacturer's written instructions using natural means of ventilation or, where this is inadequate, forced-air circulation.

1.8 COORDINATION

A. Jobsite conditions of each through-penetration firestopping system must meet all details of the UL-Classified System selected. If jobsite conditions do not match any UL-classified systems, contact firestop manufacturer for alternative systems or Engineer Judgment Drawings.

1. Verify that the schedule is current at the time of construction, and that each referenced system is suitable for the intended application.

B. Coordinate work with other trades to assure that penetration-opening sizes are appropriate for penetrant locations.

C. Coordinate construction of openings and penetrating items to ensure that through-penetration firestopping systems are installed according to specified requirements.

D. Coordinate sizing of sleeves, openings, core-drilled holes, and cut openings to accommodate through-penetration firestopping systems.

E. Do not cover up through-penetration firestopping system installations that will become concealed behind other construction until each installation has been examined building inspector, if required by authorities having jurisdiction.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products and firestopping systems that may be incorporated into the Work include, but are not limited to the following:

1. Hilti, Inc.
2. RectorSeal.
3. Specified Technologies, Inc. (STI).
4. Tremco.
5. 3M; Fire Protection Products Division.

2.2 FIRESTOPPING MATERIALS

A. VOC Content: Penetration firestopping sealants and sealant primers shall comply with the following limits for VOC content:

1. Sealant Primers for Nonporous Substrates: 250 g/L.
2. Sealant Primers for Porous Substrates: 775 g/L.
3. Methylene chloride and perchloroethylene may not be intentionally added to sealants.

B. Compatibility: Provide through-penetration firestopping systems that are compatible with one

another; with the substrates forming openings; and with the items, if any, penetrating through-penetration firestopping systems, under conditions of service and application, as demonstrated by through-penetration firestopping system manufacturer based on testing and field experience.

C. Materials: Provide through-penetration firestopping systems containing primary materials and fill materials which are part of the tested assemblies indicated in the approved Through-Penetration Firestop System Schedule submittal. Fill materials are those referred to in directories of referenced testing and inspecting agencies as "fill," "void," or "cavity" materials.

1. Available Products: Subject to compliance with requirements, through-penetration firestopping products that may be incorporated into the Work include, but are not limited to the following:
   a. BioFireshield; RectorSeal Smoke and Acoustic Sealant.
   b. Hilti; CP 606 Flexible Firestop Sealant.
   c. Hilti; CP 653 BA Firestop Speed Sleeve.
   d. Hilti; FS-ONE MAX Intumescent Firestop Sealant.
   e. STI; SpecSeal LCI Intumescent Firestop Sealant.
   f. Tremco; TREMstop Acrylic.

D. Accessories: Provide components for each through-penetration firestopping system that are needed to install fill materials and to comply with Part 1 "Performance Requirements" Article. Use only components specified by through-penetration firestopping system manufacturer and approved by qualified testing and inspecting agency for firestopping systems indicated.

2.3 MIXING

A. For those products requiring mixing before application, comply with through-penetration firestopping system manufacturer's written instructions for accurate proportioning of materials, water (if required), type of mixing equipment, selection of mixer speeds, mixing containers, mixing time, and other items or procedures needed to produce products of uniform quality with optimum performance characteristics for application indicated.

PART 3 EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for opening configurations, penetrating items, substrates, and other conditions affecting performance of work.

1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning: Clean out openings immediately before installing through-penetration firestopping systems to comply with firestopping system manufacturer's written instructions and with the following requirements:

1. Remove from surfaces of opening substrates and from penetrating items foreign materials that could interfere with adhesion of through-penetration firestopping systems.
2. Clean opening substrates and penetrating items to produce clean, sound surfaces capable

of developing optimum bond with through-penetration firestopping systems. Remove loose particles remaining from cleaning operation.
3. Remove laitance and form-release agents from concrete.

B. Priming: Prime substrates where recommended in writing by through-penetration firestopping system manufacturer using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.

C. Taping: Use masking tape to prevent through-penetration firestopping systems from contacting adjoining surfaces that will remain exposed on completion of Work and that would otherwise be permanently stained or damaged by such contact or by cleaning methods used to remove smears from firestopping system materials. Remove tape as soon as possible without disturbing firestopping system's seal with substrates.

3.3 THROUGH-PENETRATION FIRESTOP SYSTEM INSTALLATION

A. General: Install through-penetration firestopping systems to comply with Part 1 "Performance Requirements" Article and with firestopping system manufacturer's written installation instructions and published drawings for products and applications indicated.

B. Install forming/damming/backing materials and other accessories of types required to support fill materials during their application and in the position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.

C. Install fill materials for firestopping systems by proven techniques to produce the following results:

1. Fill voids and cavities formed by openings, forming materials, accessories, and penetrating items as required to achieve fire-resistance ratings indicated.
2. Apply materials so they contact and adhere to substrates formed by openings and penetrating items.
3. For fill materials that will remain exposed after completing Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

3.4 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified independent testing and inspecting agency to perform field tests and inspections indicated below and prepare test reports, as required by 2015 IBC 1705.17 and 1705.17.1.

1. Independent inspecting agency shall comply with ASTM E 2174 requirements including those related to qualifications, conducting inspections, and preparing test reports
2. Cooperate with field quality control personnel. Allow inspectors access to scaffolding and work areas, as needed to perform inspections.

B. Repair or replace work where test results and inspections indicate that it does not comply with specified requirements.

C. Additional testing and inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

D. Proceed with enclosing through-penetration firestopping systems with other construction only after inspection reports are issued and firestop installations comply with requirements.

3.5 CLEANING AND PROTECTING

A. Clean excess materials adjacent to openings as Work progresses by methods and with cleaning materials that are approved in writing by through-penetration firestopping system manufacturers and that do not damage materials in which openings occur.

B. Provide final protection and maintain conditions during and after installation that ensure that through-penetration firestopping systems are without damage or deterioration at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated through-penetration firestopping systems immediately and install new materials to produce systems complying with specified requirements.

END OF SECTION

This page left intentionally blank.

SECTION 078440

FIRE-RESISTIVE JOINT SYSTEMS

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the Work of this Section, including but not limited to fire-resistive joint systems for the following:

1. Floor-to-floor joints.
2. Floor-to-wall joints.
3. Head-of-wall joints.
4. Wall-to-wall joints.
5. Perimeter fire-resistive joint systems consisting of floor-to-wall joints between perimeter edge of fire-resistance-rated floor assemblies and exterior curtain walls.

B. Related Work: The following items are not included in this Section and will be performed under the designated Sections:

1. Section 078410 - PENETRATION FIRESTOPPING for firestopping.
2. Division 21 - FIRE SUPPRESSION for fire-protection piping penetrations.
3. Division 22 - PLUMBING for piping penetrations.
4. Division 23 - HEATING, VENTILATING AND AIR CONDITIONING for duct and piping penetrations.
5. Division 26 - ELECTRICAL for cable and conduit penetrations.

1.3 PERFORMANCE REQUIREMENTS

A. General: Provide fire-resistive joint systems that are produced and installed to resist spread of fire according to requirements indicated, resist passage of smoke and other gases, and maintain original fire-resistance rating of assembly in which fire-resistive joint systems are installed.

B. For fire-resistive systems exposed to view, provide products with flame-spread and smoke-developed indexes of less than 25 and 450, respectively, as determined per ASTM E 84.

1.4 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings: For each fire-resistive joint system, show each kind of construction condition in

which joints are installed; also show relationships to adjoining construction. Include fire-resistive joint system design designation of testing and inspecting agency acceptable to authorities having jurisdiction that demonstrates compliance with requirements for each condition indicated.

1. Submit documentation, including illustrations, from a qualified testing and inspecting agency that is applicable to each fire-resistive joint system configuration for construction and penetrating items.

C. Fire-Resistive Joint Systems Schedule: For each fire-resistive joint system. Include location and design designation of qualified testing agency.

1. Where Project conditions require modification to a qualified testing agency's illustration for a particular fire-resistive joint system condition, submit illustration, with modifications marked, approved by fire-resistive joint system manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly.

D. Product Certificates: For each type of fire-resistive joint system, signed by product manufacturer.

E. Qualification Data: For Installer.

F. Field quality-control test reports.

G. Research/Evaluation Reports: For each type of fire-resistive joint system.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: A firm experienced in installing through-penetration fire stop systems similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction of a minimum of five projects with a record of successful performance. Qualifications include having the necessary experience, staff, and training to install manufacturer's products per specified requirements. Evidence of FMG 4991 approval is acceptable for installer qualifications, but not mandatory.

B. Installation Responsibility: Assign installation of through-penetration firestop systems and fire-resistive joint systems in Project to a single qualified installer.

C. Source Limitations: Obtain fire-resistive joint systems, for each kind of joint and construction condition indicated, through one source from a single manufacturer.

D. Fire-Test-Response Characteristics: Provide fire-resistive joint systems that comply with the following requirements and those specified in Part 1 "Performance Requirements" Article:

1. Fire-resistance tests are performed by a qualified testing and inspecting agency. A qualified testing and inspecting agency is UL or another agency performing testing and follow-up inspection services for fire-resistive joint systems acceptable to authorities having jurisdiction.
2. Fire-resistive joint systems are identical to those tested per methods indicated in Part 1 "Performance Requirements" Article and comply with the following:

a. Fire-resistive joint system products bear classification marking of qualified testing and inspecting agency.
b. Fire-resistive joint systems correspond to those indicated by referencing system designations of the qualified testing and inspecting agency.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver fire-resistive joint system products to Project site in original, unopened containers or packages with qualified testing and inspecting agency's classification marking applicable to Project and with intact and legible manufacturers' labels identifying product and manufacturer, date of manufacture, lot number, shelf life, curing time, and mixing instructions for multicomponent materials.

B. Store and handle materials for fire-resistive joint systems to prevent their deterioration or damage due to moisture, temperature changes, contaminants, or other causes.

1.7 PROJECT CONDITIONS

A. Environmental Limitations: Do not install fire-resistive joint systems when ambient or substrate temperatures are outside limits permitted by fire-resistive joint system manufacturers or when substrates are wet due to rain, frost, condensation, or other causes.

B. Ventilate fire-resistive joint systems per manufacturer's written instructions by natural means or, if this is inadequate, forced-air circulation.

1.8 COORDINATION

A. Coordinate construction of joints to ensure that fire-resistive joint systems are installed according to specified requirements.

B. Coordinate sizing of joints to accommodate fire-resistive joint systems.

C. Do not cover up through-penetration firestop system installations that will become concealed behind other construction until each installation has been examined building inspector, if required by authorities having jurisdiction.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Available Products: Subject to compliance with requirements, fire-resistive joint systems that may be incorporated into the Work include, but are not limited to the following:

1. Hilti, Inc.
2. Metacaulk; RectorSeal Corporation.
3. Specified Technologies, Inc. (STI).
4. 3M; Fire Protection Products Division.

2.2 FIRE-RESISTIVE JOINT SYSTEMS

A. Low-Emitting Materials: Fire-resistive joint system sealants shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

B. VOC Content: Provide fire-resistive joint system sealants that comply with the following limits for VOC content:

1. Architectural Sealants: 250 g/L.
2. Sealant Primers for Nonporous Substrates: 250 g/L.
3. Sealant Primers for Porous Substrates: 775 g/L.
4. Methylene chloride and perchloroethylene may not be intentionally added to sealants.

C. General: Where required, provide fire-resistive joint systems that are produced and installed to resist spread of fire according to requirements indicated, resist passage of smoke and other gases, and maintain original fire-resistance rating of assemblies in or between which fire-resistive joint systems are installed. Fire-resistive joint systems shall accommodate building movements without impairing their ability to resist the passage of fire and hot gases.

D. Joints in or between Fire-Resistance-Rated Construction: Provide fire-resistive joint systems with ratings determined per ASTM E 1966 or UL 2079.

E. Joints at Exterior Curtain-Wall/Floor Intersections: Provide fire-resistive joint systems with rating determined by ASTM E 119 based on testing at a positive pressure differential of 0.01-inch wg (2.49 Pa) or ASTM E 2307.

1. Fire-Resistance Rating: Equal to or exceeding the fire-resistance rating of the floor assembly.

F. Joints in Smoke Barriers: Provide fire-resistive joint systems with ratings determined per UL 2079.

1. L-Rating: Not exceeding 5.0 cfm/ft (0.00775 cu. m/s x m) of joint at 0.30 inch wg (74.7 Pa) at both ambient and elevated temperatures.

G. Compatibility: Provide fire-resistive joint systems that are compatible with joint substrates, under conditions of service and application, as demonstrated by fire-resistive joint system manufacturer based on testing and field experience.

H. Accessories: Provide components of fire-resistive joint systems, including primers and forming materials, that are needed to install fill materials and to comply with Part 1 "Performance Requirements" Article. Use only components specified by fire-resistive joint system manufacturer and approved by the qualified testing and inspecting agency for systems indicated.

PART 3 EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for joint configurations, substrates, and other conditions affecting performance of work.

1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning: Clean joints immediately before installing fire-resistive joint systems to comply with fire-resistive joint system manufacturer's written instructions and the following requirements:

1. Remove from surfaces of joint substrates foreign materials that could interfere with adhesion of fill materials.
2. Clean joint substrates to produce clean, sound surfaces capable of developing optimum bond with fill materials. Remove loose particles remaining from cleaning operation.
3. Remove laitance and form-release agents from concrete.

B. Priming: Prime substrates where recommended in writing by fire-resistive joint system manufacturer using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.

C. Masking Tape: Use masking tape to prevent fill materials of fire-resistive joint system from contacting adjoining surfaces that will remain exposed on completion of Work and that would otherwise be permanently stained or damaged by such contact or by cleaning methods used to remove smears from fire-resistive joint system materials. Remove tape as soon as possible without disturbing fire-resistive joint system's seal with substrates or damaging adjoining surfaces.

3.3 INSTALLATION

A. General: Install fire-resistive joint systems to comply with Part 1 "Performance Requirements" Article and fire-resistive joint system manufacturer's written installation instructions for products and applications indicated.

B. Install forming/packing/backing materials and other accessories of types required to support fill materials during their application and in position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.

C. Install fill materials for fire-resistive joint systems by proven techniques to produce the following results:

1. Fill voids and cavities formed by openings and forming/packing/backing materials as required to achieve fire-resistance ratings indicated.
2. Apply fill materials so they contact and adhere to substrates formed by joints.
3. For fill materials that will remain exposed after completing Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

3.4 FIELD QUALITY CONTROL

A. Inspecting Agency: Owner will engage a qualified testing agency to perform tests and inspections and prepare test reports, as required by 2015 IBC 1705.17 and 1705.17.2. Independent inspecting agency shall comply with ASTM E 2393 requirements including those related to qualifications, conducting inspections, and preparing test reports.

B. Testing Services: Inspecting of completed installations of fire-resistive joint systems shall take place in successive stages as installation of fire-resistive joint systems proceeds. Do not proceed with installation of joint systems for the next area until inspecting agency determines completed work shows compliance with requirements.

1. Inspecting agency shall state in each report whether inspected fire-resistive joint systems comply with or deviate from requirements.

C. Remove and replace fire-resistive joint systems where inspections indicate that they do not comply with specified requirements.

D. Additional inspecting, at Contractor's expense, will be performed to determine compliance of replaced or additional work with specified requirements.

E. Proceed with enclosing fire-resistive joint systems with other construction only after inspection reports are issued and fire-resistive joint systems comply with requirements.

3.5 CLEANING AND PROTECTING

A. Clean off excess fill materials adjacent to joints as Work progresses by methods and with cleaning materials that are approved in writing by fire-resistive joint system manufacturers and that do not damage materials in which openings occur.

B. Provide final protection and maintain conditions during and after installation that ensure fire-resistive joint systems are without damage or deterioration at time of Substantial Completion. If damage or deterioration occurs despite such protection, cut out and remove damaged or deteriorated fire-resistive joint systems immediately and install new materials to produce fire-resistive joint systems complying with specified requirements.

END OF SECTION

SECTION 079200

JOINT SEALANTS

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Joint sealants and fillers, at exterior and interior.

1.3 PERFORMANCE REQUIREMENTS

A. Provide elastomeric joint sealants that establish and maintain watertight and airtight continuous joint seals without staining or deteriorating joint substrates.

B. Provide joint sealants for interior applications that establish and maintain airtight and water-resistant continuous joint seals without staining or deteriorating joint substrates.

1.4 SUBMITTALS

A. Product Data: For each product indicated.

B. Samples for Verification: For each type and color of joint sealant required, provide Samples with joint sealants in 1/2-inch- wide joints formed between two 6-inch-long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.

C. Joint-Sealant Schedule: Include the following information:

1. Joint-sealant application, joint location, and designation.
2. Joint-sealant manufacturer and product name.
3. Joint-sealant formulation.
4. Joint-sealant color.

D. Qualification Data: For Installer and qualified testing agency.

E. Product Test Reports: Based on comprehensive testing of product formulations performed by a qualified testing agency, indicating that sealants comply with requirements.

F. Preconstruction Field Test Reports: Indicate which sealants and joint preparation methods resulted in optimum adhesion to joint substrates based on preconstruction testing specified in "Quality Assurance" Article.

G. Compatibility and Adhesion Test Reports: From sealant manufacturer, indicating the following:

1. Materials forming joint substrates and joint-sealant backings have been tested for compatibility and adhesion with joint sealants.
2. Interpretation of test results and written recommendations for primers and substrate preparation needed for adhesion.

H. Field Test Report Log: For each elastomeric sealant application.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: Manufacturer's authorized Installer who is approved or licensed for installation of elastomeric sealants required for this Project.

B. Product Testing: Test joint sealants using a qualified testing agency.

1. Testing Agency Qualifications: Qualified according to ASTM C 1021 to conduct the testing indicated.

C. Source Limitations: Obtain each type of joint sealant through one source from a single manufacturer.

D. Preconstruction Compatibility and Adhesion Testing: Submit to joint-sealant manufacturers, for testing indicated below, samples of materials that will contact or affect joint sealants.

1. Use manufacturer's standard test method to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of joint sealants to joint substrates.
   a. Adhesion Testing: Use ASTM C 794 to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of joint sealants to joint substrates.
   b. Compatibility Testing: Use ASTM C 1087 to determine sealant compatibility when in contact with joint sealant backing and glazing and gasket materials.
2. Schedule sufficient time for testing and analyzing results to prevent delaying the Work.
3. For materials failing tests, obtain joint-sealant manufacturer's written instructions for corrective measures including use of specially formulated primers.
4. Testing will not be required if joint-sealant manufacturers submit joint preparation data that are based on previous testing of current sealant products for adhesion to, and compatibility with, joint substrates and other materials matching those submitted.

E. Preconstruction Field-Adhesion Testing: Before installing elastomeric sealants, field test their adhesion to Project joint substrates as follows:

1. Locate test joints where indicated on Project or, if not indicated, as directed by Architect.
2. Conduct field tests for each application indicated below:
   a. Each type of elastomeric sealant and joint substrate indicated.
   b. Each type of nonelastomeric sealant and joint substrate indicated.
3. Notify Architect seven days in advance of dates and times when test joints will be erected.

a. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C 1193.
   1). For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.

4. Report whether sealant in joint connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each type of product and joint substrate. For sealants that fail adhesively, retest until satisfactory adhesion is obtained.
5. Evaluation of Preconstruction Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing, in absence of other indications of noncompliance with requirements, will be considered satisfactory. Do not use sealants that fail to adhere to joint substrates during testing.

F. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01.

1.6 PROJECT CONDITIONS

A. Do not proceed with installation of joint sealants under the following conditions:

1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
2. When joint substrates are wet.
3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.

1.7 WARRANTY

A. Special Installer's Warranty: Installer's standard form in which Installer agrees to repair or replace elastomeric joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

B. Special Manufacturer's Warranty: Manufacturer's standard form in which elastomeric sealant manufacturer agrees to furnish elastomeric joint sealants to repair or replace those that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

C. Special warranties specified in this Article exclude deterioration or failure of joint sealants from the following:

1. Movement of the structure caused by stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.
2. Disintegration of joint substrates from natural causes exceeding design specifications.
3. Mechanical damage caused by individuals, tools, or other outside agents.
4. Changes in sealant appearance caused by accumulation of dirt or other atmospheric contaminants.

PART 2 PRODUCTS

2.1 MATERIALS, GENERAL

A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by sealant manufacturer, based on testing and field experience.

B. Colors of Exposed Joint Sealants: Provide colors as selected by the Architect from manufacturer's full range of standard and custom colors; maximum of five colors, three standard colors and two custom colors.

2.2 JOINT SEALANTS

A. Elastomeric Sealants: Comply with ASTM C 920 and other requirements indicated for each liquid-applied chemically curing sealant specified, including those referencing ASTM C 920 classifications for type, grade, class, and uses related to exposure and joint substrates.

B. Stain-Test-Response Characteristics: Elastomeric sealants shall be nonstaining to porous substrates. Provide products that have undergone testing according to ASTM C 1248 and have not stained porous joint substrates indicated for Project.

C. Suitability for Contact with Food: Where elastomeric sealants are indicated for joints that will come in repeated contact with food, provide products that comply with 21 CFR 177.2600 or ANSI/NSF Standard 51.

D. Exterior Silicone Sealant, Single-Component Neutral-Curing Type: ASTM C 920, Type S, Grade NS, Class 50, Use NT, M, G, A.

1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
   a. Dow Corning Corporation; 790.
   b. GE Silicones; SilPruf LM SCS2700.
   c. Pecora Corporation; 864 NST (low modulus type).
   d. Tremco Inc.; Spectrem 1.
2. Extent of Use: Exterior joints in vertical and soffit surfaces.

E. Exterior Urethane Sealant, Multicomponent Pourable (Self-Leveling) Type for Pedestrian Traffic: ASTM C 920, Type M, Grade P, Class 25, Use T, M, & O.

1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
   a. MAPEI Corporation; Mapeflex P2 SL.
   b. Pecora Corporation; Urexpan NR-200.
   c. Sika; Sikaflex-2c SL.
   d. Tremco Inc.; THC-901.
2. Extent of Use: Exterior joints in horizontal surfaces.

F. Interior Sanitary Silicone Sealant, Single-Component Mildew-Resistant, Acid-Curing (Acetoxy) Type: ASTM C 920, Type S, Grade NS, Class 25, Use NT, G, A, and O.

1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
   a. GE Silicones; Sanitary SCS1700.
   b. Pecora; 898 NST.
   c. Tremco; Tremsil 200.
2. Extent of Use: Interior sanitary joints at toilet rooms, kitchens, and other wet areas.

G. Interior Acrylic Latex Sealant: Acrylic latex or siliconized acrylic latex, ASTM C 834, Type OP, Grade NF; water-based (solvent-free) products.

1. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:
   a. Pecora Corporation; AC-20+ Silicone.
   b. Sherwin-Williams (S-W); Powerhouse 1100A.
   c. Tremco Inc.; Tremflex 834.
2. Extent of Use: Interior non-moving joints.

2.3 JOINT-SEALANT BACKING

A. Sealant Backing Material, General: Nonstaining; compatible with joint substrates, sealants, primers, and other joint fillers; and approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.

B. Cylindrical Sealant Backings: ASTM C 1330, Type B (bicellular material with a surface skin) or other type, as approved in writing by joint-sealant manufacturer for joint application indicated, and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.

1. Basis of Design: Armacell Canada Inc.; ITP Standard Backer Rod.

C. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint where such adhesion would result in sealant failure. Provide self-adhesive tape where applicable.

2.4 MISCELLANEOUS MATERIALS

A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.

B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.

C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

PART 3 EXECUTION

3.1 EXAMINATION

A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting joint-sealant performance.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
2. Clean porous joint substrate surfaces by brushing, grinding, blast cleaning, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include concrete, masonry, unglazed surfaces of ceramic tile, and exterior insulation and finish systems.
3. Remove laitance and form-release agents from concrete.
4. Clean nonporous surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following metal, glass, porcelain enamel, and glazed surfaces of ceramic tile.

B. Joint Priming: Prime joint substrates, where recommended in writing by joint-sealant manufacturer, based on preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.

C. Masking Tape: Use masking tape where required to prevent contact of sealant with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

3.3 INSTALLATION OF JOINT SEALANTS

A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.

B. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.

C. Install sealant backings of type indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.

1. Do not leave gaps between ends of sealant backings.
2. Do not stretch, twist, puncture, or tear sealant backings.
3. Remove absorbent sealant backings that have become wet before sealant application and replace them with dry materials.

D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.

E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:

1. Place sealants so they directly contact and fully wet joint substrates.
2. Completely fill recesses in each joint configuration.
3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.

F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.

1. Remove excess sealant from surfaces adjacent to joints.
2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
3. Provide concave joint configuration per Figure 5A in ASTM C 1193, unless otherwise indicated.

3.4 FIELD QUALITY CONTROL

A. Field-Adhesion Testing: Field test joint-sealant adhesion to joint substrates as follows:

1. Extent of Testing: Test completed and cured sealant joints as follows:
   a. Perform one test for each 1000 feet of joint length thereafter or one test per each floor per elevation.
2. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C1193 or Method A, Tail Procedure, in ASTM C1521.
   a. For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.
3. Inspect tested joints and report on the following:
   a. Whether sealants filled joint cavities and are free of voids.
   b. Whether sealant dimensions and configurations comply with specified requirements.
   c. Whether sealants in joints connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. Compare these results to determine if adhesion complies with sealant manufacturer's field-adhesion hand-pull test criteria.
4. Record test results in a field-adhesion-test log. Include dates when sealants were installed, names of persons who installed sealants, test dates, test locations, whether joints were primed, adhesion results and percent elongations, sealant material, sealant configuration, and sealant dimensions.

5. Repair sealants pulled from test area by applying new sealants following same procedures used originally to seal joints. Ensure that original sealant surfaces are clean and that new sealant contacts original sealant.

B. Evaluation of Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

3.5 CLEANING

A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

3.6 PROTECTION

A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out and remove damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

END OF SECTION

SECTION 081113

HOLLOW METAL DOORS AND FRAMES

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Standard hollow-metal steel doors and frames, exterior.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 042000 - UNIT MASONRY for building anchors into masonry construction.
2. Section 087100 - DOOR HARDWARE for door hardware, including thresholds and weatherstripping.
3. Section 088000 - GLAZING for glazed lites.
4. Section 099000 - PAINTING AND COATING for field painting steel doors and frames.

1.3 DEFINITIONS

A. Minimum Thickness: Minimum thickness of base metal without coatings in accordance with NAAMM-HMMA 803 or ANSI/SDI A250.8.

1.4 SUBMITTALS

A. Product Data: For each product specified.

1. Include construction details, material descriptions, core descriptions, label compliance, fire-resistance rating, temperature-rise ratings, and finishes.

B. Shop Drawings:

1. Elevations of each door design.
2. Details of doors, including vertical and horizontal edge details and metal thicknesses.
3. Frame details for each frame type, including dimensioned profiles and metal thicknesses.
4. Locations of reinforcement and preparations for hardware.
5. Details of each different wall opening condition.
6. Details of anchorages, joints, field splices, and connections.
7. Details of accessories.
8. Details of moldings, removable stops, and glazing.
9. Details of conduit and preparations for power, signal, and control systems.

C. Product Schedule: For hollow-metal doors and frames, prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with final door hardware schedule.

D. Qualification Data: For Installer and door inspector.

E. Product Test Reports: For each type of fire-rated hollow-metal door and frame assembly for tests performed by a qualified testing agency indicating compliance with performance requirements.

F. Field quality-control reports.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: An employer of workers trained and approved by manufacturer.

B. Door Inspector Qualifications:

1. Fire-Rated Door Inspector Qualifications: Inspector for field quality-control inspections of fire-rated door assemblies shall comply with qualifications set forth in NFPA 80, Section 5.2.3.1.
2. Egress Door Inspector Qualifications: Inspector for field quality-control inspections of egress door assemblies shall comply with qualifications set forth in NFPA 101, Section 7.2.1.15.4.

C. Source Limitations: Obtain standard steel doors and frames through one source from a single manufacturer.

D. Fire-Rated Door, Assemblies: Assemblies complying with NFPA 80 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire-protection ratings and temperature-rise limits indicated, based on testing at positive pressure according to NFPA 252 or UL 10C.

1. Smoke- and Draft-Control Assemblies: Listed and labeled for smoke and draft control by a qualified testing agency acceptable to authorities having jurisdiction, based on testing according to UL 1784 and installed in compliance with NFPA 105.
2. Temperature-Rise Limit: Where indicated on Drawings, provide doors that have a maximum transmitted temperature end point of not more than 450 deg F above ambient after 30 minutes of standard fire-test exposure.

E. Fire-Rated, Borrowed-Light Assemblies (Including Sidelights and Transoms): Complying with NFPA 80 and listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction for fire-protection ratings indicated, based on testing according to NFPA 257 or UL 9.

F. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver doors and frames palletized, wrapped, or crated to provide protection during transit and Project-site storage. Do not use nonvented plastic.

B. Deliver welded frames with two removable spreader bars across bottom of frames, tack welded to jambs and mullions.

C. Store doors and frames vertically under cover at Project site with head up. Place on minimum 4-inch-high wood blocking. Provide minimum 1/4-inch space between each stacked door to permit air circulation.

1.7 PROJECT CONDITIONS

A. Field Measurements: Verify actual dimensions of openings by field measurements before fabrication.

1.8 COORDINATION

A. Coordinate anchorage installation for hollow metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.

B. Coordinate requirements for installation of door hardware, electrified door hardware, and access control and security systems.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Ceco Door Products; an ASSA ABLOY Group Company.
2. CURRIES Company; an ASSA ABLOY Group Company.
3. de LaFontaine.
4. Philipp Manufacturing Company.
5. Steelcraft; an ALLEGION (formerly Ingersoll-Rand) company.

2.2 MATERIALS

A. Cold-Rolled Steel Sheet: ASTM A 1008/A 1008M, Commercial Steel (CS), Type B; suitable for exposed applications.

B. Hot-Rolled Steel Sheet: ASTM A 1011/A 1011M, Commercial Steel (CS), Type B; free of scale, pitting, or surface defects; pickled and oiled.

C. Metallic-Coated, (Galvanized/Galvannealed) Steel Sheet: ASTM A 653/A 653M, Commercial Steel (CS), Type B; with minimum G60/A60 metallic coating.

D. Frame Anchors: ASTM A 879/A 879M, Commercial Steel (CS), 04Z coating designation; mill phosphatized.

1. For anchors built into exterior walls, steel sheet complying with ASTM A 1008/A 1008M or ASTM A 1011/A 1011M, hot-dip galvanized according to ASTM A 153/A 153M, Class B.

E. Inserts, Bolts, and Fasteners: Hot-dip galvanized according to ASTM A 153/A 153M.

F. Powder-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hollow metal frames of type indicated.

G. Insulation: As recommended by manufacturer.

H. Glazing: Comply with requirements in Section 088000 - GLAZING.

2.3 STANDARD STEEL DOORS

A. General: Provide doors of design indicated, not less than thickness indicated; fabricated with smooth surfaces, without visible joints or seams on exposed faces, unless otherwise indicated. Comply with ANSI A250.8.

1. Design: Flush panel.
2. Core Construction: Manufacturer's standard kraft-paper honeycomb, polystyrene, polyurethane, mineral-board, or vertical steel-stiffener core that produces doors complying with ANSI A250.8.

    a. Fire Door Core: As required to provide fire-protection and temperature-rise ratings indicated.
    b. Exterior Doors: Where indicated, provide doors fabricated with thermal-resistance value (R-value) of not less than 2.8 when tested according to ASTM C 1363.

3. Top and Bottom Edges: Closed with flush or inverted end closures or channels of same material as face sheets. Seal joints against water penetration.
4. Tolerances: Comply with SDI 117, "Manufacturing Tolerances for Standard Steel Doors and Frames."

B. Exterior Doors: Face sheets fabricated from metallic-coated (galvanized/galvannealed) steel sheet. Provide doors complying with requirements indicated below by referencing ANSI A250.8 for level and model and ANSI A250.4 for physical-endurance level:

1. Level 3 and Physical Performance Level A (Extra Heavy Duty), Model 2 (Seamless), 1-3/4 inches thick.
2. Face Sheets: 0.053 inches (16 ga) thick, min.

C. Hardware Reinforcement: Fabricate according to ANSI/SDI A250.6 with reinforcing plates from same material as door face sheets.

D. Fabricate concealed stiffeners and hardware reinforcement from either cold- or hot-rolled steel sheet.

2.4 STANDARD STEEL FRAMES

A. General: Comply with ANSI A250.8 and with details indicated for type and profile.

B. Exterior Frames: Fabricated from metallic-coated (galvanized/galvannealed) steel sheet.

1. Fabricate frames with full profile welded joints and thermal breaks.
2. Frames for Level 3 Steel Doors: 0.067-inch-thick (14 ga) steel sheet.

C. Hardware Reinforcement: Fabricate according to ANSI/SDI A250.6 with reinforcement plates from same material as frames.

2.5 FRAME ANCHORS

A. Jamb Anchors:

1. Masonry Type: Adjustable strap-and-stirrup or T-shaped anchors to suit frame size, not less than 0.042 inch thick, with corrugated or perforated straps not less than 2 inches wide by 10 inches long; or wire anchors not less than 0.177 inch thick.
2. Stud-Wall Type: Designed to engage stud, welded to back of frames; not less than 0.042 inch thick.
3. Compression Type for Drywall Slip-on Frames: Adjustable compression anchors.
4. Postinstalled Expansion Type for In-Place Concrete or Masonry: Minimum 3/8-inch- diameter bolts with expansion shields or inserts. Provide pipe spacer from frame to wall, with throat reinforcement plate, welded to frame at each anchor location.

B. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor.

1. Monolithic Concrete Slabs: Clip-type anchors, with two holes to receive fasteners.
2. Separate Topping Concrete Slabs (Underlayment): Adjustable-type anchors with extension clips, allowing not less than 2-inch height adjustment. Terminate bottom of frames at finish floor surface.

2.6 HOLLOW METAL PANELS

A. Provide hollow metal panels of same materials, construction, and finish as specified for adjoining hollow metal work.

2.7 STOPS AND MOLDINGS

A. Frames for Glazed Lites in Doors: 20 gauge thick, fabricated from steel.

1. Basis-of-Design: Anemostat Door Products; Anemostat LoPro Vision Lite Frame.

B. Loose Stops for Glazed Lites in Frames: Minimum 0.032 inch thick, fabricated from same material as frames in which they are installed.

2.8 FABRICATION

A. Fabricate hollow metal work to be rigid and free of defects, warp, or buckle. Accurately form metal to required sizes and profiles, with minimum radius for thickness of metal. Where practical, fit and assemble units in manufacturer's plant. To ensure proper assembly at Project site, clearly identify work that cannot be permanently factory assembled before shipment.

B. Tolerances: Fabricate hollow metal work to tolerances indicated in SDI 117.

C. Hollow Metal Doors:

1. Exterior Doors: Provide weep-hole openings in bottom of exterior doors to permit moisture to escape. Seal joints in top edges of doors against water penetration.
2. Glazed Lites: Factory cut openings in doors.
3. Astragals: Provide overlapping astragal on one leaf of pairs of doors where required by NFPA 80 for fire-performance rating or where indicated. Extend minimum 3/4 inch beyond edge of door on which astragal is mounted.

D. Hollow Metal Frames: Where frames are fabricated in sections due to shipping or handling limitations, provide alignment plates or angles at each joint, fabricated of same thickness metal as frames.

1. Full Profile Welded Frames at Fire-Rated Doors and Exterior Doors: Weld joints continuously; grind, fill, dress, and make smooth, flush, and not visible.
2. Interlocking (Knock-Down) Frames at 20-Minute-Rated Doors and Non-Rated Doors: Interlocking with visible seams.
3. Sidelight and Transom Bar Frames: Provide closed tubular members with no visible face seams or joints, fabricated from same material as doorframe. Fasten members at crossings and to jambs by butt welding.
4. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
5. Floor Anchors: Weld anchors to bottom of jambs and mullions with at least four spot welds per anchor.

6. Jamb Anchors: Provide number and spacing of anchors as follows:

    a. Masonry Type: Locate anchors not more than 18 inches from top and bottom of frame. Space anchors not more than 32 inches o.c. and as follows:

        1) Two anchors per jamb up to 60 inches high.
        2) Three anchors per jamb from 60 to 90 inches high.
        3) Four anchors per jamb from 90 to 120 inches high.
        4) Four anchors per jamb plus 1 additional anchor per jamb for each 24 inches or fraction thereof above 120 inches high.

    b. Stud-Wall Type: Locate anchors not more than 18 inches from top and bottom of frame. Space anchors not more than 32 inches o.c. and as follows:

        1) Three anchors per jamb up to 60 inches high.
        2) Four anchors per jamb from 60 to 90 inches high.
        3) Five anchors per jamb from 90 to 96 inches high.
        4) Five anchors per jamb plus 1 additional anchor per jamb for each 24 inches or fraction thereof above 96 inches high.
        5) Two anchors per head for frames above 42 inches wide and mounted in metal-stud partitions.

    c. Compression Type: Not less than two anchors in each jamb.
    d. Postinstalled Expansion Type: Locate anchors not more than 6 inches from top and bottom of frame. Space anchors not more than 26 inches o.c.

7. Door Silencers: Except on weather-stripped doors, drill stops to receive door silencers as follows. Keep holes clear during construction.

    a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.
    b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.

E. Hardware Preparation: Factory prepare hollow metal work to receive templated mortised hardware; include cutouts, reinforcement, mortising, drilling, and tapping according to the Door Hardware Schedule and templates furnished as specified in Section 087100 - DOOR HARDWARE.

1. Locate hardware as indicated, or if not indicated, according to ANSI/SDI A250.8.
2. Reinforce doors and frames to receive nontemplated, mortised and surface-mounted door hardware.
3. Comply with BHMA A156.115 for preparing hollow-metal doors and frames for hardware.

4. Coordinate locations of conduit and wiring boxes for electrical connections with Division 26 - ELECTRICAL.

F. Glazed Lites: Provide stops and moldings around glazed lites where indicated. Form corners of stops and moldings with butted or mitered hairline joints.

1. Provide stops and moldings flush with face of door, and with square stops unless otherwise indicated.
2. Multiple Glazed Lites: Provide fixed and removable stops and moldings, so that each glazed lite is capable of being removed independently.
3. Provide fixed frame moldings on outside of exterior and on secure side of interior doors and frames. Provide loose stops and moldings on inside of doors and frames.
4. Coordinate rabbet width between fixed and removable stops with type of glazing and type of installation indicated.
5. Provide stops for installation with countersunk flat- or oval-head machine screws spaced uniformly not more than 9 inches o.c. and not more than 2 inches o.c. from each corner.

2.9 STEEL FINISHES

A. Prime Finish: Apply manufacturer's standard epoxy primer immediately after cleaning and pretreating.

1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with ANSI/SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.
2. Refer to Section 099000 – PAINTING AND COATING for field-applied coating.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for embedded and built-in anchors to verify actual locations before frame installation.

C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Remove welded-in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces.

B. Prior to installation, adjust and securely brace welded hollow metal frames for squareness, alignment, twist, and plumbness to the following tolerances:

1. Squareness: Plus or minus 1/16 inch, measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
2. Alignment: Plus or minus 1/16 inch, measured at jambs on a horizontal line parallel to plane of wall.
3. Twist: Plus or minus 1/16 inch, measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
4. Plumbness: Plus or minus 1/16 inch, measured at jambs on a perpendicular line from head to floor.

C. Drill and tap doors and frames to receive nontemplated, mortised, and surface-mounted door hardware.

3.3 INSTALLATION

A. Install hollow metal work plumb, rigid, properly aligned, and securely fastened in place; comply with Drawings and manufacturer's written instructions.

B. Hollow Metal Frames: Comply with ANSI/SDI A250.11.

1. Set frames accurately in position, plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces, leaving surfaces smooth and undamaged.

a. At fire-protection-rated openings, install frames according to NFPA 80.
b. Where frames are fabricated in sections because of shipping or handling limitations, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces.
c. Install frames with removable glazing stops located on secure side of opening.
d. Remove temporary braces necessary for installation only after frames have been properly set and secured.
e. Check plumbness, squareness, and twist of frames as walls are constructed. Shim as necessary to comply with installation tolerances.

2. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor, and secure with postinstalled expansion anchors.

    a. Floor anchors may be set with power-actuated fasteners instead of postinstalled expansion anchors if so indicated and approved on Shop Drawings.

3. Metal-Stud Partitions: Solidly pack insulation behind frames.
4. Masonry Walls: Coordinate installation of frames to allow for filling space between frames and masonry with insulation.
5. Concrete Walls: Solidly fill space between frames and concrete with insulation.
6. In-Place Concrete or Masonry Construction: Secure frames in place with postinstalled expansion anchors. Countersink anchors, and fill and make smooth, flush, and invisible on exposed faces.
7. In-Place Gypsum Board Partitions: Secure frames in place with postinstalled expansion anchors through floor anchors at each jamb. Countersink anchors, and fill and make smooth, flush, and invisible on exposed faces.
8. Ceiling Struts: Extend struts vertically from top of frame at each jamb to overhead structural supports or substrates above frame unless frame is anchored to masonry or to other structural support at each jamb. Bend top of struts to provide flush contact for securing to supporting construction. Provide adjustable wedged or bolted anchorage to frame jamb members.
9. Installation Tolerances: Adjust hollow metal door frames for squareness, alignment, twist, and plumb to the following tolerances:

    a. Squareness: Plus or minus 1/16 inch, measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.
    b. Alignment: Plus or minus 1/16 inch, measured at jambs on a horizontal line parallel to plane of wall.
    c. Twist: Plus or minus 1/16 inch, measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
    d. Plumbness: Plus or minus 1/16 inch, measured at jambs at floor.

C. Hollow Metal Doors: Fit hollow metal doors accurately in frames, within clearances specified below. Shim as necessary.

1. Non-Fire-Rated Steel Doors: Comply with ANSI/SDI A250.8.
2. Fire-Rated Doors: Install doors with clearances according to NFPA 80.
3. Smoke-Control Doors: Install doors according to NFPA 105.

D. Glazing: Comply with hollow metal manufacturer's written instructions.

1. Secure stops with countersunk flat- or oval-head machine screws spaced uniformly not more than 9 inches o.c. and not more than 2 inches o.c. from each corner.

3.4 FIELD QUALITY CONTROL

A. Inspection Agency: Engage a qualified inspector to perform inspections and to furnish reports to Architect.

B. Inspections:

1. Fire-Rated Door Inspections: Inspect each fire-rated door in accordance with NFPA 80, Section 5.2.
2. Egress Door Inspections: Inspect each door equipped with panic hardware, each door equipped with fire exit hardware, each door located in an exit enclosure, each electrically controlled egress door, and each door equipped with special locking arrangements in accordance with NFPA 101, Section 7.2.1.15.

C. Repair or remove and replace installations where inspections indicate that they do not comply with specified requirements.

D. Reinspect repaired or replaced installations to determine if replaced or repaired door assembly installations comply with specified requirements.

E. Prepare and submit separate inspection report for each fire-rated door assembly indicating compliance with each item listed in NFPA 80 and NFPA 101.

3.5 ADJUSTING AND CLEANING

A. Final Adjustments: Check and readjust operating hardware items immediately before final inspection. Leave work in complete and proper operating condition. Remove and replace defective work, including hollow metal work that is warped, bowed, or otherwise unacceptable.

B. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.

C. Metallic-Coated (Galvanized/Galvannealed) Surface Touchup: Clean abraded areas and repair with galvanizing repair paint according to manufacturer's written instructions.

END OF SECTION

SECTION 083110

ACCESS DOORS AND FRAMES

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Access doors and frames for walls and ceilings.

1.3 SUBMITTALS

A. Product Data: For each type of access door and frame indicated. Include construction details, fire ratings, materials, individual components and profiles, and finishes.

B. Shop Drawings: Show fabrication and installation details of access doors and frames for each type of substrate. Include plans, elevations, sections, details, and attachments to other work.

C. Samples: For each door face material, at least 3 by 5 inches in size, in specified finish.

D. Access Door and Frame Schedule: Provide complete access door and frame schedule, including types, locations, sizes, latching or locking provisions, and other data pertinent to installation.

E. Ceiling Coordination Drawings: Reflected ceiling plans, drawn to scale, on which ceiling-mounted items including access doors and frames, lighting fixtures, diffusers, grilles, speakers, sprinklers, and special trim are shown and coordinated with each other.

1.4 QUALITY ASSURANCE

A. Source Limitations: Obtain each type of access door and frame through one source from a single manufacturer.

B. Fire-Rated Access Doors and Frames: Units complying with NFPA 80 that are identical to access door and frame assemblies tested for fire-test-response characteristics per the following test method and that are listed and labeled by UL or another testing and inspecting agency acceptable to authorities having jurisdiction:

1. NFPA 252 for vertical access doors and frames.
2. ASTM E 119 for horizontal access doors and frames.

C. Size Variations: Obtain Architect's acceptance of manufacturer's standard-size units, which may vary slightly from sizes indicated.

1.5 COORDINATION

A. Verification: Determine specific locations and sizes for access doors needed to gain access to concealed plumbing, mechanical, or other concealed work, and indicate in the schedule specified in "Submittals" Article.

PART 2 PRODUCTS

2.1 STEEL MATERIALS

A. Steel Plates, Shapes, and Bars: ASTM A 36/A 36M.

1. ASTM A 123/A 123M, for galvanizing steel and iron products.
2. ASTM A 153/A 153M, for galvanizing steel and iron hardware.

B. Steel Sheet: Electrolytic zinc-coated, ASTM A 879/A 879M with cold-rolled steel sheet substrate complying with ASTM A 1008/A 1008M, Commercial Steel (CS), exposed.

C. Steel Finishes: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.

1. Surface Preparation for Steel Sheet: Clean surfaces to comply with SSPC-SP 1, "Solvent Cleaning," to remove dirt, oil, grease, or other contaminants that could impair paint bond. Remove mill scale and rust, if present, from uncoated steel, complying with SSPC-SP 5/NACE No. 1, "White Metal Blast Cleaning," or SSPC-SP 8, "Pickling."
   a. Galvanizing Repair Paint: High-zinc-dust-content paint for regalvanizing welds in steel, complying with SSPC-Paint 20.
2. Factory-Primed Finish: Apply shop primer immediately after cleaning and pretreating.

D. Drywall Beads: Edge trim formed from 0.0299-inch zinc-coated steel sheet formed to receive joint compound and in size to suit thickness of gypsum board.

2.2 STAINLESS-STEEL MATERIALS

A. Rolled-Stainless-Steel Floor Plate: ASTM A 793, manufacturer's standard finish.

B. Stainless-Steel Sheet, Strip, Plate, and Flat Bars: ASTM A 666, Type 316. Remove tool and die marks and stretch lines or blend into finish.

1. Finish: Directional Satin Finish, No. 4.

2.3 ACCESS DOORS AND FRAMES FOR WALLS AND CEILINGS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Acudor Products, Inc.
2. Babcock-Davis.
3. Dur-Red Products.
4. JL Industries (a division of Activar Construction Products Group).
5. Karp Associates, Inc.
6. Larsen's Manufacturing Company.
7. Milcor Inc.
8. Nystrom, Inc.

B. Flush Access Doors and Trimless Frames: Fabricated from steel sheet at typical areas and from stainless-steel sheet at toilet and wet areas.

1. Locations: Wall and ceiling surfaces.
2. Door: Minimum 0.060-inch-thick sheet metal, set flush with surrounding finish surfaces.
3. Frame: Minimum 0.060-inch-thick sheet metal with drywall bead flange.
4. Hinges: Continuous piano.
5. Lock: Cylinder.
    a. Lock Preparation: Prepare door panel to accept cylinder specified in Section 087100, DOOR HARDWARE.

C. Recessed Access Doors and Trimless Frames: Fabricated from steel sheet at typical areas and from stainless-steel sheet at toilet and wet areas.

1. Locations: Wall and ceiling surfaces.
2. Door: Minimum 0.060-inch-thick sheet metal in the form of a pan recessed 5/8 inch for gypsum board infill.
3. Frame: Minimum 0.060-inch-thick sheet metal with drywall bead for gypsum board surfaces.
4. Hinges: Concealed pivoting rod hinge.
5. Lock: Cylinder.
    a. Lock Preparation: Prepare door panel to accept cylinder specified in Section 087100, DOOR HARDWARE.

D. Fire Rated, Uninsulated, Flush Access Doors and Frames with Exposed Trim: Fabricated from steel at typical areas and from stainless-steel sheet at toilets and wet areas.

1. Locations: Wall surfaces.
2. Fire-Resistance Rating: Not less than that of adjacent construction.
3. Door: Minimum 0.060-inch-thick sheet metal, flush construction.
4. Frame: Minimum 0.060-inch-thick sheet metal with 1-inch-wide, surface-mounted trim.
5. Hinges: Continuous piano.
6. Automatic Closer: Spring type.
7. Lock: Self-latching device with cylinder lock.
    a. Lock Preparation: Prepare door panel to accept cylinder specified in Section 087100, DOOR HARDWARE

2.4 FABRICATION

A. General: Provide access door and frame assemblies manufactured as integral units ready for installation.

B. Metal Surfaces: For metal surfaces exposed to view in the completed Work, provide materials with smooth, flat surfaces without blemishes. Do not use materials with exposed pitting, seam marks, roller marks, rolled trade names, or roughness.

C. Doors and Frames: Grind exposed welds smooth and flush with adjacent surfaces. Furnish attachment devices and fasteners of type required to secure access panels to types of supports indicated.

1. For trimless frames with drywall bead, provide edge trim for gypsum board and gypsum base securely attached to perimeter of frames.
2. For trimless frames with plaster bead for full-bed plaster applications, provide zinc-coated expanded metal lath and exposed casing bead welded to perimeter of frames.
3. Provide mounting holes in frames for attachment of units to metal or wood framing.
4. Provide mounting holes in frame for attachment of masonry anchors.

D. Recessed Access Doors: Form face of panel to provide recess for application of applied finish. Reinforce panel as required to prevent buckling.

1. For recessed doors with plaster infill, provide self-furring expanded metal lath attached to door panel.

E. Latching Mechanisms: Furnish number required to hold doors in flush, smooth plane when closed.

1. For cylinder lock, furnish two keys per lock and key all locks alike.
2. For recessed panel doors, provide access sleeves for each locking device. Furnish plastic grommets and install in holes cut through finish.

PART 3 EXECUTION

3.1 INSTALLATION

A. Comply with manufacturer's written instructions for installing access doors and frames.

B. Set frames accurately in position and attach securely to supports with plane of face panels aligned with adjacent finish surfaces.

C. Install doors flush with adjacent finish surfaces or recessed to receive finish material.

3.2 ADJUSTING AND CLEANING

A. Adjust doors and hardware after installation for proper operation.

B. Remove and replace doors and frames that are warped, bowed, or otherwise damaged.

END OF SECTION

SECTION 084110

ALUMINUM-FRAMED STOREFRONTS

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Exterior aluminum-framed storefronts.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 079200 - JOINT SEALANTS for installation of joint sealants installed with aluminum-framed systems and for sealants to the extent not specified in this Section.
2. Section 088000 - GLAZING for glazing requirements to the extent not specified in this Section.

1.3 PERFORMANCE REQUIREMENTS

A. Delegated Design: Design storefront system, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

B. General: Provide aluminum-framed systems, including anchorage, capable of withstanding, without failure, the effects of the following:

1. Structural loads.
2. Thermal movements.
3. Dimensional tolerances of building frame and other adjacent construction.
4. Failure includes the following:

a. Deflection exceeding specified limits.
b. Thermal stresses transferred to building structure.
c. Framing members transferring stresses, including those caused by thermal and structural movements, to glazing.
d. Noise or vibration created by wind and thermal and structural movements.
e. Loosening or weakening of fasteners, attachments, and other components.
f. Sealant failure.
g. Failure of operating units to function properly.

C. Structural Loads: Wind and seismic loads as indicated on the Structural Drawings, but not less than that required by Code.

D. Deflection of Framing Members:

1. Deflection Normal to Wall Plane: Limited to 1/175 of clear span for spans up to 13 feet 6 inches (and to 1/240 of clear span plus 1/4 inch for spans greater than 13 feet 6 inches or an amount that restricts edge deflection of individual glazing lites to 3/4 inch, whichever is less.
2. Deflection Parallel to Glazing Plane: Limited to 1/360 of clear span or 1/8 inch, whichever is smaller, amount not exceeding that which reduces glazing bite to less than 75 percent of design dimension and that which reduces edge clearance between framing members and glazing or other fixed components directly below to less than 1/8 inch and clearance between members and operable units directly below to less than 1/16 inch.

E. Thermal Movements: Provide aluminum-framed systems that allow for thermal movements resulting from the following maximum change (range) in ambient and surface temperatures. Base engineering calculation on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.

1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.

F. Air Infiltration: Provide storefront which comply with the following. Test unit in accordance with ASTM E 283.

1. Storefront, ASHRAE Requirement: 0.06 cfm/sf maximum air leakage at a pressure differential of 1.57 psf or higher.

G. Water Leakage Test: Test fixed framing system in accordance with ASTM E 331.

1. Test Pressure: 8 psf.
2. Performance: No leakage as defined in test method at specified test pressure. No uncontrolled water penetrating system or appearing on normally exposed interior surfaces.

H. Solar Heat-Gain Coefficient: Provide storefront with a whole-unit SHGC maximum of 0.40, determined according to NFRC 200 procedures. Submit proof of compliance with submittals as specified.

I. Thermal Transmittance: Provide storefront that have a U-value of 0.57 BTU/hour/sq. ft./degrees F at 15-mph exterior wind velocity, when tested in accordance with AAMA 1503.1. Test unit to be 4 ft. x 6 ft. Submit proof of compliance with submittals as specified.

J. Condensation Resistance: Provide aluminum-framed systems with fixed glazing and framing areas having condensation-resistance factor (CRF) of not less than 65 for fixed storefront units.

1.4 SUBMITTALS

A. Product Data: Include installation instructions, construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of product indicated. Indicate special procedures and perimeter conditions requiring special attention.

B. Shop Drawings: Prepared under the supervision of a qualified professional engineer detailing fabrication and assembly of aluminum-framed systems. For aluminum-framed systems. Include plans, elevations, sections, details, and attachments to other work.

1. For installed products indicated to comply with design loads, include structural analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
2. Include structural analysis of story drift and deflection from anticipated live loads, and determination whether head receptors are required.
3. Include details of provisions for system expansion and contraction and for draining moisture occurring within the system to the exterior.
4. For entrances, include hardware schedule and indicate operating hardware types, functions, quantities, and locations.
5. Wiring diagrams for power, signal, and control wiring.
6. Activation and safety devices.
7. Include full-size isometric details of each vertical-to-horizontal intersection of storefronts, showing the following:

    a. Joinery, including concealed welds.
    b. Anchorage.
    c. Expansion provisions
    d. Glazing
    e. Flashing and drainage.

8. Include details showing interface with perimeter conditions to depict interface with adjacent thermal, weather, air and vapor barriers, and adjacent flashings.
9. Shop drawings must be signed and stamped by a professional engineer.

C. Delegated-Design Submittal: For storefront systems indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation. Show structural testing for attachment of the storefront to the existing structure. Contractor should survey slab edge locations and conditions of the embeds to develop the attachment details.

D. Samples for Verification: For each type of exposed finish required, in manufacturer's standard sizes.

E. Qualification Data: For Installer.

F. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for aluminum-framed systems.

G. Performance Reports: Based on systems, components and glazing methods proposed for use on this Project, proof that units as glazed for this Project meet or exceed Code requirements for the following:

1. U-value.
2. Solar heat-gain coefficient.

H. Maintenance Data: For aluminum-framed systems to include in maintenance manuals.

I. Warranties: Special warranties specified in this Section.

1.5 QUALITY ASSURANCE

A. Engineering Responsibility: Preparation of Shop Drawings, design calculations, and other structural data by a qualified professional engineer.

B. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in the jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of storefront systems that are similar to those indicated for this Project in material, design, and extent.

C. Installer Qualifications: Capable of assuming engineering responsibility and performing work of this Section and who is acceptable to manufacturer.

D. Accessible Entrances: Comply with authorities having jurisdiction, local state building code and the U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disabilities Act (ADA), Accessibility Guidelines for Buildings and Facilities (ADAAG)."

E. Preinstallation Conference: Conduct conference at Project site. Review methods and procedures related to storefront system, including, but not limited to, the following:

1. Review structural load limitations.
2. Review and finalize construction schedule and verify availability of materials, Installer’s personnel, equipment, and facilities needed to make progress and avoid delays.
3. Review required testing, inspection, and certifying procedures.

1.6 PROJECT CONDITIONS

A. Field Measurements: Verify actual locations of structural supports for aluminum-framed systems by field measurements before fabrication and indicate measurements on Shop Drawings.

1. Established Dimensions: Where field measurements cannot be made without delaying the Work, establish dimensions and proceed with fabricating aluminum-framed systems without field measurements. Coordinate construction to ensure that actual dimensions correspond to established dimensions.

1.7 WARRANTY

A. Special Finish Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components on which finishes fail within specified warranty period. Warranty does not include normal weathering.

1. Warranty Period: 10 years from date of Substantial Completion.

B. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of aluminum-framed storefronts that fail in materials or workmanship within specified warranty period.

1. Failures include, but are not limited to, the following:

a. Structural failures including, but not limited to, excessive deflection.
b. Faulty operation of operators, controls, and hardware.
c. Deterioration of metals, metal finishes, and other materials beyond normal weathering and use.

2. Warranty Period: Two years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Storefront, Thermal Break, 2 inch by 4-1/2 inch profile:

a. EFCO Corporation, 403X.
b. Kawneer North America, 451UT. (Basis-of-Design)
c. Oldcastle BuildingEnvelope, 3000XT.
d. Tubelite Inc., TU24000.
e. YKK AP America Inc., YES 45 XT.

2.2 MATERIALS

A. Aluminum: Alloy and temper recommended by manufacturer for type of use and finish indicated.

1. Sheet and Plate: ASTM B 209.
2. Extruded Bars, Rods, Profiles, and Tubes: ASTM B 221.
3. Extruded Structural Pipe and Tubes: ASTM B 429.
4. Structural Profiles: ASTM B 308/B 308M.
5. Welding Rods and Bare Electrodes: AWS A5.10/A5.10M.

B. Steel Reinforcement: With manufacturer's standard corrosion-resistant primer complying with SSPC-PS Guide No. 12.00 applied immediately after surface preparation and pretreatment. Select surface preparation methods according to recommendations in SSPC-SP COM and prepare surfaces according to applicable SSPC standard.

1. Structural Shapes, Plates, and Bars: ASTM A 36/A 36M.
2. Cold-Rolled Sheet and Strip: ASTM A 1008/A 1008M.
3. Hot-Rolled Sheet and Strip: ASTM A 1011/A 1011M.

2.3 FRAMING SYSTEMS

A. Framing Members: Manufacturer's standard extruded-aluminum framing members of thickness required and reinforced as required to support imposed loads.

1. Construction: Dual thermal-break.

B. Brackets and Reinforcements: Manufacturer's standard high-strength aluminum with nonstaining, nonferrous shims for aligning system components.

C. Fasteners and Accessories: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding fasteners and accessories compatible with adjacent materials.

1. Where fasteners are subject to loosening or turning out from thermal and structural movements, wind loads, or vibration, use self-locking devices.
2. Reinforce members as required to receive fastener threads.
3. Use exposed fasteners with countersunk Phillips screw heads, finished to match framing system.

D. Concrete and Masonry Inserts: Hot-dip galvanized cast-iron, malleable-iron, or steel inserts complying with ASTM A 123/A 123M or ASTM A 153/A 153M requirements.

E. Flashing: Manufacturer's standard corrosion-resistant, nonstaining, nonbleeding flashing compatible with adjacent materials. Form exposed flashing from sheet aluminum finished to match framing and of sufficient thickness to maintain a flat appearance without visible deflection.

F. Framing System Gaskets and Sealants: Manufacturer's standard recommended by manufacturer for joint type.

2.4 GLAZING SYSTEMS

A. Glazing: As specified in Section 088000 - GLAZING.

B. Glazing Gaskets: Manufacturer's standard compression types, replaceable, molded or extruded, that maintain uniform pressure and watertight seal.

C. Spacers and Setting Blocks: Manufacturer's standard elastomeric types.

2.5 ACCESSORY MATERIALS

A. Insulating Materials: As recommended by manufacturer.

B. Joint Sealants: For installation at perimeter of aluminum-framed systems, as specified in Section 079200 - JOINT SEALANTS.

C. Bituminous Paint: Cold-applied asphalt-mastic paint complying with SSPC-Paint 12 requirements except containing no asbestos, formulated for 30-mil thickness per coat.

2.6 FABRICATION

A. Form aluminum shapes before finishing.

B. Weld in concealed locations to greatest extent possible to minimize distortion or discoloration of finish. Remove weld spatter and welding oxides from exposed surfaces by descaling or grinding.

C. Framing Members, General: Fabricate components that, when assembled, have the following characteristics:

1. Profiles that are sharp, straight, and free of defects or deformations.
2. Accurately fitted joints with ends coped or mitered.
3. Means to drain water passing joints, condensation occurring within framing members, and moisture migrating within the system to exterior.
4. Physical and thermal isolation of glazing from framing members.
5. Accommodations for thermal and mechanical movements of glazing and framing to maintain required glazing edge clearances.
6. Fasteners, anchors, and connection devices that are concealed from view to greatest extent possible.

D. Mechanically Glazed Framing Members: Fabricate for flush glazing (without projecting stops).

E. After fabrication, clearly mark components to identify their locations in Project according to Shop Drawings.

2.7 ALUMINUM FINISHES

A. General: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.

B. Finish designations prefixed by AA comply with the system established by the Aluminum Association for designating aluminum finishes.

C. Clear Anodic Finish: AAMA 611, AA-M12C22A41, Class I, 0.018 mm or thicker.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine areas, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of work.

1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. General:

1. Comply with manufacturer's written instructions.
2. Do not install damaged components.
3. Fit joints to produce hairline joints free of burrs and distortion.
4. Rigidly secure nonmovement joints.
5. Install anchors with separators and isolators to prevent metal corrosion and electrolytic deterioration.
6. Seal joints watertight, unless otherwise indicated.

B. Metal Protection:

1. Where aluminum will contact dissimilar metals, protect against galvanic action by painting contact surfaces with primer or by applying sealant or tape or installing nonconductive spacers as recommended by manufacturer for this purpose.
2. Where aluminum will contact concrete or masonry, protect against corrosion by painting contact surfaces with bituminous paint.

C. Install components to drain water passing joints, condensation occurring within framing members, and moisture migrating within the system to exterior.

D. Set continuous sill members and flashing in full sealant bed as specified in Section 079200 - JOINT SEALANTS and to produce weathertight installation.

E. Install components plumb and true in alignment with established lines and grades, without warp or rack.

F. Install glazing as specified in Section 088000 - GLAZING.

G. Erection Tolerances: Install aluminum-framed systems to comply with the following maximum tolerances:

1. Location and Plane: Limit variation from true location and plane to 1/8 inch in 12 feet; 1/4 inch over total length.
2. Alignment:

   a. Where surfaces abut in line, limit offset from true alignment to 1/16 inch.
   b. Where surfaces meet at corners, limit offset from true alignment to 1/32 inch.

3. Diagonal Measurements: Limit difference between diagonal measurement to 1/8 inch.

3.3 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections, and assist Contractor with diagnosis of test specimen and perimeter joint sealants, in the event of failures. Testing agency shall prepare reports and submit to Contractor with copy to Owner, and Architect.

B. Pre-Testing Meeting: Include Owner, Architect, Contractor, installing subcontractors, manufacturer technical representative, and testing agency to review relevant pre-installation meeting minutes and to discuss testing scope, locations, frequency, Contractor's field quality control plan, and to verify all systems are designed to withstand specified testing requirements.

C. Field Quality-Control Testing: Perform the following test on representative areas of aluminum-framed storefronts. Testing shall be conducted as early into the schedule as is practical.

1. Test Areas:

   a. Test areas to include head, jamb, sill, spandrel glass interface (if applicable), outside corner, inside corner, transition to operable windows (if applicable), storefront system opening perimeter sealant joint, and other locations as selected by Architect and testing agency. Test only after perimeter sealants have cured.
   b. All interior gypsum board and finishes to be left uninstalled or removed prior to testing to allow for visual access to interior perimeter joint of storefront system.
   c. To allow visual access to the outside primary seal and storefront frame perimeter, do not install interior perimeter joint sealant. If interior sealant line is required by storefront system manufacturer to maintain continuity of air or weather barrier or the storefront system itself, it shall remain in place during air and water testing. Upon completion of water testing, portions of the interior sealant line shall be removed as directed by the Architect to provide visual access to the storefront frame perimeter and the exterior perimeter weather sealant joints.

2. Testing Frequency and Location: Perform a minimum of two tests in areas as directed by Architect and testing agency, unless otherwise indicated.
3. Testing:

   a. Water-Spray Test: Before installation of interior finishes has begun, areas designated by Architect shall be tested according to AAMA 501.2 and shall not evidence water penetration.
      1) Allowable Water Infiltration: No water penetration. Water penetration, or water leakage, is defined as any water penetrating assemblies or water that appears on any indoor surface of the fenestration product from sources other than condensation.

D. Remedial Work: Aluminum-framed storefronts will be considered defective if they do not pass tests and inspections.

1. Repair or remove and replace work where test results and inspections indicate that it does not comply with specified requirements.
2. If the field test reveals leakage, points of entry and paths of flow of water shall be identified, analyzed, and necessary remedial work shall be established, subject to Architect's review and comment.
3. Repairs and/or modifications shall be made and, after adequate curing of all sealants, re-test to successful conclusion.
4. Any resulting repairs due to systemic storefront or installation issues shall be made to both installed storefront and storefront yet to be installed, as required.

E. Additional Testing and Inspections: Additional testing and inspections of repaired and/or replaced fenestration units to determine compliance with the specified performance requirements shall be performed at the Contractor's expense.

1. Testing of repaired fenestration shall occur on one or more units at the discretion of the Owner and Architect.

END OF SECTION

SECTION 085110

ALUMINUM WINDOWS

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Fixed aluminum-framed windows with factory-installed glass and glazing.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 084110 - ALUMINUM-FRAMED STOREFRONTS.
2. Section 088000 - GLAZING for requirements for glass and glazing.

1.3 PERFORMANCE REQUIREMENTS

A. General: Provide aluminum windows capable of complying with performance requirements indicated, based on testing manufacturer's windows that are representative of those specified and that are of test size indicated below:

1. Minimum size required by AAMA/NWWDA 101/I.S.2.

B. AAMA/NWWDA Performance Requirements: Provide aluminum windows of the performance class and grade indicated that comply with AAMA/NWWDA 101/I.S.2.

1. Performance Class: Architectural Grade AW.
2. Performance Grade: Minimum for performance class indicated.
3. Exception to AAMA/NWWDA 101/I.S.2: In addition to requirements for performance class and performance grade, design glass framing system to limit lateral deflections of glass edges to less than 1/175 of glass-edge length or 3/4 inch whichever is less, at design pressure based on the following:

C. Structural Performance: Provide aluminum windows capable of withstanding the following, including wind loads based on passing AAMA/NWWDA 101/I.S.2, Uniform Load Structural Test, at basic wind speed indicated and as required by Code:

1. Deflection: Design glass framing system to limit lateral deflections of glass edges to less than 1/175 of glass-edge length or 3/4 inch, whichever is less, at design pressure based on structural computations.
2. Wind and Seismic Loads: As indicated on the Structural Drawings, but not less than that required by Code.

3. Movements of supporting structure including, but not limited to, story drift and deflection from uniformly distributed and concentrated live loads as required by Code. Deflection may require special considerations including but not limited to head receptors.

D. Air Infiltration: Maximum rate not more than indicated when tested according to AAMA/NWWDA 101/I.S.2, Air Infiltration Test.

1. Maximum Rate: As required by Code.

E. Water Resistance: No water leakage as defined in AAMA/NWWDA referenced test methods at a water test pressure equaling that indicated, when tested according to AAMA/NWWDA 101/I.S.2, Water Resistance Test.

1. Test Pressure: 15 percent of positive design pressure, but not less than 2.86 lbf/sq. ft. or more than 12 lbf/sq. ft.

F. Condensation-Resistance Factor: Provide aluminum windows tested for thermal performance according to AAMA 1503, showing a CRF of 52 where windows are indicated to be "thermally improved."

G. Thermal Transmittance: Provide aluminum windows with a whole-window U-value maximum indicated at 15-mph exterior wind velocity and winter condition temperatures when tested according to AAMA 1503.

1. U-Value: As required by Code. Submit proof of compliance with submittals as specified.

H. Solar Heat-Gain Coefficient: Provide aluminum windows with a whole-window SHGC maximum as required by Code, determined according to NFRC 200 procedures. Submit proof of compliance with submittals as specified.

I. Thermal Movements: Provide aluminum windows, including anchorage, that accommodate thermal movements of units resulting from the following maximum change (range) in ambient and surface temperatures without buckling, distortion, opening of joints, failure of joint sealants, damaging loads and stresses on glazing and connections, and other detrimental effects. Base engineering calculation on actual surface temperatures of materials due to solar heat gain and nighttime-sky heat loss.

1. Temperature Change (Range): 120 deg F, ambient; 180 deg F material surfaces.

1.4 SUBMITTALS

A. Product Data: For each type of product indicated.

1. Include construction details, material descriptions, fabrication methods, dimensions of individual components and profiles, hardware, finishes, and operating instructions.

B. Shop Drawings: Include plans, elevations, sections, details, hardware, attachments to other Work, operational clearances, and the following:

1. Mullion details, including reinforcement and stiffeners.
2. Joinery details.
3. Expansion provisions.
4. Flashing and drainage details.
5. Weather-stripping details.

6. Thermal-break details.
7. Glazing details.
8. Window cleaning provisions.
9. Window System Operators: Show locations, mounting, and details for installing operator components and controls.
10. For installed products indicated to comply with design loads, include structural analysis data signed and sealed by the qualified professional engineer responsible for their preparation and used to determine the following:

    a. Structural test pressures and design pressures from basic wind speeds indicated.
    b. Deflection limitations of glass framing systems.

C. Samples for Verification: Full-size window of each type of window.

D. Qualification Data: For Installer, professional engineer and testing agency.

E. Field Quality-Control Test Reports: From a qualified testing and inspecting agency engaged by Contractor.

F. Product Test Reports: Based on evaluation of comprehensive tests performed within the last four years by a qualified testing agency, for each type, grade, and size of aluminum window. Test results based on use of downsized test units will not be accepted.

G. Performance Reports: Based on systems, components and glazing methods proposed for use on this Project, proof that windows as glazed for this Project meet or exceed Code requirements for the following:

1. U-value.
2. Solar heat-gain coefficient.

1.5 QUALITY ASSURANCE

A. Installer Qualifications: An installer acceptable to aluminum window manufacturer for installation of units required for this Project.

B. Engineering Responsibility: Preparation of Shop Drawings, design calculations, and other structural data by a qualified professional engineer.

C. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in the state the project is located, and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of windows that are similar to those indicated for this Project in material, design, and extent.

D. Source Limitations: Obtain aluminum windows through one source from a single manufacturer.

E. Product Options: Information on Drawings and in Specifications establishes requirements for aluminum windows' aesthetic effects and performance characteristics. Aesthetic effects are indicated by dimensions, arrangements, alignment, and profiles of components and assemblies as they relate to sightlines, to one another, and to adjoining construction. Performance characteristics are indicated by criteria subject to verification by one or more methods including preconstruction testing, field testing, and in-service performance.

F. Fenestration Standard: Comply with AAMA/NWWDA 101/I.S.2, "Voluntary Specifications for Aluminum, Vinyl (PVC) and Wood Windows and Glass Doors," for minimum standards of

performance, materials, components, accessories, and fabrication unless more stringent requirements are indicated.

1. Provide AAMA certified aluminum windows with an attached label.

G. Glazing Publications: Comply with published recommendations of glass manufacturers and GANA's "Glazing Manual" unless more stringent requirements are indicated.

H. Mockups: Build mockups to verify selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Build mockup for types of windows indicated, in locations shown on Drawings.

I. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01. Review methods and procedures related to aluminum windows including, but not limited to, the following:

1. Inspect and discuss condition of substrate and other preparatory work performed by other trades.
2. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
3. Review required testing and inspecting procedures.

1.6 PROJECT CONDITIONS

A. Field Measurements: Verify aluminum window openings by field measurements before fabrication and indicate measurements on Shop Drawings.

1. Established Dimensions: Where field measurements cannot be made without delaying the Work, establish opening dimensions and proceed with fabricating aluminum windows without field measurements. Coordinate wall construction to ensure that actual opening dimensions correspond to established dimensions.

1.7 WARRANTY

A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace aluminum windows that fail in materials or workmanship within specified warranty period. Failures include, but are not limited to, the following:

1. Failure to meet performance requirements.
2. Structural failures including excessive deflection.
3. Water leakage, air infiltration, or condensation.
4. Faulty operation of movable sash and hardware.
5. Deterioration of metals, metal finishes, and other materials beyond normal weathering.
6. Insulating glass failure.

B. Warranty Period: Ten years from date of Substantial Completion.

C. Warranty Period for Metal Finishes: Ten years from date of Substantial Completion.

D. Warranty Period for Glass: Ten years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

1. Gerkin Windows & Doors.
2. Manko Window Systems.

2.2 MATERIALS

A. Aluminum Extrusions: Alloy and temper recommended by aluminum window manufacturer for strength, corrosion resistance, and application of required finish, but not less than 22,000-psi (150-MPa) ultimate tensile strength, not less than 16,000-psi (110-MPa) minimum yield strength, and not less than 0.062-inch (1.6-mm) thickness at any location for the main frame and sash members.

B. Fasteners: Aluminum, nonmagnetic stainless steel, epoxy adhesive, or other materials warranted by manufacturer to be noncorrosive and compatible with aluminum window members, trim, hardware, anchors, and other components.

1. Reinforcement: Where fasteners screw anchor into aluminum less than 0.125 inch (3.2 mm) thick, reinforce interior with aluminum or nonmagnetic stainless steel to receive screw threads, or provide standard, noncorrosive, pressed-in, splined grommet nuts.
2. Exposed Fasteners: Unless unavoidable for applying hardware, do not use exposed fasteners. For application of hardware, use fasteners that match finish of member or hardware being fastened, as appropriate.

C. Anchors, Clips, and Accessories: Aluminum, nonmagnetic stainless steel, or zinc-coated steel or iron complying with ASTM B 633 for SC 3 severe service conditions; provide sufficient strength to withstand design pressure indicated.

D. Reinforcing Members: Aluminum, nonmagnetic stainless steel, or nickel/chrome-plated steel complying with ASTM B 456 for Type SC 3 severe service conditions, or zinc-coated steel or iron complying with ASTM B 633 for SC 3 severe service conditions; provide sufficient strength to withstand design pressure indicated.

E. Compression-Type Weather Stripping, typical: Provide compressible weather stripping designed for permanently resilient sealing under bumper or wiper action and for complete concealment when aluminum window is closed.

F. Replaceable Weather Seals: Comply with AAMA 701/702.

G. Sealant: For sealants required within fabricated windows, provide window manufacturer's standard, permanently elastic, nonshrinking, and nonmigrating type recommended by sealant manufacturer for joint size and movement.

2.3 GLAZING

A. Insulating-Glass Units for Vertical Glazing: 1 inch thick (25.0 mm) insulating glass consisting of two lites of 1/4 inch (6 mm) glass, low e coating on the No. 2 surface and argon gas filled. Provide one of the following or equal:

1. Vitro Architectural Glass (formerly PPG Industries); Graylite II.

    a. Visible Light Transmittance: 7 percent.
    b. Reflectance Visible Light, Exterior: 4 percent.
    c. U Value (Winter): 0.29.
    d. Solar Heat Gain Coefficient: 0.11.

B. Glazing System: Manufacturer's standard factory-glazing system that produces weathertight seal.

2.4 HARDWARE

A. Hardware Requirements: Provide hardware that complies with AAMA/NWWDA 101/I.S.2.

1. Hardware Finishes: To be selected by Architect from manufacturer’s full range.

2.5 ACCESSORIES

A. Window Cleaner Anchor Bolts: Provide window cleaner anchor bolts of standard design, complying with requirements of authorities having jurisdiction. Fabricate bolts of nonmagnetic stainless steel.

1. Reinforce window units or mullions to receive bolts and provide additional anchorage of units at bolt locations.

2.6 FABRICATION

A. General: Fabricate aluminum windows, in sizes indicated, that comply with AAMA/NWWDA 101/I.S.2 for performance class and performance grade indicated. Include a complete system for assembling components and anchoring windows.

B. Thermally Improved Construction: Fabricate aluminum windows with an integral, concealed, low-conductance thermal barrier; located between exterior materials and window members exposed on interior side; in a manner that eliminates direct metal-to-metal contact.

C. Weather Stripping: Provide full-perimeter weather stripping for each operable sash and ventilator.

D. Weep Holes: Provide concealed weep holes and internal passages to conduct infiltrating water to exterior.

E. Mullions: Provide mullions and cover plates as shown, matching window units, complete with anchors for support to structure and installation of window units. Allow for erection tolerances and provide for movement of window units due to thermal expansion and building deflections, as indicated. Provide mullions and cover plates capable of withstanding design loads of window units.

F. Factory-Glazed Fabrication: Glaze aluminum windows in the factory where practical and possible for applications indicated. Comply with AAMA/NWWDA 101/I.S.2.

2.7 FINISHES

A. General: Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.

B. Finish designations prefixed by AA comply with the system established by the Aluminum Association for designating aluminum finishes.

C. Clear Anodic Finish: AAMA 611, AA-M12C22A41, Class I, 0.018 mm or thicker.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine openings, substrates, structural support, anchorage, and conditions, with Installer present, for compliance with requirements for installation tolerances; rough opening dimensions; levelness of sill plate; coordination with wall flashings, vapor retarders, and other built-in components; operational clearances; and other conditions affecting performance of work.

1. Masonry Surfaces: Visibly dry and free of excess mortar, sand, and other construction debris.
2. Metal Surfaces: Dry; clean; free of grease, oil, dirt, rust, corrosion, and welding slag; without sharp edges or offsets at joints.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

A. General: Comply with manufacturer's written instructions for installing windows, hardware, accessories, and other components; Drawings; and Shop Drawings.

B. Install windows level, plumb, square, true to line, without distortion or impeding thermal movement, anchored securely in place to structural support, and in proper relation to wall flashing and other adjacent construction.

C. Set sill members in bed of sealant or with gaskets, as indicated, for weathertight construction.

D. Install windows and components to drain condensation, water penetrating joints, and moisture migrating within windows to the exterior.

E. Metal Protection: Separate aluminum and other corrodible surfaces from sources of corrosion or electrolytic action at points of contact with other materials by complying with requirements specified in "Dissimilar Materials" Paragraph in Appendix B in AAMA/NWWDA 101/I.S.2.

3.3 FIELD QUALITY CONTROL

A. Testing Agency: Owner will engage a qualified testing agency to perform tests and inspections, and assist Contractor with diagnosis of test specimen and perimeter joint sealants, in the event of failures. Testing agency shall prepare reports and submit to Contractor with copy to Owner, and Architect.

B. Pre-Testing Meeting: Include Owner, Architect, Contractor, installing subcontractors, manufacturer technical representative, and testing agency to review relevant pre-installation meeting minutes and discuss testing scope, locations, frequency, Contractor's field quality control plan, and to verify all systems are designed to withstand specified testing requirements.

C. Field-Quality Control Testing: Perform the following tests on representative windows as selected by Architect and qualified testing and inspection agency and on mockup. Testing shall be conducted as early into the schedule as is practical.

1. Test Areas:

   a. Test areas to include head, jamb, sill, window door opening perimeter sealant joint, and other locations as selected by Architect and testing agency. Test only after perimeter sealants have cured.
   b. All interior gypsum board and finishes to be left uninstalled or removed prior to testing to allow for visual access to interior perimeter joint of window system.
   c. To allow visual access to the outside primary seal and window frame perimeter, do not install interior perimeter joint sealant. If interior sealant line is required by window manufacturer to maintain continuity of air or weather barrier or the window system itself, it shall remain in place during air and water testing. Upon completion of water testing, portions of the interior sealant line shall be removed as directed by the Architect to provide visual access to the window frame perimeter and the exterior perimeter weather sealant joints.

2. Testing Frequency: Minimum four windows, one of each type on each facade as selected by Architect and testing agency; and mockup.
3. Testing:

   a. Air-Infiltration Testing:

      1) Test Pressure: That required to determine compliance with AAMA/WDMA/CSA 101/I.S.2/A440 performance class and grade indicated.
      2) Allowable Air-Leakage Rate: ASTM E 783 at 1.5 times the applicable AAMA/WDMA/CSA 101/I.S.2/A440 rate for specified performance class and grade, rounded down to one decimal place.

   b. Water-Resistance Testing:

      1) Test Pressure: ASTM E 1105 at test pressure required (no reduction) to determine compliance with AAMA/WDMA/CSA 101/I.S.2/A440 performance class and grade specified.
      2) Allowable Water Infiltration: No water penetration. Water penetration, or water leakage, is defined as any water penetrating assemblies or water that appears on any indoor surface of the fenestration product from sources other than condensation.

D. Remedial Work: Windows will be considered defective if they do not pass tests and inspections.

1. Repair or remove and replace work where test results and inspections indicate that it does not comply with specified requirements.
2. If the field test reveals leakage, points of entry and paths of flow of water shall be identified, analyzed, and necessary remedial work shall be established, subject to Architect's review and comment.
3. Repairs and/or modifications shall be made and, after adequate curing of all sealants, re-test to successful conclusion.
4. Any resulting repairs due to systemic window or installation issues shall be made to both installed windows and windows yet to be installed, as required.

E. Additional Testing and Inspections: Additional testing and inspections of repaired and/or replaced fenestration units to determine compliance with the specified performance requirements shall be performed at the Contractor's expense.

1. Testing of repaired fenestration shall occur on one or more units at the discretion of the Owner and Architect.

3.4 ADJUSTING

A. Adjust operating sashes and ventilators, screens, hardware, operators, and accessories for a tight fit at contact points and weather stripping for smooth operation and weathertight closure. Lubricate hardware and moving parts.

3.5 PROTECTION AND CLEANING

A. Protect window surfaces from contact with contaminating substances resulting from construction operations. In addition, monitor window surfaces adjacent to and below exterior concrete and masonry surfaces during construction for presence of dirt, scum, alkaline deposits, stains, or other contaminants. If contaminating substances do contact window surfaces, remove contaminants immediately according to manufacturer's written recommendations.

B. Clean aluminum surfaces immediately after installing windows. Avoid damaging protective coatings and finishes. Remove excess sealants, glazing materials, dirt, and other substances.

C. Clean factory-glazed glass immediately after installing windows. Comply with manufacturer's written recommendations for final cleaning and maintenance. Remove nonpermanent labels and clean surfaces.

D. Remove and replace glass that has been broken, chipped, cracked, abraded, or damaged during construction period.

END OF SECTION

SECTION 08 71 00 – DOOR HARDWARE

PART 1 - GENERAL

1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.02 SUMMARY

A. Section includes:

1. Mechanical and electrified door hardware for:

a. Swinging doors.

2. Field verification, preparation and modification of existing doors and frames to receive new door hardware.
3. The intent of the hardware specification is to specify the hardware for interior and exterior doors, and to establish a type, continuity, and standard of quality. However, it is the door hardware supplier's responsibility to thoroughly review existing conditions, schedules, specifications, drawings, and other Contract Documents to verify the suitability of the hardware specified.

B. Exclusions: Unless specifically listed in hardware sets, hardware is not specified in this section for:

1. Windows
2. Cabinets (casework), including locks in cabinets
3. Signage
4. Toilet accessories
5. Overhead doors

C. Related Sections:

1. Division 01 Section "Alternates" for alternates affecting this section.
2. Division 07 Section "Joint Sealants" for sealant requirements applicable to threshold installation specified in this section.
3. Division 09 sections for touchup, finishing or refinishing of existing openings modified by this section.
4. Division 26 sections for connections to electrical power system and for low-voltage wiring.
5. Division 28 sections for coordination with other components of electronic access control system.

1.03 REFERENCES

A. UL - Underwriters Laboratories

1. UL 10B - Fire Test of Door Assemblies
2. UL 10C - Positive Pressure Test of Fire Door Assemblies
3. UL 1784 - Air Leakage Tests of Door Assemblies
4. UL 305 - Panic Hardware

B. DHI - Door and Hardware Institute

1. Sequence and Format for the Hardware Schedule
2. Recommended Locations for Builders Hardware
3. Key Systems and Nomenclature

C. ANSI - American National Standards Institute

1. ANSI/BHMA A156.1 - A156.29, and ANSI/BHMA A156.31 - Standards for Hardware and Specialties

1.04 SUBMITTALS

A. General:

1. Submit in accordance with Conditions of Contract and Division 01 requirements.
2. Highlight, encircle, or otherwise specifically identify on submittals deviations from Contract Documents, issues of incompatibility or other issues which may detrimentally affect the Work.
3. Prior to forwarding submittal, comply with procedures for verifying existing door and frame compatibility for new hardware, as specified in PART 3, “EXAMINATION” article, herein.

B. Action Submittals:

1. Product Data: Technical product data for each item of door hardware, installation instructions, maintenance of operating parts and finish, and other information necessary to show compliance with requirements.
2. Door Hardware Schedule: Submit schedule with hardware sets in vertical format as illustrated by Sequence of Format for the Hardware Schedule as published by the Door and Hardware Institute. Indicate complete designations of each item required for each door or opening, include:

    a. Door Index; include door number, heading number, and Architects hardware set number.
    b. Opening Lock Function Spreadsheet: List locking device and function for each opening.
    c. Quantity, type, style, function, size, and finish of each hardware item.
    d. Name and manufacturer of each item.
    e. Fastenings and other pertinent information.
    f. Location of each hardware set cross-referenced to indications on Drawings.
    g. Explanation of all abbreviations, symbols, and codes contained in schedule.
    h. Mounting locations for hardware.
    i. Door and frame sizes and materials.
    j. Name and phone number for local manufacturer's representative for each product.
    k. Operational Description of openings with any electrified hardware (locks, exits, electromagnetic locks, electric strikes, automatic operators, door position switches, magnetic holders or closer/holder units, and access control components).

Operational description should include operational descriptions for: egress, ingress (access), and fire/smoke alarm connections.

1) Submittal Sequence: Submit door hardware schedule concurrent with submissions of Product Data, Samples, and Shop Drawings. Coordinate submission of door hardware schedule with scheduling requirements of other work to facilitate fabrication of other work that is critical in Project construction schedule.

3. Key Schedule:

   a. After Keying Conference, provide keying schedule listing levels of keying as well as explanation of key system's function, key symbols used and door numbers controlled.
   b. Use ANSI/BHMA A156.28 “Recommended Practices for Keying Systems” as guideline for nomenclature, definitions, and approach for selecting optimal keying system.
   c. Provide 3 copies of keying schedule for review prepared and detailed in accordance with referenced DHI publication. Include schematic keying diagram and index each key to unique door designations.
   d. Index keying schedule by door number, keyset, hardware heading number, cross keying instructions, and special key stamping instructions.
   e. Provide one complete bitting list of key cuts and one key system schematic illustrating system usage and expansion.
      1) Forward bitting list, key cuts and key system schematic directly to Owner, by means as directed by Owner.

   f. Prepare key schedule by or under supervision of supplier, detailing Owner’s final keying instructions for locks.

4. Templates: After final approval of hardware schedule, provide templates for doors, frames and other work specified to be factory or shop prepared for door hardware installation.

C. Informational Submittals:

1. Qualification Data: For Supplier, Installer and Architectural Hardware Consultant.
2. Product data for electrified door hardware:

   a. Certify that door hardware approved for use on types and sizes of labeled fire-rated doors complies with listed fire-rated door assemblies.

3. Warranty: Special warranty specified in this Section.

D. Closeout Submittals:

1. Operations and Maintenance Data: Provide in accordance with Division 01 and include:

   a. Complete information on care, maintenance, and adjustment; data on repair and replacement parts, and information on preservation of finishes.
   b. Catalog pages for each product.
   c. Final approved hardware schedule, edited to reflect conditions as-installed.
   d. Final keying schedule
   e. Copy of warranties including appropriate reference numbers for manufacturers to identify project.

1.05 QUALITY ASSURANCE

A. Supplier Qualifications and Responsibilities: Recognized architectural hardware supplier with record of successful in-service performance for supplying door hardware similar in quantity, type, and quality to that indicated for this Project and that provides certified Architectural Hardware Consultant (AHC) available to Owner, Architect, and Contractor, at reasonable times during the Work for consultation.

1. Warehousing Facilities: In Project's vicinity.
2. Scheduling Responsibility: Preparation of door hardware and keying schedules.
3. Engineering Responsibility: Preparation of data for electrified door hardware, including Shop Drawings, based on testing and engineering analysis of manufacturer's standard units in assemblies similar to those indicated for this Project.
4. Coordination Responsibility: Assist in coordinating installation of electronic security hardware with Architect and electrical engineers and provide installation and technical data to Architect and other related subcontractors.

a. Upon completion of electronic security hardware installation, inspect and verify that all components are working properly.

B. Single Source Responsibility: Obtain each type of door hardware from single manufacturer.

C. Fire-Rated Door Openings: Provide door hardware for fire-rated openings that complies with NFPA 80 and requirements of authorities having jurisdiction. Provide only items of door hardware that are listed products tested by Underwriters Laboratories, Intertek Testing Services, or other testing and inspecting organizations acceptable to authorities having jurisdiction for use on types and sizes of doors indicated, based on testing at positive pressure and according to NFPA 252 or UL 10C and in compliance with requirements of fire-rated door and door frame labels.

D. Electrified Door Hardware: Listed and labeled as defined in NFPA 70, Article 100, by testing agency acceptable to authorities having jurisdiction.

E. Accessibility Requirements: For door hardware on doors in an accessible route, comply with governing accessibility regulations cited in “REFERENCES” article, herein.

F. Keying Conference

1. Incorporate keying conference decisions into final keying schedule after reviewing door hardware keying system including:

a. Function of building, flow of traffic, purpose of each area, degree of security required, and plans for future expansion.
b. Preliminary key system schematic diagram.
c. Requirements for key control system.
d. Requirements for access control.
e. Address for delivery of keys.

G. Pre-installation Conference

1. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
2. Inspect and discuss preparatory work performed by other trades.
3. Inspect and discuss electrical roughing-in for electrified door hardware.
4. Review sequence of operation for each type of electrified door hardware.

5. Review required testing, inspecting, and certifying procedures.

H. Coordination Conferences:

1. Installation Coordination Conference: Prior to hardware installation, schedule and hold meeting to review questions or concerns related to proper installation and adjustment of door hardware.
2. Electrified Hardware Coordination Conference: Prior to ordering electrified hardware, schedule and hold meeting to coordinate door hardware with security, electrical, doors and frames, and other related suppliers.

1.06 DELIVERY, STORAGE, AND HANDLING

A. Inventory door hardware on receipt and provide secure lock-up for hardware delivered to Project site.

B. Tag each item or package separately with identification coordinated with final door hardware schedule, and include installation instructions, templates, and necessary fasteners with each item or package.

1. Deliver each article of hardware in manufacturer’s original packaging.

C. Project Conditions:

1. Maintain manufacturer-recommended environmental conditions throughout storage and installation periods.
2. Provide secure lock-up for door hardware delivered to Project. Control handling and installation of hardware items so that completion of Work will not be delayed by hardware losses both before and after installation.

D. Protection and Damage:

1. Promptly replace products damaged during shipping.
2. Handle hardware in manner to avoid damage, marring, or scratching. Correct, replace or repair products damaged during Work.
3. Protect products against malfunction due to paint, solvent, cleanser, or any chemical agent.

E. Deliver keys and permanent cores to Owner by registered mail or overnight package service.

1.07 COORDINATION

A. Coordinate layout and installation of floor-recessed door hardware with floor construction. Cast anchoring inserts into concrete.

B. Installation Templates: Distribute for doors, frames, and other work specified to be factory or shop prepared. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing door hardware to comply with indicated requirements.

C. Security: Coordinate installation of door hardware, keying, and access control with Owner's security consultant.

D. Electrical System Roughing-In: Coordinate layout and installation of electrified door hardware with connections to power supplies and building safety and security systems.

E. Existing Openings: Where existing doors, frames and/or hardware are to remain, field verify existing functions, conditions and preparations and coordinate to suit opening conditions and to provide proper door operation.

1.08 WARRANTY

A. Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of door hardware that fail in materials or workmanship within specified warranty period.

1. Warranty Period: Beginning from date of Substantial Completion, for durations indicated by the manufacturer.
2. Warranty does not cover damage or faulty operation due to improper installation, improper use or abuse.

PART 2 - PRODUCTS

2.01 MANUFACTURERS

A. Approval of manufacturers and/or products other than those listed as “Scheduled Manufacturer” or “Acceptable Manufacturers” in the individual article for the product category shall be in accordance with QUALITY ASSURANCE article, herein.

B. Approval of products from manufacturers indicated in “Acceptable Manufacturers” is contingent upon those products providing all functions and features and meeting all requirements of scheduled manufacturer’s product.

C. Where specified hardware is not adaptable to finished shape or size of members requiring hardware, furnish suitable types having same operation and quality as type specified, subject to Architect's approval.

2.02 MATERIALS

A. Fasteners

1. Provide hardware manufactured to conform to published templates, generally prepared for machine screw installation.
2. Furnish screws for installation with each hardware item. Finish exposed (exposed under any condition) screws to match hardware finish, or, if exposed in surfaces of other work, to match finish of this other work including prepared for paint surfaces to receive painted finish.
3. Provide concealed fasteners for hardware units exposed when door is closed except when no standard units of type specified are available with concealed fasteners. Do not use thru-bolts for installation where bolt head or nut on opposite face is exposed in other work unless thru-bolts are required to fasten hardware securely. Review door specification and advise Architect if thru-bolts are required.
4. Install hardware with fasteners provided by hardware manufacturer.

B. Modification and Preparation of Existing Doors: Where existing door hardware is indicated to be removed and reinstalled.

1. Provide necessary fillers, Dutchmen, reinforcements, and fasteners, compatible with existing materials, as required for mounting new opening hardware and to cover existing door and frame preparations.
2. Use materials which match materials of adjacent modified areas.
3. When modifying existing fire-rated openings, provide materials permitted by NFPA 80 as required to maintain fire-rating.

C. Provide screws, bolts, expansion shields, drop plates and other devices necessary for hardware installation.

1. Where fasteners are exposed to view: Finish to match adjacent door hardware material.

2.03 HINGES

A. Manufacturers and Products:

1. Scheduled Manufacturer and Product: Ives 5BB series.
2. Acceptable Manufacturers and Products: Hager BB series, McKinney TB/T4B series, Stanley FBB Series.

B. Requirements:

1. Provide hinges conforming to ANSI/BHMA A156.1.
2. 1-3/4 inch (44 mm) thick doors, up to and including 36 inches (914 mm) wide:

    a. Exterior: Standard weight, bronze or stainless steel, 4-1/2 inches (114 mm) high
    b. Interior: Standard weight, steel, 4-1/2 inches (114 mm) high

3. 1-3/4 inch (44 mm) thick doors over 36 inches (914 mm) wide:

    a. Exterior: Heavy weight, bronze/stainless steel, 5 inches (127 mm) high
    b. Interior: Heavy weight, steel, 5 inches (127 mm) high

4. 2 inches or thicker doors:

    a. Exterior: Heavy weight, bronze or stainless steel, 5 inches (127 mm) high
    b. Interior: Heavy weight, steel, 5 inches (127 mm) high

5. Provide three hinges per door leaf for doors 90 inches (2286 mm) or less in height, and one additional hinge for each 30 inches (762 mm) of additional door height.
6. Where new hinges are specified for existing doors or existing frames, provide new hinges of identical size to hinge preparation present in existing door or existing frame.
7. All hinges to have non-removable pins.
8. Width of hinges: 4-1/2 inches (114 mm) at 1-3/4 inch (44 mm) thick doors, and 5 inches (127 mm) at 2 inches (51 mm) or thicker doors. Adjust hinge width as required for door, frame, and wall conditions to allow proper degree of opening.
9. Provide hinges with electrified options as scheduled in the hardware sets. Provide with sufficient number and wire gage to accommodate electric function of specified hardware. Locate electric hinge at second hinge from bottom or nearest to electrified locking component.
10. Provide mortar guard for each electrified hinge specified.
11. All hinges to be ball bearing.

2.04 CYLINDRICAL LOCKS – GRADE 1

A. Manufacturers and Products:

1. Scheduled Manufacturer and Product: Schlage ND series.
2. Acceptable Manufacturers and Products: None.

B. Requirements:

1. Provide cylindrical locks conforming to ANSI/BHMA A156.2 Series 4000, Grade 1, and UL Listed for 3 hour fire doors.
2. Cylinders: Refer to “KEYING” article, herein.
3. Provide locks with standard 2-3/4 inches (70 mm) backset, unless noted otherwise, with 1/2 inch latch throw. Provide proper latch throw for UL listing at pairs.
4. Provide locksets with separate anti-rotation thru-bolts, and no exposed screws.
5. Provide independently operating levers with two external return spring cassettes mounted under roses to prevent lever sag.
6. Provide standard ASA strikes unless extended lip strikes are necessary to protect trim.
7. Provide electrified options as scheduled in the hardware sets.
8. Lever Trim: Solid cast levers without plastic inserts and wrought roses on both sides.

    a. Tactile Warning (Knurling): Where required by authority having jurisdiction. Provide on levers on exterior (secure side) of doors serving rooms considered to be hazardous.

2.05 EXIT DEVICES

A. Manufacturers and Products:

1. Scheduled Manufacturer and Product: Von Duprin 99 Series.
2. Acceptable Manufacturers and Products: None.

B. Requirements:

1. Provide exit devices tested to ANSI/BHMA A156.3 Grade 1 and UL listed for Panic Exit or Fire Exit Hardware.
2. Cylinders: Refer to “KEYING” article, herein.
3. Provide touchpad type exit devices, fabricated of brass, bronze, stainless steel, or aluminum, plated to standard architectural finishes to match balance of door hardware.
4. Touchpad must extend a minimum of one half of door width. No plastic inserts are allowed in touchpads.
5. Provide exit devices with deadlatching feature for security and for future addition of alarm kits and/or other electrified requirements.
6. Provide flush end caps for exit devices.
7. Provide exit devices with manufacturer’s approved strikes.
8. Provide exit devices cut to door width and height. Install exit devices at height recommended by exit device manufacturer, allowable by governing building codes, and approved by Architect.
9. Mount mechanism case flush on face of doors, or provide spacers to fill gaps behind devices. Where glass trim or molding projects off face of door, provide glass bead kits.
10. Provide cylinder or hex-key dogging as specified at non fire-rated openings.
11. Removable Mullions: 2 inches (51 mm) x 3 inches (76 mm) steel tube. Where scheduled as keyed removable mullion, provide type that can be removed by use of a keyed cylinder, which is self-locking when re-installed.

12. Provide electrified options as scheduled.
13. Install all panic hardware with thru bolts.
14. Provide exit devices with optional trim designs to match other lever and pull designs used on the project.

    a. Tactile Warning (Knurling): Where required by authority having jurisdiction. Provide on levers on exterior (secure side) of doors serving rooms considered to be hazardous.

2.06 CYLINDERS

A. Manufacturers:

   1. Scheduled Manufacturer: Best.

B. Requirements:

   1. Provide interchangeable cylinders/cores to match Owner's existing key system, compliant with ANSI/BHMA A156.5; latest revision; cylinder face finished to match lockset, manufacturer's series as indicated. Refer to "KEYING" article, herein.

C. Construction Keying:

   1. Replaceable Construction Cores.

      a. Provide temporary construction cores replaceable by permanent cores, furnished in accordance with the following requirements.
         1) 3 construction control keys
         2) 12 construction change (day) keys.

      b. Owner or Owner's Representative will replace temporary construction cores with permanent cores.

2.07 KEYING

A. Provide a factory registered keying system, complying with guidelines in ANSI/BHMA A156.28, incorporating decisions made at keying conference.

B. Provide cylinders/cores keyed into Owner's existing factory registered keying system.

C. Comply with guidelines in ANSI/BHMA A156.28, incorporating decisions made at keying conference.

D. Requirements:

   1. Provide permanent cylinders/cores keyed by the manufacturer according to the following key system.

      a. Master Keying system as directed by the Owner.

   2. Forward bitting list and keys separately from cylinders, by means as directed by Owner. Failure to comply with forwarding requirements will be cause for replacement of cylinders/cores involved at no additional cost to Owner.
   3. Provide keys with the following features:

a. Material: Nickel silver; minimum thickness of .107-inch (2.3mm)

4. Identification:

a. Mark permanent cylinders/cores and keys with applicable blind code per DHI publication “Keying Systems and Nomenclature” for identification. Do not provide blind code marks with actual key cuts.
b. Identification stamping provisions must be approved by the Architect and Owner.
c. Stamp cylinders/cores and keys with Owner’s unique key system facility code as established by the manufacturer; key symbol and embossed or stamped with “DO NOT DUPLICATE” along with the “PATENTED” or patent number to enforce the patent protection.
d. Failure to comply with stamping requirements will be cause for replacement of keys involved at no additional cost to Owner.
e. Forward permanent cylinders/cores to Owner, separately from keys, by means as directed by Owner.

5. Quantity: Furnish in the following quantities.

a. Change (Day) Keys: 3 per cylinder/core.
b. Permanent Control Keys: 3.
c. Master Keys: 6.

2.08 DOOR CLOSERS

A. Manufacturers and Products:

1. Scheduled Manufacturer and Product: LCN 4040XP series.
2. Acceptable Manufacturers and Products: None.

B. Requirements:

1. Provide door closers conforming to ANSI/BHMA A156.4 Grade 1 requirements by BHMA certified independent testing laboratory. ISO 9000 certify closers. Stamp units with date of manufacture code.
2. Provide door closers with fully hydraulic, full rack and pinion action with high strength cast iron cylinder, and full complement bearings at shaft.
3. Cylinder Body: 1-1/2 inch (38 mm) diameter with 3/4 inch (19 mm) diameter double heat-treated pinion journal.
4. Hydraulic Fluid: Fireproof, passing requirements of UL10C, and requiring no seasonal closer adjustment for temperatures ranging from 120 degrees F to -30 degrees F.
5. Spring Power: Continuously adjustable over full range of closer sizes, and providing reduced opening force as required by accessibility codes and standards.
6. Hydraulic Regulation: By tamper-proof, non-critical valves, with separate adjustment for latch speed, general speed, and backcheck.
7. Provide closers with solid forged steel main arms and factory assembled heavy-duty forged forearms for parallel arm closers.
8. Pressure Relief Valve (PRV) Technology: Not permitted.
9. Finish for Closer Cylinders, Arms, Adapter Plates, and Metal Covers: Powder coating finish which has been certified to exceed 100 hours salt spray testing as described in ANSI Standard A156.4 and ASTM B117, or has special rust inhibitor (SRI).
10. Provide special templates, drop plates, mounting brackets, or adapters for arms as required for details, overhead stops, and other door hardware items interfering with closer mounting.
11. Install all closers with thru bolts.

2.09 PROTECTION PLATES

A. Manufacturers:

1. Scheduled Manufacturer: Ives.
2. Acceptable Manufacturers: Burns, Rockwood.

B. Requirements:

1. Provide kick plates, mop plates, and armor plates minimum of 0.050 inch (1 mm) thick, beveled four edges as scheduled. Furnish with sheet metal or wood screws, finished to match plates.
2. Sizes of plates:

    a. Kick Plates: 12 inches (254 mm) high by 2 inches (51 mm) less width of door on single door and pairs of doors with mullions, 1 inch (25 mm) less width of door on pairs
    b. Armor Plates: 42 inches (914 mm) high by 2 inches (51 mm) less width of door on single doors, 1 inch (25 mm) less width of door on pairs

2.10 OVERHEAD STOPS AND OVERHEAD STOP/HOLDERS

A. Manufacturers:

1. Scheduled Manufacturers: Glynn-Johnson.
2. Acceptable Manufacturers: Rixson, Sargent.

B. Requirements:

1. Provide heavy duty concealed mounted overhead stop or holder as specified for exterior and interior vestibule single acting doors.
2. Provide heavy duty concealed mounted overhead stop or holder as specified for double acting doors.
3. Provide heavy or medium duty and concealed or surface mounted overhead stop or holder for interior doors as specified. Provide medium duty surface mounted overhead stop for interior doors and at any door that swings more than 140 degrees before striking wall, open against equipment, casework, sidelights, and where conditions do not allow wall stop or floor stop presents tripping hazard.
4. Where overhead holders are specified provide friction type at doors without closer and positive type at doors with closer.

2.11 DOOR STOPS AND HOLDERS

A. Manufacturers:

1. Scheduled Manufacturer: Ives.
2. Acceptable Manufacturers: Burns, Rockwood.

B. Provide door stops at each door leaf:

1. Provide wall stops wherever possible. Provide convex type where mortise type locks are used and concave type where cylindrical type locks are used.

2. Where a wall stop cannot be used, provide universal floor stops for low or high rise options.
3. Where wall or floor stop cannot be used, provide medium duty surface mounted overhead stop.

2.12 THRESHOLDS, SEALS, DOOR SWEEPS, AUTOMATIC DOOR BOTTOMS, AND GASKETING

A. Manufacturers:

1. Scheduled Manufacturer: Zero International.
2. Acceptable Manufacturers: National Guard, Reese.

B. Requirements:

1. Provide thresholds, weather-stripping (including door sweeps, seals, and astragals) and gasketing systems (including smoke, sound, and light) as specified and per architectural details. Match finish of other items.
2. Smoke- and Draft-Control Door Assemblies: Where smoke- and draft-control door assemblies are required, provide door hardware that meets requirements of assemblies tested according to UL 1784 and installed in compliance with NFPA 105.
3. Size of thresholds:

   a. Saddle Thresholds: 1/2 inch (13 mm) high by jamb width by door width
   b. Bumper Seal Thresholds: 1/2 inch (13 mm) high by 5 inches (127 mm) wide by door width

4. Provide door sweeps, seals, astragals, and auto door bottoms only of type where resilient or flexible seal strip is easily replaceable and readily available.

2.13 SILENCERS

A. Manufacturers:

1. Scheduled Manufacturer: Ives.
2. Acceptable Manufacturers: Burns, Rockwood.

B. Requirements:

1. Provide "push-in" type silencers for hollow metal or wood frames.
2. Provide one silencer per 30 inches (762 mm) of height on each single frame, and two for each pair frame.
3. Omit where gasketing is specified.

2.14 FINISHES

A. Finish: BHMA 626/652 (US26D); except:

1. Hinges at Exterior Doors: BHMA 630 (US32D)
2. Continuous Hinges: BHMA 630 (US32D)
3. Continuous Hinges: BHMA 628 (US28)
4. Push Plates, Pulls, and Push Bars: BHMA 630 (US32D)
5. Protection Plates: BHMA 630 (US32D)

6. Overhead Stops and Holders: BHMA 630 (US32D)
7. Door Closers: Powder Coat to Match
8. Wall Stops: BHMA 630 (US32D)
9. Latch Protectors: BHMA 630 (US32D)
10. Weatherstripping: Clear Anodized Aluminum
11. Thresholds: Mill Finish Aluminum

PART 3 - EXECUTION

3.01 EXAMINATION

A. Prior to installation of hardware, examine doors and frames, with Installer present, for compliance with requirements for installation tolerances, labeled fire-rated door assembly construction, wall and floor construction, and other conditions affecting performance.

B. Field verify existing doors and frames receiving new hardware and existing conditions receiving new openings. Verify that new hardware is compatible with existing door and frame preparation and existing conditions.

C. Examine roughing-in for electrical power systems to verify actual locations of wiring connections before electrified door hardware installation.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.02 PREPARATION

A. Where on-site modification of doors and frames is required:

1. Carefully remove existing door hardware and components being reused. Clean, protect, tag, and store in accordance with storage and handling requirements specified herein.
2. Field modify and prepare existing door and frame for new hardware being installed.
3. When modifications are exposed to view, use concealed fasteners, when possible.
4. Field verify required latch height with existing frame.
5. Prepare hardware locations and reinstall in accordance with installation requirements for new door hardware and with:

    a. Steel Doors and Frames: For surface applied door hardware, drill and tap doors and frames according to ANSI/SDI A250.6.
    b. Wood Doors: DHI WDHS.5 "Recommended Hardware Reinforcement Locations for Mineral Core Wood Flush Doors."
    c. Doors in rated assemblies: NFPA 80 for restrictions on on-site door hardware preparation.

3.03 INSTALLATION

A. Mount door hardware units at heights to comply with the following, unless otherwise indicated or required to comply with governing regulations.

1. Standard Steel Doors and Frames: ANSI/SDI A250.8.
2. Custom Steel Doors and Frames: HMMA 831.

3. Wood Doors: DHI WDHS.3, "Recommended Locations for Architectural Hardware for Wood Flush Doors."

B. Install each hardware item in compliance with manufacturer's instructions and recommendations, using only fasteners provided by manufacturer.

C. Do not install surface mounted items until finishes have been completed on substrate. Protect all installed hardware during painting.

D. Set units level, plumb and true to line and location. Adjust and reinforce attachment substrate as necessary for proper installation and operation.

E. Drill and countersink units that are not factory prepared for anchorage fasteners. Space fasteners and anchors according to industry standards.

F. Install operating parts so they move freely and smoothly without binding, sticking, or excessive clearance.

G. Hinges: Install types and in quantities indicated in door hardware schedule but not fewer than quantity recommended by manufacturer for application indicated or one hinge for every 30 inches (750 mm) of door height, whichever is more stringent, unless other equivalent means of support for door, such as spring hinges or pivots, are provided.

H. Lock Cylinders: Install construction cores to secure building and areas during construction period.

1. Replace construction cores with permanent cores as indicated in keying section.

I. Wiring: Coordinate with Division 26, ELECTRICAL sections for:

1. Conduit, junction boxes and wire pulls.
2. Connections to and from power supplies to electrified hardware.
3. Connections to fire/smoke alarm system and smoke evacuation system.
4. Connection of wire to door position switches and wire runs to central room or area, as directed by Architect.
5. Testing and labeling wires with Architect's opening number.

J. Door Closers: Mount closers on room side of corridor doors, inside of exterior doors, and stair side of stairway doors from corridors. Mount closers so they are not visible in corridors, lobbies and other public spaces unless approved by Architect.

K. Closer/Holders: Mount closer/holders on room side of corridor doors, inside of exterior doors, and stair side of stairway doors.

L. Power Supplies: Locate power supplies as indicated or, if not indicated, above accessible ceilings or in equipment room, or alternate location as directed by Architect.

M. Thresholds: Set thresholds in full bed of sealant complying with requirements specified in Division 07 Section "Joint Sealants."

N. Stops: Provide floor stops for doors unless wall or other type stops are indicated in door hardware schedule. Do not mount floor stops where they may impede traffic or present tripping hazard.

O. Perimeter Gasketing: Apply to head and jamb, forming seal between door and frame.

P. Meeting Stile Gasketing: Fasten to meeting stiles, forming seal when doors are closed.

Q. Door Bottoms: Apply to bottom of door, forming seal with threshold when door is closed.

3.04 ADJUSTING

A. Initial Adjustment: Adjust and check each operating item of door hardware and each door to ensure proper operation or function of every unit. Replace units that cannot be adjusted to operate as intended. Adjust door control devices to compensate for final operation of heating and ventilating equipment and to comply with referenced accessibility requirements.

1. Electric Strikes: Adjust horizontal and vertical alignment of keeper to properly engage lock bolt.
2. Door Closers: Adjust sweep period to comply with accessibility requirements and requirements of authorities having jurisdiction.

B. Occupancy Adjustment: Approximately three to six months after date of Substantial Completion, Installer's Architectural Hardware Consultant must examine and readjust each item of door hardware, including adjusting operating forces, as necessary to ensure function of doors and door hardware.

3.05 CLEANING AND PROTECTION

A. Clean adjacent surfaces soiled by door hardware installation.

B. Clean operating items as necessary to restore proper function and finish.

C. Provide final protection and maintain conditions that ensure door hardware is without damage or deterioration at time of Substantial Completion.

3.06 DOOR HARDWARE SCHEDULE

A. Hardware items are referenced in the following hardware. Refer to the above-specifications for special features, options, cylinders/keying, and other requirements.

B. Hardware Sets:

Abbreviation	Name
BES	Best Locking Systems
IVE	H.B. Ives
LCN	LCN Commercial Division
SCH	Schlage Lock Company
VON	Von Duprin
ZER	Zero International Inc

Hardware Group No. 01
For use on Door #(s):
17B 18B 20B
Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	SET	EXTERIOR HINGE	5BB1 SERIES (QTY, WEIGHT, SIZE, AS REQ'D) NRP	630	IVE
1	EA	STOREROOM LOCK	ND80BD RHO	626	SCH
1	EA	PERMANENT CORE	MATCH EXISTING KEY SYSTEM	626	BES
1	EA	SURFACE CLOSER (W/ SPRING STOP)	4040XP SCUSH TBWMS	689	LCN
1	EA	KICK PLATE	8400 12" B-CS	630	IVE
1	SET	GASKETING	8305A @ HEAD & JAMBS	AL	ZER
1	EA	DOOR SWEEP	39A	A	ZER
1	EA	SADDLE THRESHOLD	1/2" HIGH X DEPTH AS REQ'D	AL	ZER

Hardware Group No. 02
For use on Door #(s):
24A 25A
Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	SET	EXTERIOR HINGE	5BB1 SERIES (QTY, WEIGHT, SIZE, AS REQ'D) NRP	630	IVE
1	EA	PANIC HARDWARE	LD-99-NL-SNB	626	VON
1	EA	PERMANENT CORE	MATCH EXISTING KEY SYSTEM	626	BES
1	EA	SURFACE CLOSER (W/ SPRING STOP)	4040XP SCUSH TBWMS	689	LCN
1	EA	KICK PLATE	8400 12" B-CS	630	IVE
1	SET	GASKETING	8305A @ HEAD & JAMBS	AL	ZER
1	EA	DOOR SWEEP	39A	A	ZER
1	EA	SADDLE THRESHOLD	1/2" HIGH X DEPTH AS REQ'D	AL	ZER

Door#	HwSet#
17B	01
18B	01
20B	01
24A	02
25A	02

END OF SECTION

SECTION 088000

GLAZING

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Glass and glazing for the following products and applications:

    a. Steel doors, frames and sidelights specified in Section 081113 - HOLLOW METAL DOORS AND FRAMES.
    b. Glazed storefronts specified in Section 084110 - ALUMINUM-FRAMED STOREFRONTS.
    c. Interior lites.
    d. Security glazing film.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 081400 - FLUSH WOOD DOORS for factory glazing.
2. Section 085110 - ALUMINUM WINDOWS for factory glazing.

1.3 DEFINITIONS

A. Manufacturers of Glass Products: Firms that produce primary glass, fabricated glass, or both, as defined in referenced glazing publications.

B. Glass Thicknesses: Indicated by thickness designations in millimeters according to ASTM C 1036.

C. Interspace: Space between lites of an insulating-glass unit that contains dehydrated air or a specified gas.

D. Deterioration of Coated Glass: Defects developed from normal use that are attributed to the manufacturing process and not to causes other than glass breakage and practices for maintaining and cleaning coated glass contrary to manufacturer's written instructions. Defects include peeling, cracking, and other indications of deterioration in metallic coating.

E. Deterioration of Insulating Glass: Failure of hermetic seal under normal use that is attributed to the manufacturing process and not to causes other than glass breakage and practices for maintaining and cleaning insulating glass contrary to manufacturer's written instructions.

Evidence of failure is the obstruction of vision by dust, moisture, or film on interior surfaces of glass.

1.4 PERFORMANCE REQUIREMENTS

A. General: Provide glazing systems capable of withstanding normal thermal movement and wind and impact loads (where applicable) without failure, including loss or glass breakage attributable to the following: defective manufacture, fabrication, and installation; failure of sealants or gaskets to remain watertight and airtight; deterioration of glazing materials; or other defects in construction.

B. Glass Design: Glass thickness designations indicated are minimums and are for detailing only. Confirm glass thicknesses by analyzing Project loads and in-service conditions. Provide glass lites in the thickness designations indicated for various size openings, but not less than thicknesses and in strengths (annealed or heat treated) required to meet or exceed the following criteria:

1. Glass Thicknesses: Select minimum glass thicknesses to comply with ASTM E 1300, according to the following requirements:

a. Specified Design Wind Loads: As required by Code.
b. Probability of Breakage for Vertical Glazing: 8 lites per 1000 for lites set vertically or not more than 15 degrees off vertical and under wind action.

1) Load Duration: 60 seconds or less.

c. Maximum Lateral Deflection: For the following types of glass supported on all 4 edges, provide thickness required that limits center deflection at design wind pressure to 1/50 times the short side length or 1 inch, whichever is less.

1) For monolithic-glass lites heat-treated to resist wind loads.
2) For insulating glass.

d. Minimum Glass Thickness for Exterior Lites: Not less than 6 mm.

C. Thermal Movements: Provide glazing that allows for thermal movements resulting from the following maximum change (range) in ambient and surface temperatures acting on glass framing members and glazing components. Base engineering calculation on surface temperatures of materials due to both solar heat gain and nighttime-sky heat loss.

1. Temperature Change (Range): 120 deg F, ambient; 180 deg F, material surfaces.

D. Thermal and Optical Performance Properties: Provide glass with performance properties specified based on manufacturer's published test data, as determined according to procedures indicated below:

1. For monolithic-glass lites, properties are based on units with lites 6.0 mm thick.
2. For insulating-glass units, properties are based on units with lites 6.0 mm thick and a nominal 1/2-inch-wide interspace.
3. Center-of-Glass Values: Based on using LBL-44789 WINDOW 6.3 computer program for the following methodologies:

a. U-Factors: NFRC 100 expressed as Btu/ sq. ft. x h x deg F.
b. Solar Heat Gain Coefficient: NFRC 200.

c. Solar Optical Properties: NFRC 300.

1.5 SUBMITTALS

A. Product Data: For each glass product and glazing material indicated.

B. Samples: 12-inch- square Samples for each type of glass and glass assembly, glazing sealants.

C. Glazing Schedule: Use same designations indicated on Drawings for glazed openings in preparing a schedule listing glass types and thicknesses for each size opening and location.

D. Product Certificates: Signed by manufacturers of glass and glazing products certifying that products furnished comply with requirements.

1. For solar-control low-e-coated glass, provide documentation demonstrating that manufacturer of coated glass is certified by coating manufacturer.

E. Qualification Data: For installers.

F. Preconstruction Adhesion and Compatibility Test Report: From glazing sealant manufacturer indicating glazing sealants were tested for adhesion to glass and glazing channel substrates and for compatibility with glass and other glazing materials.

G. Product Test Reports: For each type of glazing products:

H. Warranties: Special warranties specified in this Section.

1.6 QUALITY ASSURANCE

A. Installer Qualifications: An experienced installer who has completed glazing similar in material, design, and extent to that indicated for this Project; whose work has resulted in glass installations with a record of successful in-service performance..

B. Source Limitations for Glass: Obtain the following through one source from a single manufacturer for each glass type: clear float glass, laminated glass and insulating glass.

C. Source Limitations for Glass Sputter-Coated with Solar-Control Low-E Coatings: Where solar-control low-e coatings of a primary glass manufacturer that has established a certified fabricator program is specified, obtain sputter-coated solar-control low-e-coated glass in fabricated units from a manufacturer that is certified by coated-glass manufacturer.

D. Source Limitations for Glazing Accessories: Obtain glazing accessories through one source from a single manufacturer for each product and installation method indicated.

E. Elastomeric Glazing Sealant Product Testing: Obtain sealant test results for product test reports in "Submittals" Article from a qualified testing agency based on testing current sealant formulations within a 36-month period.

1. Sealant Testing Agency Qualifications: An independent testing agency qualified according to ASTM C 1021 to conduct the testing indicated.
2. Test elastomeric glazing sealants for compliance with requirements specified by reference to ASTM C 920, and where applicable, to other standard test methods.

F. Preconstruction Adhesion and Compatibility Testing: Submit to elastomeric glazing sealant manufacturers, for testing indicated below, samples of each glazing material type, tape sealant, gasket, glazing accessory, and glass-framing member that will contact or affect elastomeric glazing sealants:

1. Use ASTM C 1087 to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of glazing sealants to glass, tape sealants, gaskets, and glazing channel substrates.
2. Submit not fewer than eight pieces of each type of material, including joint substrates, shims, joint-sealant backings, secondary seals, and miscellaneous materials.
3. Schedule sufficient time for testing and analyzing results to prevent delaying the Work.
4. For materials failing tests, obtain sealant manufacturer's written instructions for corrective measures, including the use of specially formulated primers.
5. Testing will not be required if elastomeric glazing sealant manufacturers submit data based on previous testing of current sealant products for adhesion to, and compatibility with, glazing materials matching those submitted.

G. Safety Glazing Products: Comply with testing requirements in 16 CFR 1201.

1. Subject to compliance with requirements, obtain safety glazing products permanently marked with certification label of the Safety Glazing Certification Council or another certification agency acceptable to authorities having jurisdiction.
2. Where glazing units, including Kind FT glass and laminated glass, are specified in Part 2 articles for glazing lites more than 9 sq. ft. in exposed surface area of one side, provide glazing products that comply with Category II materials, for lites 9 sq. ft. or less in exposed surface area of one side, provide glazing products that comply with Category I or II materials, except for hazardous locations where Category II materials are required by 16 CFR 1201 and regulations of authorities having jurisdiction.

H. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below, unless more stringent requirements are indicated. Refer to these publications for glazing terms not otherwise defined in this Section or in referenced standards.

1. GANA Publications: GANA's "Glazing Manual."
2. IGMA Publication for Insulating Glass: SIGMA TM-3000, "Glazing Guidelines for Sealed Insulating Glass Units."

I. Insulating-Glass Certification Program: Permanently marked either on spacers or on at least one component lite of units with appropriate certification label of the following testing and inspecting agency:

1. Insulating Glass Certification Council.

J. Mockups: Build mockups to verify selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Build mockup for types of windows indicated, in locations shown on Drawings.

K. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01.

1.7 DELIVERY, STORAGE, AND HANDLING

A. Protect glazing materials according to manufacturer's written instructions and as needed to prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.

B. For insulating-glass units that will be exposed to substantial altitude changes, comply with insulating-glass manufacturer's written recommendations for venting and sealing to avoid hermetic seal ruptures.

1.8 PROJECT CONDITIONS

A. Environmental Limitations: Do not proceed with glazing when ambient and substrate temperature conditions are outside limits permitted by glazing material manufacturers and when glazing channel substrates are wet from rain, frost, condensation, or other causes.

1. Do not install liquid glazing sealants when ambient and substrate temperature conditions are outside limits permitted by glazing sealant manufacturer or below 40 deg F.

1.9 WARRANTY

A. Manufacturer's Special Warranty for Coated-Glass Products: Manufacturer's standard form, made out to the Owner and signed by coated-glass manufacturer agreeing to replace coated-glass units that deteriorate as defined in "Definitions" Article, f.o.b. the nearest shipping point to Project site, within specified warranty period indicated below.

1. Warranty Period: Ten years from date of Substantial Completion.

B. Manufacturer's Special Warranty on Insulating Glass: Manufacturer's standard form, made out to the Owner and signed by insulating-glass manufacturer agreeing to replace insulating-glass units that deteriorate as defined in "Definitions" Article, f.o.b. the nearest shipping point to Project site, within specified warranty period indicated below.

1. Warranty Period: Ten years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 INSULATING-GLASS UNITS

A. Insulating-Glass Units for Vertical Glazing: 1 inch thick (25.0 mm) insulating glass consisting of two lites of 1/4 inch (6 mm) glass, low e coating on the No. 2 surface and argon gas filled. Provide one of the following or equal:

1. Vitro Architectural Glass (formerly PPG Industries); Graylite II.

a. Visible Light Transmittance: 7 percent.
b. Reflectance Visible Light, Exterior: 4 percent.
c. U Value (Winter): 0.29.
d. Solar Heat Gain Coefficient: 0.11.

2.2 GLASS PRODUCTS

A. Heat-Treated Float Glass: ASTM C 1048; Type I; Quality-Q3; Class I (clear) unless otherwise indicated; of kind and condition indicated.

1. Fabrication Process: By horizontal (roller-hearth) process with roll-wave distortion parallel to bottom edge of glass as installed unless otherwise indicated.
2. For uncoated glass, comply with requirements for Condition A.
3. For coated vision glass, comply with requirements for Condition C (other coated glass).

B. Tempered Float Glass: ASTM C 1048; Type I (transparent flat glass); Quality-Q3; Kind FT; 1/4 inch thick unless indicated otherwise.

C. Insulating-Glass Units, General: Factory-assembled units consisting of sealed lites of glass separated by an argon-filled interspace, and complying with ASTM E2190 and with requirements specified in this Section.

1. Provide Kind HS (heat-strengthened) float glass in place of annealed glass where needed to resist thermal stresses induced by differential shading of individual glass lites and to comply with glass design requirements specified in Part 1 “Performance Requirements” paragraph.
2. Provide Kind FT (fully tempered) glass lites where safety glass is indicated.
3. Overall Unit Thickness and Thickness of Each Lite: Dimensions indicated for insulating-glass units are nominal and the overall thicknesses of units are measured perpendicularly from outer surfaces of glass lites at unit’s edge.
4. Sealing System: Dual seal, with primary and secondary sealants as follows:

    a. Manufacturer’s Standard Sealants. Butyl primary and silicone secondary sealants. Secondary sealant shall cover entire spacer bar at IGU perimeter.

5. Spacer Specifications: Manufacturer’s standard spacer material. Spacer corners shall be bent, soldered, or welded. Keyed spacer corners will not be accepted. Spacer may have a mid-span spacer key located at the midpoint of the insulating glass unit head. Where a mid-span spacer key is used, the key must be fully embedded (all sides) in butyl sealant.

D. Security Glazing Film: Translucent, dimensionally stable, cast PVC film, 2-mil-minimum thickness, with pressure-sensitive, clear adhesive back for adhering to glass and releasable protective backing.

1. Manufacturers: Subject to compliance with requirements, available manufacturers that may be incorporated into the Work include, but are not limited to, the following:

    a. Avery Dennison, Graphics.
    b. FDC Graphic Films, Inc.
    c. Madico, Inc.
    d. 3M Scotchcal.

2. Basis-of-Design Product: 3M Scotchcal; S800.
3. Comply with requirements for safety glazing.
4. Use: Suitable for exterior and interior applications.
5. Patterns: As selected by Architect from manufacturer’s full range.

2.3 GLAZING SEALANTS

A. General: Provide products of type indicated, complying with the following requirements:

1. Compatibility: Verify glazing sealants that are compatible with one another and with other materials they will contact, including glass products, seals of insulating-glass units, interlayer of laminated glass, and glazing channel substrates, under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.
2. Suitability: Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated and for conditions existing at time of installation.
3. Colors of Exposed Glazing Sealants: As selected by Architect from manufacturer's full range.
4. VOC Emissions: Provide sealants in compliance with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
5. VOC Content:

    a. Structural Glazing Adhesives: 100 g/L.
    b. Architectural Sealants: 250 g/L.

6. Methylene chloride and perchloroethylene may not be intentionally added to sealants.

B. Elastomeric Glazing Sealants: Comply with ASTM C 920 and other requirements indicated for each liquid-applied chemically curing sealant specified, including those referencing ASTM C 920 classifications for type, grade, class, and uses related to exposure and joint substrates.

1. Single-Component Neutral- and Basic-Curing Silicone Glazing Sealants:

    a. Dow Corning Corporation; 790.
    b. GE Silicones; SilPruf LM SCS2700.
    c. Tremco Inc.; Spectrem 1.

2.4 GLAZING TAPES

A. Back-Bedding Mastic Glazing Tapes: Preformed, butyl-based elastomeric tape with a solids content of 100 percent; nonstaining and nonmigrating in contact with nonporous surfaces; with or without spacer rod as recommended in writing by tape and glass manufacturers for application indicated; packaged on rolls with a release paper backing; and complying with ASTM C 1281 and AAMA 800 for project conditions.

B. Expanded Cellular Glazing Tapes: Closed-cell, PVC foam tapes; factory coated with adhesive on both surfaces; packaged on rolls with release liner protecting adhesive; and complying with AAMA 800 for the following types:

1. Type 1, for glazing applications in which tape acts as the primary sealant.
2. Type 2, for glazing applications in which tape is used in combination with a full bead of liquid sealant.

2.5 MISCELLANEOUS GLAZING MATERIALS

A. General: Provide products of material, size, and shape complying with referenced glazing standard, requirements of manufacturers of glass and other glazing materials for application indicated, and with a proven record of compatibility with surfaces contacted in installation.

B. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.

C. Setting Blocks: Elastomeric material with a Shore, Type A durometer hardness of 85, plus or minus 5.

D. Spacers: Elastomeric blocks or continuous extrusions with a Shore, Type A durometer hardness required by glass manufacturer to maintain glass lites in place for installation indicated.

E. Edge Blocks: Elastomeric material of hardness needed to limit glass lateral movement (side walking).

2.6 FABRICATION OF GLAZING UNITS

A. Fabricate glazing units in sizes required to glaze openings indicated for Project, with edge and face clearances, edge and surface conditions, and bite complying with written instructions of product manufacturer and referenced glazing publications, to comply with system performance requirements.

B. Clean-cut or flat-grind vertical edges of butt-glazed monolithic lites in a manner that produces square edges with slight kerfs at junctions with outdoor and indoor faces.

C. Grind smooth and polish exposed glass edges and corners.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine framing glazing, with Installer present, for compliance with the following:

1. Manufacturing and installation tolerances, including those for size, squareness, and offsets at corners.
2. Presence and functioning of weep system.
3. Minimum required face or edge clearances.
4. Effective sealing between joints of glass-framing members.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Clean glazing channels and other framing members receiving glass immediately before glazing. Remove coatings not firmly bonded to substrates.

3.3 GLAZING, GENERAL

A. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.

B. Glazing channel dimensions, as indicated on Drawings, provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances. Adjust as required by Project conditions during installation.

C. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass is glass with edge damage or other imperfections that, when installed, could weaken glass and impair performance and appearance.

D. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction sealant-substrate testing.

E. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.

F. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.

G. Provide spacers for glass lites where length plus width is larger than 50 inches as follows:

1. Locate spacers directly opposite each other on both inside and outside faces of glass. Install correct size and spacing to preserve required face clearances, unless gaskets and glazing tapes are used that have demonstrated ability to maintain required face clearances and to comply with system performance requirements.
2. Provide 1/8-inch minimum bite of spacers on glass and use thickness equal to sealant width. With glazing tape, use thickness slightly less than final compressed thickness of tape.

H. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and according to requirements in referenced glazing publications.

I. Set glass lites in each series with uniform pattern, draw, bow, and similar characteristics.

J. Security Glazing Film: Apply squarely aligned to glass edges, uniformly smooth, and free from tears, air bubbles, wrinkles, and rough edges, in single sheet completely overlaying the back face of clean glass, according to manufacturer's written instructions, including surface preparation and application temperature limitations.

3.4 TAPE GLAZING

A. Position tapes on fixed stops so that, when compressed by glass, their exposed edges are flush with or protrude slightly above sightline of stops.

B. Install tapes continuously, but not necessarily in one continuous length. Do not stretch tapes to make them fit opening.

C. Cover vertical framing joints by applying tapes to heads and sills first and then to jambs. Cover horizontal framing joints by applying tapes to jambs and then to heads and sills.

D. Place joints in tapes at corners of opening with adjoining lengths butted together, not lapped. Seal joints in tapes with compatible sealant approved by tape manufacturer.

E. Do not remove release paper from tape until just before each glazing unit is installed.

F. Center glass lites in openings on setting blocks and press firmly against tape by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings.

3.5 SEALANT GLAZING (WET)

A. Install continuous spacers, or spacers combined with cylindrical sealant backing, between glass lites and glazing stops to maintain glass face clearances and to prevent sealant from extruding into glass channel and blocking weep systems until sealants cure. Secure spacers or spacers and backings in place and in position to control depth of installed sealant relative to edge clearance for optimum sealant performance.

B. Force sealants into glazing channels to eliminate voids and to ensure complete wetting or bond of sealant to glass and channel surfaces.

C. Tool exposed surfaces of sealants to provide a substantial wash away from glass.

3.6 CLEANING AND PROTECTION

A. Protect exterior glass from damage immediately after installation by attaching crossed streamers to framing held away from glass. Do not apply markers to glass surface. Remove nonpermanent labels, and clean surfaces.

B. Protect glass from contact with contaminating substances resulting from construction operations, including weld splatter. If, despite such protection, contaminating substances do come into contact with glass, remove substances immediately as recommended by glass manufacturer.

C. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than once a month, for buildup of dirt, scum, alkaline deposits, or stains; remove as recommended in writing by glass manufacturer.

D. Remove and replace glass that is broken, chipped, cracked, or abraded or that is damaged from natural causes, accidents, and vandalism, during construction period.

END OF SECTION

SECTION 096800

CARPETING

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Carpet sheet.
2. Carpet accessories.
3. Substrate preparation for carpet and accessories.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 096510 - RESILIENT FLOORING AND ACCESSORIES for resilient wall base and accessories installed with carpet.

1.3 SUBMITTALS

A. Product Data: For each type of product indicated.

1. Include manufacturer's written data on physical characteristics, durability, and fade resistance. Include installation recommendations for each type of substrate required.

B. Shop Drawings: Show the following:

1. Columns, doorways, enclosing walls or partitions, built-in cabinets, and locations where cutouts are required in carpet.
2. Carpet type, color, and dye lot.
3. Seam locations, types, and methods.
4. Type of subfloor.
5. Type of installation.
6. Pattern type, repeat size, location, direction, and starting point.
7. Pile direction.
8. Type, color, and location of insets and borders.
9. Type, color, and location of edge, transition, and other accessory strips.
10. Transition details to other flooring materials.

C. Samples: For each of the following products and for each color and texture required. Label each Sample with manufacturer's name, material description, color, pattern, and designation indicated on Drawings and in schedules.

1. Sheet Carpet: 12-inch- square Sample.
   a. Carpet Seam: 6-inch Sample.

2. Exposed Edge, Transition, and other Accessory Stripping: 12-inch-long Samples.

D. Product Schedule: Use same room and product designations indicated on Drawings and in schedules.

E. Sample Warranties: For special warranties.

F. Maintenance Data: For carpet to include in maintenance manuals specified in Division 01. Include the following:

1. Methods for maintaining carpet, including cleaning and stain-removal products and procedures and manufacturer's recommended maintenance schedule.
2. Precautions for cleaning materials and methods that could be detrimental to carpet.

1.4 QUALITY ASSURANCE

A. Carpeting Standard: Comply with the Carpet and Rug Institute’s “Commercial Carpet, Standard for Installation of Commercial Carpet, CRI 104” 2015 edition.

B. Installer Qualifications: An experienced installer who is certified by the Floor Covering Installation Board or who can demonstrate compliance with its certification program requirements.

C. Mockups: Before installing carpet, build mockups to verify selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.5 DELIVERY, STORAGE, AND HANDLING

A. General: Comply with CRI 104, Section 4, "Storage and Handling."

B. Deliver carpet in original mill protective covering with mill register numbers and tags attached.

1.6 PROJECT CONDITIONS

A. General: Comply with CRI 104, Section 7, "Site Conditions."

B. Environmental Limitations: Do not install carpet until wet work in spaces is complete and dry, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

C. Do not install carpet over concrete slabs until slabs have cured and are sufficiently dry to bond with adhesive and concrete slabs have pH range recommended by carpet manufacturer.

D. Where demountable partitions, equipment, or other items are indicated for installation on top of carpet, install carpet before installing these items.

1.7 WARRANTY

A. General Warranty: Special warranty specified in this Article shall not deprive the Owner of other rights the Owner may have under other provisions of the Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of the Contract Documents.

B. Special Carpet Warranty: Written warranty, signed by carpet manufacturer agreeing to replace carpet that does not comply with requirements or that fails within specified warranty period. Warranty does not include deterioration or failure of carpet due to unusual traffic, failure of substrate, vandalism, or abuse. Failures include, but are not limited to, more than 10 percent loss of face fiber, edge raveling, snags, runs, and delamination.

1. Warranty Period: Ten years from date of Substantial Completion.

1.8 EXTRA MATERIALS (ATTIC STOCK)

A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Carpet: Full-width rolls equal to 5 percent of amount installed for each type indicated, but not less than 10 sq. yd.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Acceptable Products: Subject to compliance with requirements, provide the following:

1. Tarkett; Powerbond.

2.2 CARPET

A. Performance Characteristics:

1. Critical Radiant Flux Classification: Not less than 0.45 W/sq. cm according to NFPA 253.
2. Smoke Density: Not more than 450, when tested in accordance with ASTM E 662 or NFPA 258.
3. Electrostatic Propensity: Less than 3.5 kV according to AATCC 134.

2.3 INSTALLATION ACCESSORIES

A. Trowelable Leveling and Patching Compounds: Latex-modified, hydraulic-cement-based formulation provided by or recommended by the carpet manufacturer.

B. Adhesives: Water-resistant, mildew-resistant, nonstaining type to suit products and subfloor conditions indicated, that complies with flammability requirements for installed carpet and that is recommended by carpet manufacturer.

C. Seaming Adhesive, for Sheet Carpet: Hot-melt adhesive tape or similar product recommended by carpet manufacturer for taping seams and butting cut edges at backing to form secure seams and to prevent pile loss at seams.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for maximum moisture content, alkalinity range, installation tolerances, and other conditions affecting carpet performance. Verify that substrates and conditions are satisfactory for carpet installation and comply with requirements specified.

B. Examine carpet for type, color, pattern, and potential defects.

C. Concrete Subfloors: Comply with CRI 104, Section 6, “Testing.” Verify that concrete slabs comply with ASTM F 710 and the following:

1. Slab substrates are dry and free of curing compounds, sealers, hardeners, and other materials that may interfere with adhesive bond. Determine adhesion and dryness characteristics by performing bond and moisture tests recommended by the carpet manufacturer.
2. Subfloors are free of cracks, ridges, depressions, scale, and foreign deposits.

D. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. General: Comply with CRI 104, Section 8, "Substrate Preparation”; and carpet manufacturer's written installation instructions for preparing substrates indicated to receive carpet installation.

B. Concrete Substrates: Prepare according to ASTM F 710.

1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
2. Alkalinity and Adhesion Testing: Perform tests recommended by flooring manufacturer. Proceed with installation only after substrate alkalinity falls within a range on pH scale not less than 5 or more than 9 pH, or as otherwise required in writing by manufacturer of flooring.
3. Moisture Vapor Emission Testing:

    a. Perform anhydrous calcium chloride test, ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. in 24 hours, or as otherwise required in writing by manufacturer of flooring.

4. Relative Humidity Testing:

    a. Perform relative humidity test, ASTM F 2170. Proceed with installation only after substrates have a maximum relative humidity level of 75 percent, or as otherwise required in writing by manufacturer of flooring.

5. Perform tests indicated above and as recommended by flooring manufacturer. Proceed with installation only after substrates pass testing.

C. Use trowelable leveling and patching compounds, according to manufacturer's written instructions, to fill cracks, holes, and depressions in substrates.

D. Broom and vacuum clean substrates to be covered immediately before installing carpet. After cleaning, examine substrates for moisture, alkaline salts, carbonation, or dust. Proceed with installation only after unsatisfactory conditions have been corrected.

3.3 INSTALLATION

A. Carpet Sheet, Direct-Glue-Down Installation: Comply with CRI Carpet Installation Standard, Section 13, "Direct Glue-Down Installation."

1. Comply with carpet sheet manufacturer's written recommendations for seam locations and direction of carpet; maintain uniformity of carpet direction and lay of pile. At doorways, center seams under the door in closed position.

B. Install pattern parallel to walls and borders.

C. Do not bridge building expansion joints with carpet.

D. Cut and fit carpet to butt tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, edgings, thresholds, and nosings. Bind or seal cut edges as recommended by carpet manufacturer.

E. Extend carpet into toe spaces, door reveals, closets, open-bottomed obstructions, removable flanges, alcoves, and similar openings.

F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on finish flooring as marked on subfloor. Use nonpermanent, nonstaining marking device.

3.4 CLEANING AND PROTECTION

A. Perform the following operations immediately after installing carpet:

1. Remove excess adhesive, seam sealer, and other surface blemishes using cleaner recommended by carpet manufacturer.
2. Remove yarns that protrude from carpet surface.
3. Vacuum carpet using commercial machine with face-beater element and HEPA filter.

B. Protect installed carpet to comply with CRI 104, Section 13, "Direct Glue Down", 13.7.2 “” Materials for Protection”.

C. Protect carpet against damage from construction operations and placement of equipment and fixtures during the remainder of construction period. Use protection methods indicated or recommended in writing by carpet manufacturer.

END OF SECTION

SECTION 099000

PAINTING AND COATING

PART 1 GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Field painting of exposed interior items and surfaces.
2. Field painting of exposed exterior items and surfaces.
3. Surface preparation for painting.

1.3 DEFINITIONS AND EXTENT

A. General: Standard coating terms defined in ASTM D 16 apply to this Section.

1. Flat refers to a lusterless or matte finish with a gloss range below 15 when measured at an 85-degree meter.
2. Eggshell refers to low-sheen finish with a gloss range between 20 and 35 when measured at a 60-degree meter.
3. Semigloss refers to medium-sheen finish with a gloss range between 35 and 70 when measured at a 60-degree meter.
4. Full gloss refers to high-sheen finish with a gloss range more than 70 when measured at a 60-degree meter.

B. This Section includes surface preparation and field painting of exposed exterior and interior items and surfaces.

1. Surface preparation, priming, and finish coats specified in this Section are in addition to shop priming and surface treatment specified in other Sections.

C. Paint exposed surfaces, except where these Specifications indicate that the surface or material is not to be painted or is to remain natural. If an item or a surface is not specifically mentioned, paint the item or surface the same as similar adjacent materials or surfaces. If a color of finish is not indicated, Architect will select from standard colors and finishes available.

1. Painting includes field painting of exposed bare and covered pipes and ducts (including color coding), hangers, exposed steel and iron supports, and surfaces of mechanical and electrical equipment that do not have a factory-applied final finish.

D. Do NOT paint prefinished items, concealed surfaces, finished metal surfaces, operating parts, and labels.

1. Prefinished items include the following factory-finished components:
   a. Architectural woodwork.
   b. Acoustical wall panels.
   c. Toilet enclosures.
   d. Metal lockers.
   e. Kitchen appliances.
   f. Elevator entrance doors and frames.
   g. Elevator equipment.
   h. Finished mechanical and electrical equipment.
   i. Light fixtures.
2. Concealed surfaces include walls or ceilings in the following generally inaccessible spaces:
   a. Foundation spaces.
   b. Furred areas.
   c. Ceiling plenums.
   d. Utility tunnels.
   e. Pipe spaces.
   f. Duct shafts.
   g. Elevator shafts.
3. Finished metal surfaces include the following:
   a. Anodized aluminum.
   b. Stainless steel.
   c. Chromium plate.
   d. Copper and copper alloys.
   e. Bronze and brass.
4. Operating parts include moving parts of operating equipment and the following:
   a. Valve and damper operators.
   b. Linkages.
   c. Sensing devices.
   d. Motor and fan shafts.
5. Labels: Do not paint over UL, FMG, or other code-required labels or equipment name, identification, performance rating, or nomenclature plates.

1.4 SUBMITTALS

A. Product Data: For each paint system indicated. Include block fillers and primers.

   1. Material List: An inclusive list of required coating materials. Indicate each material and cross-reference specific coating, finish system, and application. Identify each material by manufacturer's catalog number and general classification.
      a. Disclose material ingredients by name and Chemical Abstract Service (CAS) Registry Number.
   2. Manufacturer's Information: Manufacturer's technical information, including label analysis and instructions for handling, storing, and applying each coating material.

B. Samples for Verification: For each color and material to be applied, with texture to simulate actual conditions, on representative Samples of the actual substrate.

   1. Provide stepped Samples, defining each separate coat, including block fillers and primers. Use representative colors when preparing Samples for review. Resubmit until required sheen, color, and texture are achieved.
   2. Provide a list of materials and applications for each coat of each Sample. Label each Sample for location and application.
   3. Submit two 8 inch by 12 inch Samples for each type of finish coating for Architect's review of color and texture only.

C. Qualification Data: For Applicator.

1.5 QUALITY ASSURANCE

A. Applicator Qualifications: A firm or individual experienced in applying paints and coatings similar in material, design, and extent to those indicated for this Project, whose work has resulted in applications with a record of successful in-service performance.

B. Source Limitations: Obtain block fillers and primers for each coating system from the same manufacturer as the finish coats.

C. Mockups: Provide a full-coat benchmark finish sample for each type of coating and substrate required. Comply with procedures specified in PDCA P5. Duplicate finish of approved sample Submittals.

1. Architect will select one room or surface to represent surfaces and conditions for application of each type of coating and substrate.
   a. Wall Surfaces: Provide samples on at least 100 sq. ft.
   b. Small Areas and Items: Architect will designate items or areas required.
2. Apply benchmark samples, according to requirements for the completed Work, after permanent lighting and other environmental services have been activated. Provide required sheen, color, and texture on each surface.
   a. After finishes are accepted, Architect will use the room or surface to evaluate coating systems of a similar nature.
3. Final approval of colors will be from benchmark samples.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver materials to Project site in manufacturer's original, unopened packages and containers bearing manufacturer's name and label and the following information:

1. Product name or title of material.
2. Product description (generic classification or binder type).
3. Manufacturer's stock number and date of manufacture.
4. Contents by volume, for pigment and vehicle constituents.
5. Thinning instructions.
6. Application instructions.
7. Color name and number.
8. VOC content.

B. Store materials not in use in tightly covered containers in a well-ventilated area at a minimum ambient temperature of 45 deg F. Maintain storage containers in a clean condition, free of foreign materials and residue.

1. Protect from freezing. Keep storage area neat and orderly. Remove oily rags and waste daily.

1.7 PROJECT CONDITIONS

A. Apply waterborne paints only when temperatures of surfaces to be painted and surrounding air are between 50 and 90 deg F.

B. Apply solvent-thinned paints only when temperatures of surfaces to be painted and surrounding air are between 45 and 95 deg F.

C. Do not apply paint in snow, rain, fog, or mist; or when relative humidity exceeds 85 percent; or at temperatures less than 5 deg F above the dew point; or to damp or wet surfaces.

1. Painting may continue during inclement weather if surfaces and areas to be painted are enclosed and heated within temperature limits specified by manufacturer during application and drying periods.

1.8 EXTRA MATERIALS (ATTIC STOCK)

A. Furnish extra materials that match and are from same production runs as products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Paint: Furnish one unopened gallon of each type of paint and coating work, in color and gloss as used for the Project.

PART 2 PRODUCTS

2.1 MANUFACTURERS

A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work are listed in the Finish Schedule at the end of this Section.

2.2 PAINT MATERIALS, GENERAL

A. Material Compatibility: Provide block fillers, primers, and finish-coat materials that are compatible with one another and with the substrates indicated under conditions of service and application, as demonstrated by manufacturer based on testing and field experience.

B. Material Quality: Provide manufacturer's best-quality paint material of the various coating types specified that are factory formulated and recommended by manufacturer for application indicated. Paint-material containers not displaying manufacturer's product identification will not be acceptable.

1. Proprietary Names: Use of manufacturer's proprietary product names to designate colors or materials is not intended to imply that products named are required to be used to the exclusion of equivalent products of other manufacturers. Furnish manufacturer's material data and certificates of performance for proposed substitutions.

C. Paint Colors (PT-#): Refer to Finish Schedule.

PART 3 EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Applicator present, for compliance with requirements for paint application.

1. Proceed with paint application only after unsatisfactory conditions have been corrected and surfaces receiving paint are thoroughly dry.
2. Start of painting will be construed as Applicator's acceptance of surfaces and conditions within a particular area.

B. Coordination of Work: Review other Sections in which primers are provided to ensure compatibility of the total system for various substrates. On request, furnish information on characteristics of finish materials to ensure use of compatible primers.

1. Notify Architect about anticipated problems when using the materials specified over substrates primed by others.

3.2 PREPARATION

A. General: Remove hardware and hardware accessories, plates, machined surfaces, lighting fixtures, and similar items already installed that are not to be painted. If removal is impractical or impossible because of size or weight of the item, provide surface-applied protection before surface preparation and painting.

1. After completing painting operations in each space or area, reinstall items removed using workers skilled in the trades involved.

B. Cleaning: Before applying paint or other surface treatments, clean substrates of substances that could impair bond of the various coatings. Remove oil and grease before cleaning.

1. Schedule cleaning and painting so dust and other contaminants from the cleaning process will not fall on wet, newly painted surfaces.

C. Surface Preparation: Clean and prepare surfaces to be painted according to manufacturer's written instructions and technical bulletins for each particular substrate condition and as specified.

1. Provide barrier coats over incompatible primers or remove and reprime.
2. Cementitious Materials: Prepare concrete, concrete unit masonry, cement plaster, and mineral-fiber-reinforced cement panel surfaces to be painted. Remove efflorescence, chalk, dust, dirt, grease, oils, and release agents. Roughen as required to remove glaze. If hardeners or sealers have been used to improve curing, use mechanical methods of surface preparation.
   a. Use abrasive blast-cleaning methods if recommended by paint manufacturer.
   b. Determine alkalinity and moisture content of surfaces by performing appropriate tests. If surfaces are sufficiently alkaline to cause the finish paint to blister and burn, correct this condition before application. Do not paint surfaces if moisture content exceeds that permitted in manufacturer's written instructions.
   c. Clean concrete floors to be painted with a 5 percent solution of muriatic acid or other etching cleaner. Flush the floor with clean water to remove acid, neutralize with ammonia, rinse, allow to dry, and vacuum before painting.
3. Wood: Clean surfaces of dirt, oil, and other foreign substances with scrapers, mineral spirits, and sandpaper, as required. Sand surfaces exposed to view smooth and dust off.
   a. Scrape and clean small, dry, seasoned knots, and apply a thin coat of recommended knot sealer before applying primer. After priming, fill holes and imperfections in finish surfaces with putty or plastic wood filler. Sand smooth when dried.
   b. Prime, stain, or seal wood to be painted immediately on delivery. Prime edges, ends, faces, undersides, and back sides of wood, including cabinets, counters, cases, and paneling.
   c. If transparent finish is required, backprime with clear sealer.

d. Backprime paneling on interior partitions where masonry, plaster, or other wet wall construction occurs on back side.
e. Seal tops, bottoms, and cutouts of unprimed wood doors with a heavy coat of varnish or sealer immediately on delivery.

4. Ferrous Metals: Clean ungalvanized ferrous-metal surfaces that have not been shop coated; remove oil, grease, dirt, loose mill scale, and other foreign substances. Use solvent or mechanical cleaning methods that comply with SSPC's recommendations.
   a. Exterior Exposed Steel: Clean steel surfaces in accordance with SSPC-SP 6/NACE No. 3 Commercial Blast Cleaning. Abrasive blast cleaned surfaces shall exhibit a uniform, angular profile of 1.5-3.0 mils. Prime cleaned surfaces within 8 hours and prior to surface rusting.
   b. Interior Exposed Steel, in Humid Environments: Clean steel surfaces in accordance with SSPC-SP 6/NACE No. 3 Commercial Blast Cleaning. Abrasive blast cleaned surfaces shall exhibit a uniform, angular profile of 1.5-3.0 mils. Prime cleaned surfaces within 8 hours and prior to surface rusting.
   c. Interior Exposed Steel, in Dry Environments: Clean steel surfaces in accordance with SSPC-SP2 or SP3 Hand or Power Tool Cleaning.
5. Galvanized Surfaces: Clean galvanized surfaces in accordance with SSPC-SP16 Brush off Blast Cleaning of Galvanized Steel and NonFerrous Metals, to achieve a minimum 1 mil anchor profile.

D. Material Preparation: Mix and prepare paint materials according to manufacturer's written instructions.

1. Maintain containers used in mixing and applying paint in a clean condition, free of foreign materials and residue.
2. Stir material before application to produce a mixture of uniform density. Stir as required during application. Do not stir surface film into material. If necessary, remove surface film and strain material before using.
3. Use only thinners approved by paint manufacturer and only within recommended limits.

E. Tinting: Tint each undercoat a lighter shade to simplify identification of each coat when multiple coats of same material are applied. Tint undercoats to match the color of the finish coat, but provide sufficient differences in shade of undercoats to distinguish each separate coat.

3.3 APPLICATION

A. General: Apply paint according to manufacturer's written instructions. Use applicators and techniques best suited for substrate and type of material being applied.

1. Paint colors, surface treatments, and finishes are indicated in the paint schedules.
2. Do not paint over dirt, rust, scale, grease, moisture, scuffed surfaces, or conditions detrimental to formation of a durable paint film.
3. Provide finish coats that are compatible with primers used.
4. The term "exposed surfaces" includes areas visible when permanent or built-in fixtures, grilles, convector covers, covers for finned-tube radiation, and similar components are in place. Extend coatings in these areas, as required, to maintain system integrity and provide desired protection.
5. Paint surfaces behind movable equipment and furniture the same as similar exposed surfaces. Before final installation of equipment, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
6. Paint interior surfaces of ducts with a flat, nonspecular black paint where visible through registers or grilles.
7. Paint backsides of access panels and removable or hinged covers to match exposed

surfaces.
8. Finish exterior doors and doors in wet areas on tops, bottoms, and side edges the same as exterior faces.
9. Sand lightly between each succeeding enamel or varnish coat.

B. Scheduling Painting: Apply first coat to surfaces that have been cleaned, pretreated, or otherwise prepared for painting as soon as practicable after preparation and before subsequent surface deterioration.

1. The number of coats and film thickness required are the same regardless of application method. Do not apply succeeding coats until previous coat has cured as recommended by manufacturer. If sanding is required to produce a smooth, even surface according to manufacturer's written instructions, sand between applications.
2. Omit primer over metal surfaces that have been shop primed and touchup painted.
3. If undercoats, stains, or other conditions show through final coat of paint, apply additional coats until paint film is of uniform finish, color, and appearance. Give special attention to ensure that edges, corners, crevices, welds, and exposed fasteners receive a dry film thickness equivalent to that of flat surfaces.
4. Allow sufficient time between successive coats to permit proper drying. Do not recoat surfaces until paint has dried to where it feels firm, and does not deform or feel sticky under moderate thumb pressure, and until application of another coat of paint does not cause undercoat to lift or lose adhesion.

C. Application Procedures: Apply paints and coatings by brush, roller, spray, or other applicators according to manufacturer's written instructions.

1. Brushes: Use brushes best suited for type of material applied. Use brush of appropriate size for surface or item being painted.
2. Rollers: Use rollers of carpet, velvet-back, or high-pile sheep's wool as recommended by manufacturer for material and texture required.
3. Spray Equipment: Use airless spray equipment with orifice size as recommended by manufacturer for material and texture required.

D. Minimum Coating Thickness: Apply paint materials no thinner than manufacturer's recommended spreading rate to achieve dry film thickness indicated. Provide total dry film thickness of the entire system as recommended by manufacturer.

E. Mechanical and Electrical Work: Painting of mechanical and electrical work is limited to items exposed in equipment rooms and occupied spaces.

F. Mechanical items to be painted include, but are not limited to, the following:

1. Uninsulated metal piping.
2. Uninsulated plastic piping.
3. Pipe hangers and supports.
4. Tanks that do not have factory-applied final finishes.
5. Visible portions of internal surfaces of metal ducts, without liner, behind air inlets and outlets.
6. Duct, equipment, and pipe insulation having "all-service jacket" or other paintable jacket material.
7. Mechanical equipment that is indicated to have a factory-primed finish for field painting.

G. Electrical items to be painted include, but are not limited to, the following:

1. Switchgear.

2. Panelboards.
3. Electrical equipment that is indicated to have a factory-primed finish for field painting.

H. Block Fillers: Apply block fillers to concrete masonry block at a rate to ensure complete coverage with pores filled.

I. Prime Coats: Before applying finish coats, apply a prime coat, as recommended by manufacturer, to material that is required to be painted or finished and that has not been prime coated by others. Recoat primed and sealed surfaces where evidence of suction spots or unsealed areas in first coat appears, to ensure a finish coat with no burn-through or other defects due to insufficient sealing.

J. Pigmented (Opaque) Finishes: Completely cover surfaces as necessary to provide a smooth, opaque surface of uniform finish, color, appearance, and coverage. Cloudiness, spotting, holidays, laps, brush marks, runs, sags, ropiness, or other surface imperfections will not be acceptable.

K. Transparent (Clear) Finishes: Use multiple coats to produce a glass-smooth surface film of even luster. Provide a finish free of laps, runs, cloudiness, color irregularity, brush marks, orange peel, nail holes, or other surface imperfections.

1. Provide satin finish for final coats.

L. Completed Work: Match approved samples for color, texture, and coverage. Remove, refinish, or repaint work not complying with requirements.

3.4 FIELD QUALITY CONTROL

A. The Owner reserves the right to invoke the following test procedure at any time and as often as the Owner deems necessary during the period when paint is being applied:

1. The Owner will engage a qualified independent testing agency to sample paint material being used. Samples of material delivered to Project will be taken, identified, sealed, and certified in the presence of Contractor.
2. Testing agency will perform appropriate tests for the following characteristics as required by the Architect.
3. The Architect may direct Contractor to stop painting if test results show material being used does not comply with specified requirements. Contractor shall remove noncomplying paint from Project site, pay for testing, and repaint surfaces previously coated with the noncomplying paint. If necessary, Contractor may be required to remove noncomplying paint from previously painted surfaces if, on repainting with specified paint, the two coatings are incompatible.

3.5 CLEANING

A. Cleanup: At the end of each workday, remove empty cans, rags, rubbish, and other discarded paint materials from Project site.

1. After completing painting, clean glass and paint-spattered surfaces. Remove spattered paint by washing and scraping without scratching or damaging adjacent finished surfaces.

3.6 PROTECTION

A. Protect work of other trades, whether being painted or not, against damage from painting. Correct damage by cleaning, repairing or replacing, and repainting, as approved by Architect.

B. Provide "Wet Paint" signs to protect newly painted finishes. After completing painting operations, remove temporary protective wrappings provided by others to protect their work.

1. After work of other trades is complete, touch up and restore damaged or defaced painted surfaces. Comply with procedures specified in PDCA P1.

3.7 PAINT SCHEDULE

A. Schedule: Provide products and number of coats specified. Use of manufacturer's proprietary product names to designate colors, materials, generic class, standard of quality and performance criteria and is not intended to imply that products named are required to be used to the exclusion of equivalent performing products of other manufacturers.

B. Interior Paint Schedule, Typical:

1. Interior Gypsum Wallboard (GWB), Latex Paint Finish:
   a. One Coat, Primer: MPI 50 X-Green and 149 X-Green.
      1). Moore; Ultra Spec 500 Interior Latex Primer N534.
      2). PPG; Pure Performance Interior Latex Primer 9-900.
      3). PPG; Speedhide Zero VOC Interior Primer 6-4900XI series.
      4). PPG; Speedhide Pro EV Zero VOC Interior Primer 12-900XI series.
      5). S-W; ProMar 200 HP Zero VOC Interior Primer.
   b. And Two Coats, Flat Finish: At ceilings and elsewhere as indicated. MPI 53 X-Green.
      1). Moore; Ultra Spec 500 Interior Latex Flat T535.
      2). PPG; Speedhide Zero VOC Interior Latex Flat 6-4110XI series.
      3). PPG; Speedhide Pro EV Zero VOC Interior Latex Flat 12-110XI series.
      4). S-W; ProMar 400 HP Zero VOC Interior Flat.
   c. or
   d. And Two Coats, Eggshell Finish: At walls and elsewhere as indicated. MPI 144 X-Green.
      1). Moore; Ultra Spec 500 Interior Latex Eggshell T538.
      2). PPG; Speedhide Zero VOC Interior Latex Eggshell 6-4310XI series.
      3). PPG; Speedhide Pro EV Zero VOC Interior Latex Eggshell 12-110XI series.
      4). S-W; ProMar 200 HP Zero VOC Interior Eg-Shel.
   e. or
   f. And Two Coats, Semi-Gloss Finish: At toilet rooms, other wet areas, and elsewhere as indicated. MPI 54 X-Green.
      1). Moore; Ultra Spec 500 Interior Latex Semi-Gloss T546.
      2). PPG; Speedhide Zero VOC Interior Latex Semi-Gloss 6-4510XI series.
      3). PPG; Speedhide Pro EV Zero VOC Interior Latex Semi-Gloss 12-110XI series.
      4). S-W; ProMar 200 HP Zero VOC Interior Semi-Gloss.
2. Interior Architectural Woodwork, Finish Carpentry, and Wood Doors (softwoods, paint grade hardwoods, MDF, MDO, and hardwood veneers), Latex Paint Finish:
   a. One Coat, Primer:
      1) Moore; Ultra Spec 500 Interior Latex Primer 534.
      2) Pittsburgh Paints; Seal Grip Interior/Exterior Acrylic Universal Primer/Sealer 17-921XI series.
      3) S-W; ProMar 200 HP Zero VOC Interior Primer.

b. And Two Coats, Semi-Gloss:
1) Moore; Ultra Spec 500 Interior Latex Satin Pearl 545.
2) Pittsburgh Paints; Speedhide Max Zero VOC Interior Latex Lo-Lustre 6-9610 Series.
3) S-W; ProMar 200 HP Zero VOC Interior Semi-Gloss.

3. Interior Concrete Masonry Unit (CMU), Latex Paint Finish:
a. One Coat, Block Filler:
1). Moore; Ultra Spec Hi-Build Masonry Block Filler 571.
2). PPG; Perma-Crete 4-603. Less than 100 g/L.
3). PPG; Speedhide Interior Masonry Hi Fill Latex Block Filler 6-15XI.
4). S-W; PrepRite Block Filler B25W25.
b. And Two Coats, Eggshell Finish: At walls and elsewhere as indicated.
1). Moore; Ultra Spec 500 Interior Latex Eggshell T538.
2). PPG; Speedhide Zero VOC Interior Latex Eggshell 6-4310XI series.
3). S-W; ProMar 200 HP Zero VOC Interior Eg-Shel.
4. Interior Exposed Steel, Joists, Ductwork, Conduit and Similar Items (where indicated), Waterborne Dry-Fall or Dry-Fog Painted System:
a. One Coat:
1). Moore; Latex Dry Fall Flat 395 at 2.5 to 3.0 mils DFT.
2). PPG; Speedhide Super Tech WB Interior Dry-Fog Latex 6-725XI Flat at 2.0 to 2.5 mils DFT.
3). S-W; WB Pro Industrial Waterborne Acrylic Dryfall Flat B42 series at 2.5 to 3.0 mils DFT.
4). Tnemec 115 WB Unibond DF at 2.5 to 3.0 mils DFT.
5. Interior Concrete Floor, Clear Exposed Sealer (Silicate type):
a. One Coat:
1). Curecrete Chemical; Ashford Formula.
2). Tnemec (Chem Probe); Series 629 CT Densifyer.
3). WR Meadows; Liqui-Hard.
4). Laticrete; L&M Seal Hard.
5). Prosoco; Consolideck LS.

C. Interior Paint Schedule, High Performance and Specialty Systems:

1. Interior Gypsum Wallboard and Plaster at Laboratories, Toilet Rooms, and Other Wet Areas, Urethane Coating:
a. Surface Preparation: Cured, clean and dry, free of surface contaminants.
b. One Coat:
1). Tnemec 201 Epoxoprime at 3.0- 4.0 mils DFT.
2). PPG PMC Amerlock Sealer at 3.0 to 4.5 mils DFT.
3). Dupont Hi-Solids Colar primer at 3.0 to 4.0 mils DFT.
4). International Interseal 670 HS at 3.0 to 4.0 mils DFT.
c. And One Coat:
1). Tnemec 280 Tneme-glaze at 6.0 to 8.0 mils DFT.
2). PPG PMC Amercoat 351 Epoxy at 6.0 to 8.0 mils DFT.
3). Dupont 100 % Solids Epoxy at 8.0-10.0 mils.
4). International Interseal 670 HS at 3.0 to 4.0 mils DFT.
d. And One Coat:
1). Tnemec 1080 or 1081 Endurashield WB at 3.0 to 3.5 mils DFT.
2). PPG PMC AmerShield VOC at 2.0 to 3.0 mils DFT.
3). Dupont WB Urethane at 3.5 to 4.0 mils DFT.
4). International Water Borne Urethane at 3.0 to 4.0 mils DFT.
2. Interior Gypsum Wallboard, Epoxy/Acrylic Coating:
a. Surface Preparation: Cured, clean and dry, free of surface contaminants.
b. Two Coats: Tnemec 27WB at 8-10 mils DFT.

c. And One Coat: Tnemec 1028 at 2-3 mils DFT.

3. Interior Concrete Ceiling Surfaces in Dry Areas, Acrylic Paint Finish:
   a. One Coat:
      1). Tnemec 151 Elasto-Grip at 2.0 mils DFT.
      2). PPG PMC Amerlock Sealer at 1.0 mils DFT.
      3). Dupont High Solids Acrylic Primer at 2.0 mils DFT.
      4). International Intercryl 520 at 3.0 mils DFT.
   b. And Two Coats, Semi-Gloss Finish:
      1). Tnemec 1028/1029 Enduratone at 2.0 –3.0 mils DFT per coat min.
      2). PPG PMC Amercoat 220 at 3.0 mils DFT.
      3). Dupont High Solids Acrylic at 3.0 mils DFT.
      4). International Intercryl 530 at 3.0 mils DFT.
4. Interior Concrete Masonry Units, Epoxy/Acrylic Coating:
   a. Surface Preparation: Cured, clean and dry, free of surface contaminants.
   b. One Coat: Tnemec 130 Envirofil at 100 sqft/gal.
   c. And One Coat: Tnemec 27WB at 8-10 mils DFT.
   d. And One Coat: Tnemec 1028 at 2-3 mils DFT.
5. Interior Concrete Masonry Units, Epoxy/Urethane Coating:
   a. Surface Preparation: Cured, clean and dry, free of surface contaminants.
   b. One Coat:
      1). Tnemec 130 Envirofil at 100 sqft/gal.
      2). PPG PMC Nu-Klad 965 at 100 sqft/gal.
      3). Dupont 25P at 100 sq/ft/gal.
      4). International Acrylic Cementitious Block Filler at 80 sqft/gal.
   c. And One Coat:
      1). Tnemec 280 Tneme-Glaze at 6.0 8.0 mils DFT.
      2). PPG PMC Amercoat 351 6.0 to 8.0 mils DFT.
      3). Dupont 100% Solids Epoxy at 7.0 to 9.0 mils DFT.
      4). International Interseal 670 HS at 8.0 to 10.0 mils DFT.
   d. And One Coat:
      1). Tnemec 1080 or 1081 EnduraShield at 3.0 to 4.0 mils DFT.
      2). PPG PMC AmerShield VOC at 3.0 to 4.0 mils DFT.
      3). Dupont Imron WB Urethane at 3.0 to 4.0 mils DFT.
      4). International Water Borne Urethane at 3.0 to 4.0 mils DFT.
6. Interior Concrete Walls Exposed to View, Urethane Coating:
   a. Surface Preparation: Cured, clean and dry, free of surface contaminants.
   b. And One Coat:
      1). Tnemec 201 Epoxoprime at 3.0- 4.0 mils DFT.
      2). PPG PMC Amerlock Sealer at 3.0 to 4.5 mils DFT.
      3). Dupont Hi-Solids Colar primer at 3.0 to 4.0 mils DFT.
      4). International Interseal 670 HS at 3.0 to 4.0 mils DFT.
   c. And One Coat:
      1). Tnemec 280 Tneme-glaze at 6.0 to 8.0 mils DFT.
      2). PPG PMC Amercoat 351 Epoxy at 6.0 to 8.0 mils DFT.
      3). Dupont 100 % Solids Epoxy at 8.0-10.0 mils.
      4). International Interseal 670 HS at 3.0 to 4.0 mils DFT.
   d. And One Coat:
      1). Tnemec 1080 or 1081 EnduraShield at 3.0 to 3.5 mils DFT.
      2). PPG PMC AmerShield VOC at 2.0 to 3.0 mils DFT.
      3). Dupont WB Urethane at 3.5 to 4.0 mils DFT.
      4). International Water Borne Urethane at 3.0 to 4.0 mils DFT.
7. Interior Concrete Walls Exposed to View (Non-Immersion Service), Epoxy Coating:
   a. Surface Preparation: Cured, clean and dry, free of surface contaminants.
   b. One Coat:

1). Tnemec 201 Epoxoprime at 2.0 to 3.0 mils DFT.
2). PPG PMC Amerlock Sealer at 1.0 to 1.5 mils DFT.
3). Dupont 25P Epoxy at 6.0 to 8.0 mils DFT.
4). International Interseal 670 HS at 3.0 to 4.0 mils DFT.

c. And One Coat:
1). Tnemec 280 Tneme-Glaze at 6.0 to 8.0 mils DFT.
2). PPG PMC Amercoat 133 at 6.0 to8.0 mils DFT.
3). Dupont 100% Solids Epoxy at 8.0 to 10.mils DFT.
4). International Interseal 670 HS at 3.0 to 4.0 mils DFT.

d. And One Coat:
1). Tnemec 1080 or 1081 Endura-Shield 2.0 to 3 mils DFT.
2). PPG PMC AmerShield VOC at 2.0 to 3.0 mils DFT.
3). Dupont WB Urethane at 3.0 to 4.0 mils DFT.
4). International Water Borne Urethane at 3.0 to 4.0 mils DFT.

8. Interior Concrete Ceiling (both new and previously painted), Painted Finish:
a. Surface Preparation: Cured clean and dry.
b. One Coat:
1). Tnemec 151 Elasto-grip at 2.0 mils DFT.
2). RD Coatings Multiprim at 1.0-2.0 mils DFT.
c. And Two Coats:
1). Tnemec 158 Biolastic at 8.0 mils DFT.
2). RD Coatings ElastoFlex at 6.0 to 8.0 mils DFT.

9. Interior Exposed Steel, Joists, Ductwork, Conduit and Similar Items (where indicated), Dry-Fall or Dry-Fog Painted System:
a. One Coat:
1). Tnemec 115 WB Unibond at 2.5 to 3.0 mils DFT.
2). International Intercryl 530 at 2.5 to 3.0 mils DFT.
3). PPG PMC Amercoat 220 Acrylic at 3.0 mils DFT.
4). RD Coatings Muracryl at 2.0 to 3.0 mils DFT.

10. Mechanical Room Concrete Floor System, Waterborne Urethane, dry film thickness 28 mils: Surface preparation: Grind concrete; shot-blast not required.
a. Primer: RD Unifix at 1.0-1.5 mils DFT.
b. Second Coat: RD Elastodeck Slurry with broadcast aggregate, 25 mils DFT.
c. Third Coat: RD Monograph pigmented topcoat, 2-3 mils DFT.

11. Heavy Duty Mechanical Room Concrete Floor, Epoxy Coating System:
a. One Coat:
1). Tnemec 201 Epoxoprime at 4.0 to 6.0 mils DFT.
2). Dex-O-Tex C Bond Coat at 6.0-7.0 mils DFT.
3). RD Coatings Unifix at 2.0 mils DFT.
b. And One Coat:
1). Tnemec 206 Flexible Epoxy Underlayment at 60 mils DFT.
2). Dex-O-Tex Cheminert SC Membrane at 70-80 mils DFT.
3). RD Coatings Elasto Deck at 50-80 mils DFT.
c. And Two Coats:
1). Tnemec 297 at 3.0 mils DFT.
2). Dex-O-Tex Quik-Glaze at 7.0-8.0 mils DFT.
3). RD Coatings Muracryl at 3.0 mils DFT.

D. Mechanical and Electrical Work: Paint all exposed items throughout the project except factory finished items with factory-applied baked enamel finishes which occur in mechanical rooms or areas, and excepting chrome or nickel plating, stainless steel, and aluminum other than mill finished. Paint all exposed ductwork and inner portion of all ductwork. Same as specified for other interior metals, hereinabove.

END OF SECTION

SECTION 099805

MASONRY STAINING

PART 1 - GENERAL

1.1 SECTION INCLUDES

A. This Section includes brush-applied proven masonry stain applied to porous exterior surfaces including the following:
   1. Clay masonry units.

1.2 RELATED SECTIONS

A. Section 042000 – Unit Masonry.

B. Section 040120 – Masonry Restoration and Cleaning.

1.3 SUBMITTALS

A. Product Data: For each type of stain indicated.
   1. Manufacturer's Information: Manufacturer's technical information, and if needed, instructions for handling and storing exterior masonry stain.

B. Qualification Data: For Applicator.

C. Benchmark Samples (mockups): Provide up to five (5) color enhanced loose units that represent the over-all color range to determine closest approved sample matching to existing masonry. A field sample can be created on a 10 sq. ft. area to be determined by the Owner and the Architect on the actual surface of the building to be stained.

D. Project List: Submit a list of 10 successful projects over the last 15 years:
   1. The date on which the work was completed.
   2. The precise location of the job including description of the structure or portion of the structure stained, street address, city, state and zip code.
   3. Name of product used.
   4. Before and after pictures.

1.4 QUALITY ASSURANCE

A. Manufacturer Qualifications: Minimum 20 years experience and successful in-service performance in applying a ceramic based proven masonry stain.

B. Applicator Qualifications: A firm experienced in applying a ceramic based proven masonry stain, design and extent to those indicated for this project. Whose company has resulted in applications with a record of successful in-service performance that exceeds 20 years.

1.5 PROJECT CONDITIONS

A. Temperature Limitations: Apply stains only when temperatures of surfaces to be stained and the surrounding air are between 45 degrees F (7 degrees C) and 100 degrees F (32 degrees C).

B. Weather Limitations: Do not apply stain in snow, rain, dense fog or mist; when the relative humidity exceeds 95%, also do not apply to damp or wet surfaces.
   1. Allow wet surfaces to dry thoroughly and attain temperature and conditions specified before starting or continuing with application.

PART 2 - PRODUCTS

2.1 MANUFACTURER

A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
   1. BrickImaging.
   2. Dyebrick.
   3. Masonry Cosmetics Inc.

B. Basis-of-Design: BrickImaging; Stayntech.

2.2 UNIT MASONRY STAIN MATERIALS, GENERAL

A. Materials: Exterior water-based polymer blend that dries to a durable flat finish.

B. Materials once applied should not leave a visible gloss, sheen or film on masonry units.

C. VOC Content is to be very low and shall have a maximum value of 0.01 g/g.

PART 3 - EXECUTION

3.1 PREPARATION

A. General: Remove hardware, machined surfaces, lighting fixtures and similar items already installed that are not being stained. If removal is impractical or not possible because of size and weight of the item, provide surface- applied protection before surface preparation and staining.
   1. After completing staining operations, reinstall items removed using workers skilled in trades involved.

B. Surface Preparation: Clean and prepare surfaces to be stained according to manufacturer's written instructions for each particular substrate condition and as specified.
   1. Remove surface dirt, oil or grease by washing with a detergent solution recommended by masonry manufacturer; rinse thoroughly with clean water and allow to dry.
   2. Walls will need to be free of any acid or cleaning solution residue prior to any staining. Keep the PH level on the wall as close to neutral as possible.
   3. Ensure structurally sound surfaces that are dry, clean and free of the following: dirt, moisture, loose particles, oil, grease, asphalt, tar, paint, wax, rust, waterproofing, curing and parting compounds and other foreign matter.

3.2 APPLICATION

A. Mixing: Mix and prepare stains according to the manufacturer's written instructions. Stir stain thoroughly before applying and frequently during application to maintain color consistency.
   1. Maintain containers used in mixing and application in a clean condition, free of foreign materials and residue.
   2. Stir material before application to ensure all materials stay suspended. Stir as required during application.

B. Minimum Application Rate: Apply stain to manufacturer's recommended required rate, measured by bricks stained per brush, to ensure proper penetration..
   1. Do not apply stain on surfaces that are not sufficiently dry. If succeeding application is needed, ensure that the surface is dry before re-applying.
   2. Apply stain with brush by hand to provide a uniform blending of color to the masonry

wall.

3.3 FIELD QUALITY CONTROL

A. Architect or Owner shall review and approve “artistic” application of stain by Contractor in a test area, mock-up panel or loose samples, and as accepted for approved benchmark samples.

3.4 CLEANING

A. Cleanup: At the end of each work day, remove empty cans, rags, rubbish and other discarded materials from the project site.
   1. After completing staining, clean window glass and other surfaces. Remove splattered stain by proper methods without scratching or damaging adjacent finished surfaces.
   2. Dispose of excess materials according to state, federal and local governmental regulations.

3.5 PROTECTION

A. Protect work of other trades as necessary, whether being stained or not, against damage from staining. Correct damage by cleaning, repairing and re-staining as approved by Architect.

END OF SECTION

This page left intentionally blank.

SECTION 101100

VISUAL DISPLAY SURFACES

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Markerboards.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 061000 - ROUGH CARPENTRY for wood blocking.

1.3 SUBMITTALS

A. Product Data: For each type of product indicated.

B. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.

1. Show location of panel joints.
2. Show location of special-purpose graphics for visual display surfaces.
3. Include sections of typical trim members.
4. Include mounting devices and details.

C. Samples: For each type of visual display surface indicated:

1. Actual sections of visual display surfaces.

D. Product Test Reports: Based on evaluation of comprehensive tests performed by a qualified testing agency, for surface-burning characteristics of fabrics.

E. Maintenance Data: For visual display surfaces to include in maintenance manuals.

1.4 QUALITY ASSURANCE

A. Source Limitations: Obtain each type of visual display surface through one source from a single manufacturer.

B. Surface-Burning Characteristics: Comply with ASTM E 84 by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.

1. Flame-Spread Index: 25 or less.
2. Smoke-Developed Index: 50 or less.

C. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 01.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver factory-built visual display boards, including factory-applied trim where indicated, completely assembled in one piece without joints, where possible. If dimensions exceed maximum manufactured panel size, provide two or more pieces of equal length as acceptable to Architect. When overall dimensions require delivery in separate units, prefit components at the factory, disassemble for delivery, and make final joints at the site.

B. Store visual display units vertically with packing materials between each unit.

1.6 PROJECT CONDITIONS

A. Field Measurements: Verify dimensions by field measurements before fabrication and indicate measurements on Shop Drawings.

1. Established Dimensions: Where field measurements cannot be made without delaying the Work, establish dimensions and proceed with fabricating visual display surfaces without field measurements. Coordinate wall construction to ensure that actual dimensions correspond to established dimensions.
2. Allow for trimming and fitting where taking field measurements before fabrication might delay the Work.

PART 2 - PRODUCTS

2.1 MARKERBOARD ASSEMBLIES

A. Porcelain-Enamel Markerboards: Balanced, high-pressure, factory-laminated markerboard assembly of 3-ply construction consisting of backing sheet, core material, and 0.021-inch-thick, porcelain-enamel face sheet.

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

a. Claridge Products; LCS Porcelain.
b. Egan Visual; EVS.
c. MooreCo; Dura-Rite Whiteboards
d. Steelcase Company; PolyVision products.

2. Manufacturer's Standard Core: Minimum 1/4 inch thick, with manufacturer's standard moisture-barrier backing with binder containing no added formaldehyde.
3. Fire Rating: ASTM E 84, Class A.
4. Color: White, low gloss finish.
5. Laminating Adhesive: Manufacturer's standard moisture-resistant thermoplastic type.

2.2 ACCESSORIES

A. Aluminum Frames and Trim: Factory-applied, fabricated from not less than 0.062-inch-thick, extruded aluminum; of size and shape indicated.

1. Marker Trays: Manufacturer's standard, continuous tray.

B. Mounting Devices: Concealed on backside of panels, recommended to support weight of panel, and as follows:

1. Metal Clips or Bar Hangers: Manufacturer's standard two-part metal "Z" clips, with one part of each clip mechanically attached to back of unit and the other part to substrate, designed to permit unit removal.

C. Adhesive: Mildew-resistant, nonstaining adhesive, for use with specific visual display surfaces and substrate application, as recommended in writing by visual display surface manufacturer.

2.3 FABRICATION

A. Porcelain-Enamel Visual Display Assemblies: Laminate porcelain-enamel face sheet and backing sheet to core material under heat and pressure with manufacturer's standard flexible, waterproof adhesive.

B. Factory-Assembled Visual Display Units: Coordinate factory-assembled units with trim and accessories indicated. Join parts with a neat, precision fit.

C. Aluminum Frames and Trim: Fabricate units straight and of single lengths, keeping joints to a minimum. Miter corners to neat, hairline closure.

2.4 ALUMINUM FINISHES

A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.

B. Protect mechanical finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.

C. Finish designations prefixed by AA comply with the system established by the Aluminum Association for designating aluminum finishes.

D. Class II, Clear Anodic Finish: AA-M12C22A31 (Mechanical Finish: nonspecular as fabricated; Chemical Finish: etched, medium matte; Anodic Coating: Architectural Class II, clear coating 0.010 mm or thicker) complying with AAMA 611.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates and conditions, with Installer present, for compliance with requirements for installation tolerances, surface conditions of wall, and other conditions affecting performance.

B. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 PREPARATION

A. Remove dirt, scaling paint, projections, and depressions that will affect smooth, finished surfaces of visual display boards.

B. Prepare surfaces to achieve a smooth, dry, clean surface free of flaking, unsound coatings, cracks, defects, and substances that will impair bond between visual display boards and surfaces.

3.3 INSTALLATION

A. General: Install visual display surfaces in locations and at mounting heights indicated on Drawings, or if not indicated, at heights indicated below. Keep perimeter lines straight, level, and plumb. Provide grounds, clips, backing materials, brackets, anchors, trim, and accessories necessary for complete installation.

1. Join adjacent wall panels with concealed steel splines for smooth alignment.
2. Where markerboards abut, install with clean, trimless butt joints.

3.4 CLEANING AND PROTECTION

A. Clean visual display surfaces according to manufacturer's written instructions. Attach one cleaning label to visual display surface in each room.

B. Touch up factory-applied finishes to restore damaged or soiled areas.

C. Cover and protect visual display surfaces after installation and cleaning.

END OF SECTION

SECTION 122400

SHADES

PART 1 - GENERAL

1.1 GENERAL PROVISIONS

A. Attention is directed to the CONTRACT AND GENERAL CONDITIONS and all Sections within DIVISION 01 - GENERAL REQUIREMENTS which are hereby made a part of this Section of the Specifications.

1.2 DESCRIPTION OF WORK

A. Work Included: Provide labor, materials and equipment necessary to complete the work of this Section, including but not limited to the following:

1. Roller shades, with manual shade operators.

B. Related Work: The following items are not included in this Section and are specified under the designated Sections:

1. Section 061000 - ROUGH CARPENTRY for wood blocking and grounds for mounting roller shades and accessories.

1.3 SUBMITTALS

A. Product Data: For each type of product indicated.

1. Include styles, material descriptions, construction details, dimensions of individual components and profiles, features, finishes, and operating instructions.

B. Shop Drawings: Show location and extent of roller shades. Include elevations, sections, details, and dimensions not shown in Product Data. Show installation details, mountings, attachments to other work, operational clearances, and relationship to adjoining work.

C. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, based on input from installers of the items involved:

1. Ceiling suspension system members and attachment to building structure.
2. Ceiling-mounted or penetrating items including light fixtures, air outlets and inlets, speakers, sprinklers, recessed shades, and special moldings at walls, column penetrations, and other junctures of acoustical ceilings with adjoining construction.
3. Shade mounting assembly and attachment.
4. Size and location of access to shade operator and adjustable components.
5. Minimum Drawing Scale: 1/4 inch = 1 foot.

D. Samples for Initial Selection: For each colored component of each type of shade indicated.

1. Include similar Samples of accessories involving color selection.

E. Samples for Verification: For each type of roller shade.

1. Shade Cloth Material: Not less than 10 inches square. Mark interior face of material if applicable. Show complete pattern repeat.
2. Roller Shade: Full-size operating unit, not less than 16 inches wide by 36 inches long for each type of roller shade indicated.
3. Installation Accessories, including Valance: Full-size unit, not less than 10 inches long.

F. Window Treatment Schedule: For roller shades. Use same designations indicated on Drawings.

G. Qualification Data: For Installer.

H. Product Certificates: For each type of roller shade, signed by product manufacturer.

I. Product Test Reports: For each type of shade cloth material, for tests performed a qualified testing agency.

J. Operations and Maintenance Data: For roller shades to include in maintenance manuals. Include the following:

1. Methods for maintaining roller shades and finishes.
2. Precautions about cleaning materials and methods that could be detrimental to fabrics, finishes, and performance.
3. Operating hardware.

1.4 QUALITY ASSURANCE

A. Installer Qualifications: Fabricator of products.

B. Source Limitations: Obtain roller shades through one source from a single manufacturer.

C. Fire-Test-Response Characteristics: Provide roller shade cloth materials with the fire-test-response characteristics indicated, as determined by testing identical products per test method indicated below by UL or another testing and inspecting agency acceptable to authorities having jurisdiction:

1. Flame-Resistance Ratings: Passes NFPA 701, with no added chemical flame retardants.

D. Operating Mechanism Safety Characteristics: Comply with ANSI/WCMA A100.1-2022, Standard for Safety of Window Covering Products.

E. Regulatory Requirements, Accessibility: Comply with the U.S. Architectural & Transportation Barriers Compliance Board's "Americans with Disabilities Act (ADA) and Accessibility Guidelines for Buildings and Facilities (ADAAG)."

F. Mockups: Build mockups to verify selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver shades in factory packages, marked with manufacturer, product name, and location of installation using same designations indicated on Drawings.

1.6 PROJECT CONDITIONS

A. Environmental Limitations: Do not install roller shades until construction and wet and dirty finish work in spaces, including painting, is complete and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

B. Field Measurements: Where roller shades are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements on Shop Drawings. Allow clearances for operable glazed units' operation hardware throughout the entire operating range. Notify Architect of discrepancies. Coordinate fabrication schedule with construction progress to avoid delaying the Work.

1.7 EXTRA MATERIALS (ATTIC STOCK)

A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Rollers Shades: Full-size units equal to 5 percent of quantity installed for each size, color, and shade cloth material indicated, but not fewer than two units.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

A. Available Products: Subject to compliance with requirements, products that may be incorporated into the Work include, but are not limited to, the following:

1. Draper Inc.
2. Hunter Douglas Architectural (formerly Nysan).
3. LuTek. (Basis-of-Design)
4. Lutron Electronics Co.
5. MechoShade Systems, Inc.
6. Rollease Acmeda Contract.

2.2 ROLLER SHADES

A. Shadecloth Materials:

1. Solar Control: Transparent (1% or greater), 100% polyester or polylactic acid (PLA) biopolymer fabric, PVC-free, antimony-trioxide free.
2. Fire-Test-Response Characteristics: Passes NFPA 701, with no chemical flame retardants.
3. Bottom Hem: Straight.
4. Colors: To be selected by Architect from manufacturer’s full range.

B. Rollers: Electrogalvanized or epoxy primed steel or extruded-aluminum tube of diameter and wall thickness required to support and fit internal components of operating system and the weight and width of shadecloth material without sagging; designed to be easily removable from support brackets; with removable spline fitting integral channel in tube for attaching shade material.

1. Direction of Roll: Regular, from back of roller, unless indicated otherwise.

C. Mounting Brackets: Brackets or endcaps, corrosion resistant and compatible with roller assembly, operating mechanism, installation accessories, and mounting location and conditions indicated.

D. Fascia: L-shaped, formed-steel sheet or extruded aluminum; long edges returned or rolled; continuous panel concealing front and bottom of shade roller, brackets, and operating hardware and operators; length as indicated on Drawings removable design for access.

E. Top/Back Cover: L-shaped; material and finish to match fascia; combining with fascia and end caps to form a six-sided headbox enclosure sized to fit shade roller and operating hardware inside.

F. Pocket-Style Headbox: U-shaped, formed-steel sheet or extruded aluminum; long edges returned or rolled; with a bottom cover consisting of slot opening of minimum dimension to allow lowering and raising of shade and a removable or an openable, continuous metal access panel concealing shade roller, brackets, and operating hardware and operators within.

G. Bottom Bar: Steel or extruded aluminum. Provide concealed, by pocket of shade material, internal-type bottom bar with concealed weight bar as required for smooth, properly balanced shade operation.

H. Mounting: As indicated on Drawings, mounting permitting easy removal and replacement without damaging roller shade or adjacent surfaces and finishes.

I. Hold-Down Brackets and Hooks or Pins: Manufacturer's standard for anchoring roller shade bottom in place and keeping shade cloth material taut.

2.3 ROLLER SHADE FABRICATION

A. Product Description: Roller shade consisting of a roller, a means of supporting the roller, a flexible sheet or cloth of material carried by the roller, a means of attaching the material to the roller, a bottom bar, and an operating mechanism that lifts and lowers the shade.

B. Concealed Components: Noncorrodible or corrosion-resistant-coated materials.

1. Lifting Mechanism: With permanently lubricated moving parts.

C. Unit Sizes: Obtain units fabricated in sizes to fill window and other openings as follows, measured at 74 deg F:

1. Shade Units Installed between (Inside) Jambs: Edge of shade not more than 1/4 inch from face of jamb. Length equal to head to sill dimension of opening in which each shade is installed.
2. Shade Units Installed Outside Jambs: Width and length as indicated, with terminations between shades of end-to-end installations at centerlines of mullion or other defined vertical separations between openings.

D. Installation Brackets: Designed for easy removal and reinstallation of shade, for supporting fascia, roller, and operating hardware and for hardware position and shade mounting method indicated.

E. Installation Fasteners: No fewer than two fasteners per bracket, fabricated from metal noncorrosive to shade hardware and adjoining construction; type designed for securing to supporting substrate; and supporting shades and accessories under conditions of normal use.

F. Color-Coated Finish: For metal components exposed to view, apply manufacturer's standard baked finish complying with manufacturer's written instructions for surface preparation including pretreatment, application, baking, and minimum dry film thickness.

2.4 MANUALLY OPERATED SHADES

A. Operating Mechanisms: Comply with ANSI/WCMA A100.1-2022, Safety Standard for Operating Cords on Custom Window Covering.

1. Cordless Operating Mechanisms: With clutch that stops shade movement when released; permanently adjusted and lubricated.
2. Accessible Operation: With bottom bar clips and pull hooks as required.

PART 3 - EXECUTION

3.1 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances, operational clearances, other conditions affecting performance.

1. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 ROLLER SHADE INSTALLATION

A. Install roller shades level, plumb, and aligned with adjacent units according to manufacturer's written instructions, and located so shade cloth is not closer than 2 inches to interior face of glass. Allow clearances for window operation hardware.

1. Accessible Manual Operation: Install bottom bar clips and pull hooks as required.

3.3 ADJUSTING

A. Adjust and balance roller shades to operate smoothly, easily, safely, and free from binding or malfunction throughout entire operational range.

3.4 CLEANING AND PROTECTION

A. Clean roller shade surfaces after installation, according to manufacturer's written instructions.

B. Provide final protection and maintain conditions, in a manner acceptable to manufacturer and Installer, that ensure that roller shades are without damage or deterioration at time of Substantial Completion.

C. Replace damaged roller shades that cannot be repaired, in a manner approved by Architect, before time of Substantial Completion.

3.5 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain roller shades. Refer to Division 01 Sections for contract closeout procedures.

END OF SECTION

SECTION 26 05 00 - COMMON WORK RESULTS FOR ELECTRICAL

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

A. All drawings associated with the entire project, including general provisions of the Contract, including The General Conditions of the Contract for Construction, General and Supplementary Conditions and Division-1 Conditions specification sections shall apply to the Division 26 specifications and drawings. The Contractor shall be responsible for reviewing and becoming familiar with the aforementioned and all other Contract Documents associated with the project.

B. Where contradictions occur between this section and Division 1, the more stringent requirement shall apply.

C. Contractor shall be defined as any and all entities involved with the construction of the project.

1.2 SUMMARY:

A. This Section specifies the basic requirements for electrical installations and includes requirements common to more than one section of Division 26 and Division 28. It expands and supplements the requirements specified in sections of Division 1 through 50.

1.3 ELECTRICAL INSTALLATIONS:

A. Drawings are diagrammatic in character and do not necessarily indicate every required conduit, box, fitting, etc.

B. Drawings and specifications are complementary. Whatever is called for in either is binding as though called for in both. Report any discrepancies to the Engineer and obtain written instructions before proceeding. Where any contradictions occur between the specifications and the drawings the more stringent requirement shall apply. The contractor shall include pricing for the more stringent and expensive requirements.

C. Drawings shall not be scaled for rough-in measurements or used as shop drawings. Where drawings are required for these purposes or must be made from field measurement, take the necessary measurements and prepare the drawings.

D. The exact location for some items in this specification may not be shown on the drawings. The location of such items may be established by the Engineer during the progress of the work.

E. The contractor shall perform the installation in such a manner as to conform to the structure, avoid obstructions, preserve headroom, and keep openings and passageways clear, without further instructions or costs to the Owner. All equipment shall be installed so access is maintained for serviceability.

F. Before any work is begun, determine that equipment will properly fit the space and that conduit can be run as contemplated without interferences between systems, with structural elements or with the work of other trades.

G. Verify all dimensions by field measurements.

H. Arrange for chases, slots, and openings in other building components to accommodate electrical installations.

I. Sequence, coordinate, and integrate installations of electrical materials and equipment for efficient flow of the work. Give particular attention to large equipment requiring an access path for positioning prior to closing-in the building or space.

J. Where mounting heights are not detailed or dimensioned, install electrical conduits, boxes, and overhead equipment to provide the maximum headroom possible. In general, keep installations tight to structure.

K. Install electrical equipment to facilitate maintenance and repair or replacement of equipment components as much as practical and connect equipment for ease of disconnecting and removal with minimum of interference with other installations.

L. Make allowance for expansion and contraction for all building electrical components and conduit systems that are subject to such.

M. The ceiling space shall not be “layered”. It is the contractor’s responsibility to offset and coordinate any systems as required to allow installation within the identified ceiling cavity. The contractor shall include labor and material in the base bid to accommodate such offsets.

N. In general, all conduit systems shall be routed as high as possible. Keep all equipment in accessible areas such as corridors and coordinate with systems and equipment from other sections.

O. Coordinate the installation of required supporting devices and sleeves to be set in poured-in-place concrete and other structural components, as they are constructed.

P. Coordinate the installation of electrical materials and equipment above and below ceilings with suspension system, luminaires, and other building components. Ductwork and piping shall not be installed above electrical panelboards, switchboards, motor control centers, and transformers.

Q. Coordinate the installation of electrical materials in casework, millwork, and furniture systems. For systems that are furnished with raceways, boxes, devices, cabling, and/or conductors, ensure that all NEC requirements are met as well as requirements in other applicable sections of these specifications. Physical separation shall be provided between different branches of power and between power and low voltage cabling.

1.4 COORDINATION:

A. Work out all installation conditions in advance of installation. The Contractor shall be responsible for preparing coordination drawings, showing all work, in all areas. The Contractor shall be responsible for providing all labor and material, including but not limited to all fittings, hangers, control devices, lighting, low voltage equipment, cable tray, conduit, transformers, disconnects, etc., necessary to overcome congested conditions at no increase in contract sum. The Contractors base bid shall include all time and manpower necessary to develop such coordination efforts and drawings. Increases to contract sum or schedule shall not be considered for such effort.

B. Provide proper documentation of equipment, product data and shop drawings to all entities involved in the project. Coordination shall include, but not be limited to the following:

1. Fire Alarm Contractor shall provide shop drawings to other Contractors as required.
2. Automatic Temperature Controls, Building Management and Testing, Adjusting and Balancing Contractors shall be provided with equipment product data and shop drawings from other Division 23 and Division 26 Contractors and shall furnish the same information involving control devices to the appropriate Contractor.
3. Automatic Doors and controls, Elevators and other building access equipment shall have cut sheets reviewed and shall furnish the same information to the appropriate Contractor.

C. Coordination Drawings:

1. Coordination drawings shall be prepared by the Contractor for his utilization and are his responsibility to assure systems will be installed in a manner to allow all systems to function properly.
2. Prepare and submit a set of coordination drawings showing major elements, components, and systems of electrical equipment and materials in relationship with other building components. Prepare drawings to an accurate scale of 1/4"=1'-0" or larger. Indicate the locations of all equipment and materials, including clearances for servicing and maintaining equipment. Indicate movement and positioning of large equipment into the building during construction.
3. Coordination drawings are informational submittals. Submit coordination drawings to Engineer for information only to document proper coordination of all portions of work and that coordination issues have been identified and resolved prior to submitting to the Engineer and prior to commencing construction in each affected area. The review of the coordination drawings by the Engineer does not constitute a relief of responsibility of the Contractor or a change to the contract documents. The Contractor shall have sole responsibility in developing a fully coordinated and integrated ceiling cavity.
4. Clearly indicate solutions to space problems. Identification of space problems without solutions is not acceptable. Only areas clearly identified will be reviewed.
5. Prepare coordination drawings and other Shop Drawings at a suitable scale, showing the required dimension. In addition to the mentioned areas and systems above, also submit specific equipment installations, including, but not limited to the following:

    a. Feeder conduits

6. Electronic drawings are available for the Contractor’s use pending a signed Cator, Ruma & Associates Electronic File Agreement. The Engineer’s Construction Documents cannot be used directly for coordination drawings, as they are for information and initial coordination only.
7. Wiring Diagrams: Provide wiring diagrams indicating field installed electrical power, control wiring, cabling layouts, overcurrent protective devices, equipment, and equipment connections.

D. Existing Conditions:

1. Contractor shall carefully survey existing conditions prior to bidding work. In addition, Contractor shall complete a thorough ceiling cavity survey prior to developing Coordination drawings.
2. Contractor shall be responsible for showing all existing conditions on the coordination drawings.
3. Provide proper coordination of electrical work with existing conditions.
4. Contractor shall report any issues or conflicts immediately to Engineer before commencing with work and prior to purchasing equipment and materials.

1.5 COORDINATION WITH OTHER DIVISIONS:

A. General:

1. Coordinate all work to conform to the progress of the work of other trades.
2. Complete the entire installation as soon as the condition of the building permits. No extras will be allowed for corrections of ill-timed work when such corrections are required for proper installation of other work.

B. Coordinate ceiling cavity space carefully with all trades. In the event of conflict, install mechanical and electrical systems within the cavity space allocation in the following order of priority:

1. Equipment and required clearances.
2. Plumbing waste, cooling coil drain piping and roof drain mains and leaders.
3. Ductwork mains.
4. Plumbing vent piping.
5. Gas systems.
6. Low pressure ductwork and air devices.
7. Electrical and communication conduits, raceways, and cable tray.
8. Domestic hot and cold water.
9. Hydronic piping.
10. Fire sprinkler mains, branch piping and drops (locate as tight to structure as possible).
11. DDC control wiring and other low voltage systems.
12. Fire alarm systems.

C. Chases, Inserts and Openings:

1. Provide measurements, drawings, and layouts so that openings, inserts, and chases in new construction can be built in as construction progresses.
2. Check sizes and locations of openings provided, including the access panels for equipment in hard lid ceilings and wall cavities.
3. Any cutting and patching made necessary by failure to provide measurements, drawings, and layouts at the proper time shall be done at no additional cost in contract sum.

D. Support Dimensions: Provide dimensions and drawings so that concrete bases and other equipment supports to be provided under other sections of the specifications can be built at the proper time.

E. Coordinate the installation of required supporting devices and sleeves to be set in poured in place concrete and other structural components, as they are constructed.

F. Coordinate the cutting and patching of building components to accommodate the installation of electrical equipment and materials.

G. Modifications required as result of failure to resolve interferences, provide correct coordination drawings or call attention to changes required in other work as result of modifications shall be paid for by responsible Contractor/Subcontractor.

1.6 DESIGN WORK REQUIRED BY CONTRACTOR:

A. The construction of this project requires the Contractor to include the detailing and design of several systems and/or subsystems. All such design work associated with the development of the coordination drawings shall be the complete responsibility of the Contractor.

B. The Contractor shall take the full responsibility to develop and complete routing strategies which will allow fully coordinated system to be installed in a fully functional manner. The

Engineers' contract drawings shall be for system design intent and general configurations.

C. Systems or subsystems which require design responsibility by the contractor include but are not limited to:

1. Final coordinated distribution systems within the ceiling cavity.
2. Any system not fully detailed.
3. Equipment supports, hangers, anchors, and seismic systems not fully detailed nor specified in these documents or catalogued by the manufacturer.
4. Seismic restraint systems.

1.7 PROJECT CONDITIONS:

A. The contractor shall be required to attend a pre-bid walk-thru if required and shall make themselves familiar with the existing conditions. No additional costs to the Owner shall be accepted for additional work for existing conditions.

B. Field verify all conditions prior to submitting bids.

C. Report any damaged equipment or systems to the Owner prior to any work.

D. Protect all work against theft, injury, or damage from all causes until it has been tested and accepted.

E. Be responsible for all damage to the property of the Owner or to the work of other contractors during the construction and guarantee period. Repair or replace any part of the work which may show defect during one year from the final acceptance of all work, provided such defect is, in the opinion of the Architect, due to imperfect material or workmanship and not due to the Owner's carelessness or improper use.

F. The Contractor shall coordinate and cooperate with Owner at all times for all new-to-existing connections.

G. Coordinate all services shutdown with the Owner; provide temporary services. Coordinate any required disruptions with Owner, at a minimum one week in advance.

H. Minimize disruptions to operation of electrical systems in occupied areas.

1.8 SAFETY:

A. Refer to Division 1.

1.9 EQUAL EMPLOYMENT OPPORTUNITY REQUIREMENTS:

A. Refer to Division 1 and conform with the Owners requirements.

1.10 REQUIREMENTS OF REGULATORY AGENCIES:

A. Refer to Division 1.

B. Execute and inspect all work in accordance with Underwriters Laboratories (UL), and all local and state codes, rules, and regulations applicable to the trade affected as a minimum, but if the plans and/or specifications call for requirements that exceed these rules and regulations, the more stringent requirement shall be followed. Follow

application sections and requirements and testing procedures of NFPA, IEEE, NEMA, CBM, ANSI, NECA, ICEA, NETA, and IETA.

C. Comply with standards in effect at the date of these Contract Documents, except where a standard or specific date or edition is indicated.

D. Energy Codes: All equipment and installations shall conform to Federal, State, and local Energy Conservation Standards.

E. The handling, removal and disposal of regulated liquids or other materials shall be in accordance with U.S. EPA, state, and local regulations.

F. The handling, removal and disposal of lead-based paint and other lead containing materials shall comply with EPA, OSHA, and any other Federal, State, or local regulations.

G. After entering into contract, Contractor will be held to complete all work necessary to meet these requirements without additional expense to the Owner.

H. All material used on this project shall be UL listed and labeled and be acceptable to the authority having jurisdiction as suitable for the use intended.

1.11 PERMITS AND FEES:

A. Refer to Division 1.

B. Contractor shall arrange for and pay for all construction permits, inspections, licenses and certificates required in connection with the work.

1.12 PROJECT SEISMIC REQUIREMENTS:

A. Installation shall comply with the local seismic requirements for the area of installation. Provide restraints, bracing, anchors, vibration isolation, seismic snubbers, and all other components required for the installation.

B. All electrical and fire alarm systems shall be installed to meet NFPA and IBC Seismic requirements.

1. Where any conflicts arise the more stringent requirements shall be applicable.
2. The design of the seismic restraints shall be the responsibility of the contractor.

1.13 PRODUCT OPTIONS AND SUBSTITUTIONS:

A. Refer to the Instructions to Bidders and Division 1.

B. The burden of proof that the proposed equipment is equal in size, capacity, performance, and other pertinent criteria for this specific installation, or superior to that specified is up to the Contractor. If substitutions are not granted, the specified materials and equipment must be installed. Where substituted equipment is allowed, it shall be the Contractor's responsibility to notify all related trades of the accepted substitution and to assume full responsibility for all costs caused as a result of the substitution.

C. Materials and equipment of equivalent quality shall be submitted for substitution prior to bidding. This may be done by submitting to the Architect/Engineer at least ten (10)

working days prior to the bid date requesting prior review. This submittal shall include all data necessary for complete evaluation of the product.

1. Substitutions shall only be allowed upon the written approval of the Architect/Engineer
2. The Contractor shall be responsible for the removal, replacement, and remedy of any system or equipment which has been installed which does not meet the specifications and scheduled performance or which does not have prior approval.

D. Bidders opting to bid or propose comparable products (either a product by a listed acceptable manufacturer in the respective specification section or a substitution request) are responsible for:

1. Confirming the proposed equipment will fit in the space available, including the equipment's clearance requirements.
2. Coordination of any variance from basis-of-design in weight, electrical requirements, other utility requirements, etc. with other trades.
3. Inclusion in the bid of any applicable costs for changes in prime bidder's and their sub bidders' work required to accommodate the utilization of the comparable product.
4. The contractor shall bear all responsibility including any changes to mechanical, plumbing, electrical, structural or architectural design. These changes shall be clearly identified and presented to the Design Team.

1.14 SUBMITTALS:

A. General

1. Refer to the Conditions of the Contract (General and Supplementary), Division 1.
2. Contractor shall provide a submittal schedule appropriate for the size and schedule of the project. Limit the number of large submittals being reviewed at one time and coordinate timing of sections that are dependent on each other, i.e., submit coordination and short circuit study prior to or together with gear, overcurrent protection devices, ATS, etc.
3. The Contractor shall identify any "long lead time" items which may impact the overall project schedule. If these submittal requirements affect the schedule, the Contractor shall identify the impacts and confer with the Engineer within two weeks of entering into the contract.
4. The front of each submittal package shall be identified with the specification section number, job name, Owner's project number, date, Prime Contractor and Subcontractor's names, addresses, and contact information, etc. Each Specification Section shall be submitted individually, and submittal shall be tabbed for the equipment/materials/etc. within the section. Submittals that are not complete with the required information will not be reviewed and will be sent back to be corrected.
5. Submittals shall be provided electronically. All electronic submittals need to be complete with all design information and stamped for conformity by the contractor. Submittals will be reviewed, marked appropriately, and returned by the same means as received.
6. An index shall be provided which includes:

    a. Product
    b. Plan Code (if applicable)
    c. Specification Section
    d. Manufacturer and Model Number

7. Submittal schedule shall be provided for review within four (4) working weeks from award of contract to successful bidder.

B. Basis of Design: The manufacturer's material or equipment listed first in the specifications or on the drawings are the basis of design and are provided for the establishment of size, capacity, grade, and quality. If the contractor proposes alternates or substitutions in lieu of the first names, the cost of any changes in construction required by their use shall be borne by this Contractor.

C. All equipment shall conform to the State and/or local Energy Conservation Standards

D. Contractor Review: Submittal of shop drawings, product data, and samples will be accepted only when submitted by the Contractor. Each submittal shall be reviewed by the contractor for general conformance with contract requirements and stamped by the respective contractor prior to submittal to the Architect/Engineer. Any submittal not stamped or complete will be sent back. Data submitted from subcontractors and material suppliers directly to the Architect/Engineer will not be processed unless written prior approval is obtained by the Contractor.

E. Submittal Review Process: Before starting work, prepare and submit to the Architect/Engineer shop drawings and descriptive product data required for the project. Continue to submit in the stated format after each Architect/Engineer's action until a "No Exception Taken" or "Make Correction Noted" action is received. When a "Make Corrections Noted" is received, make the required corrections for inclusion in the operation and maintenance manual (O&M). Submittals marked "Make Corrections Noted" shall not be resubmitted during the submittal process. Unless each item is identified with specification section and sufficient data to identify its compliance with the specifications and drawings, the item will be returned "Revise and Resubmit". Where an entire submittal package is returned for action by the Contractor, the Engineer may summarize comments in letter format and return the entire set. Submittals shall be prepared per the ELECTRICAL SUBMITTAL CHECKLIST, at the end of this section; supplemental requirements are listed in each Division 26 Section.

F. The Design Professional’s review and appropriate action on all submittals and shop drawings is only for the limited purpose of checking for conformance with the design concept and the information expressed in the contract documents. This review shall not include:

1. Accuracy or completeness of details, such as quantities, dimensions, weights or gauges, fabrication processes
2. Construction means or methods
3. Coordination of the work with other trades
4. Construction safety precautions

G. The Design Professional’s review shall be conducted with reasonable promptness while allowing sufficient time in the Design Professional’s judgment to permit adequate review. Review of a specific item shall not indicate that the Design Professional has reviewed the entire assembly of which the item is a component.

H. The Design Professional shall not be responsible for any deviations from the contract documents not brought specifically to the attention of the Design Professional in writing by the Contractor. This shall clearly identify the design and the specific element which vary from the Design. The Contractor shall be responsible for all remedies for lack of strict conformance associated with these criteria.

I. The Design Professional shall not be required to review partial submissions or those for which submissions of correlated items have not been received.

J. If more than two submittals (either for product data, shop drawings, record drawings, test reports, or O&Ms) are made by the Contractor, the Owner reserves the right to charge the Contractor for subsequent reviews by their consultants. Such extra fees shall be deducted from payments by the Owner to the Contractor.

K. The contractor shall cloud all changes made on submittals that are marked “Revise and Resubmit.”

L. Required Submittals: Provide submittals for each item of equipment specified or scheduled in the contract documents. See table at the end of this section.

M. Submit letters certifying compliance with ANSI standards for medium or high voltage gear. These letters shall be signed by a corporate officer and shall list applicable standards. Letters signed by local representatives will not be acceptable.

N. Submit proposed changes to electrical room or other equipment room layouts when revised from contract documents prior to installation.

O. Mark submittals with designations as shown on the drawings and identify as required by specification sections. Identification shall contain the information as required in details and each label shall be submitted in list form with disconnects, panelboards, switchboards, overcurrent protection devices and utilization equipment.

1.15 SPECIFIC CATEGORY SUBMITTAL REQUIREMENTS:

A. Product Listing:

1. Prepare listing of major electrical equipment and materials for the project, within (2) two weeks of signing the Contract Documents and transmit to the Architect.

   a. Provide all information requested.
   b. Submit this listing as a part of the submittal requirement; see Paragraph 1.15 "PRODUCT OPTIONS AND SUBSTITUTIONS."

2. When two or more items of the same material or equipment are required (lighting, wiring devices, switchgear, panelboards, protective devices, etc.) they shall be of the same manufacturer. Product manufacturer uniformity does not apply to raw materials, bulk materials steel bar stock, welding rods, solder, fasteners, except as otherwise indicated.

   a. Provide products which are compatible within systems and other connected items.

3. For conduit, wire and fittings, the Contractor shall select a prime and alternate manufacturer from the list of acceptable manufacturers provided in the appropriate sections of this Division. The prime and alternate manufacturers shall be identified in the product listing. The contractor shall make every effort to use the prime manufacturer for the entire project. If products from this manufacturer are unavailable, the Contractor shall use the listed alternate with the following provisions.

   a. Wire: All wire placed in a single conduit or installed in multiple conduits making up parallel feeders shall be of the same manufacturer.
   b. Conduit and Fittings: All conduits and fittings installed exposed within the same room or immediate area shall be of the same manufacturer.

B. Schedule of Values

1. Provide Preliminary Schedule of Values to Engineer with product data submittal within four (4) weeks from award of contract to successful bidder. Provide according to the following descriptions:

    a. General Construction (total)
    b. Demolition
    c. Distribution
    d. P.A./Sound/Intercom

2. Provide a final Schedule of Values at close-out of project including updated values based on actual installation.

C. Product Data:

1. Where pre-printed data covers more than one distinct product, size, type, material, trim, accessory group or other variation, mark submitted copy to indicate which of the variations is to be provided.
2. Delete or mark-out portions of pre-printed data which are not applicable.
3. Where operating ranges are shown, mark data to show portion of range required for project application.
4. For each product, include the following:

    a. Sizes.
    b. Weights.
    c. Speeds.
    d. Capacities.
    e. Conduit and electrical connection sizes and locations.
    f. Statements of compliance with the required standards and regulations.
    g. Performance data.
    h. Manufacturer's specifications.
    i. Housing and proposed finishes.
    j. NEMA or other ratings that apply.

5. Checklist: Where identified in ELECTRICAL SUBMITTAL CHECKLIST or within individual Division 26 Sections or necessary for confirmation of products, submit a detailed checklist which acknowledges compliance or a reason for non-compliance to each of the specification requirements. Arrange the checklist according to the headings of each item identified in each specification (i.e. Shop Drawings, Wiring Diagrams, Product requirements, individual line items, etc.) Mark items as "N/A" where the item is not applicable.

D. Shop Drawings:

1. Shop Drawings are defined as electrical system layout drawings prepared specifically for this project, or fabrication and assembly type drawings of system components to show more detail than typical pre-printed materials.
2. Prepare Electrical Shop Drawings, except diagrams, to accurate scale, min 1/8”=1'-0", Electrical rooms shall be 1/4”=1’-0” unless otherwise noted.
3. Shop drawings shall include:

    a. Proposed equipment installations.
    b. Electrical characteristics and connection requirements.
    c. Clearance dimensions at critical locations.
    d. Dimensions of spaces required for operation and maintenance.
    e. Interfaces with other work, including structural support.

f. Elevations in areas with multiple pieces of equipment on common walls or to clarify incoming/exiting methods/clearances, etc.
g. Wall and floor penetrations.
h. Wiring diagrams showing all components, internal connecting wiring, and contractor connection requirements including terminal blocks/lugs, wire sizes, etc.

E. Test Reports:

1. Submit test reports which have been signed and dated by the accredited firm or testing agency performing the test.
2. Prepare test reports in the manner specified in the standard or regulation governing the test procedure (if any) as indicated.
3. Submit test reports as required for O & M manuals.

F. Software Licenses: Provide documentation of ownership under the owner's corporate name (coordinate with owner's representative for exact ownership wording) for Software Licenses provided as part of the work. Include information for updates, subscription requirements if applicable, backup, support, login, passwords, date when purchased, expiration date if applicable, version, etc. Include in the O & M Manual after review and "No Exceptions Taken" has been accomplished.

1.16 DELIVERY, STORAGE AND HANDLING:

A. Refer to the Division 1 Sections on Transportation and Handling and Storage and Protection.

B. Deliver products to project properly identified with names, model numbers, types, grades, compliance labels, and similar information needed for distinct identifications; adequately packaged and protected to prevent damage during shipment, storage, and handling.

C. Check delivered equipment against contract documents and submittals.

D. Store equipment and materials at the site, unless off-site storage is authorized in writing. Protect stored equipment and materials from damage and weather.

E. Coordinate deliveries of electrical materials and equipment to minimize construction site congestion. Limit each shipment of materials and equipment to the items and quantities needed for the smooth and efficient flow of installations.

1.17 DEMOLITION/REMODEL WORK:

A. Refer to Division 1 Section on Summary of work for requirements on working in Owner-occupied areas of the existing building and Division 2 section on selective demolition. The following paragraphs supplement the requirements of other Divisions.

B. During the demolition phase of this contract, it is the responsibility of this Contractor to carefully remove existing equipment, conduits, boxes, and related items either as shown on the demolition drawings as being removed, or as required for the work. These items shall be tagged, protected from damage, and stored as directed by the Owner. A list of all items stored shall be turned over to the Architect/Engineer. At the completion of the remodeling work or when directed by the Architect, all stored items not reused or wanted by the Owner shall be removed from the premises.

C. The project involves renovation and remodel of the existing building. On the drawings, work may be denoted by showing items as bold or light line weight and certain renovation symbols are used. These indications and symbols are amplified as follows:

1. **Bold Print** (when used): Work included in this contract is denoted in bold print or darker line weight.
2. Light Print (when used): Work shown lightly indicates existing conditions to remain.

R = Existing item to be removed. Contractor shall remove the existing item and the associated existing wiring. Where the raceway serving the equipment is accessible (via removal of suspended ceiling, crawl space, etc.) the raceway shall also be removed. Where the removal of a raceway leaves visible evidence on an existing surface which is not being repaired or replaced by the General Contractor, this contractor shall repair the surface. Where the existing raceway is concealed, the outlet box shall be cleaned, and a blank cover-plate installed. Where the concealed raceway is uncovered by demolition performed by the General Contractor, the raceway shall be removed (or extended to new location if appropriate).

ER = Existing item to remain, replace device, maintain circuit continuity. Contractor shall perform the following function based upon the item to remain:

Luminaires - Clean.
Switches - Remove and replace with new in existing box.
Receptacles - Remove and replace with new in existing box.
Clock - Remove and replace with new in existing box.

RL = Existing item to be Relocated. Contractor shall remove the existing item, and store in a safe place. The existing item shall be relocated to the new position as called for on the drawings. At Contractor's option, the existing wiring may be extended (unused boxes shall be removed and conduit and wiring extended from nearest concealed box unless specifically noted otherwise), or new wiring may be run from the source. Based upon the item to be relocated, the Contractor shall perform the following function:

Luminaires - Clean and reinstall in new location.
Receptacles - Clean and reinstall in new location.

D. Existing equipment that is removed and not scheduled to be reused shall remain the property of the Owner and be delivered for disposition unless specifically indicated otherwise and shall be stored in a location designated by the Owner. Items which are removed and not wanted by the Owner shall become the property of the Contractor and shall be removed from the site.

E. Existing equipment that is removed and is to be reused shall be cleaned, serviced and operable before being reinstalled.

F. Revise panelboard schedules to reflect removal or relocation of equipment. Circuit integrity of equipment in adjacent areas shall be left intact.

G. Where remodeling interferes with existing circuits and equipment which are not to be removed, such circuits and equipment shall be reworked and relocated as required to complete the project.

H. The Contractor shall remove all distribution equipment, conductors, etc., which are indicated to be removed or which must be removed to accommodate demolition.

Equipment to be removed may require reworking conduit and wiring to maintain service to other equipment.

I. Where remodeling interferes with circuits serving areas outside of the project or phase limits or which are remodeled in later phases of the project, circuits shall be reworked, or temporary circuits provided as required.

J. Existing equipment and circuiting shown are based on field surveys and/or Owner furnished drawings. The Contractor shall verify conditions as they exist with necessary adjustments being made to the drawing information.

K. Coordinate the routing of all conduits with the existing mechanical and plumbing systems to avoid conflicts with ducts, pipes, etc. Where existing electrical boxes, conduit, or equipment interfere with installation of new ducts, plumbing, walls, soffits, luminaires, outlets, etc., the Contractor shall resolve the conflict with the appropriate trade.

L. Reuse of existing luminaires, devices, conduits, boxes, or equipment will be permitted only where specifically indicated on the drawings or allowed under the appropriate section of the specifications.

M. Electrical Outages: Electrical outages must be held to a minimum. The Contractor shall submit a Method of Procedure (MOP) for each outage to the Owner, detailing the reasons for the outage, areas affected, sequence of procedures to accomplish work, estimated maximum length of time along with the date and time of day outage will occur. The Contractor shall meet with the Owner to set a schedule and date for the outage based on the MOP. Due to the critical implications of power outages, the Owner may direct the Contractor as to the time of day or night and date an outage may take place.

1. The Contractor will be responsible for providing temporary power required for the duration of the outages. The required outages to connect and disconnect the temporary power will require a MOP as described above.
2. Log each approved and implemented MOP and submit with O&M Manuals.

N. PCB Ballasts: PCB type ballasts may be present in existing luminaires. If PCB ballasts are discovered by the Contractor, report such occurrence to the Owner immediately. The Contractor shall remove and dispose of PCB type ballasts at an E.P.A. (Environmental Protection Agency) approved site in the prescribed manner acceptable to the EPA. The Contractor shall pay all fees associated with this work.

O. Hazardous Material: If suspected hazardous material, in any form, is discovered by this Contractor in the process of their work, they shall report such an occurrence to the Owner immediately. The Owner will determine the action to be taken. Hazardous material removed is not a part of the work to be done under this Division.

P. Lamp Disposal: Contractor is responsible for sending removed lamps to be recycled. The Contractor shall ensure the recycling agency meets RCRA and CERCLA regulations. Provide certificate of compliance in O&M Manuals.

1.18 CUTTING AND PATCHING:

A. Cutting and patching of electrical equipment, components, and materials may be required for removal and legal disposal of selected materials, components, and equipment. Coordinate the cutting and patching of building components to accommodate the installation of electrical equipment and materials.

B. Refer to Division 1 for cutting and patching requirements.

C. Do not endanger or damage installed work through procedures and processes of cutting and patching.

D. Arrange for repairs required to restore other work, because of damage caused as a result of electrical installations.

E. No additional compensation will be authorized for cutting and patching work that is necessitated by ill-timed, defective, or nonconforming installations.

F. Perform cutting, fitting, and patching of electrical equipment and materials required to:

1. Uncover work to provide for installation of ill-timed work.
2. Remove and replace defective work.
3. Remove and replace work not conforming to requirements of the Contract Documents.
4. Remove samples of installed work as specified for testing.
5. Install equipment and materials in existing structures.
6. Upon written instructions from the Architect/Engineer, uncover and restore work to provide for Architect/Engineer observation of concealed work.

G. Cut, remove, and legally dispose of selected electrical equipment, components, and materials as indicated, including, but not limited to removal of conductors, conduit, luminaires, boxes, devices and other electrical items made obsolete by the new work.

H. Protect the structure, furnishings, finishes, and adjacent materials not indicated or scheduled to be removed.

I. Provide and maintain temporary partitions or dust barriers adequate to prevent the spread of dust and dirt to adjacent areas.

J. Locate, identify, and protect electrical services passing through remodel or demolition area and serving other areas required to be maintained operational.

1.19 ROUGH IN:

A. Verify final locations for rough ins with field measurements and with the requirements of the actual equipment to be connected.

B. Refer to equipment shop drawings and manufacturer's requirements for actual provided equipment for rough in requirements.

C. Work through all coordination before rough in begins.

1.20 ACCESSIBILITY:

A. Install equipment and materials to provide required code clearances and access for servicing and maintenance. Coordinate the final location with piping, ducts, and equipment of other trades to insure proper access for all trades. Coordinate locations of concealed equipment, disconnects, and boxes with access panels and doors. Allow ample space for removal of parts, fuses, lamps, etc. that require replacement or servicing.

B. Extend all conduits so that junction and pull boxes are in accessible locations.

C. Provide access panel or doors where equipment or boxes are concealed behind finished surfaces.

D. Furnish hinged steel access doors with concealed latch, whether shown on drawings or not, in all walls and ceilings for access to all concealed valves, shock absorbers, air vents, motors, fans, balancing cocks, and other operating devices requiring adjustment or servicing. Refer to Division 1 for access door specification and requirements.

E. The minimum size of any access door shall not be less than the size of the equipment to be removed or 12 inches x 12 inches if used for service only.

F. Furnish doors to trades performing work in which they are to be built, in ample time for building in as the work progresses. Whenever possible, group equipment to permit use of minimum number of access doors within a given space.

G. Factory manufactured doors shall be compatible with the finish in which they are to be installed.

H. Access doors in fire-rated walls and ceilings shall have equivalent U.L. label and fire rating.

1.21 TESTING:

A. Submit test reports as outlined in Division 1 Sections on Quality Control Services and each Division 26 Section.

B. Testing as required by these specifications shall pertain to all equipment, wiring, devices, etc. installed under this contract and being reused.

C. General Scope:

1. Perform all tests and operational checks to assure that all electrical equipment, both Contractor and Owner-supplied, is operational within industry and manufacturer's tolerances and is installed in accordance with design specifications.
2. The tests and operational checks shall determine the suitability for energization.
3. Schedule tests and give a minimum of two weeks advance notice to the Architect/Engineer. Reschedule testing for Owner convenience if required.

D. Test Report: Submit the completed report to the Architect/Engineer no later than fifteen (15) days after completion of test unless directed otherwise. The test report shall be bound, and its contents certified. A final compilation of all Test Reports shall be submitted with the Testing and Equipment Settings Report (Refer to Operation and Maintenance Data paragraphs).

E. Each test report shall include the following:

1. Project information including building name, address, date, and other pertinent information.
2. List of equipment tested.
3. Description of test.
4. List of test equipment used and calibration date.
5. Baseline, acceptable, or published target value for test with code or standard reference indicating where value was derived.
6. Test results that summarize all measured values with baseline values.
7. Conclusions and recommendations.

8. Appendix, including appropriate test forms that show all measured values.

F. Failure to Meet Test:

1. Any system material or workmanship which is found defective based on performance tests shall be reported directly to the Architect/Engineer.
2. All failed tests shall be sent immediately by email to Architect/Engineer with proposed corrective action and proposed re-test date and time.
3. Contractor shall replace the defective material or equipment as necessary and have test repeated until test proves satisfactory without additional cost to the Owner.

G. The testing agency shall have a calibration program which maintains all applicable test instrumentation within rated accuracy. The accuracy shall be traceable to the National Institute of Standards and Technology (NIST) in an unbroken chain. Instruments shall be calibrated in accordance with the following frequency schedule:

1. Field Instruments: 6 months
2. Laboratory Instruments: 12 months
3. Leased specialty equipment: 12 months. (Where accuracy is guaranteed by lessor
4. Dated calibration labels shall be visible on all test equipment.

1.22 NAMEPLATE DATA:

A. Provide equipment with permanent operational data nameplate on each item of power operated equipment, indicating manufacturer, product name, model number, serial number, capacity, operating and power characteristics, labels of tested compliances, and similar essential data. Install equipment so that the nameplate is readily visible.

B. Phase Rotation

1. Existing Building: Match existing phase rotation.

1.23 CLEANING:

A. Refer to the Division 1 Section on project closeout or final cleaning for general requirements for final cleaning.

B. Clean all luminaires, lamps and lenses per manufacturer’s recommendations prior to final acceptance. Replace all inoperative lamps.

1.24 RECORD DOCUMENTS:

A. Refer to the Division 1 Section on Project Closeout or Project Record Documents for requirements. The following paragraphs supplement the requirements of Division 1.

B. The Contractor shall keep a complete set of construction as-built drawings in custody during the entire period of construction at the construction site. Documents shall be updated on a weekly basis.

C. The Contractor shall obtain the most current set of drawings from the design team. The Contractor’s as-built drawings shall include redlines and notations indicating actual field conditions as installed prior to submitting to the Engineer for final record document production.

D. Submitted as-built drawings may NOT solely refer to RFI, ASI, or Change Order numbers and must accurately reflect the as-built conditions.

E. Revisions to the Contract Documents shall be legible and shall be prepared using the following color scheme.

1. Red shall indicate new items, location deviations, routing deviations, circuiting modifications, etc.
2. Green shall indicate items removed or deleted.
3. Blue shall be used for relevant notes and descriptions necessary for clarification of as-built modifications.

F. Drawings shall be marked to indicate, but not limited to the following, modifications to the Contract Documents:

1. Conduit size, routing, and location both exterior and interior
2. Equipment locations, dimensioned from column lines
3. Concealed equipment, dimensioned to column lines
4. Distribution equipment size, ratings, connections, and locations
5. Fuse and circuit breaker size and arrangements
6. Revised locations of any power, lighting, lighting control, fire alarm device, or any other electrical device or component; including device mounting heights
7. Modifications to branch circuit device circuiting shall be clearly annotated on the associated floor plans.
8. Support and hanger details
9. Concealed control system devices
10. Any other relevant deviations

G. Mark as-built drawings to indicate approved substitutions; Addenda; Change Orders; actual equipment and materials used.

H. Schedules:

1. Mark luminaire schedule on drawings to indicate manufacturer and complete catalog numbers of installed equipment.
2. Mark schedules including panelboard, switchboard, motor control center, mechanical, kitchen and similar equipment schedules on drawings to indicate installed equipment and materials used, and any deviations or revisions to electrical load data and calculations.
3. Modifications to branch circuit device circuiting, circuit breaker size, etc. shall be clearly annotated on the associated panelboard schedule.

I. At the completion of the project, obtain from the Architect a complete set of the Contract Documents in a read-only electronic format (PDF unless otherwise noted). This set will include all revisions officially documented through the Architect/Engineer. Using the above color scheme, transfer any undocumented revisions from the construction site record drawings to this complete set. Submit marked up and completed documents to the Architect/Engineer. This contract will not be considered completed until these record documents have been received and reviewed by the Architect/Engineer.

1. Annotation of as-built modifications made on PDF documents shall NOT be flattened or mask the original content.

J. Contractor may propose methods of maintaining record documents on electronic media. Obtain approval of Engineer and Owner prior to proceeding. Marked-up PDF format, readable by Bluebeam is preferred.

K. Construction As-Built Drawings shall be submitted completely separate from the Operation and Maintenance Data documents.

L. If any of the above conditions are not met, the Engineer reserves the right to reject the Construction As-Built Drawing submittal and request resubmission of the drawings by the Contractor.

M. One full size set of record drawing one-line diagrams shall be posted in the electrical room.

1.25 OPERATION AND MAINTENANCE DATA:

A. Refer to the Division 1 Section on project closeout or operation and maintenance data for procedures and requirements for preparation and submittal of maintenance manuals.

B. No later than four (4) weeks prior to the completion of the project provide complete set of operating and maintenance manuals, or as specified in Sections of Division 1 (whichever is more stringent). Operation and Maintenance Data shall be submitted in electronic format.

C. Operation and Maintenance Data: Submit operation and maintenance data in maintenance manual in accordance with requirements of applicable Division 26 Sections and Division 1. Provide Operating and Maintenance Instructions in electronic format covering all equipment furnished. Manuals shall include all information required below, as indicated in each Division 26 Section, and the following for each piece of equipment:

1. The job name and address, contractor’s name, address, and phone number, and each subcontractor's name, address, and phone number shall be identified at the front of the electronic submittal.
2. Name, address, and telephone number to be contacted of the local authorized service organization/company and individual to be contacted for service and maintenance for each item of equipment.
3. Submit operation and maintenance data, schedule of recommended service and parts lists for all materials and products specified and intended for installation. Include description of function, normal operating characteristics and limitations, fuse curves, engineering data and tests, and complete nomenclature and commercial numbers of all replaceable parts.
4. Manufacturer's printed operating procedures to include start-up, break-in, routine and normal operating instructions; regulation, control, stopping, shut-down, and emergency instructions; and summer and winter operating instructions.
5. Maintenance procedures for routine preventative maintenance and troubleshooting; disassembly, repair, and reassembly; aligning and adjusting instructions.
6. Servicing instructions and lubrication charts and schedules.
7. Manufacturer's service manuals for all electrical equipment provided under this contract.
8. Complete equipment and protection wiring diagrams. All wiring diagrams shall show color coding of all connections and mounting dimensions of equipment.
9. Equipment identification numbers and adjustment clearly indicated for each piece of equipment.
10. Electrical System and Equipment Warranties.
11. Provide manuals tabbed and divided into major sections and special equipment. Mark the individual equipment when more than one model or make is listed on a page. Provide a detailed table of contents.
12. Record Set of Shop Drawings: Shop drawings corrected to show as-built conditions. Transfer modifications from field set.
13. Equipment Testing Report including all test reports and Equipment Settings Report indicating final configurations and settings.

D. Operation and Maintenance Data documents shall be submitted completely separate from the Construction As-Built Drawings.

E. This contract will not be considered completed nor will final payment be made until all specified material, including test reports, settings reports, and final Schedule of Values with all Electrical and Information Technology change order costs included and identified is provided and the manual is reviewed by the Architect/Engineer.

1.26 PROJECT CLOSEOUT LIST:

A. In addition to the requirements specified in Division 1, complete the requirements listed below.

1. The contractor shall be responsible for providing the items listed on the Electrical Submittal Checklist prior to applying for certification of substantial completion. Refer to individual specification sections for additional requirements (Checklist is located at the end of this section.)
2. Final payment will not be authorized until all items on the final punch list have been complete.

1.27 WARRANTIES:

A. Refer to the Division 1 Section on Warranties and Bonds for procedures and submittal requirements for warranties. Refer to individual equipment specifications for warranty requirements. In no case shall the warranty for the total electrical system be less than one year from the date of acceptance by the Owner.

B. Compile and assemble the warranties specified in Division 26, into a separated set of vinyl covered, three ring binders, tabulated, and indexed for easy reference.

C. Provide complete warranty information for each item. Information to include product or equipment description, date of beginning of warranty or bond; duration of warranty or bond; and names, addresses, and telephone numbers and procedures for filing a claim and obtaining warranty services.

1.28 CONSTRUCTION REQUIREMENTS:

A. The contractor shall maintain and have available at the jobsite current information on the following at all times:

1. Up-to-date record drawings.
2. Addenda
3. Change Orders
4. Submittals
5. Site observation reports with current status of all action items.
6. Test results; including recorded values, procedures, and other findings.
7. Outage information.

1.29 ELECTRICAL SUBMITTAL CHECKLIST:

A. Provide submittals including shop drawings, product data, product checklists, tests and reports, training, extra material, coordination drawings, record drawings, O&M manuals, device setting reports, and software licenses per the following schedule:

C – Product Checklist; Q – Qualifications, CD – Coordination Drawings, RD - Record Drawings, D – Device Setting Report; S – Software License, W – Special Project Warranty

SPEC Section	TITLE	Requirements									
		Report Data		Test	Factory Test	Report	Factory Rep Supervision at Site	Training Req'd at Site	Extra Material	O&M	Other
		Shop Drawings	Product Data								
26 05 00	Common Work Results For Electrical										
	Existing Conditions Survey Drawings	X									
	Seismic Design Parameters per Local Authority	X	X			X				X	
	Temporary Facilities	X	X			X					
	Product Listing		X							X	C
	Preliminary Schedule Of Values					X					
	Final Schedule Of Values					X				X	
	Lamp disposal Certificates /PCB/Hazardous Material			X		X				X	
	Tests	X	X	X	X	X	X	X		X	D
	Completed/Signed MOP's					X				X	
	Record Drawings including changes to existing Equip.	X								X	
	O&M Manuals	X	X	X	X	X			X	X	C,D,S
	Project Closeout List					X				X	
	Contractor/Equipment Warranties					X				X	
26 05 19	Low Voltage Electrical Power Conductors And Cables		X	X		X				X	
26 05 26	Grounding And Bonding For Electrical Systems	X	X	X		X				X	
26 05 29	Hangers And Supports For Electrical Systems	X	X							X	
26 05 33	Raceway And Boxes For Electrical Systems	X	X								CD, RD
	Conduit		X								CD, RD
	Surface Metal Raceway	X	X							X	CD, RD
	Wireways	X	X							X	CD, RD
26 05 34	Cabinets, Boxes & Fittings	X	X								CD, RD
26 05 53	Identification For Electrical Systems	X	X							X	
26 05 83	Wiring Connections	X	X	X							D
26 27 26	Wiring Devices		X	X		X				X	
26 28 00	Low Voltage Circuit Protective Devices	X	X	X		X		X	X	X	C, D.S

END SECTION 26 05 00

SECTION 26 05 19 – LOW VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

PART 1 - GENERAL

1.1 SUMMARYTEST:

A. This section includes wires, cables, and connectors for power, lighting, signal, control, and related systems rated 600 volts or less.

1.2 QUALITY ASSURANCE:

A. Manufacturers: Firms regularly engaged in the manufacture of electrical wire and cable products of types, sizes, and ratings required, whose products have been in satisfactory use in similar service for not less than 5 years.

B. Installer's Qualifications: Firm with at least 3 years of successful installation experience with projects utilizing electrical wiring and cabling work similar to that required for this project.

C. Conform to applicable code regulations regarding toxicity of combustion products of insulating materials.

1.3 SUBMITTALS:

A. See Section 26 05 00 Common Work Results for Electrical for Submittal requirements. Supplemental information is listed within this section.

B. Product Data: Submit manufacturer's data on electrical wires, cables, and connectors.

1.4 DELIVERY, STORAGE, AND HANDLING:

A. Deliver wire and cable properly packaged in factory fabricated type containers or wound on NEMA-specified type wire and cable reels.

B. Store wire and cable in clean dry space in original containers. Protect products from weather, damaging fumes, construction debris and traffic.

C. Handle wire and cable carefully to avoid abrading, puncturing, and tearing wire and cable insulation and sheathing. Ensure that dielectric resistance integrity of wires/cables is maintained.

PART 2 - PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS:

A. Manufacturers: Subject to compliance with requirements, provide products by the following (for each type of wire, cable, and connector):

1. Wire and Cable:

a. Belden
b. Cerrowire
c. Encore Wire
d. General Cable Corporation.
e. Southwire Company
f. Okonite

g. Superior Essex

2. Connectors:

a. Emerson
b. AMP, Inc.
c. Burndy Corporation.
d. Ideal Industries, Inc.
e. 3M Company
f. ABB

2.2 WIRES AND CABLES:

A. General: Provide wire and cable suitable for the temperature, conditions, and location where installed.

B. Conductors: Provide stranded conductors and approved connectors for all power, control, and lighting circuits.

C. Conductor Material: Use the following material for sizes indicated.

1. No. 1 AWG and Smaller and all grounding system conductors not sharing a common raceway: copper
2. No 1/0 AWG and Larger: 8000 Series electrical grade aluminum alloy 600v, except where another specific material is indicated.
3. Conductor sizes indicated on One line or schedules may be based on copper, see individual drawings for details. Sizes are based on copper if no designation is shown, Sizes are based on aluminum if Al is included in nomenclature. Modify conductor sizes as required to provide equivalent ampacity to indicated copper conductors. (A minus tolerance of 2 percent is permissible if ampacities remain above those shown in NEC Ampacity Tables.) Fully adapt and adjust the electrical system to size aluminum in lieu of copper. This includes, but is not limited to, the following actions:

a. Where connecting to equipment whose manufacturer requires copper conductors' connection, provide copper conductors from source, i.e. circuit breaker, disconnect, etc., and provide all necessary splices, splice boxes and other devices required to satisfy manufacturer requirements. Do not otherwise intermix copper and aluminum conductors.
b. Increase conduit size and increase sizes of pull boxes, junction boxes, and gutter space as required to accommodate larger aluminum conductors. Make structural, mechanical, and other construction adjustments necessitated by these changes.
c. Assure the pulling tension rating and support requirements of the aluminum conductors is adequate for wiring runs indicated.
d. Assure that equipment at which aluminum conductors terminate is UL listed and manufacturer approved for use with aluminum and so labeled.
e. Submit to the Architect/Engineer a record of actions taken in accordance with the above including marked-up project drawings, copies of manufacturer literature and communications and written conductor re-sizing calculations.
f. Do not reduce raceway or enclosure sizes as part of the above adjustments.

4. Metal Clad Cable - Type MC: Sizes 12 AWG and 10 AWG, copper conductors with 600-volt thermoplastic insulation rated 90 degrees C, galvanized steel interlocked metal type covering.

5. Cables: Provide the following types of cables in NEC approved locations and applications where permitted by the contract documents. Cables shall be U.L. listed and approved by the local building authority. All cables shall contain a green insulated equipment ground conductor of the same size as the neutral conductor.

2.3 CONNECTORS:

A. Description: Provide UL-type, factory fabricated, solderless metal connectors of sizes, ampacity ratings, materials, types and classes for applications and for services indicated. Use connectors with temperatures equal to or greater than those of the wires upon which used.

B. Provide 2-hole compression lugs for all power feeder, neutral, and grounding connections when installed on bus bars. (Including phase, neutral and grounding conductors).

C. Provide connectors that are designed to accept stranded conductors where stranded conductors are used.

PART 3 - EXECUTION

3.1 WIRE AND CABLE INSTALLATION SCHEDULE:

A. Building Wire: Install all building wire in raceway regardless of location.

B. Metal Clad Cable:

1. Maximum of 6 feet unsupported length for connecting luminaires in accessible ceilings to the local junction box.
2. Maximum of 6 feet unsupported length for connecting luminaires in non-accessible ceilings to the local junction box.
3. In stud walls and casework for horizontal branch circuit runs between devices.
4. For vertical branch circuit drops from a local junction box in each room above an accessible ceiling to the direct or single device in a stud wall, casework, under counter lighting.
5. May not be used for the following:

    a. Branch circuit home runs
    b. Feeders

6. Branch circuit conductors shall match color coding schedule within this specification section.

3.2 INSTALLATION OF WIRES AND CABLES:

A. General: Install electrical cables, wires, and connectors in compliance with applicable requirements of NEC, NEMA, UL, and NECA's "Standard of Installation", and in accordance with recognized industry practices.

B. Coordinate wire/cable installation work, including electrical raceway and equipment connection work, with other work.

C. Pull conductors simultaneously where more than one is being installed in the same raceway. Use pulling compound or lubricant, where necessary; compound used must not deteriorate conductor or insulation.

D. Use pulling means including fish tape, cable, rope, and basket weave wire/cable grips which will not damage cables or raceway. Do not use rope hitches for pulling attachment to wire or cable.

E. Keep conductor splices to a minimum. Splice only in accessible junction boxes. No splices are allowed in feeder, control, or fire alarm wiring. Connect un-spliced wire to numbered terminal strips at each end.

F. Install splices and taps which possess equivalent or better mechanical strength and insulation ratings than conductors being spliced.

G. Use splice and tap connectors which are compatible with conductor material.

H. Tighten electrical connectors and terminals, including screws and bolts, in accordance with manufacturer's published torque tightening values. Where manufacturer's torquing requirements are not indicated, tighten connectors and terminals to comply with tightening torques specified in UL Std. 486A for copper and 486B for aluminum.

I. Support cables above accessible ceilings. Independent from the ceiling suspension system to support cables from structure, do not rest on ceiling tiles.

J. Provide adequate length of conductors within electrical enclosures and train the conductors to terminal points with no excess. Bundle multiple conductors, with conductors larger than No. 10 AWG cabled to individual circuits. Make terminations so there is no bare conductor at the terminal.

K. Use solderless pressure connectors with insulating covers for copper wire splices and taps, 8 AWG and larger. For 10 AWG and smaller, use insulated screw on type spring wire connectors with plastic caps, push on type is not acceptable.

L. Use copper compression connectors for copper wire splices and taps, 1/0 AWG and larger. Tape uninsulated conductors and connectors with electrical tape to 150 percent of the insulation value of the conductor.

M. Make splices, taps and terminations to carry full ampacity of conductors without perceptible temperature rise.

N. Thoroughly tape the ends of spare conductors in boxes and cabinets.

O. Install exposed cable, parallel and perpendicular to surfaces, or exposed structural members, and follow surface contours, where possible.

P. Make all ground, neutral and line connections to receptacle and wiring device terminals as recommended by the manufacturer. Provide ground jumper from outlet box to individual ground terminal of devices.

Q. Branch circuits whose length from panel to first outlet exceeds 100 feet for 120-volt circuits or 175 feet for 277-volt circuit shall be 10 AWG or larger, as required to comply with the National Electrical Code.

R. Parallel conductors shall be cut to the same length.

S. All splices in control panels, terminal junction boxes, low voltage control circuits, fire alarm, etc., conductors shall be on numbered terminal strip.

T. Where conduit is not required, plenum rated cable shall be provided in ceiling, floor, or other air plenum spaces.

U. Provide wire training, lacing, labeling, and terminal blocks as required in panelboards and all control cabinets including, but not limited to, lighting, transfer switch, fire alarm, and security cabinets. All wiring shall be installed neatly and be labeled to match wiring diagrams, control devices, etc.

1. Make temporary connections to panelboard devices with sufficient slack conductor to facilitate reconnections required for balancing loads between phases.

V. Color coding of switch legs, travelers, etc. shall be different and distinct from phase and neutral conductors. Where systems utilize two (2) different voltages, the color coding of switch legs, travelers, etc. shall be different and distinct for each voltage system.

W. In each switchboard, switchgear, MCC, and ATS, neatly bundle each feeder group and attach to the equipment bracing.

3.3 FIELD QUALITY CONTROL:

A. Test installed wires and cables with 1000 VDC megohm meter to determine insulation resistance levels to ensure requirements are fulfilled. Test shall be made on all feeders regardless of size and on all branch circuits with No. 4 AWG and larger conductors. The megger values obtained shall be compared to the minimum values listed in NETA. All phase conductors and cables shall be meggered after installation, and prior to termination. Submit test report.

B. Prior to energization, test wires and cables for electrical continuity and for short circuits.

C. Subsequent to wire and cable hook-ups, energize circuitry and demonstrate functioning in accordance with requirements. Where necessary, correct malfunctioning units, and then retest to demonstrate compliance.

3.4 COLOR CODING SCHEDULE:

A. Color code secondary service, feeder, and branch circuit conductors as follows:

120/208 Volts	Phase
Black	A
Red	B
Blue	C
White	Neutral
Green	Ground

B. Conductors shall be solid color for entire length. Where circuits are combined within a single conduit and neutrals are dedicated to a phase, provide striping for the full length of neutral conductor insulation to match the color code of the associated phase conductor.

C. If solid color conductor insulation is not available and specific acceptance is given by the engineer for use of black conductor insulation, provide the following:

1. Conductors 6 AWG and smaller shall be solid color for the entire length.
2. Conductors 4 AWG and larger shall have either solid color insulation as specified above for the entire length or be black with color coding at each termination and in each box or enclosure. For 6 inches use half-lapped 3/4-inch plastic tape in the above specified color.

Do not cover cable identification markings. Adjust tape locations to prevent covering of markings.

END OF SECTION 26 05 19

SECTION 26 05 26 – GROUNDING AND BONDING FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY:

A. This Section includes solid grounding of electrical systems and equipment. It includes basic requirements for grounding for protection of life, equipment, circuits, and systems. Grounding requirements specified in this Section may be supplemented in other sections of these Specifications.

1.2 SUBMITTALS:

A. See Section 26 05 00 Common Work Results for Electrical for Submittal requirements. Supplemental information is listed within this section.

1.3 QUALITY ASSURANCE:

A. Listing and Labeling: Provide products specified in this Section that are listed and labeled. The terms "listed" and "labeled" shall be defined as they are in the National Electrical Code, Article 100.

B. Manufacturer's Qualifications: Firms regularly engaged in manufacture of grounding and bonding products, of types, and ratings required, and ancillary grounding materials, including stranded cable, copper braid and bus, grounding electrodes and plate electrodes, and bonding jumpers whose products have been in satisfactory use in similar service for not less than 5 years.

C. Installer's Qualifications: Firm with at least 3 years of successful installation experience on projects with electrical grounding work similar to that required for the project.

PART 2 - PRODUCTS

2.1 MANUFACTURERS:

A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. Burndy Corporation
2. Cadweld Div.; Erico Products Inc.
3. Ideal Industries
4. OZ Gedney Div.
5. Thermoweld
6. ABB Installation Products
7. nVent ERICO

2.2 GROUNDING AND BONDING PRODUCTS:

A. Products: Of types indicated and of sizes and ratings to comply with NEC. Where types, sizes, ratings, and quantities indicated are in excess of NEC requirements, the more stringent requirements and the greater size, rating, and quantity indications govern.

B. Conductor Materials: Copper.

2.3 WIRE AND CABLE CONDUCTORS:

A. General: Comply with Division 26 Section on Wires and Cables. Conform to NEC, except as otherwise indicated, for conductor properties, including stranding.

B. Equipment Grounding Conductor: Green insulated.

2.4 MISCELLANEOUS CONDUCTORS:

A. Ground Bus: Bare annealed copper bars of rectangular cross section.

2.5 CONNECTOR PRODUCTS:

A. General: Listed and labeled as grounding connectors for the materials used.

PART 3 - EXECUTION

3.1 APPLICATION:

A. Equipment Grounding Conductor: Comply with NEC for sizes and quantities of equipment grounding conductors, except where larger sizes or more conductors are indicated.

1. Install separate insulated equipment grounding conductors with circuit conductors for the following in addition to those locations where required by Code:

a. Feeders and branch circuits.
b. Provide individual grounding and neutral conductors for each isolated ground receptacle. When individual or groups of isolated ground receptacles are on dedicated circuits, individual ground and neutral conductors for each circuit is acceptable.

2. Nonmetallic Raceways: Install an insulated equipment ground conductor in nonmetallic raceways unless they are designated for telephone or data cables.

B. All systems shall be grounded in accordance with the NEC.

3.2 INSTALLATION:

A. General: Ground electrical systems and equipment in accordance with NEC requirements except where the Drawings or Specifications exceed NEC requirements. Connect together system neutral, service equipment enclosures, exposed noncurrent carrying metal parts of electrical equipment, metal raceway systems, grounding conductor in raceways and cables, receptacle ground connectors, and plumbing systems.

B. Route grounding conductors along the shortest and straightest paths possible without obstructing access or placing conductors where they may be subjected to strain, impact, or damage, except as indicated.

.

C. Where grounding conductors, grounding electrode conductors, or bonding conductors are non-exposed, identify each with a 6-inch band of green tape at each end and at 10-foot intervals. When run in conduits, provide color banding on conduit per section on Electrical Identification.

3.3 CONNECTIONS:

A. General: Make connections in such a manner as to minimize possibility of galvanic action or electrolysis. Select connectors, connection hardware, conductors, and connection methods so metals in direct contact will be galvanically compatible.

1. Use electroplated or hot coated materials to assure high conductivity and make contact points closer in order of galvanic series.
2. Make connections with clean bare metal at points of contact.
3. Coat and seal connections involving dissimilar metals with inert material such as red lead paint to prevent future penetration of moisture to contact surfaces.

B. Terminate insulated equipment grounding conductors for feeders and branch circuits with pressure type grounding lugs. Where metallic raceways terminate at metallic housings without mechanical and electrical connection to the housing, terminate each conduit with a grounding bushing. Connect grounding bushings with a bare grounding conductor to the ground bus in the housing. Bond electrically non-continuous conduits at both entrances and exits with grounding bushings and bare grounding conductors. Terminate each conductor on an individual ground lug terminal.

C. Tighten grounding and bonding connectors and terminals, including screws and bolts, in accordance with manufacturer's published torque tightening values for connectors and bolts. Where manufacturer's torquing requirements are not indicated, tighten connections to comply with torque tightening values specified in UL 486A.

D. Compression Type Connections: Use hydraulic compression tools to provide the correct circumferential pressure for compression connectors. Use tools and dies recommended by the manufacturer of the connectors. Provide embossing die code or other standard method to make a visible indication that a connector has been adequately compressed on the ground conductor.

END OF SECTION 26 05 26

This page left intentionally blank.

SECTION 26 05 29 – HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY:

A. This Section includes secure support from the building structure for electrical items by means of hangers, supports, anchors, sleeves, inserts, seals, and associated fastenings.

1.2 SUBMITTALS:

A. See Section 26 05 00 Common Work Results for Electrical for Submittal requirements. Supplemental information is listed within this section.

B. Product data for each type of product specified.

1. Hanger and support schedule showing manufacturer's figure number, size, spacing, features, and application for each required type of hanger, support, sleeve, seal, and fastener to be used.

C. Shop drawings indicating details of fabricated products and materials.

PART 2 - PRODUCTS

2.1 MANUFACTURERS:

A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. Slotted Metal Angle and U-Channel Systems:

a. Atkore
b. Eaton

2. Conduit Sealing Bushings:

a. Eaton
b. Hubbell
c. ABB

2.2 COATINGS:

A. Coating: Supports, support hardware, and fasteners shall be protected with zinc coating or with treatment of equivalent corrosion resistance using approved alternative treatment, finish, or inherent material characteristic. Products for use outdoors shall be hot dip galvanized.

2.3 MANUFACTURED SUPPORTING DEVICES:

A. Raceway Supports: Clevis hangers, riser clamps, conduit straps, threaded C-clamps with retainers, ceiling trapeze hangers, wall brackets, and spring steel clamps.

B. Fasteners: Types, materials, and construction features as follows:

1. Expansion Anchors: Carbon steel wedge or sleeve type.
2. Toggle Bolts: All steel springhead type.

3. Powder-Driven Threaded Studs: Heat treated steel, designed specifically for the intended service.

C. Conduit Sealing Bushings: Factory fabricated watertight conduit sealing bushing assemblies suitable for sealing around conduit, or tubing passing through concrete floors and walls. Construct seals with steel sleeve, malleable iron body, neoprene sealing grommets or rings, metal pressure rings, pressure clamps, and cap screws.

D. Cable Supports for Vertical Conduit: Factory fabricated assembly consisting of threaded body and insulating wedging plug for non-armored electrical cables in riser conduits. Provide plugs with number and size of conductor gripping holes as required to suit individual risers. Construct body of malleable iron casting with hot dip galvanized finish.

E. U-Channel Systems: 12-gauge steel channels, with 9/16-inch diameter holes, at a minimum of 8 inches on center, in top surface. Provide fittings and accessories that mate and match with U-channel and are of the same manufacture.

F. Supports: Provide supporting devices of types, sizes and materials indicated; and having the following construction features:

1. One-Hole Conduit Straps: For supporting 1 inch and smaller rigid metal conduit; galvanized steel.
2. Two-Hole Conduit Straps: For supporting larger than 1 inch metal conduit, galvanized steel; 3/4-inch strap width; and 2-1/8 inch between center of screw holes.

2.4 FABRICATED SUPPORTING DEVICES:

A. General: Shop or field fabricated supports or manufactured supports assembled from U-channel components.

B. Steel Brackets: Fabricated of angles, channels, and other standard structural shapes. Connect with welds and machine bolts to form rigid supports.

C. Pipe Sleeves: Provide pipe sleeves of one of the following:

1. Steel Pipe: Fabricate from Schedule 40 galvanized steel pipe.
2. EMT, IMC, or Rigid Conduit.

2.5 FIRE SEALS:

A. Material: Fire stopping material shall be asbestos free, 100 percent intumescent, have code approval under BOCA, ICBO, SSBC, NFPA 101, NFPA 70, and be capable of maintaining an effective barrier against flame and gases in compliance with the following requirements.

B. Flame Spread: 25 or less, ASTM E84

C. Fire Resistance and Hose Stream Tests: Fire stopping materials shall be rated "F" and "T" in accordance with ASTM E 814 or UL 1479. Rating periods shall conform to the following:
(F) 3 (T) 3 Time-rated floor or wall assemblies.

(F) 3 (T) 3 Openings between floor slabs and curtain wall.

D. Manufacturers: Subject to compliance with requirements, provide fire seals of the following:

1. 3M Company

2. STI
3. Tremco
4. Hilti

PART 3 - EXECUTION

3.1 INSTALLATION:

A. Install supporting devices to fasten electrical components securely and permanently in accordance with NEC requirements.

B. Coordinate with the building structural system and with other electrical installations.

C. Junction Box Supports: Comply with the NEC and the following requirement:

1. Use 1/4-inch all-thread rod from structure to support junction boxes.

D. Raceway Supports: Comply with the NEC and the following requirements:

1. Conform to manufacturer's recommendations for selection and installation of supports.
2. The strength of each support shall be adequate to carry present and future load multiplied by a safety factor of at least four. Where this determination results in a safety allowance of less than 200 lbs., provide additional strength until there is a minimum of 200 lbs. safety allowance in the strength of each support.
3. Install individual and multiple (trapeze) raceway hangers and riser clamps as necessary to support raceways. Provide U-bolts, clamps, attachments, and other hardware necessary for hanger assembly and for securing hanger rods and conduits.
4. Use #9 ceiling wire to support individual conduits up to 3/4-inch with spring steel fasteners. Use of ceiling support wires is unacceptable.
5. Support parallel runs of horizontal raceways together on trapeze type hangers. Use 3/8-inch diameter or larger threaded steel rods for support.
6. Support individual horizontal raceways by separate pipe hangers. Spring steel fasteners may be used in lieu of hangers only for 1-1/2-inch and smaller raceways serving lighting and receptacle branch circuits above suspended ceilings only. For hanger rods with spring steel fasteners, use 1/4-inch diameter or larger threaded steel. Use spring steel fasteners that are specifically designed for supporting single conduits or tubing. For hanger rods supporting 1-1/2-inch or larger conduits provide 3/8-inch minimum threaded steel rods with pipe hangers.
7. Space supports for raceways in accordance with NEC. When there are 4 or more 2-inch conduits in a trapeze, supports shall be spaced 5 feet O.C.
8. In all runs, arrange support so the load produced by the weight of the raceway and the enclosed conductors is carried entirely by the conduit supports with no weight load on raceway terminals.
9. Threaded rod supports to have bottoms cut off at a maximum length of 2-inches.
10. Attachment of electrical supports to piping, ductwork, mechanical equipment or conduit is not allowed.
11. Provide Anti-Rattle clips every 36 inches on conduit run horizontally inside metal studs.

E. Conductor or Cable Supports: Comply with the NEC and the following requirements:

1. Support individual conductors or cables by separate clamps with rubber or plastic grommet, fasten using a non-metallic bolt and nut, and secure clamps to strut supports anchored to structure (multiple clamps may be secured to a single strut support). Individual conductors or cables may be served utilizing a vinyl or fiberglass clamp which shall be anchored to the structure.

2. Space supports as follows:

   a. Horizontal conductors not more than 3 feet o.c.
   b. Vertical conductors not more than 5 feet o.c.

3. Install simultaneously with installation of conductors.
4. MC Cable shall be supported by UL listed clip or clamp.
5. Cable ties shall not be used as a means of support for any electrical or low voltage cable.

F. Miscellaneous Supports: Support miscellaneous electrical components separately and as required to produce the same structural safety factors as specified for raceway supports. Install metal channel racks for mounting cabinets, panelboards, disconnects, control enclosures, pull boxes, junction boxes, transformers, and other devices.

G. In overhead spaces, support metal boxes directly from the building structure via 1/4-inch minimum all-thread or by bar hangers. Where bar hangers are used, attach the bar to raceways on opposite sides of the box and support the raceway with an approved type of fastener not more than 24-inches from the box. Supporting metal boxes utilizing ceiling type wire is not acceptable.

H. Sleeves: Provide a sleeve for cables when passing through a non-fire rated wall to provide protection of cable.

I. Conduit Seals: Install seals for conduit penetrations of exterior walls below grade. Tighten sleeve seal screws until sealing grommets have expanded to form watertight seal.

J. Fastening: Unless otherwise indicated, fasten electrical items and their supporting hardware securely to the building structure, including but not limited to conduits, raceways, cables, cable trays, busways, cabinets, panelboards, transformers, boxes, disconnect switches, and control components in accordance with the following:

1. Fasten by means of wood screws on wood, toggle bolts on hollow masonry units, concrete inserts or expansion bolts or self-drilling masonry anchors on concrete or solid masonry, cast in inserts on precast structures, spring tension clamps on steel. Drilling of structural steel members is prohibited. Threaded studs driven by a powder charge and provided with lock washers and nuts may be used instead of expansion bolts and machine or wood screws, where authorized by the Owner and structural engineer. Do not weld conduit, pipe straps, or items other than threaded studs to steel structures. In partitions of light steel construction, use sheet metal screws.
2. Coordinate with the owner and structural engineer and obtain written prior approval of all work on concrete beams. Holes cut to depth of more than 1-1/2 inches in reinforced concrete beams or to depth of more than 3/4 inch in concrete shall not cut the main reinforcing bars. Fill holes that are not used.
3. Ensure that the load applied to any fastener does not exceed 25 percent of the proof test load. Use vibration- and shock-resistant fasteners for attachments to concrete slabs.

3.2 PERSONNEL PROTECTION:

A. Where U-channel systems, angles, brackets, or other standard structural metal shapes are readily accessible and exposed to personnel, provide plastic or rubber end caps.

B. Where threaded rod supports are readily accessible and exposed to personnel, provide plastic or rubber end caps.

3.3 FIRE STOPPING LOCATIONS:

A. Preparation:

1. Coordination: Coordinate the work with other trades. Fire stopping materials at penetrations of insulated pipes and ducts can be applied after insulation is in place. If insulation is composed of combustible material, the thickness of fire stopping materials must be equivalent to that of the insulation. If the insulation is composed of non-combustible material, it may be considered as part of the penetrating item.
2. Surface Preparation: Surface Preparation to be in contact with fire stopping materials shall be free of dirt, grease, oil, loose material, or other substances that may affect proper fitting or the required fire resistance.

B. Installation: Install fire-stopping materials in accordance with the manufacturer's instructions.

C. Cleaning: After completion of fire stopping work in any area, equipment shall be reviewed and walls, ceilings and all other surfaces shall be cleaned of deposits of firestop materials.

D. Inspection: The architect may select, and the Owner will pay an independent testing laboratory to examine fire stopped areas to ensure proper installation prior to concealing or enclosing the fire stopped areas.

END OF SECTION 26 05 29

This page left intentionally blank.

SECTION 26 05 33 - RACEWAY AND WIREWAY FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY:

A. Extent of raceway work is indicated by drawings and schedules. Provide complete conduit systems for all conductors unless otherwise specified.

B. Types of raceways specified in this section include the following:

1. Electrical Metallic Tubing (EMT).
2. Flexible Metal Conduit (FMC).
3. Intermediate Metal Conduit (IMC).
4. Liquidtight Flexible Metal Conduit (LFMC).
5. Non-metallic Conduit and Ducts.
6. Rigid Metal Conduit (RMC).
7. Surface metal raceways.
8. Wireways.
9. Rigid Aluminum Conduit.

1.2 QUALITY ASSURANCE:

A. Manufacturers: Firms regularly engaged in the manufacture of raceway systems of types and sizes required, whose products have been in satisfactory use in similar service for not less than 5 years.

B. Installer's Qualifications: Firm with at least 3 years of successful installation experience on projects with electrical raceway work similar to that required for this project.

1.3 SUBMITTALS:

A. See Section 26 05 00 Common Work Results for Electrical for Submittal requirements. Supplemental information is listed within this section.

B. Product Data: Submit manufacturer's technical product data, including specifications and installation instructions, for each type of raceway system required. Include data substantiating the materials comply with requirements.

C. Shop Drawings: Submit dimensioned drawings of surface metal raceway systems showing layout of raceways and fittings, spatial relationships to associated equipment, and adjoining raceways, if any. Show connections to electrical power panels and feeders.

PART 2 - PRODUCTS

2.1 MANUFACTURERS:

A. Subject to compliance with requirements, provide products by the following:

1. Metallic Conduit:

a. Atkore
b. Wheatland
c. Western Tube & Conduit
d. Nucor Tubular

2. Steel Fittings:

   a. Hubbell
   b. Emerson
   c. Picoma
   d. ABB

3. Conduit Bodies:

   a. Hubbell
   b. Appleton
   c. Eaton

4. Surface Metal Raceways:

   a. Legrand
   b. Hubbell
   c. Mono-Systems, Inc.

5. Wireway:

   a. Schneider Electric Erickson Electric Equipment Co.
   b. Hoffman Engineering Co.

2.2 METAL CONDUIT AND TUBING:

A. Electrical Metallic Tubing (EMT):

1. Conduit: Galvanized steel tubing.
2. Fittings: Steel compression fittings for rain-tight and concrete-tight applications. Steel set screw for all other connections. Setscrew quick fit type for 2-1/2 inches and larger may be used. Connectors shall have insulated throat or threaded nylon bushing.

B. Rigid Aluminum Conduit:

1. Not allowed unless otherwise noted.

C. Flexible Metal Conduit (FMC):

1. Conduit: Continuous spiral wound, interlocked, zinc-coated steel, approved for grounding.
2. Fittings: Zinc coated, malleable iron. Straight connector shall be one-piece body, female end with clamp and deep slotted machine screw for securing conduit, and threaded male end provided with a locknut. Angle connectors shall be two-piece body with removable upper section, female end with clamp and deep slotted machine screw for securing conduit, and threaded male end provided with a locknut. All fittings shall be terminated with threaded bushings having nylon insulated throats.

2.3 CONDUIT BODIES:

A. General: Types, shapes, and sizes, as required to suit individual applications and NEC requirements. Provide matching gasketed covers secured with corrosion-resistant screws.

B. Metallic Conduit and Tubing: Use malleable iron conduit bodies. Use bodies with threaded hubs for threaded raceways and in hazardous locations.

C. Nonmetallic Conduit: Use nonmetallic conduit bodies.

2.4 WIREWAYS:

A. General: Provide electrical wireways of types, grades, sizes, and number of channels for each type of service as indicated. Provide complete assembly of raceway including, but not limited to, couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other components and accessories as required for complete system.

B. Lay-In Wireways: Construct lay-in wireways with hinged covers in accordance with UL 870 with components UL listed. Construct units to be capable of sealing cover in closed position with sealing wire.

1. Connectors: Provide wireway connectors suitable for "lay-in" conductors, with connector covers permanently attached so that removal is not necessary to utilize the lay-in feature.
2. Finish: Protect sheet metal parts with rust inhibiting coating and baked enamel finish. Plate finish hardware to prevent corrosion. Protect screws installed toward inside of wireway with spring nuts to prevent wire insulation damage.

2.5 SURFACE METAL RACEWAYS:

A. General: Sizes and channels as indicated. Provide fittings that match and mate with raceway. All circuits should be either factory or field installed shall have a separate neutral conductor. Verify color with Architect/Engineer prior to order.

B. Boxes for surface raceways: Designed, manufactured, and supplied by raceway manufacturer for use with specified raceway.

2.6 CONDUIT SIZES:

A. Conduit sizes shall be as shown on the drawings. If the conduit size is not given on the drawings, the conduit shall be sized in accordance with NEC based on the number of conductors enclosed plus a parity sized equipment ground conductor and be subject to the following minimum sizes:

1. RMC, IMC, and EMT: 3/4-inch for all runs.
2. FMC and LFMC: 1/2-inch for all runs.
3. MC Cable: 3/8-inch to under-counter luminaires, 1/2-inch for all other runs.
4. Underground or Concrete Encased Nonmetallic Conduit: 3/4-inch for all runs.

2.7 RACEWAY SEALING COMPOUND:

A. Non-hardening, safe for human skin contact, not deleterious to cable insulation, workable at temperatures as low as 35 deg. F (1 deg. C), withstands temperature of 300 deg. F (149 deg. C) without slump, and adheres to clean surfaces of plastic ducts, metallic conduits, conduit coatings, concrete, masonry, lead, cable sheaths, cable jackets, insulation materials and the common metals.

PART 3 - EXECUTION

3.1 INSPECTION:

A. Examine areas and conditions under which raceways are to be installed, and substrate which will support raceways. Provide notification in writing of conditions detrimental to proper

completion of the work. Do not proceed with work until unsatisfactory conditions have been corrected in a manner acceptable to Installer.

3.2 CONDUIT SCHEDULE:

A. Raceways in all areas shall be EMT unless otherwise noted below.

B. .

C. Use FMC inside movable partition wireways, from junction boxes to devices and between devices in casework, from outlet boxes to recessed luminaires, and for "fishing" of existing walls.

D. Rework or extensions of existing conduit shall include the use of similar materials to the existing conduit type unless otherwise noted.

3.3 INSTALLATION OF CONDUITS:

A. General: Install electrical raceways in accordance with manufacturer's written installation instruction, applicable requirements of NEC, and as follows:

1. Conceal all conduits unless indicated otherwise, within finished walls, ceilings, and floors. Keep raceways at least 6 inches away from parallel runs of flues and steam or hot water pipes. Install raceways level and square and at proper elevations.
2. Provide Anti-Rattle clips every 36 inches on conduit run horizontally inside metal studs.
3. Elevation of Raceway:
    a. Where horizontal raceway is installed near water and steam piping, route raceway above piping and as close to structure as possible and practical.
    b. Route raceway as close to structure as possible.
4. Complete installation of electrical raceways before starting installation of conductors within raceways.
5. Provide supports for raceways as specified elsewhere in Division 26.
6. Prevent foreign matter from entering raceways by using temporary closure protection.
7. Make bends and offsets so the inside diameter is not effectively reduced. Unless otherwise indicated, keep the legs of a bend in the same plane and the straight legs of offsets parallel.
8. Use raceway fittings that are types compatible with the associated raceway and suitable for the use and location. Install expansion fittings across all structural construction joints and expansion/deflection couplings across all structural expansion joints.
9. Install expansion fittings across all structural construction joints and expansion/ deflection couplings across all structural expansion joints.
10. Run raceways parallel and perpendicular to building elements and other equipment with a minimum of bends in the shortest practical distance considering the type of building construction and obstructions except as otherwise indicated.
11. Install exposed raceways parallel and perpendicular to nearby surfaces or structural members and follow the surface contours as much as practical.
12. Install vertical feeder conduits in exterior walls, core walls, or chase spaces. Do not install in interior wall partition areas.
13. Run exposed and parallel raceways together. Make bends in parallel runs from the same center line so that the bends are parallel. Factory elbows may be used only where they can be installed parallel. In other cases, provide field bends for parallel raceways.
14. Make raceway joints tight. Where joints cannot be made tight, use bonding jumpers to provide electrical continuity of the raceway system. Make raceway terminations tight.

Where terminations are subject to vibration, use bonding bushings or wedges to assure electrical continuity. Where subject to vibration or dampness, use insulating bushings to protect conductors. Joints in non-metallic conduits shall be made with solvent cement in strict accordance with manufacturer's recommendations.

15. Tighten set screws of thread less fittings with suitable tool.
16. Terminations: Where raceways are terminated with locknuts and bushings, align the raceway to enter squarely and install the locknuts with dished part against the box. EMT shall be secured with one locknut and shall have nylon insulated throats or threaded nylon bushings from 1/2-inch to 1-inch. 1-1/4-inch and above shall be metal with nylon insulated throats. Use grounding type bushings for feeder conduits at switchboards, panelboards, pull boxes, transformers, motor control centers, VFD's, etc.
17. Conduit sleeves shall have bushings as described for terminations.
18. Where terminating in threaded hubs, screw the raceway or fitting tight into the hub so the end bears against the wire protection shoulder. Where chase nipples are used, align the raceway so the coupling is square to the box, and tighten the chase nipple so no threads are exposed.
19. Provide nylon pull string with printed footage indicators having not less than 200 pounds tensile strength. Leave not less than 12 inches of slack at each end of the pull string. Identify with tags at each end the origin and destination of each empty conduit and indicate same on all empty or spare conduits on the as-built drawings.
20. Install raceway sealing compound in accordance with the manufacturer’s written instructions at the following points:

    a. Where conduits pass from warm locations to cold locations, such as the boundaries of refrigerated spaces and air-conditioned spaces.
    b. Where conduits enter through a foundation wall or stub-up through a slab on grade floor.

21. Flexible Connections: Use short length (maximum of 6 feet) of FMC for recessed and semi-recessed luminaires, for equipment subject to vibration, noise transmission, or movement; and for all motors. Use LFMC in wet locations. Install separate equipment grounding conductor across flexible connections. Where PVC conduit/couplings have been approved for exterior use and are exposed to sunlight, provide UV rated PVC coatings or protect with 2 coats of water based latex paint that is chemically compatible with the PVC products. Color selection shall be by the Architect.
22. Where conduits are to be installed through structural framing members, the Contractor shall provide sleeves. The Architect/Engineer's written approval must be obtained prior to cutting, notching, or drilling of structural framing members.
23. Ream the ends of all cut and/or threaded conduit. Ends shall be cut square.
24. Use of running threads for rigid or intermediate metallic conduit are not permitted. When threaded couplings cannot be used, provide 3-piece union or solid coupling.
25. Conduits shall not cross pipe shafts or ventilation duct openings. Where conduits must penetrate air-tight spaces or plenums, seal around the conduit with a mastic acceptable to the Architect/Engineer.
26. Install an insulated equipment grounding conductor in all conduits.
27. Where individual conduits penetrate existing fire-rated walls and floors, pack void around conduit with fire rated insulation and seal opening around conduit with UL listed foamed silicone elastomer compound. Where conduits penetrate exterior walls, new floors, or roof, provide pipe sleeve one size larger than conduit, pack void around conduit with fire rated insulation, and seal opening around conduit with UL listed foam silicone elastomer compound.
28. Where conduit sleeves penetrate fire rated floors or walls for installation of system cables, AC or MC cables, or modular wiring cables pack void around cables or empty sleeve with fire rated insulation and fill ends with fire-resistive compound. Seal opening around sleeve with UL listed foam silicone elastomer compound.
29. Provide separate raceway systems for each of the following:

a. Power Distribution
b. Communications and Data

30. Paint new exposed conduits to match existing exposed conduits where installed in areas with existing painted conduits or where otherwise indicated.
31. Provide rebar and tie downs for all conduits and conduit racks to be installed with concrete or slurry to prevent conduit “float”.
32. In open ceiling areas, other than equipment rooms, all wiring and cabling to be installed in conduit.

B. Install labeling as required in Division 26 section - “Identification for Electrical Systems”.

3.4 INSTALLATION OF SURFACE RACEWAYS AND WIREWAYS:

A. Surface Raceways and Wireways: Mechanically assemble metal enclosures and raceways to form continuous electrical conductor and connect to electrical boxes, fittings and cabinets as to provide effective electrical continuity and rigid mechanical assembly.

1. Where practicable, avoid use of dissimilar metals throughout the system to eliminate possibility of electrolysis. Where dissimilar metals are in contact, coat all surfaces with corrosion inhibiting compound before assembling.
2. Install expansion fittings in all raceways wherever structural expansion joints are crossed.
3. Make changes in direction of raceway run with proper fittings, supplied by raceway manufacturer. Field bends of raceway sections are not permitted.
4. Properly support and anchor raceways for their entire length by structural materials. Raceways are not to span any space unsupported.
5. Use boxes as supplied by raceway manufacturer wherever junction, pull or device boxes are required. Standard electrical "handy" boxes, etc., are not permitted for use with surface raceway installations.
6. Install an insulated grounding conductor in all wireways and surface raceways. Bond grounding conductor to all wireways and surface raceways.
7. Paint new exposed surface metal raceway to match adjacent surfaces where raceway is installed in finished areas such as lobbies, corridors, and normally occupied spaces.
8. Surface raceways and wireways are acceptable only where specifically indicated on the drawings. The proposed use of surface raceways and wireways shall be submitted for review by the Engineer prior to installation.
9. Common wireways are not acceptable for convergence of multiple circuits unless specifically indicated on the drawings. The proposed use of a common wireway shall be submitted for review by the Engineer prior to installation.
10. The proposed use of wireways above or below panelboards, switchboards, motor control centers, and other electrical equipment shall be submitted along with a layout drawing for review by the Engineer prior to installation.

3.5 ADJUSTING AND CLEANING:

A. Upon completion of installation of raceways, inspect interiors of raceways; clear all blockages and remove burrs, dirt, and construction debris.

END OF SECTION 26 05 33

SECTION 26 05 34 - CABINETS, BOXES, AND FITTINGS

PART 1 - GENERAL

1.1 SUMMARY:

A. This section includes cabinets, boxes, and fittings for electrical installations and certain types of electrical fittings not covered in other sections. Types of products specified in this section include:

1. Outlet and device boxes
2. Pull and junction boxes
3. Cabinets
4. Hinged door enclosures

B. Conduit-body-type electrical enclosures and wiring fittings are specified in the Division 26 Section on Raceways.

1.2 DEFINITIONS:

A. Device Box: An outlet box designed to house a receptacle device, or a wiring box designed to house a switch.

B. Enclosure: A box, case, cabinet, or housing for electrical wiring or components.

C. Outlet Box: A wiring enclosure where current is taken from a wiring system to supply utilization equipment.

D. Wiring Box: An enclosure designed to provide access to wiring systems or for the mounting of indicating devices or switches for controlling electrical circuits.

1.3 SUBMITTALS:

A. See Section 26 05 00 Common Work Results for Electrical for Submittal requirements. Supplemental information is listed within this section.

B. Submit product data for cabinets and enclosures with classification higher than NEMA 1.

C. Shop drawings for floor boxes and boxes, enclosures, and cabinets that are to be shop fabricated (non-stock items). For shop fabricated junction and pull boxes, show accurately scaled views and spatial relationships to adjacent equipment. Show box types, dimensions, and finishes.

PART 2 - PRODUCTS

2.1 MANUFACTURERS:

A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. Cabinets:

a. Hoffman Engineering Co.
b. Erickson Electrical Equipment Co.
c. Schneider Electric

2.2 CABINETS, BOXES, AND FITTINGS, GENERAL:

A. Electrical Cabinets, Boxes, and Fittings: Of indicated types, sizes, and NEMA enclosure classes. Where not indicated, provide units of types, sizes, and classes appropriate for the use and location. Provide all items complete with covers including blank covers for unused boxes, knockout closures for unused openings and other accessories required for the intended use. Provide gaskets for units in damp or wet locations. Provide protective pocket inside front cover with schematic diagram, connection diagram, and layout drawing of control wiring and components within enclosure.

2.3 MATERIALS AND FINISHES:

A. Sheet Steel: Flat-rolled, code-gage, galvanized steel.

B. Fasteners for General Use: Corrosion resistant screws and hardware including cadmium and zinc plated items.

C. Fasteners for Damp or Wet Locations: Stainless steel screws and hardware.

D. Exterior Finish: Gray baked enamel for items exposed in finished locations except as otherwise indicated.

2.4 METAL OUTLET, DEVICE, AND SMALL WIRING BOXES:

A. General: Conform to UL 514A, "Metallic Outlet Boxes, Electrical," and UL 514B, "Fittings for Conduit and Outlet Boxes." Boxes shall be of type, shape, size, and depth to suit each location and application. For multiple device installations, use multi-gang boxes. Sectional boxes are not permitted. Provide barrier for different voltage conductors in the same box.

B. Steel Boxes: Conform to NEMA OS 1, "Sheet Steel Outlet Boxes, Device Boxes, Covers, and Box Supports." Boxes shall be 4” square minimum with 2” depth minimum sheet steel with stamped knockouts, threaded screw holes and accessories suitable for each location including mounting brackets and straps, cable clamps, exterior/plaster rings and fixture studs.

2.5 PULL AND JUNCTION BOXES:

A. General: Comply with UL 50, "Electrical Cabinets and Boxes", for boxes over 100 cubic inches volume. Boxes shall have screwed or bolted on covers of material same as box and shall be of size and shape to suit application.

B. Steel Boxes: Sheet steel with welded seams. Where necessary to provide a rigid assembly, construct with internal structural steel bracing.

PART 3 - EXECUTION

3.1 INSTALLATION, GENERAL:

A. Locations: Install items where indicated and where required to suit code requirements and installation conditions. Coordinate box locations with Architectural elements including casework, backsplash, door swings, etc.

B. Cap with knock out closures all unused knockout holes where blanks have been removed and plug unused conduit hubs.

C. Support and fasten items securely in accordance with Division 26 Section on Supporting Devices.

D. Sizes shall be adequate to meet NEC volume requirements, but in no case smaller than sizes indicated. Size boxes to accommodate wire pulling, splices, taps, equipment connections and code compliance.

E. Remove sharp edges where they may come in contact with wiring or personnel.

3.2 APPLICATIONS:

A. Outlet Boxes and Fittings: Install outlet and device boxes and associated covers and fittings of materials and NEMA types suitable for each location and in conformance with the following requirements:

1. Interior Dry Locations: Sheet steel, NEMA Type 1.

B. Pull and Junction Boxes: Install pull and junction boxes of materials and NEMA types suitable for each location except as otherwise indicated.

3.3 INSTALLATION OF OUTLET BOXES:

A. Outlets at Windows and Doors: Locate close to window trim. For outlets indicated above doors center outlets above the door opening except as otherwise indicated.

B. Column and Pilaster Locations: Locate outlet boxes for switches and receptacles on columns or pilasters so the centers of the columns are clear for future installation of partitions.

C. Locations in Special Finish Materials: For outlet boxes for receptacles and switches mounted in desks or furniture cabinets or in glazed tile, concrete block, marble, brick, stone or wood walls, use rectangular shaped boxes with square corners and straight sides. Install such boxes without plaster rings. Saw cut all recesses for outlet boxes in exposed masonry walls.

D. Mounting: Mount outlet boxes for switches and receptacles with the long axis vertical or as indicated. Three or more gang boxes shall be mounted with the long axis horizontal. Locate box covers or device plates so they will not span different types of building finishes either vertically or horizontally. Locate boxes for switches near doors on the side opposite the hinges and close to door trim, even though electrical floor plans may show them on hinge side. Provide far side box supports for electrical switch boxes installed on metal studs and provide stud-to-stud support for electrical receptacle boxes installed on metal studs.

E. Ceiling Outlets: For fixtures, where wiring is concealed, use outlet boxes 4 inches square by 1-1/2 inches deep, minimum.

F. Cover Plates for Surface Boxes: Use plates sized to box front without overlap.

G. Protect outlet boxes to prevent entrance of plaster, and debris. Thoroughly clean foreign material from boxes before conductors are installed.

H. Existing Outlet Boxes: Where extension rings are required to be installed, drill new mounting holes in the rings to align with the mounting holes on the existing boxes where existing holes are not aligned.

I. Back-to-back outlet boxes are not permitted. Separate boxes a minimum of 6 inches in standard walls and 24 inches in acoustical walls.

3.4 INSTALLATION OF PULL AND JUNCTION BOXES:

A. Box Selection: For boxes in main feeder conduit runs, use sizes not smaller than 8 inches square by 4 inches deep. Do not exceed 6 entering and 6 leaving raceways in a single box. Quantities of conductors (including equipment grounding conductors) in pull or junction box shall not exceed the following:

Size of Largest Conductors in Box	Maximum no. of Conductors in Box
No. 4/0 AWG	30
250 KCMIL	20
500 KCMIL	15
Over 500 KCMIL	10

B. Cable Supports: Install clamps, grids, or devices to which cables may be secured. Arrange cables so they may be readily identified. Support cable at least every 30 inches inside boxes.

C. Mount pull boxes in inaccessible ceilings with the covers flush with the finished ceiling. Where possible, locate pull and junction boxes above accessible ceilings in finished areas.

3.5 GROUNDING:

A. Electrically ground metallic cabinets, boxes, and enclosures. Where wiring to item includes a grounding conductor, provide a grounding terminal in the interior of the cabinet, box or enclosure.

3.6 CLEANING AND FINISH REPAIR:

A. Upon completion of installation, inspect components. Remove burrs, dirt, and construction debris and repair damaged finish including chips, scratches, abrasions and weld marks.

B. Galvanized Finish: Repair damage using a zinc-rich paint recommended by the tray manufacturer.

C. Painted Finish: Repair damage using matching corrosion inhibiting touch-up coating.

END OF SECTION 26 05 34

SECTION 26 05 53 – IDENTIFICATION FOR ELECTRICAL SYSTEMS

PART 1 - GENERAL

1.1 SUMMARY:

A. This Section includes identification of electrical materials, equipment, and installations. It includes requirements for electrical identification components including but not limited to the following:

1. Identification labeling for raceways, cables, and conductors.
2. Operational instruction signs.
3. Warning and caution signs.
4. Equipment labels and signs.

B. Identification required in this section shall apply to equipment furnished in Division 26 and any other applicable Divisions including Division 23.

1.2 SUBMITTALS:

A. See Section 26 05 00 Common Work Results for Electrical for Submittal requirements. Supplemental information is listed within this section.

B. Product Data for each type of product specified.

C. Submit schedule of identification nomenclature to be used for identification signs and labels for each type of equipment.

1.3 QUALITY ASSURANCE:

A. ANSI Compliance: Comply with requirements of ANSI Standard A13.1, "Scheme for the Identification of Piping Systems," regarding type and size of lettering for raceway and cable labels.

PART 2 - PRODUCTS

2.1 MANUFACTURERS:

A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. Ideal Industries, Inc.
2. Markal Corp.
3. Panduit Corp.
4. W.H. Brady, Co.
5. 3M Company

2.2 ELECTRICAL IDENTIFICATION PRODUCTS:

A. Wire/Cable Designation Tape Markers: Vinyl or vinyl cloth, self-adhesive, wraparound, cable/conductor markers with preprinted numbers and letters.

B. Engraved, Plastic Laminated Labels, Signs, and Instruction Plates: Engraving stock melamine plastic laminate, 1/16-inch minimum thick for signs up to 20 square inches, or 8 inches in length; 1/8-inch thick for larger sizes. Engraved legend in white letters on black face for normal and white letters on red face for emergency, black letters on yellow face for UPS and punched for

mechanical fasteners. Where required for ground connections, provide engraved legend in white letters on green face.

C. Fasteners for Plastic Laminated and Metal Signs: Self-tapping stainless-steel screws when screw ends do not protrude into working areas of equipment otherwise use number 10/32 stainless steel machine screws with nuts and flat and lock washers or rivets.

D. Cable Ties: Fungus-inert, self-extinguishing, one-piece, self-locking nylon cable ties, 0.18-inch minimum width, 50 lb. minimum tensile strength, and suitable for a temperature range from minus 50 degrees F to 350 degrees F. Provide ties in specified colors when used for color coding.

E. Adhesive Marking Tape for Device Cover Plates: 3/8-inch Kroy tape or Brother labels with 3/16-inch minimum height letters. Tape shall have black letters on clear background for normal and red letters on clear background for emergency. Embossed Dymo-Tape labels are not acceptable.

PART 3 - EXECUTION

3.1 INSTALLATION:

A. Lettering and Graphics: Coordinate names, abbreviations, colors, and other designations used in electrical identification work with corresponding designations specified or indicated. Install numbers, lettering, and colors as approved in submittals and as required by code. Clean surfaces to receive nameplates and labels and install nameplates and labels on front of equipment parallel with equipment/raceway/cable/wire/etc. lines.

B. Install identification devices in accordance with manufacturer's written instructions and requirements of NEC.

C. Sequence of Work: Where identification is to be applied to surfaces that require finish, install identification after completion of finish work.

D. Identify Junction, Pull and Connection Boxes: Identification of systems and circuits shall indicate system voltage and identity of contained circuits on outside of box cover. Color code shall be same as raceway systems. Use self-adhesive marking tape labels at exposed locations and indelible black marker at concealed boxes.

E. Circuit Identification: Tag or label conductors as follows:

1. Future Connections: Conductors indicated to be for future connection or connection under another contract with identification indicating source and circuit numbers.
2. Multiple Circuits: Where multiple branch circuits, control wiring or communications/signal conductors are terminated or spliced in a box or enclosure, label each conductor or cable with circuit number. For control, fire alarm, and communications/signal wiring, use wire/cable marking tape at terminations in wiring boxes, troughs, and control cabinets. Use consistent letter/number conductor designations throughout on wire/cable marking tapes.
3. Match identification markings with designations used in panelboards shop drawings, Contract Documents, and similar previously established identification schemes for the facility's electrical installations.

F. Apply warning, caution and instruction signs and stencils as follows:

1. Install warning, caution or instruction signs where required by NEC, where indicated, or where reasonably required to assure safe operation and maintenance of electrical systems and of the items to which they connect. Install engraved plastic laminated instruction signs with approved legend where instructions or explanations are needed for system or equipment operation. Install butyrate signs with metal backing for outdoor items.

G. Install equipment/system circuit/device identification as follows:

1. Apply equipment identification labels of engraved plastic laminate on each major unit of electrical equipment in building, including central or master unit of each electrical system. This includes communication/signal/alarm systems unless unit is specified with its own self-explanatory identification. Text shall match terminology and numbering of the Contract Documents and shop drawings. Apply labels for each unit of the following categories of electrical equipment.

a. Electrical cabinets, and enclosures

H. Apply circuit/control/item designation labels of engraved plastic laminate for disconnect switches, breakers, pushbuttons, pilot lights, motor control centers, and similar items for power distribution and control components above, except panelboards and alarm/signal components, where labeling is specified elsewhere.

I. Install labels at locations as required and at locations for best convenience of viewing without interference with operation and maintenance of equipment.

J. Provide adhesive marking tape labels for identification of individual receptacles including receptacles in furniture systems and light switch wall-plates. Locate tape on front of plate and identify panel and branch circuit serving the receptacle. Provide tape labels for identification of individual switches or thermal overload switches which serve as equipment disconnects. Locate the tape on the front of the cover-plate and identify panel and branch circuit serving the equipment.

END OF SECTION 26 05 53

This page left intentionally blank.

SECTION 26 05 83 – WIRING CONNECTIONS

PART 1 - GENERAL

1.1 SUMMARY:

A. Extent of electrical connections for equipment is indicated by drawings and schedules. Electrical connections are hereby defined to include connections used for providing electrical power to equipment.

B. Applications of electrical power connections specified in this section include the following:

1. To grounds.
2. Other connections as shown.

1.2 QUALITY ASSURANCE:

A. Manufacturers: Firms regularly engaged in manufacture of electrical connectors and terminals, of types and ratings required, and ancillary connection materials, including electrical insulating tape, soldering fluxes, and cable ties, whose products have been in satisfactory use in similar service for not less than 5 years.

B. Installer's Qualifications: Firms with at least 2 years of successful installation experience with projects utilizing electrical connections for equipment similar to that required for this project.

1.3 SUBMITTALS:

A. See Section 26 05 00 Common Work Results for Electrical for Submittal requirements. Supplemental information is listed within this section.

B. Product Data: Submit manufacturer's data on electrical connections for equipment products and materials. All mechanical and plumbing equipment shall be coordinated with unit nameplate information of the actual nameplate to be included on the equipment. As a minimum, information shall include: Operating Voltage; MCA (Min. circuit amperes); FLA (Full load amperes); MFS (Max. fuse size) or MOCP (Max. overcurrent protection); and SCCR (Short Circuit Current Rating) and shall match electrical equipment and protection/distribution sizes and be rated for available short circuit currents as shown on the drawings. Bracing for equipment shall be provided at incoming terminals and as an option throughout the equipment for the available fault current or downstream equipment and devices shall be protected by current limiting fuses.

1.4 DEFINITIONS:

A. Load voltage wiring shall be defined as:

1. Conduit and wiring required to carry power to motors and other equipment or devices. Wiring from control devices to equipment that carry power to drive that equipment such as line voltage thermostats, etc., shall be included as load voltage wiring. Wiring that provides power to control panels, control transformers, control relays, time clocks, etc., shall also be included as load voltage wiring.

1.5 DELIVERY, STORAGE, AND HANDLING:

A. Deliver electrical connection products wrapped in proper factory fabricated type containers.

B. Store electrical connection products in original cartons and protect from weather, construction traffic and debris.

C. Handle electrical connection products carefully to prevent breakage, denting, and scoring finish.

PART 2 - PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS:

A. Manufacturer: Subject to compliance with requirements, provide circuit and motor disconnects by one of the following:

1. ABB
2. Eaton
3. Schneider Electric
4. Siemens Energy & Automation, Inc.

2.2 GENERAL:

A. Overcurrent Protective Devices (OCPDs): Provide type, rating, and features as indicated. Comply with Division 26 Section on Low Voltage Circuit Protective Devices, with OCPDs adapted to equipment connection installation. Tandem circuit breakers shall not be used. Multiple breakers shall have common trip.

B. Provide motor controllers that are horsepower rated to suit the motor controlled.

C. Contacts shall open each ungrounded connection to the motor. Contacts shall be NEMA rated, 75 degrees C.

D. Overload relays shall be ambient-compensated type with inverse-time-current characteristic. Provide with heaters or sensors in each phase matched to nameplate full load current of the specific motor to which connected with appropriate adjustment for duty cycle and power factor correction supplied with the motor.

2.3 MATERIALS AND COMPONENTS:

A. General: For each electrical connection indicated, provide complete assembly of materials, including but not necessarily limited to, pressure connectors, terminals (lugs), electrical insulating tape, electrical solder, electrical soldering flux, heat-shrinkable insulating tubing, cable ties, solderless wire-nuts, disconnect, starter, contactor, relays, etc., and other items and accessories as needed to complete splices and terminations of types indicated.

B. Metal Conduit, Tubing and Fittings:

1. General: Provide metal conduit, tubing and fittings of types, grades, sizes and weights (wall thicknesses) indicated for each type of service. Provide products complying with Division-26 section on Raceways.

C. Wires, Cables, and Connectors:

1. General: Provide wires, cables, and connectors complying with Division-26 section on Wires and Cables.
2. Wires/Cables: Unless otherwise indicated, provide wires/cables (conductors) for electrical connections which match, including sizes, ratings, and material of wires/cables which are supplying electrical power.

3. Connectors and Terminals: Provide electrical connectors and terminals which mate and match, including sizes and ratings, with equipment terminals recommended by equipment manufacturer for intended applications.
4. Electrical Connection Accessories: Provide electrical insulating tape, heat-shrinkable insulating tubing and boots, electrical solder, electrical soldering flux, wire-nuts and cable ties as recommended for use by accessories manufacturers for type services indicated.
5. Cord and Plug Connected Equipment: Where indicated, contractors shall provide a length of SO cord complete with a straight blade or twist-lock receptacle for connection of equipment. Cord and plug rating shall be suitable for the connected equipment load and rating of the branch circuit overcurrent protective device. Plug shall match receptacle configuration included on the plans and cord length shall be as required. Contractor shall connect cord to equipment.

PART 3 - EXECUTION

3.1 INSPECTION:

A. Inspect area and conditions under which electrical connections for equipment are to be installed and notify Contractor in writing of conditions detrimental to proper completion of the work. Do not proceed with the work until unsatisfactory conditions have been corrected in a manner acceptable to Installer.

3.2 INSTALLATION OF ELECTRICAL CONNECTIONS:

A. Furnish, set in place, and wire (except as may be otherwise indicated) all heating, ventilating, air conditioning, plumbing and fire protection, elevator, etc., motors and controls in accordance with the following schedule and in accordance with equipment manufacturer's written instructions and with recognized industry practices, and complying with applicable requirements of UL, NEC and NECA's "Standard of Installation" to ensure that products fulfill requirements. Carefully coordinate with work performed under the Mechanical Division of these Specifications.

B. Coordinate with other work, including wires/cables, raceway, and equipment installation, as necessary to properly interface installation of electrical connections for equipment with other work.

C. Connect electrical power supply conductors to equipment conductors in accordance with equipment manufacturer's written instructions and wiring diagrams. Mate and match conductors of electrical connections for proper interface between electrical power supplies and installed equipment.

D. Maintain existing electrical service and feeders to equipment serving occupied areas and operational facilities, unless otherwise indicated, or when authorized otherwise in writing by Owner, or Architect/Engineer. Provide temporary service during interruptions to existing facilities. When necessary, schedule momentary outages for replacing existing wiring systems with new wiring systems. When that "cutting over" has been successfully accomplished, remove, relocate, or abandon existing wiring as indicated.

E. Cover splices with electrical insulating material equivalent to, or of greater insulation resistivity rating, than electrical insulation rating of the spliced conductors.

F. Prepare cables and wires, by cutting and stripping covering armor, jacket, and insulation properly to ensure uniform and neat appearance where cables and wires are terminated. Exercise care to avoid cutting through tapes which will remain on conductors. Also avoid "ringing" copper conductors while skinning wire.

G. Trim cables and wires as short as practicable and arrange routing to facilitate inspection, testing and maintenance.

H. Tighten connectors and terminals, including screws and bolts, in accordance with equipment manufacturers published torque tightening values for equipment connectors. Accomplish tightening by utilizing proper torqueing tools, including torque screwdriver, beam-type torque wrench, and ratchet wrench with adjustable torque settings. Where manufacturer's torquing requirements are not available, tighten connectors and terminals to comply with torqueing values contained in UL's 486A.

I.

J. Make wiring connections in control panel or in wiring compartment of pre-wired equipment and interconnecting wiring in accordance with manufacturer's instructions.

K. Provide circuit and motor disconnect switches as indicated and where required by Code. Comply with switch manufacturers printed installation instructions. Install within sight of motors.

L. All splices in control panels, terminal junction boxes, low voltage control circuits and fire alarm conductors shall be on numbered terminal strip.

M. Each branch circuit serving dedicated, isolated or emergency receptacles, multi-outlet assemblies or equipment connections shall be furnished with a dedicated neutral conductor. Neutrals common to more than one circuit shall only be permitted where specifically noted.

N. Where conduit is not required, plenum rated cable shall be provided in ceiling, floor or other air plenum spaces.

3.3 FIELD QUALITY CONTROL:

A. Upon completion of installation of electrical connections, and after circuitry has been energized with rated power source, test connections to demonstrate capability and compliance with requirements. Ensure that direction of rotation of each motor fulfills requirement. Correct malfunctioning units at site, then retest to demonstrate compliance.

END OF SECTION 26 05 83

SECTION 26 27 26 - WIRING DEVICES

PART 1 - GENERAL

1.1 SUMMARY:

A. The extent of wiring device work is indicated by drawings and schedules. Wiring devices are defined as single discrete units of electrical distribution systems which are intended to carry but not utilize electric energy.

B. Types of electrical wiring devices in this section include the following:

1. Receptacles.
2. Ground-fault circuit interrupters.
3. Wall-plates.
4. Plugs and connectors.

1.2 QUALITY ASSURANCE:

A. Manufacturers: Firms regularly engaged in the manufacture of electrical wiring devices, of types, sizes, and ratings required, whose products have been in satisfactory use in similar service for not less than 3 years.

B. Installer's Qualifications: Firm with at least 2 years of successful installation experience on projects utilizing wiring devices similar to those required for this project.

C. Listing and Labeling: Provide products that are listed and labeled for their applications and installation conditions and for the environments in which they are installed.

1. The Terms "Listed" and "Labeled": As defined in the "National Electrical Code", Article 100.
2. Listing and Labeling Agency Qualifications: A "Nationally Recognized Testing Laboratory" (NRTL) as defined in OSHA Regulation 1910.7.

1.3 SUBMITTALS:

A. See Section 26 05 00 Common Work Results for Electrical for Submittal requirements. Supplemental information is listed within this section.

B. Samples of device plates for color selection and evaluation of technical features shall be submitted.

1.4 COORDINATION:

A. Wiring Devices for Owner Furnished Equipment: Match devices to plug connectors for Owner-furnished equipment.

B. Cord and Plug sets: Match cord and plug sets to equipment requirements.

PART 2 - PRODUCTS

2.1 ACCEPTABLE MANUFACTURERS:

A. Manufacturers: Products shall be of the same manufacturer insofar as possible. Subject to compliance with requirements, provide wiring devices of one of the following:

1. Devices, Cover Plates, Accessories:

    a. Hubbell Inc.
    b. Leviton Mfg. Co.
    c. Legrand
    d. Eaton
    e. ABB

2.2 WIRING DEVICES:

A. Color selection shall be verified with Architect/Engineer prior to ordering. Devices shall be White.

B. Receptacles:

1. All duplex, single, Isolated Ground, Tamper Resistant, Ground Fault Interrupter (GFCI), Controlled, and other special receptacles shall be minimum, specification grade commercial series, listed by Underwriter's Laboratories, UL 498 and Federal Specification FS W-C-596, 20 amp, nylon face and have a metal mounting strap with self-grounding and have a hex-head green grounding screw and be side and back wired. Each device shall bear the UL/FS Label. Meet NEMA standards for wiring devices including NEMA WD 1 for general requirements and NEMA WD 6 for dimensional standards.

    a. Each device shall have terminal screws and clamps listed for use with stranded wire. Plug-Tail device connections are acceptable.

2. Convenience Receptacle Configuration: Duplex or Single as indicated on the drawings, Type 5-20R.
3. Weather Resistant Receptacles: In addition to the above requirements all receptacles in damp and wet locations shall be WR (Weather Resistant) labeled.
4. Special Purpose Receptacle Configuration: straight blade or locking as indicated on drawings, black face.
5. Tamper Resistant Receptacles: Where indicated or required provide Duplex receptacle with integral switch and contacts to prevent energization unless a plug is inserted. Provide receptacles that are UL listed and labeled “TR”.
6. Ground Fault Interrupter Receptacles: Where indicated or required provide "local reset" auto monitoring “self-test” ground fault circuit interrupters. Provide unit capable of being installed in a 2-3/4" deep outlet box without adapter, grounding type, Class A, Group 1 per UL Standard 943. Provide visual indication of lost protection.
7. Cord and Plug Sets: Match voltage and current ratings and number of conductors to requirements of the equipment being connected.

    a. Cord: Rubber-insulated, stranded copper conductors, with type-SOW-A jacket. Grounding conductor has green insulation. Ampacity is equipment rating plus 30% minimum.
    b. Plug: Male configuration with nylon body and integral cable-clamping jaws. Match to cord and to receptacle type intended for connection.

8. Controlled Receptacles: Where indicated or required provide controlled receptacles.

    a. Split Controlled: Duplex device with the top receptacle controlled.
    b. Full Controlled: Duplex device with both receptacles controlled.
    c. Identification: Permanently marked in accordance with NEC 406.3(E).
    d. Wireless control devices shall only be allowed where specifically shown or indicated.

2.3 WIRING DEVICE ACCESSORIES:

A. Verify color and type with Architect/Engineer prior to ordering. Device color to match Wiring Device Color identified above. Verify location, height, mounting conditions, etc., of all devices with Architectural drawings prior to rough-in.

B. Wall-plates: Provide wall-plates for single and combination wiring devices, of types, sizes, and with ganging and cutouts as indicated. Select plates which mate and match wiring devices to which attached. Construct with metal screws for securing plates to devices; screw heads colored to match finish of plates. Identify all wall plates used for receptacles with branch circuit number per requirements of section on Electrical Identification. Provide blank wall plates for all cable, data, telephone and junction and outlet boxes. Where cables are routed through the wall-plate, provide grommets in wall-plate openings to protect cables. Provide plates possessing the following additional construction features:

1. Material and Finish:

    a. Flush-Mounted Wiring Devices: 0.04-inch-thick, Type 302 satin-finished stainless steel, smooth.
    b. Surface-Mounted Wiring Devices: Provide industrial-type covers sized to match the box, without exposed or projecting plate edges.

2.
3. Material and Finish: 0.04" thick brass, brushed chrome, or satin chrome where indicated.
4. Cast Metal or Aluminum: Die cast profile, ribbed for strength, flash removed, primed with gray enamel.
5. Gaskets: Resilient rubber or closed cell foam urethane.
6. Weatherproof, Exterior and other wet locations and where called out on the drawings as “WP”, provide weatherproof junction box with gaskets and cover.

    a. “In Use” type: Cover shall be rated “while in use”. Use low profile type covers with UV rated and resistant polycarbonate.
    b. Outlet box hood shall be listed as “extra duty”.

PART 3 - EXECUTION

3.1 INSTALLATION OF WIRING DEVICES:

A. Install wiring devices as indicated, in accordance with manufacturer's written instructions, applicable requirements of NEC and in accordance with recognized industry practices to fulfill project requirements.

B. Coordinate with other work, including painting, electrical boxes, and wiring work, as necessary to interface installation of wiring devices with other work.

C. Install wiring devices only in electrical boxes which are clean, free from excess building materials, dirt, and debris.

D. Install wiring devices after wiring work is completed.

E. Install wall-plates after painting work is completed.

F. Tighten connectors and terminals, including screws and bolts, in accordance with equipment manufacturer's published torque tightening values for wiring devices. Where manufacturer's

torque requirements are not indicated, tighten connectors and terminals to comply with tightening torques specified in UL Standard 486A.

G. Provide listed Class A GFCI devices as shown and as required in the NEC, including Articles 210, 422, and 620. For above counter multi-outlet assemblies which do not contain duplex receptacles that can be replaced with GFCI devices, provide GFCI circuit breakers on the branch circuit(s) feeding the assembly. Where GFCI devices are required and/or shown but are not readily accessible when equipment is installed, i.e., vending machines, kitchen equipment, electric water coolers, bottle fillers, etc., provide blank face GFCI device and cover-plate ahead of inaccessible receptacles. Mount adjacent to equipment at switch height unless otherwise shown. Install individual GFCI devices at each location shown, feed through devices are only acceptable where specifically called for.

H. Provide tamper-resistant receptacles as shown and as required in the NEC, including Article 406.

I. Receptacle Mounting: Mount device with front of device flush with the cover plate. All receptacles shall be mounted vertically with the ground pin down. Where switches and receptacles are mounted within one stud space, align vertically.

J. Switch Mounting: Switches shall be ganged and within 18” of the door jam on the strike side of the door openings unless otherwise shown. Verify door swings with Architectural drawings prior to rough-in. Switches connected to the life safety system shall not be ganged with other switches. Switch and receptacle combinations shall be installed in a 2-gang box where both are of the same voltage. provide separate boxes where different voltages are present.

K. Controlled Receptacles: Provide automatic controlled receptacles in enclosed offices, conference rooms, rooms used primarily for copy or print functions, breakrooms, classrooms, and individual workstations per IECC C405.11.

1. Provide automatic control method in each space as indicated on the drawings.

    a. Time schedule: Provide interface to existing digital lighting control system time clock controller.
    b. Occupancy sensor: Provide interface to local lighting control system sensors where noted on drawings.

2. Provide interfaces connections as required to control at least 50% of the receptacles installed in modular partitions and module office workstation systems. Provide interface connections to control at least 25% of branch circuits installed for modular furniture not shown on the construction documents.
3. Split Controlled Receptacles:

    a. Duplex: Connect top receptacle to the controlled circuit. Connect bottom receptacle to an unswitched branch circuit.
    b. Fourplex: Connect one duplex to the controlled circuit and the other duplex receptacle to an unswitched branch circuit.

4. Full Controlled Receptacles:

    a. Duplex and Fourplex: Connect entire receptacle to the controlled circuit.

3.2 PROTECTION OF WALL PLATES AND RECEPTACLES:

A. Upon installation of wall-plates and receptacles, advise Contractor regarding proper and cautious use of convenience outlets. At time of Substantial Completion, replace those items which have been damaged, including those burned and scored by faulty plugs.

3.3 GROUNDING:

A. Provide equipment grounding connections for wiring devices, unless otherwise indicated. Tighten connections to comply with tightening torques specified in UL Std. 486A to assure permanent and effective grounds.

3.4 CLEANING:

A. Internally clean devices, device outlet boxes and enclosures. Replace stained, cracked, damaged or improperly painted wall plates or devices. Remove temporary markings of labels.

3.5 TESTING:

A. Prior to energizing circuitry, test wiring for electrical continuity, and for short-circuits. Ensure proper polarity of connections is maintained and prepare test reports. After energization, test wiring devices to demonstrate compliance with requirements.

1. The tests shall be diagnostic, indicating damaged conductors, high resistance at the circuit breaker, poor connections, inadequate fault current path, defective devices or similar problems.
2. Tests for Convenience Receptacles:

    a. Line Voltage: Acceptable range is 114 to 126 V.
    b. Ground Impedance: Values of up to 2 ohms are acceptable.
    c. Polarity: Test for correct neutral conduct to neutral terminal connection.
    d. Using the test plug, verify that the device and its outlet box are securely mounted.
    e. GFCI Receptacles: Test for tripping values specified in UL 1436 and UL 943. Test with both local and remote fault simulations in accordance with manufacturing recommendations.
    f. Controlled Receptacles: Test that the automatic controls function as required.

3. Test Instruments:

    a. Use instruments that comply with UL 1436.
    b. Test Instrument for Convenience Receptacles: Digital wiring analyzer with digital readout or illuminated LED indicators of measurement.

B. Correct Deficiencies and Report:

1. Correct unsatisfactory conditions and retest to demonstrate compliance; replace devices as required to bring system into compliance.
2. Correct malfunctioning units on-site, where possible and retest to demonstrate compliance; otherwise, replace with new units and retest.
3. Prepare a report that identifies enclosure, units, conductors, and devices checked, and describes results. Include notation of deficiencies detected, remedial action taken, and observations and test results after remedial action.

END OF SECTION 26 27 26

This page left intentionally blank.

SECTION 26 28 00 - LOW-VOLTAGE CIRCUIT PROTECTIVE DEVICES

PART 1 - GENERAL

1.1 SUMMARY:

A. This section includes overcurrent protective devices (OCPDs) rated 600 V and below and switching devices commonly used with them.

B. Panelboards, Switchboards, and Motor Control Centers: Application, installation, and other related requirements for overcurrent protective device installations in distribution equipment are specified in other Division 26 sections.

1.2 DEFINITIONS:

A. Overcurrent Protective Device (OCPD): A device operative on excessive current that causes and maintains the interruption of power in the circuit it protects.

B. Ampere Squared Seconds: An expression of available thermal energy resulting from current flow. With regard to current limiting fuses and circuit breakers, the ampere squared seconds during fault current interruption represents the energy allowed to flow before the fuse or breaker interrupts the fault current within its current limiting range.

1.3 SUBMITTALS:

A. See Section 26 05 00 Common Work Results for Electrical for Submittal requirements. Supplemental information is listed within this section.

B. Product data for fuses, fusible switches, circuit breakers, and OCPD accessories specified in this Section, including descriptive data and time current curves for all protective devices and let through current curves for those with current limiting characteristics. Include coordination charts and tables and related data.

C. Submit documentation of compliance with Code and Specification requirements for circuit protective devices including but not limited to SCCR, Listings for use with downstream breakers/fuses and equipment where required, Ground Fault protection; etc.

1.4 QUALITY ASSURANCE:

A. Manufacturers: Firms regularly engaged in manufacture of overcurrent protective devices of types, sizes, and ratings required, whose products have been in satisfactory use in similar service for not less than 5 years.

B. Each type of OCPD shall be the product of a single manufacturer.

PART 2 - PRODUCTS:

2.1 MANUFACTURERS:

A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. When mounting overcurrent protective devices in panelboards, etc., provide equipment of same manufacturer as equipment into which they are being mounted.

2.2 OVERCURRENT PROTECTIVE DEVICES (OCPDS), GENERAL:

A. General: Provide OCPDs in indicated types, as integral components of panelboards, switchboards, motor control centers, and other related equipment; and as individually enclosed and mounted single units.

B. Enclosures: NEMA 250 "Enclosures for Electrical Equipment (1,000 Volts Maximum)."

C. Where OCPDs are to be installed in existing panelboards, switchboards, and motor control centers, they shall be of the same manufacture and type as those existing in the equipment. If this is not possible, provide devices which are compatible with the existing equipment and when installed will not void the U.L. label or reduce the short circuit rating of the equipment.

D. All overcurrent devices shall be individually rated for the available fault current unless otherwise noted. Series ratings of equipment will only be allowed where specifically called out.

2.3 MOLDED-CASE CIRCUIT BREAKERS:

A. General: UL 489, "Molded Case Circuit Breakers and Circuit Breaker Enclosures," and NEMA AB 1, "Molded Case Circuit Breakers."

B. Construction: Provide bolt-in type, except breakers 225 ampere frame size and larger which may be plugin type if held in place by positive locking device requiring mechanical release for removal.

C. Characteristics: Indicated frame size, trip rating, number of poles, and a short-circuit interrupting capacity rating as indicated or required to match existing devices or equipment.

D. Tripping Device: Quick-make, quick-break toggle mechanism with inverse-time delay and instantaneous overcurrent trip protection for each pole. Trip unit to be interchangeable within frame sizes for breakers 200 amperes or larger. Breakers 150 amperes and above shall have adjustable trip selection for trip units. All 120/208 volt rated breakers shall be rated and labeled "High Magnetic".

E. Adjustable Instantaneous Trip Devices: Factory adjusted to low trip setting current values. Provide adjustable instantaneous trip devices for each circuit breaker supplying individual motor loads and where indicated.

F. Enclosure for Panelboard Mounting: Suitable for panel mounting in switchboard or panelboards where indicated.

2.4 COMBINATION CIRCUIT BREAKERS AND GROUND FAULT CIRCUIT INTERRUPTERS:

A. General: UL 943 "Ground Fault Circuit Interrupters," arranged for sensing and tripping for ground fault current in addition to overcurrent and short circuit current. Provide features as follows:

1. Match features and module size of panelboard breakers and provide clear identification of ground fault trip function.

2.5 OCPD ACCESSORIES:

A. Lock-Out Devices: Provide padlocking provisions on each overcurrent protective device, lockable in the open or closed position. Provide 3 sets of lockout/tagout devices for each type of breaker or switch provided. Include tags, locks and all accessories necessary.

PART 3 - EXECUTION:

3.1 INSTALLATION:

A. OCPDs in new distribution and branch circuit equipment shall be factory installed. OCPDs in existing distribution and branch circuit equipment shall match existing for type and be provided with features as listed herein.

B. OCPDs and mounting accessories installed in existing equipment shall match the existing manufacturer and be rated for the available fault current.

3.2 IDENTIFICATION:

A. Identify components in accordance with Division 26 Section on electrical identification.

3.3 CONTROL WIRING INSTALLATION:

A. Install wiring between OCPDs and control/indication devices.

3.4 CONNECTIONS:

A. Check connectors, terminals, bus joints, and mountings for tightness. Tighten field connected connectors and terminals, including screws and bolts, in accordance with equipment manufacturer's published torque tightening values. Where manufacturer's torquing requirements are not indicated, tighten connectors and terminals to comply with tightening torques specified in UL 486A and UL 486B.

3.5 GROUNDING:

A. Provide equipment grounding connections for individually mounted OCPD units as indicated and as required by NEC. Tighten connectors to comply with tightening torques specified in UL Standard 486A to assure permanent and effective grounding.

3.6 FIELD QUALITY CONTROL:

A. Reports: Prepare written reports on tests and observations. Report defective materials and workmanship, and unsatisfactory test results. Include complete records of repairs and adjustments made. Tests shall be made on all new and existing OCPDs provided and/or connected under this project in accordance with this section.

B. Labeling: Upon satisfactory completion of tests and related effort, apply a label to tested components indicating test results, date, and responsible organization and person.

C. Schedule visual and mechanical inspections and electrical tests with at least one week's advance notification.

D. Upon completing installation of the system, perform the following tests on all new equipment and existing equipment as indicated on the drawings:

1. Visual and mechanical inspection: Include the following inspections and related work.

    a. Overcurrent Protective Device Ratings and Settings: Verify indicated ratings and settings to be appropriate for final system arrangement and parameters.
    b. Inspect for defects and physical damage, NRTL labeling, and nameplate compliance with current single line diagram.
    c. Exercise and perform operational tests of all mechanical components and other operable devices in accordance with manufacturer's instruction manual.
    d. Check tightness of electrical connections of OCPDs with calibrated torque wrench. Refer to manufacturer's instructions for proper torque values.
    e. Clean OCPDs using manufacturer's approved methods and materials.
    f. Verify installation of proper fuse types and ratings in fusible OCPDs.

2. Electrical Tests: Perform the following tests in accordance with manufacturer's instructions:

    a. Make insulation resistance tests of OCPD buses, components, and connecting supply, feeder, and control circuits.
    b. Make continuity tests of circuits.

E. Retest: Correct deficiencies identified by tests and observations and provide retesting of OCPDs by testing organization. Verify by the system tests that specified requirements are met.

3.7 CLEANING:

A. Upon completion of installation, inspect OCPDs. Remove paint splatters and other spots, dirt, and debris. Touch up scratches and mars of finish to match original finish.

3.8 DEMONSTRATION:

A. Training**:** Demonstrate OCPDs and train Owner's maintenance personnel.

B. Schedule training with at least seven days' advance notification.

END OF SECTION 26 28 00