COLORADO SPRINGS

R26-069MZ ADDENDUM #1 Q&A

1. Does the City anticipate selecting a general/prime contractor for the overall work or if this procurement is intended primarily for a specialized BAS controls contractor. If a general contractor role is contemplated, we would appreciate any guidance on the experience or team structure the City considers most important.

- This project is intended for a bas control contractor. No anticipation for a GC

2. Section 2.6 says pricing will be compared to "the budget amount." Would the City share the budget amount, or a range, for the Base Award and each alternate?

- The City cannot share the budget amount for this project.

3. Appendix B, Existing Conditions and Verification, item A says the owner "shall confirm the authoritative supervisory platform during design review." For pricing, should offerors carry integration to the existing Metasys front end, to a Niagara N4 Supervisor, or to both?

- The City has Metasys N4 and Desigo CC. We are open to other options

4. Will the City make the existing control drawings, point lists and JACE station backups available to offerors before the proposal due date?

- Yes

5. Appendix B, B.18.G excludes after-hours work unless separately priced. For Alternate Two, may VAV controller replacement on occupied floors be done during normal business hours?

- Yes. But scheduled in advance

6. Is a bid bond, or a performance and payment bond required for this award?

- No bid bond nor performance or payment bond will be required for this award.

7. Sample Contract Section 28 asks for a completed Voluntary Product Accessibility Template (WCAG edition). Does this apply to the browser-based BAS operator interface, and is it due with the proposal or at contract execution?

- This will be requested at contract award.

8. Does the three-page cover letter in Section 2.2 count toward the 25-page limit in Section 2.1?

- Does not count against the page limit.

9. Could we request mechanical drawings, control drawings, points list and number of users you want for the front end?

- Posted to Bidnet. Will post with this addendum as well.

10. Can you confirm the existing BAS front end and supervisory architecture (Metasys, Niagara N4, or other)?

- City also has Siemens Desigo CC

11. Is replacement of the three existing supervisory controllers intended to be included only under Alternate 1?

- No

12. Are current control drawings, point lists, graphics, network architecture diagrams, and BAS database backups available for review?

- See Question #9

13. Can you provide manufacturer and model information for the boilers, chillers, and VFDs?

- See Addendum #1 plan sets
  VFD -Yaskawa Return Fans model # E7BVB027ZL
  Supply Fans model #E7BVB096RL

14. Are any factory-authorized interfaces or startup services required for BACnet integration?

- No

15. Are valve schedules and damper schedules available for the devices receiving new electric actuators?

- No

16. Can existing valve bodies and dampers be assumed serviceable?

- Yes

17. Can you confirm the VAV quantities by floor, including the VAVs with baseboard heat and associated CO_2 sensors?

- See Addendum #1 plan sets

18. Does the City have a preferred BACnet architecture (IP, MS/TP, or hybrid)?

- IT would prefer an IP BACnet architecture. If the HVAC system is going to be on the same system, ideally it would be on an isolated VLAN to minimize the exposure to the HVAC system.
- I would say however that City IT would only define the BACnet architecture if it is riding the city data networks.

19. Will IT provide network drops, IP addresses, and required firewall access?

- Yes, IT will provide these items with Networks drops, IP's and firewall access once we are given the necessary requirements.

20. Should new line-voltage power and branch circuits be provided by others as stated in the RFP, with the controls contractor responsible only for low-voltage controls wiring?

- Provided by the electrical contractor

21. Are there specific outage windows, after-hours work requirements, or restrictions that should be considered during modernization activities?

- No

22. Will TAB, fire alarm testing, and any third-party commissioning activities be provided by others?

- No

23. Are existing graphics available for migration?

- Yes see Addendum 1 plan sets

24. Are there specific alarm notification requirements, recipients, or retention requirements for trends?

- Yes

25. Financial Statements required or not required?

- Not required with your submission. May be requested during evalautions.

26. Exhibit 1 - Item 13 – Are additional Qualifications required? (Page 37)

- No additional qualifications required.

27. Appendix B – Scope of Work – B.19.H – There is not a "Compliance Schedule Below" (page 74)

- Noted see Note H

28. Appendix A – Price Sheet – Is it acceptable to modify this sheet to match the proposed "Approach"? Or does it need to stay the same across all bidders?

- Please submit Appendix A – Price Sheet as shown. You may add documents to the price sheet to expand on your pricing or approach.

29. Are there any specific requirements for demolition beyond removing components, made obsolete by this upgrade? During the job walk there appear to be some older control elements that have been left by prior contractors please advise if these should be removed as well.

- No

30. The RFP contemplate cyber security expectations. Does the city have any cyber security guidelines that need to be met or adhere to, other than generally accepted principles.

Generally accepted principles are a good start, the cyber minimums that we work to meet are the following:
Implemented into City's current Single Sign-On (SSO) with Multi-Factor Authentication (MFA)
All designs must have architecture diagram(s) that clearly identify directional data flows to include ports, protocols, and services, interconnects to other networks, and VPN architecture. (Principle 2, 5, 10, 12)
If City data is stored in a vendor cloud, review of the City's Tech Rider will need to be considered for handling of city data, notifications for breaches, etc that are covered.
Protect the City data at the highest data classification level identified by the business data owner. This is provided as part of the Requirements document from the BRMs. (NOTE: IT does not classify business data unless it falls under applicable external governance such as PCI/DSS, CJIS, Colorado Privacy Law, HIPAA, HiTECH). (Principle 1 - 9, 11, 12)
When designs include data protected by applicable external governance, ensure all required security controls are applied to your design. If you can't design in the required controls, ensure you clearly identify how you designed in compensations to reduce the risk of not having the control. For example, governance logging requirements. (Principle 2, 3, 6, 9, 12)
Ensure your design meets or exceeds the Business Impact Analysis (BIA) Tier level identified by the business. To meet the BIA Tier level, you will have to ensure the solution meets/exceeds the BIA Recovery Time Objective (RTO) and Recovery Point Objective (RPO). (Principle 2, 3, 5, 6, 9)

Apply Least Privilege principal to the solution, ensuring to discuss the roles and role capabilities that are available in the solution. (Principle 7)
Ensure your design is fully functional with the current Zscaler Secure Access Service Edge (SASE) Internet Access (ZIA), Private Access (ZPA), and Cloud Access Security Broker (CASB) policies.
Service accounts shall not be interactive logon and should adhere to the Password Policy and have their passwords stored in Team Password Manager (TPM)
Ensure solutions that have a City data center, Platform as a service (PaaS), or Infrastructure as a Service (IaaS) components have clearly defined roles and responsibilities as to who is required to apply operating/Information system patches.
Incorporate patching into the City patching solution stack.
Do not design a new solution using any software/hardware that is already or within 12 months of reaching End-of-Life (El) or End-of-Support (EoS).
Review third-party software against the National Common Vulnerabilities and Exposures database

31. The RFP requires the boiler to be upgraded from lawn. Talk to Nanette. Who is the manufacturer of the boiler and who is its servicing agent?

- Viessman

32. The RFP mentions that after repairing the fire alarm in a lock to the air handling units that the fire alarm system needs to be recertified. Please confirm that the intent is to recertify and carry the cost for the entire fire alarm recertification or is this a cost that the owner will cover during its normal annual recertification?

- Contractor responsibility

33. The RSP mentions the existence of control documents and construction documents for the existing facility. Please confirm if those exist, if they do is there a way to get a copy of them either through a download or a Plant service?

- Posted to this addendum

34. Has the city done an audit of the building to determine if any asbestos-containing materials exist? If they are found during the construction process, will the city remove those materials that know expense to the contractor?

- No Asbestos survey has been completed in the project area

35. The RFP says that a project electrician will provide high-voltage wiring as required by the cultural contractor. Please confirm that the city is planning to cover these costs or if the contractor should include them in their bid?

- Include with your pricing

36. Our wireless controls, Bacnet over Zigbee acceptable for terminal unit controllers?

- Will consider if recommended

37. Should we ask for approval of using wireless controls?

- Will consider if recommended

38. Will the alternates be awarded at the time of the base contract award ? More specifically should we include project management cost for setting up a project and a future date? Should we include escalation for subsequent years?

- Alternative award will be determined at award time.

39. Is there a budget that has been established for the project? Would the city be willing to share it?

- See Question #2

40. SOW B.10and B.19.A require separate prices for each VAV floor, but the price sheet has only one line for Alternate 2. Should bidders add rows for the Basement and Floors 1–7, or attach a per-floor breakdown? If attached,

- Yes

41. Only one boiler is scheduled (B-1, Viessmann CT3-57). Please confirm one boiler BACnet interface is required, and that a Viessmann manufacturer gateway is acceptable.

- Yes

42. Price line "HWS Controller, Sensor and Pumps" and the SOW refer to "four boiler pumps and two primary pumps." The pump schedule lists P-1/P-2 as primary and standby and P-3 through P-6 as secondary HW pumps. Please confirm these are the six pumps in scope.

- P1 and P2 pumps are piped to the AHU. P3-P6 are baseboard perimeter heating.

43. The chillers are Multistack MS80T1H2W modular units, and their schedule data is blank. Does each chiller have its own LON interface, or is there a master controller? Is a Multistack-supplied BACnet gateway acceptable?

- Master controller, Yes

44. Is control of cooling tower CT-1's fan, VFD, or basin heater in scope? What is the size and type of the tower valve?

- Cooling tower does not have a VFD. Please see Mech plans (Addendum #1) and B.7.2.D and B.7.3.A

45. Please confirm that the "Four VFD BACnet Interfaces" are SF-1, SF-2, RF-1, and RF-2, and provide the VFD manufacturer and model.

- Yaskawa. Supply fans model E7BVB096RL and return fans model E7BVB0272L

46. Please list the valves included in "AHU/Unit Heater Electric Valve Actuators." The SOW lists one AHU heating valve and two unit-heater valves, but no preheat coil is scheduled. Are UH-16 and UH-17 ("Penthouse Air Handler") the AHU heating coils? Is the CC-1 chilled-water valve included? Which two unit heaters are meant?

- CC1 is a cooling and heating coil. UH16-UH17 are abandoned in place. When the outside air is below 42 degrees actuators open and the AHU provides heat , above 42 actuator open and the AHU provides cooling. The CC1 Valve will modulate to maintain discharge air temp. There are 4 valves total 2 on the HWS and 2 on the CHWS (see control and penthouse drawings.

47. Are any of the following in scope: penthouse EF-1 through EF-3, unit heaters UH-5 through UH-15, or the server-room and electrical-room exhaust fans (TF-12 through TF-14)?

- Exhaust fans 1-3 are on the BMS system and show status

48. Baseboard heat appears to be controlled by a few perimeter zone valves per floor, not one valve per VAV. Please clarify the 26 baseboard valves in B.10.C: their location, actuation type, and which space each one is controlled from

- See Mech plans (Addendum #1) hydronic heating plans for valve locations. BBR valves open when any associated VAX box temp is 1.5 degrees below set point

49. Who rebalances the boxes after the controllers are replaced, given that test and balance is excluded? Should controllers be set to the scheduled airflows or the "box label" airflows?

- Please include cost for TAB. Controllers should be set for scheduled airflow

50. What outage windows are allowed for heating (November through March) and chilled water?

- None. Will have to coordinate and schedule based on weather

51. Has an asbestos survey been completed for the penthouse and the areas above the ceilings?

- No survey has been completed in this location. One will be scheduled not sure of the timeline